TRANSCRIPT OF RECORD.

SUPREME COURT OF THE UNITED STATES.

No. 96

CLARENCE M. BUSCH, APPELLANT,

U8.

JOSHUA W. JONES AND THE W. O. HICKOK MANUFACT-URING COMPANY.

APPEAL FROM THE COURT OF APPEALS OF THE DISTRICT OF COLUMBIA.

FILED JUNE 27, 1900.

(17,816.)



(17,816.)

SUPREME COURT OF THE UNITED STATES.

No. 96.

CLARENCE M. BUSCH, APPELLANT,

US.

JOSHUA W. JONES AND THE W. O. HICKOK MANUFACT-URING COMPANY.

APPEAL FROM THE COURT OF APPEALS OF THE DISTRICT OF COLUMBIA.

INDEX.	Original.	Print.
Caption	a.	1
	-	
Transcript from the supreme court of the District of Columbia	a	1
Caption	b	1
Bill of complaint	1	1
Answer	9	6
Replication	13	10
Amendment to answer	13	10
Stipulation of counsel	14	11
Complainants' evidence in chief		11
Testimony of William Hayes Grier	18	12
E. S. B. Miller	25	18
Joshua W. Jones	32	24
T. J. W. Robertson	46	35
Complainants' evidence in rebuttal	72	54
Testimony of Theo. L. De Vinne		54
James B. Nicholson		60
Thomas B. Penicks	84	63
T. J. W. Robertson (recalled)	97	73

INDEX.

	Criticini
Complainants' Exhibits	121
Miller Sketch	121
Wood Cut of Seybold Signature Press	122
Jones Sketch	123
Jones Form of License	124
Hydraulic Presses	126
Cut of Jones Signature Press	127
Cut of Jones Bundle of Printed Signatures,	128
Thos. B. Penicks' Letter, February 25, 1879	128
February 5, 1880	129
August 3, 1886	129
Jones Steam Screw-power Signature Press	131
Jones Hand-power Signature Press	132
Stipulation of counsel	135
Drawing and specification, No. 204,741	139
Contract of Jones and Hickok Manufacturing Co	141
Testimony on behalf of respondent	144
Testimony of Harrison P. Hood	144
Defendant's Exhibits	165
Sketch of Palmer Press	165
Drawing and specification, No. 9324	166
No. 40,336	171
No. 58,779	174
No. 119,195	177
No. 48,523	179
No. 2113	181
No. 181,389	184
No. 169,518	186
No. 125,786	189
No. 394,977	191
Justice Hagner's remarks as to decree	195
Interlocutory decree	195
Report of auditor and Schedule A	196
Exceptions to auditor's report	206
Exceptions overruled and final ratification of auditor's report	207
Final decree	208
Petition for appeal and allowance of same	209
Assignment of errors	209
Memorandum: Appeal bond filed	210
Waiver of citation	211
Clerk's certificate	211
Additional transcript	212
Stipulation of counsel	213
Testimony of Charles G. Schrank.	214
Edmund H. McKee	220
Francis E. Davis	223
Alexander Stewart	227
Notary's certificate	227
Second additional transcript	228
Stipulation of counsel	229
Stipulation of counsel	229
Testimony for plaintiff	230

INDEX.		III
	Original.	Print
Testimony of Clarence M. Busch	230	179
Charles A. Suydam	235	185
Joshua W. Jones	248	197
R. A. Johnston	255	204
Joshua W. Jones (resumed)	256	205
Richard Miles	271	221
Notary's certificate	273	222
Minute entry of argument and submission	274	222
Opinion	275	223
Decree	295	236
Order allowing appeal	295	236
Bond	296	236
Citation and service	298	237
Clerk's certificate	299	238

Transcript of Record.

Court of Appeals, District of Columbia, October Term, 1899.

CLARENCE M. Busch, Appellant,

vs.

Joshua W. Jones and The W. O. Hickok Manufacturing Company.

No. 903.

Appeal from the supreme court of the District of Columbia.

Filed May 22, 1899.

b In the Court of Appeals of the District of Columbia.

CLARENCE M. Busch, Appellant, vs.
Joshua W. Jones et al.

Supreme Court of the District of Columbia.

Joshua W. Jones et al. vs.
Clarence M. Busch.

United States of America, District of Columbia, } ss:

a

Be it remembered that in the supreme court of the District of Columbia, at the city of Washington, in said District, at the times hereinafter mentioned, the following papers were filed and proceedings had in the above-entitled cause, to wit:

1 In the Supreme Court of the District of Columbia, Sitting in Equity.

Joshua W. Jones and The W. O. Hickok Manufacturing Company
against
Clarence M. Busch.

To the honorable the judges of said court:

1. Joshua W. Jones, a citizen of the State of Pennsylvania, residing at Harrisburg, in said State, and the W. O. Hickok Manufacturing Company, a corporation duly organized under the laws of the State of Pennsylvania and having its principal office and place of business at Harrisburg aforesaid, bring this bill of complaint against Clarence M. Busch, an inhabitant of the District of Columbia, and residing at Washington in said District. And thereupon your

orators complain and say: That prior to the 11th day of June, 1878, said Joshua W. Jones, being then a citizen of the United States, was the first, original and true inventor and discoverer of certain new and useful improvements in book-binders' dry press and sheet-tie, and of a certain new and useful process for treating folded sheets in dry-pressing, described in letters patent of the United States, dated June 11th, 1878, hereinafter mentioned, and which were not

known or used by others prior to his invention thereof, and had not been patented or described in any printed publication in this or any foreign country before the date of said invention or discovery thereof, and which were not and had not been at the time of his application for letters patent therefor, as hereinafter men-

tioned, in public use or on sale for more than two years.

2. That said Joshua W. Jones, being so as aforesaid, the first and original inventor and discoverer of said improvements and of said process, and being a citizen of the United States, and being desirous of obtaining the exclusive property to said invention or discovery within and for the United States, did on the 11th day of June, 1878, did, upon due application therefor, and having in all things complied with the conditions and requirements of the acts of Congress in such case made and provided, obtain letters patent of the United States for said invention or discovery, in due form of law, under the seal of the Patent Office, signed by the Secretary of the Interior and countersigned by the Commissioner of Patents, being dated the said 11th day of June, 1878, and numbered 204,741, which said letters patent are now remaining of record in the Patent Office of the United States, by which said letters patent there was granted and secured or intended to be granted and secured to the said Joshua W. Jones, his heirs, executors, administrators and assigns, for the term of seventeen years from the said 11th day of June, 1878, the full and exclusive right and liberty of making, using and vending to others to be used, the said invention or discovery described in said letters patent; a certified copy of which said letters patent is here in court ready to be produced as your honors may direct.

3. Your orators further complain and say, that prior to the 26th day of May, 1891, the said Joshua W. Jones, being then a citizen of the United States, was the first, original and true inventor and discoverer of certain new and useful improvements in book-

binders' and printers' dry-pressing, sheet-tying, smashing and tableting machines, described in letters patent of the United States dated May 26th, 1891, hereinafter mentioned and which were not known or used by others prior to his invention thereof and had not been patented or described in any printed publication in this or any foreign country before the date of the said invention or discovery thereof, and which were not and had not been at the time of his application for letters patent therefor, as hereinafter mentioned, in public use or on sale for more than two years.

4. That said Joshua W. Jones, being so as aforesaid the first and original inventor and discoverer of said improvements and being a citizen of the United States, and desirous of obtaining the exclusive property in said invention or discovery within and for the United

States, did on the 26th day of May, 1891, upon due application therefor, and having in all things complied with the conditions and requirements of the acts of Congress in such case made and provided, obtain letters patent of the United States for said invention or discovery, in due form of law, under the seal of the Patent Office, signed by the Secretary of the Interior and countersigned by the Commissioner of Patents, being dated the 26th day of May, 1891, and numbered 452,898, which said letters patent are now remaining of record in the Patent Office of the United States, by which said letters patent there was granted and secured, or intended to be granted and secured to the said Joshua W. Jones, his heirs, executors, administrators and assigns, for the term of seventeen years from the said 26th day of May, 1891, the full and exclusive right and liberty of making, using and vending to others to be used. the said invention or discovery described in said letters patent; a certified copy of which said letters patent is here in court ready to be produced as your honors may direct.

5. And your orators further show that your orators did, for a valuable consideration, enter into an agreement in writing. duly, signed, sealed and mutually delivered and dated the 27th day of December, 1889 (the application for said letters patent No. 452,898 being then pending in the Patent Office of the United States), wherein and whereby the said Joshua W. Jones granted unto the said The W. O. Hickok Manufacturing Company the exclusive license during the respective lifetimes of said letters patent to manufacture and sell to be used by others throughout the United States machines containing any of the processes, improvements or devices described and claimed in said letters patent Nos. 204.741 and 452,898, or either of them, and the said The W.O. Hickok Manufacturing Company agreed to pay to the said Joshua W. Jones a certain royalty for all machines manufactured and sold by it containing any of said processes, improvements or devices and on all supplies and appliances used in connection therewith and supplied by said company; an original or a duly authenticated copy of which agreement is here in court ready to be produced as

6. And your orators further show that by reason of the said letters patent and the said agreement as aforesaid, the said Joshua W. Jones became and is now the sole owner of the said letters patent Nos. 204,741 and 452,898, and the said The W. O. Hickok Manufacturing Company, the exclusive licensee to manufacture and sell to be used by others throughout the United States machines containing the inventions or discoveries described and claimed in said letters patent, and that the said Joshua W. Jones and the said The W. O. Hickok Manufacturing Company are entitled to use, exercise and enjoy all the exclusive rights and privileges, profits and advantages, granted and secured, or intended to be granted and secured, in and by said letters patent for and during the respective

lifetimes of said letters patent.

your honors may direct.

7. And your orators further show that the inventions or discov-

eries so patented as aforesaid and each of them are and is valuable and useful to the public and that the public have generally acquiesced in the exclusive rights of your orators, and that your orators would, but for the wrongful acts of the defendant in this case and those acting in concert with him, have made large gains and profits from said inventions, which profits your orators have been hindered from making by reason of such wrongful acts.

8. And your orators further show unto your honors, upon information and belief, that the said Clarence M. Busch, well knowing the premises and the rights and privileges granted unto your orators and in order to deprive them of the profits, benefits and advantages, which might and otherwise would have accrued to them from said inventions and letters patent, after the execution of said agreement and before the commencement of this suit, as your orators are informed and believe, without license or consent, and against the will of your orators, and in violation and infringement of the aforesaid letters patent Nos. 204,741 and 452,898, at Harrisburg, in the eastern district of Pennsylvania, and elsewhere throughout the United States, did unlawfully and wrongfully and in defiance of your orators' rights and privileges, make or cause to be made and used or cause to be used the said inventions, and is now using or causing to be used within the territory above named presses containing the said inventions, the several inventions described and claimed in each of said letters patent being used conjointly in the same press, and has been and is now using in connection and combination with said presses the process of dry-pressing described and claimed in said letters patent No. 204,741, which said unlawful making or using and preparation to use are in violation and infringement of your orators' exclusive rights and privileges under said letters patent, by reason of which they have sustained and are still sustaining great loss and damage.

 And your orators further allege that the said defendant has derived and received and is deriving and receiving from said use great gains and profits, but to what amount your orators

are ignorant.

10. And your orators specifically waive answer under oath to this

bill of complaint.

11. And forasmuch as your orators can have no adequate relief except in this court, and to the end that the defendant may, if he can, show why your orators should not have the relief hereby prayed, and may according to the best and utmost of his knowledge, remembrance, information and belief, true, direct and perfect answer make according to the best and utmost of his remembrance, information and belief of the several matters hereinbefore averred and set forth, as fully and entirely as if the same were here repeated paragraph by paragraph; and that the defendant may be compelled to account for and pay to your orators the profits unlawfully derived from the violation of the rights of your orators as above and the damages suffered by your orators because of said infringements, and be restrained from any further violation of said rights, your

orators pray that your honors may grant a writ of injunction issuing out of and under the seal of this honorable court, perpetually enjoining and restraining said defendant, his agents, servants and workmen, from any further construction, sale or use, in any manner, of said inventions or improvements, or either of them, or any part thereof, in violation of the rights of your orators as aforesaid, and also requiring the said defendant to destroy or deliver up to your orators for that purpose any and all specimens of said inventions, or any part or parts thereof in the possession or use or under the control of the defendant. And also that your honors, upon entering a decree for infringement as above prayed for, may proceed to assess or cause to be assessed under your direction, in addition to the profits to be accounted for by the defendant as aforesaid, the damages your orators have sustained by reason of said infringement.

12. And your orators pray also for a provisional or preliminary injunction to restrain and prevent the defendant from manufacturing, selling or using presses containing the said improvements, or any of them, and from using the said process during the pendency of this suit, and for such other and further relief as to your honors may seem meet and as the equity of the

case may require.

13. May it please your honors to grant unto your orators a writ of subpena, issuing out of and under the seal of this honorable court, directed to the said defendant, Clarence M. Busch, commanding him, by a day certain and under a certain penalty, to be and appear in this honorable court, then and there to make answer to this bill of complaint and to perform and abide by such order and decree as may be made against him. And your orators will ever pray.

JOSHUA W. JONES. THE W. O. HICKOK MFG. CO., Pr L. S. BIGELOW, Gen't Man'g'r & Sec'y.

M. W. JACOBS,

Solicitors and Counsel for Complainants.

STATE OF PENNSYLVANIA, ss:

Joshua W. Jones, being duly sworn according to law, deposes and says that he is one of the complainants in the above case; that he has read the foregoing bill of complaint and noted the contents thereof, and that so far as the statements therein contained are within his own knowledge they are true, and that so are as they are derived from the information of others he believes them to be true.

And he further deposes and says that he verily believes that he is the true, original and first inventor of the inventions patented to him, as set forth in said bill of complaint, and that the said inventions or discoveries had not been in use or described before the invention thereof by him.

JOSHUA W. JONES.

Subscribed and sworn to before me, this 9th day of March, 1894.

[SEAL.]

WM. M. HARGEST,

Notary Public.

8½ [Endorsed:] In the supreme court of the District of Columbia. Joshua W. Jones and The W. O. Hickok Manufacturing Co. rs. Clarence M. Busch. Bill of complaint. Robert Snodgrass, M. W. Jacobs, Harrisburg, Pa., complainants' solicitors and counsel.

Answer of Clarence M. Busch, &c.

Filed April 30, 1894.

The Supreme Court of the District of Columbia, Sitting in Equity.

Joshua W. Jones and The W. O. Hickok Manufacturing Company vs. Clarence M. Busch.

Auswer.

The answer of Clarence M. Busch, of Washington, District of Columbia, defendant, to the bill of complaint of Joshua W. Jones and the W. Hickok Manufacturing Company.

This defendant now and at all times hereafter saving and reserving to himself all and all manner of benefit or advantage of exception or otherwise that can or may be had or taken to the many errors, uncertainties or imperfections in said bill of complaint contained, for answer thereto, or to so much thereof as this defendant is advised is material or necessary for him to make answer to, answering, says:

 That he has no knowledge, save from said bill of complaint, whether the coplaintiff, The W. O. Hickok Manufacturing Company, is a corporation doing business under and by virtue of the laws of the State of Pennsylvania, but leaves the complainant- to make such

proof thereof as they may deem necessary.

1a. He is informed and believes that letters patent of the United States, No. 204,741, were issued to Joshua W. Jones on June 11, 1878, for a book-binder's dry press and sheet-tie, but denies on information and belief that the said Joshua W. Jones was the first, original and true inventor of the improvements or process set forth in the aforesaid patent and claimed therein, and he further denies that said alleged improvements or process was new or useful, or that the same had not been known or used by others prior to the alleged inven-

tion thereof by said Jones, or that the same had not been patented or described in any printed publication prior to his alleged invention thereof, and he further denies that the alleged imrovements or process had not been in public use or on sale for more than two

years prior to his application for letters patent therefor.

He is informed and believes that letters patent of the United States, No. 204,741, dated June 11, 1878, were issued to one Joshua W. Jones, purporting to grant unto said Jones, his heirs or assigns, for the term of seventeen years the full and exclusive right of making, using and vending to others to be used the alleged invention therein set forth, but is not informed, save by the bill of complaint, whether the said Jones complied with all the conditions and

requirements of the then existing laws of the United States or whether said patent was issued in due form of law and

leaves complainant- to make such proof thereof as they may,

 He is informed and believes that letters patent of the United States, No. 452,898, were issued to Joshua W. Jones, May 26, 1891, for a dry-pressing, sheet-tying, smashing and tableting machine, but denies upon information and belief that the said Jones was the first, original and true inventor of the alleged improvements set forth in said patent and claimed therein, and he further denies that said alleged improvements were new and useful, or that the same had not been known or used by others prior to the alleged invention thereof by said Jones, or that the same had not been patented or described in any printed publication prior to his alleged invention thereof, and he further denies that the alleged improvements had not been in public use or on sale for more than two years prior to his application for letters patent therefor,

4. He is informed and believes that letters patent of the United States, No. 452,898, dated May 26, 1891, were issued to one Joshua W. Jones, purporting to grant unto said Jones, his heirs and assigns, for the term of seventeen years the full and exclusive right of making, using and vending to others to be used, the alleged invention therein set forth, but is not informed, save by the bill of complaint, whether the said Jones complied with all the conditions and requirements of the then existing laws of the United States, or whether said patent was issued in due form of law and leaves complainant-

to make such proof thereof as they may.

5. That he is not advised, save by the bill of complaint, whether the said Joshua W. Jones did enter into an agreement in writing granting unto the said W. O. Hickok Manufacturing Company an exclusive license to manufacture and sell to be used by others throughout the United States, machines containing the processes, improvements or devices described and claimed in the letters patent Nos. 204,741 and 452,898, or either of them, but leaves the complainants to make such proof thereof as they may deem necessary.

6. That he is not advised, save by said bill of complaint, whether complainants are the sole owners and licensees, respectively, and are entitled to use, exercise and enjoy all the exclusive rights and privileges, profits and advantage, granted and secured, or intended to be granted and secured, in and by the letters patent Nos. 204,741 and

452,898, but leaves said complainants to make such proof thereof as

they may.

7. He denies, upon information and belief, that the public have generally acquiesced in the validity of said patents Nos. 204,741 and 452,898, or either of them, or any of the alleged rights of complainants in and under said patents; and he further denies that said complainants have any right to or would, but for the wrongful acts of this defendant and those acting in concert with him, have made large gains and profits from said alleged inventions.

 Defendant denies, upon information and belief, that he has in any manner or way whatsoever violated or infringed the said letters patent Nos. 204,741 and 452,898, or either of them, or

any legal or equitable rights secured to the complainants by reason of said patents, or that he intends so to do, either by making or using or causing to be used presses, or any device whatsoever containing or embodying, or having on them as a part thereof the alleged inventions described and claimed in said patents, or either of them; he further denies, on information and belief, that the press used by him in any manner whatsoever infringes the said letters patent, or either of them, or that he is using, or ever has used the alleged inventions patented as aforesaid, or that any actions or doings of this defendant work or ever has worked any injury to

of said alleged inventions, or either of them.

Sa. Defendant says that the press he is using is a patented one, and differs radically in construction and mode of operation from the alleged inventions shown, described, and claimed in the afore-

said complainants to deprive them of any gains or profits which they or either of them have or ever had a right to receive on account

said patents, Nos. 204,741 and 452,898, or either of them.

8b. Defendant charges, on information and belief, that the claims of said patents, Nos. 204,741 and 452,878, are void, for that in view of the state of the art, at and prior to the date of the said alleged inventions, or either of them, by said Joshua W. Jones, it required no invention to produce same, and that the alleged improvements claimed in said patents are not patentable inventions within the meaning of the law.

Sc. Defendant avers, on information and belief, that the letters patent, No. 204,741, is void, containing as it does two alleged separate and distinct inventions which are not in any way dependent

upon each other.

8d. Defendant avers, on information and belief, that the features of the alleged inventions claimed in the two patents, Nos. 204,741 and 452,898, are incapable of a conjoint use in one press, and that

said patents are improperly joined in this action.

Sc. Defendant charges, on information and belief, that the claims of the said letters patent, 204,741 and 452,898, are void for that the alleged inventions, and the same principles and combinations, or every substantial and material part thereof shown, described and claimed therein as new, were prior to the date of the application for each of said patents, and the date of the said alleged inventions by

the said Joshua W. Jones shown, described and set forth in the following publications and letters patent of the United States, viz:

"A Manual of the Art of Book-binding," by James B. Nicholson,

published at Philadelphia in 1856, page 43, et seq.

Patent No. 2113, granted T. G. Hardesty, May 27, 1841. Patent No. 9324, granted D. Kellogg, October 12, 1852.

Patent No. 40336, granted W. R. Dingman, October 20, 1863.

Patent No. 48523, granted W. P. Craig, July 4, 1865.

Patent No. 58779, granted S. Cooley, October 16, 1866.

Patent No. 119,195, granted T. Stibbs, September 19, 1871.

Patent No. 125,786, granted C. Brown, April 16, 1872.

Patent No. 150,044, granted S. Hughes, April 21, 1874. Patent No. 157,558, granted E. S. Watson, December 8, 1874.

Patent No. 169,518, granted C. Brown, November 2, 1875.

Patent No. 223,355, granted J. W. Jones, January 6, 1880. Reissue patent No. 9598, granted J. W. Jones, March 8, 1881.

Patent No. 286,839, granted A. H. Merriam, October 16, 1883.

No. 367,897, granted M. F. Doud, August 9, 1887.

Patent No. 394,977, granted R. A. Hart, December 25, 1888. Patent No. 181,389, granted J. B. Archer, August 22, 1876.

Also patented and described or contained in other letters patents, the dates and numbers of which defendant is not now able to specify but prays to be allowed to add hereafter by amendment or other-

wise, if it shall become necessary.

12

8f. Defendant, on information and belief, says, that said Joshua W. Jones was not the original and first inventor and discoverer of any material or substantial part of the devices or process set forth and claimed in the aforesaid patents Nos. 204,741 and 452,898, but on the contrary thereof the same devices and process, in all material and essential features, had been, previous to the alleged invention of said Jones, known to and used by the following-named persons, and at the following places, viz: E. H. McKee, John J. Clifford and Charles G. Schrank, all residents of Philadelphia, State of Pennsylvania, and used at the book-bindery of John Palmer, at Philadelphia aforesaid; also known to and used by others, the names of whom, and their address and place of use this defendant is not now able to specify, but prays leave to be allowed to add hereafter by amendment or otherwise, if deemed necessary.

Defendant denies that he has derived and received and is deriving and receiving great gains and profits, or any gains or profits, by any unlawful use of the alleged inventions of complainants.

10. This defendant, further answering, denies each and every other allegation in the said bill of complaint contained and not hereinbefore admitted, controverted or denied, and this defendant prays the same benefits of the facts and things herein set forth, as if, for the reason thereof, the said bill had been demurred to where a demurrer would have been proper, and the same benefit thereof as if they had been specially pleaded in said bill.

11. This defendant submits to this honorable court that said complainants have no right to any further answer to said bill, or any

2 - 96

part thereof, and that they have no right to an injunction, account or other relief prayed for in said bill of complaint. All of which matters and things this defendant is ready and willing to aver, maintain and prove as this honorable court shall direct, and humbly prays to be hence dismissed with his costs and charges in this behalf most wrongfully sustained.

(Signed)

CLARENCE M. BUSCH. O. M. HILL,

Solicitor and Counsel.

CITY OF WASHINGTON, District of Columbia, 88: 13

Clarence M. Busch, being duly sworn, deposes and says that he is the defendant in the above-entitled cause; that he has read the foregoing answer and knows the contents thereof, and that the matters and things therein set forth are true to the best of his knowledge, except as to the matters which are therein stated upon information and belief, and as to those matters he believes them to be true.

CLARENCE M. BUSCH.

Sworn to and subscribed before me this 28th day of April, 1894. GEORGE C. AUKAM, Notary Public, D. C.

SEAL.

Replication.

Filed May 28, 1894.

In the Supreme Court of the District of Columbia, Sitting in Equity.

Joshua W. Jones and The W. O. Hickok Manufacturing Company, Complainants, No. 15391, Docket 36. CLARENCE M. BUSCH.

The complainants hereby join issue with the defendant.

M. W. JACOBS,

Solicitor and Counsel for Complainants.

Amendment to Answer.

Filed October 26, 1894.

Supreme Court of the District of Columbia. In Equity.

Joshua W. Jones and The W. O. Hickok Mfg. Co. No. 15391, Docket 36, CLARENCE M. BUSCH.

Amendment to answer.

Now comes the defendant, by his solicitor and counsel, the court concurring, and by agreement of counsel for complainants, amends his answer, paragraph "8f," page 6, by inserting immediately after the name of "Schrank," line 9, the name of "Frank E. Davis," who is also a resident of Philadelphia, Pa., and knew of the use alleged in said paragraph.

Defendant, by counsel, hereby consents that the replication already filed to original answer shall be considered a replication to this amendment unless complainant desires to

further reply.

O. M. HILL, Counsel for Defendant.

October 15, 1894.

It appearing to the satisfaction of counsel for complainant-that the matter incorporated by above amendment was not within the knowledge of defendant or his counsel at the time of filing his answer, it is agreed that said amendment may be entered and filed of record.

M. W. JACOBS, Counsel for Complainant.

In the Court of Appeals of the District of Columbia.

CLARENCE M. Busch, Appellant,

18.

Joshua W. Jones and The W. O. Hickok

Manufacturing Company, Appellees.

October Term, 1899,
No. 903.

It is hereby stipulated and agreed by and between counsel for the parties hereto that "plaintiffs' (appellees') printed record," as used in the supreme court of the District of Columbia, including "Complainants' exhibits," which form the appendix to said record, may be substituted for pages 15 to 68 of the transcript of record furnished for use in this court, together with copy of patent No. 204,741, being "Complainants' Exhibit Jones' Patent No. 204,741."

CHAS. E. RIORDON,
Of Counsel for Appellants,
M. W. JACOBS,
Of Counsel for Appellees.

August 15, 1899.

(Endorsed:) No. 903. Court of Appeals, D. C., October term, 1899. Clarence M. Busch, appellant, vs. Joshua W. Jones and The W. O. Hickok Mfg. Co. Stipulation of counsel. Court of Appeals, District of Columbia. Filed Aug. 30, 1899. Robert Willett, clerk.

15 & 16 Supreme Court of the District of Columbia. In Equity.

J. W. Jones and W. O. Hickok Manufacturing Company
vs.
Clarence M. Busch.

Plaintiffs' Printed Record.

Robert Snodgrass, M. W. Jacobs, solicitors and counsel for plaintiffs. 17 Supreme Court of the District of Columbia. In Equity.

J. W. Jones and The W. O. Hickok Manufacturing Company vs. Clarence M. Busch.

Plaintiffs' Record.

Harrisburg, Pa., September 20th, 1894.

Testimony taken and proceedings had in the above-stated case, at the office of M. W. Jacobs, No. 222 Market street, Harrisburg, Pa. by stipulation of counsel and in pursuance of notice, before Frank E. Ziegler, notary public, as special examiner.

Appearances.

Robert Snodgrass and M. W. Jacobs, Esqs., for complainants. O. M. Hill, Esq., for defendant.

Counsel for defendant hereby gives notice on the record that, at the hearing of this case, he will refer to the device shown and de-

scribed in patent No. 204,741, as being in anticipation of the 8 device claimed in patent No. 452,898, both of said patents being before the court and set up in the bill of complaint.

Counsel for complainants offer in evidence letters patent No. 204,741, to Joshua W. Jones, for book-binders' dry press and sheet-tie, and the same is received and marked "Complainants' Exhibit Jones Patent No. 204,741."

Also certified copy of the articles of association of the W.O. Hickok Manufacturing Company, and the same is received and marked "Complainants' Exhibit Certified Copy of Articles of the W.O.

Hickok Manufacturing Company."

Also contract between Joshua W. Jones and the W. O. Hickok Manufacturing Company, dated Dec. 27, 1889; and by agreement of counsel a copy compared by the examiner, is to be substituted in the record for the original, and marked "Complainants' Exhibit Contract of Jones and Hickok Manufacturing Company;" the original to be produced when called for.

WILLIAM HAYES GRIER, a witness on behalf of complainants, being produced, affirmed, and examined, deposes and says:

Examined by Mr. Jacobs:

Q. 1. State your age, occupation, and place of residence.

A. I am fifty-three years of age; occupation printer; residence, Columbia, Penna.

Q. 2. What official position, under the State of Pennsylvania, do you at present occupy?

A. I am superintendent of public printing.

Q. 3. How long have you occupied that position?

A. Since the first of April, 1892, under the present appointment

Q. 4. Who does the printing and binding of public documents for the State of Pennsylvania?

A. Clarence M. Busch.

Q. 5. Where is his establishment?

A. Near the corner of Herr and Elder streets.

Q. 6. In what place? A. In Harrisburg.

Q. 7. What are your duties in connection with the public printing of the State and in connection with Mr. Busch's establishment?

A. I receive all orders for printing from all departments and make duplicates of them for the State printer, specifying how and in what manner the work is to be done. I have no supervision of Busch's establishment beyond the work he is doing for the State. My one duty is particularly to see that everything is done according to contract.

Q. 8. Do the duties of your office take you to Mr. Busch's estab-

lishment, and if so, how frequently?

A. Several times a day and pretty nearly every day in a week.

Q. 9. Please state whether or not the sheets of the work done by
Mr. Busch for the State are required to be put through the process
known in the art as dry-pressing.

(Objected to as leading.)

A. They are.

Q. 10. Please state whether or not the sheets of the work referred to are, as a matter of fact, dry-pressed at Mr. Busch's establishment.

(Same objection.)

A. They are.

Q. 11. Will you now describe by what means and in what man-

ner the dry-pressing is there done?

A. After the sheets are folded into signatures they are placed between boards and put into the dry press and pressed, and then tied with heavy twine while the pressure is on, and then removed for binding.

Q. 12. What kind of boards are used?

A. I don't know what the material of the board is,—I never examined that,—but as large as the signature of the paper when folded, and probably an inch and a half or two inches thick.

Q. 13. Are any fuller-boards used?

(Objected to as leading.)

A. No, sir. Nothing but the boards at the top and bottom of the signatures, a wooden board.

Q. 14. About how many sheets are put in the press at one time?

A. That I do not know,—the number,—but the length of the pile, or the height of the pile between boards runs from eighteen to twenty-four inches. They are never counted when put in.

Q. 15. In referring to the length of the pile do you mean when

the sheets are put into the press?

20 A. No, sir. I mean after they are tied.

Q. 16. How long are the sheets thus compressed allowed to

remain in bundles?

A. The time varies. Whenever they want to use them after a book is completed, the sheets last run off of the printing press do not remain in bundles as long as those first run off; but in nearly every book that we print the first signatures remain in bundles from three to six weeks.

Q. 17. And the last, how long?

A. The last may remain, in cases of necessity, not more than twenty-four hours. What I mean by necessity is haste to get out the book.

Q. 18. What is the purpose of allowing the sheets to remain thus tied in bundles under pressure for twenty-four hours or longer?

A. To remove the heavy impression that may have been made on the printing press and to give the paper more solidity. It takes out all indentations.

Q. 19. What do you understand by the term dry-pressing as used

in the art of printing?

A. Removing the heavy impression made by the printing press. Making the paper with a clear surface.

Q. 20. What do you mean by clear surface?

A. Smooth surface, I mean, instead of clear surface.

Q. 21. Is there any provision of the law under which the State printing is done, requiring the dry-pressing of the work?

(Objected to as leading and immaterial.)

A. Yes, sir.

Q. 22. When did Mr. Busch begin to do the printing for the State?

A. The 1st of July, 1893.

Q. 23. Do you know the name of the machine upon which the dry-pressing, which you have described, is done in Mr. Busch's establishment?

A. I only know that an inscription on the machine says that it is

built by the Seybold Machine Company of Dayton, Ohio.

Q. 24. How long has Mr. Busch had it there?

A. I do not remember the exact time, but he put it in late in 1893.

21 Q. 25. When, if you know, did he do the first dry-pressing with it?

A. That I don't know. I can't recall.

Q. 26. Has he any other machines for dry-pressing there?

A. No, sir. Q. 27. Has or has not all the work he has done for the State since he has had the machine been dry-pressed?

A. Yes, sir.

Q. 28. I hand you two sheets of signatures 15 and 15* and ask you to state whether or not either or both of them have passed through the process of dry-pressing.

(At request of complainants' counsel the sheets referred to are marked respectively "A 15*, A 15, B 15, and B 15*.")

A. A 15 and A 15* have been dry-pressed; B 15 and B 15* have

not been dry-pressed.

Q. 29. You have said in your answer to question 3 that you have been superintendent of public printing since April 1st, 1892, under your present appointment. Have you at any time occupied the same position under any other appointment?

A. Yes, sir. I was superintendent of public printing from Aug.,

1883, until the 1st of July, 1889.

Q. 30. Who were the contractors for the State printing during that term and also during your present term, prior to the date when Mr.

Busch's contract began?

A. Lane S. Hart was State printer when I was first appointed in 1883, and from the 1st of July, 1885, to the 1st of July, 1889, E. K. Meyers was State printer, and C. M. Busch State binder. The work was divided during that time. E. K. Meyers was State printer when I commenced my present term until the 1st of July, 1893; he was succeeded then by C. M. Busch.

Q. 31. Was the work of the State dry-pressed during your official

terms by the several contractors whom you have named?

A. Yes, sir.

Q. 32. By what means?

A. In the same manner it is being done today.

Q. 33. Please state by what machine or machines, if you know.

A. By the Jones machine.

Cross-examined by Mr. Hill:

X Q. 34. How long have you been engaged in the printing or bookbinding business?

A. I have been in the printing business since 1856. X Q. 35. Have you been in business for yourself?

A. I have, since 1873.

X Q. 36. Where were you engaged in business in 1873?

A. Columbia, Penna.

X Q. 37. Did you at that time have any means for dry-pressing printed signatures, and if so, of what did the means consist?

(Objected to as not proper cross-examination.)

A. We had a dry press with fuller-boards about 22 by 28 and laid the sheets on the board and pulled a screw down, an upright machine with a screw, but it is not for signatures. It was for bill-heads and letter-heads of a commercial nature.

X Q. 38. During the year 1873 did you have any occasion to

handle printed signatures for books?

(Objection continued.)

Λ. Nothing, unless it might have been constitutions and by-laws for local lodges.

X Q. 39 Have you any personal knowledge of printed signatures ever having been dry-pressed during the year 1873, or prior thereto?

(Objection continued.)

A. No; I don't.

X Q. 40. Do you know whether or not, during the year 1873 an prior thereto, indentations from printed matter where removed opressed out?

(Objection continued.)

A. At that time we did use a screw-press with fuller-boards take out indentations from bill-heads, letter-heads and circulars.

X Q. 41. When did you first work on printed signatures f books?

(Same objection.)

A. I have never outside of my own office worked on printed sinatures.

X Q. 42. When did you first do such work in your own office? (Same objection.)

A. I couldn't give any date when I first did any work of the kind. I can when I last did work of that kind.

X Q. 43. Can't you give the approximate date?

A. No, sir.

23 X Q. 44. Can you come within one year of it? A. I cannot.

X Q. 45. Can you come within five years of it?

A. No, sir; but I can come within ten years of it. I did a bool last week, a copy of which had my imprint on, done in 1883.

X Q. 46. In the art of bookbinding what do you understand 1

the term "fuller-boards"?

A. They are a heavy board. I can't describe it. I am not bookbinder by occupation and know nothing about the binding books, except what I have picked up as superintendent of publ printing. The boards used in the dry press we had in those day they called "fuller-boards." That is all I know about them. The were in the office when I went there.

X Q. 47. What time was this?

A. In the printing office in Columbia.

X Q. 48. How or in what manner were these boards used?

(Objected to as not proper cross-examination.)

A. We had large fuller-boards, as they called them. We woultake one, lay it down and take letter-head after letter-head and lathem across until we covered the whole surface. Then we would place a board on top of that and repeat the process, until we had the boards all used. The press was upright with a spiral screw coming right down onto the top. In that screw there were largeholes, in which we would place an iron bar and then screw it down until we got the pressure that we wanted.

X Q. 49. How long did you use these fuller-boards?

A. I did not use them more than three months, because I the purchased a Gordon press that did the work without any necessit of removing the impression.

X Q. 50. You state in answer 15 that signature marked "A 15*" has been dry-pressed. Please state, if you know, on what press this signature was dry-pressed.

A. Well, I didn't see it dry-pressed, and this printing is done by Mr. Busch, and I judge from that that it has been done on the ma-

chine used in his office.

X Q 51. Has the work done by Mr. Busch, on the press in his office, proven satisfactory?

(Objected to as immaterial and not proper cross-examination.)

A. Yes, sir.

24 X Q. 52. In answer 33 you speak of the Jones machine. What kind of machine do you refer to?

A. A dry press.

X Q. 53. How or by what means is this press operated?

A. By a screw, the same as the one we have up in the office, with the signatures placed between boards and tied when pressed.

Redirect examination by Mr. Jacobs:

Q. 54. De bear case. Referring to your answer to question 48 how long was it necessary to leave the letter-heads in the press between the fuller boards in order to remove the indentations?

A. We would leave them in over night.

Q. 55. How long is it necessary to leave the signatures in the dry

press used in Mr. Busch's establishment?

A Only long enough to tie them. They put in a lot of signatures, press it, put in some more and press it and keep on putting in until they have got the proper length of pile they want and the process goes on until the whole signature is pressed; it is done quickly.

Q. 56 Pleas answer the same question with regard to the Jones dry press, which you have testified was used by Mr. Busch's prede-

cessors.

A. I have seen that press, but never in operation. Have seen nothing but the bundles as tied.

Recross-examination by Mr. Hill:

X Q. 57. In your redirect answer 54, with reference to the old press used by you, you state that it was necessary to leave the printed matter in the press over night. Was this absolutely necessary?

A. It was. We would either put them in at night and leave them in until morning or put them in in the morning and leave them there until evening. We had to do it that way when we had a good

many to do.

X Q. 58. What would you do with the printed matter after it was

pressed?

A. I would take it out of the press and deliver it to the customers, if that is what I understand you to mean. This refers to commercial work entirely.

Re-redirect examination by Mr. Jacobs:

Q. 59. Taking the sheets out from between the fuller-boards involved about the same amount of labor as putting them in, did it?

A. Just the same.

WM. HAYES GRIER.

Sworn and subscribed before me this 20th day of Sept., A. D. 1894.

FRANK E. ZEIGLER, Special Examiner.

E. S. B. Miller, a witness on behalf of the complainants, being produced, affirmed and examined, deposes and says:

Examined by Mr. JACOBS:

Q. 1. State your age, occupation, and place of residence.
A. 40 years of age, cabinetmaker by trade, Harrisburg.

Q. 2. Where are you employed at present?

A. By the W. O. Hickok Manufacturing Company.

Q. 3. Will you look at the article which I now place before you

and state if you know who made it, and what it is?

A. I made it. It is a model of the press,—that is the trough part between the heads, and the heads,—in the State bindery, corner of Herr and Granite avenue, Harrisburg, Pa.

Q. 4. When did you make it?

A. Commenced it at 9 o'clock on the 23d of last June.

Q. 5. State whether or not it was made from measurements made by you of the press referred to by you in your last answer.

A. It was.

Q. 6. Is it made to a scale or not?

A. It is not. The heads two ways are half size. The carrier rods are half size. The rods that represent the screws are not. They are just in for supports. I mean by those the three large rods that keep the heads in place.

Q. 7. Are the large openings in the heads made to a scale or not?

A. Near about half size.

Q. 8. How accurately does this model represent the corresponding

parts of the press to which you have referred?

A. This model does not represent any of the operative mechanism of the press, simply the way the signatures are placed in, pressed and tied.

26 Q. 9. How closely do the heads of the model correspond

with the heads of the press?

A. They are very accurate.

Q. 10. How accurately does the arrangement of the three larger rods in the model represent the arrangement of the corresponding rods of the press?

As near as half size can be made — represent.

Q. 11. I notice a number of small holes in the two heads of the

model. Please state how closely they represent in size and arrangement similar holes in the press.

A. They are half size and represent the holes in the press.

Q. 12. Will you describe in a general way the operative mechan-

ism of the press which you say is not shown in the model?

A. The upper head is adjusted near the lower head by a-endless chain running on chain gears running on the three heavy screw-rods that support the head, by a lever fastened on the top part of the head. The power is by a double and single knuckle-joint straightening out, and released by coming together or doubling up, worked by a screw four inches in diameter.

Q. 13. To what is the power referred to in the last sentence of

your last answer applied?

A. To the process of the lower head pressing the paper against

the upper head.

Q. 14. Have you any other illustration of the press referred to by you, which you have compared with the press itself?

A. Yes, sir.

Q. 15. Please produce it.

(Witness produces paper which counsel for complainants ask to have marked for identification, "Wood cut of signature press.")

Q. 16. State whether or not your comparison satisfied you that the wood cut produced is an accurate representation of the press to which you have been referring in your testimony.

A. It's a fac-simile of the press.

Q. 17. You have spoken of the establishment in which you saw the press as being located on Herr street, in this city. Do you know by whom that establishment is owned or controlled?

A. I do.

27

Q. 18. By whom?

A. Clarence M. Busch.

Q. 19. Did you observe any markings on the press?

(Objected to as immaterial.)

A. Name plate, "The Hercules, patented March 22, 1892. Designed and built by the Seybold Machine Company, Dayton, Ohio, U. S. A."

Q. 20. Did you at any time see the press in operation there?

A. I did: three times.

Q. 21. When?

A. The 19th of June last, and the 18th and 20th of this month.

Q. 22. Referring now to the first time, what work did you then see done upon it?

A. They were pressing signatures, but being State work I don't

know what they were.

Q. 23. How were they pressing signatures? Please describe the

operation as fully as you can.

A. They first put in a board and put the signatures in, put a board in against the other head, and run their press up until it was tight,

tied the bundles together by a rope over the boards and took them out and set them aside into the bundles.

Q. 24. Do you know how many signatures were put into the ma-

chine for one operation?

A. Well, probably three hundred. In that neighborhood; I

wouldn't be positive about the exact number.

Q. 25. Were they much or little compressed by the action of the

machine?
A. About nine inches, I guess.

Q. 26. What was the length of the trough between the heads before the sheets were put in?

A. Twenty-nine and one-eighth inches between the heads.

Q. 27. What was the length of the bundle after it had been subjected to pressure?

(Objected to as immaterial.)

A. The bundles varied, from fourteen to eighteen inches.

Q. 28. Was the trough between the heads filled up with sheets? (Same objection.)

A. Once they were. I wanted to see for myself the amount of pressure that it had and the young man filled it up for me once.

Q. 29. I now hand you the sheets, which have heretofore been marked for identification "A 15, A 15*, B 15 and B 15*," and ask you to say whether you ever saw them before and what you know about them.

(Objected to as the witness has not qualified himself as as expert in regard to printed signatures.)

A. Well, "B 15 and B 15*" was pressed in a bundle on the 18th of this month and immediately taken out of the press before tying up the bundle by myself. "A 15 and A 15*" was taken out of a bundle by me, laying up in the bindery since Saturday. I took it out today. The bundle was laying in the bindery since Saturday.

Q. 30. Do you mean by the first part of your last answer that B 15 and B 15* were pressed by you, or that you merely took them

out of the bundle.

A. I mean I took the signature out of the bundle.

Q. 31. By whom was the pressing of that bundle done?

A. I don't know the young man's name. I wasn't acquainted with him. The young man that runs the press; I don't know his name.

Q. 32. You have spoken of several small rods in the press which are represented by the three small rods in the model; please tell us how they were attached to the press and what became of them when the heads were moved closer together, in the operation of pressing.

A. They were fastened in the lower head by a thread that screwed

in as if into a nut. They ran up through the holes in the upper head.

Q. 33. What use, if any, was made of the rods during the operation of pressing?

A. The only support the signatures have, to hold them in place.

Q. 34. How did the signatures rest upon them?

A. They rest on the two lower ones and against the back one.

Q. 35. How were the sheets placed with reference to their length and width?

A. The width is placed up and down in the trough, the length cross-wise.

29 Cross-examination by Mr. Hill:

X Q. 36. In the press which you saw at Mr. Busch's establishment, were the three large rods upon which the heads are mounted, screw-threaded for a larger portion of their distance between said heads as shown in wood cut of signature press?

A. Yes, sir.

X Q. 37. Then this model which you made does not correctly represent this feature of those rods, does it?

A. Not on the screw.

X Q. 38. In the operation of pressing a bundle of papers as witnessed by you in the establishment of Mr. Busch, did the lower edge of the signatures come into contact with either of the large screw-threaded rods?

A. The space in between them is larger than the signatures they

were pressing and the carrier rods were above the screws.

X Q. 39. In speaking of the press at Mr. Busch's place of business you stated in A. 28, "I wanted to see for myself the amount of pressure it had." Why did you want to see the amount — pressure it had?

A. Well, it was more for my own satisfaction. When I am around work being done I like to see the process of the work. I had never seen the press run. I didn't know there was any suit or anything of the kind at the time.

X Q. 40. Did you find out the amount of pressure it had?

A. Just by the space it pressed up.

X Q. 41. Then you don't know anything about it—how many pounds pressure there was?

A. No, sir.

X Q. 42. How came you to go to Mr. Busch's place of business, and for whom did you make this model?

A. L. S. Bigelow, superintendent of the Hickok Manufacturing

Company, where I am employed.

X Q. 43. How came you to go to Mr. Busch's place of business

today?

A. I was requested to go there by the parties I worked for and by Mr. Jones and get a signature if I could out of the bundle I saw them press on Monday, as I had marked it on Monday when I was there. 30 X Q. 44. Did Mr. Jones or any one request you to watch the operation of the press—observe its workings?

A. Not that I know of, though I told him that I had seen it

operated.

X Q. 45. Do the two lower small rods in the model correctly represent the location of the two small rods in the press with reference to the top edge of the two large rods at bottom, which support the heads in the press at Mr. Busch's establishment?

A. No, as the rods representing the screw-rods in the model is acting as supports for the head. The rods in the model stand up a

little higher than in the press.

X Q. 46. Do the small openings in the heads of this model correctly represent the number and location of the openings in the heads of the press in Mr. Busch's establishment?

A. Yes, sir.

X Q. 47. The only feature, then, that is represented in this model as being analagous to like parts in the Busch press, consists of the three small rods mounted within openings in the two movable heads. Is this correct?

A. No, the arm-holes, the cross-openings for ropes are exactly like

the Busch press.

X Q. 48. Please state just how far this model and what parts therein correctly represent like parts, and their location in the press at Mr. Busch's place of business.

A. Well, the shape of the head, the hand or arm hole, the crossopenings, the holes in the head and carrier rods that support the

signatures.

X Q. 49. Are these all the parts in the model which correctly

represent like parts in the Busch press?

A. All that I worked special on. There may be others, that I didn't bother with.

Adjourned to Sep. 21st, at 10 o'clock a. m.

SEPT. 21st-10,30 a. m.

Met pursuant to adjournment. Present: Same counsel.

Cross-examination of E. S. B. Miller resumed by Mr. Hill;

X Q. 50. In the model made by you I notice that the lower openings in the two heads for the small rods are entirely beneath a plane with the top of the two lower large rods which support

31 the head. I will ask you whether or not the lower openings in the two heads of the Busch press are beneath a plane with the top of the two lower large screw-rods which support the heads of said press.

A. No. In the model the large rods don't represent the large

rods in the press.

X Q. 51. Is if not a fact that in the Busch press the lower openings in the two heads for the small trough rods are located some

ユ マアセアリテビ

distance above a plane, with the top of the two large lower screwrods, which support the heads?

A. They are raised enough above for clearance.

X Q. 52. This model, then, does not correctly represent the location of the lower openings in the heads with reference to the screw-rods in the Busch press? Does it?

A. Not in reference to the screw-rods. No, but in reference to

the head they do.

Redirect examination by Mr. JACOBS:

Q. 53. I would like to get before the court distinctly the extent to which the model does not accurately represent Mr. Busch's press, with special reference to the position and arrangement of the three large rods supporting the heads, and I will therefore ask you to describe as fully as you can the arrangement of those rods in the press with relation to each other and with relation to the lower set of small holes in the head?

A. The inside of the upper large rod lies nearly on a line with the end of the head, with the outer edge of the head. And the outer edge of the back lower rod is nearly on a line with the inside of the upper rod. The front lower rod lays about two-thirds outside of the line of the head. And both the lower rods lays on a

line below the lower edge of the head.

Q. 54. If you can make a sketch of the location of the larger rods, with reference to the head and their arrangement with relation to each other, will you please do so? Adding, if you please, the lower line of holes with reference to the two lower large rods?

(Witness makes and produces sketch, which is offered in evidence, and marked "Complainants' Exhibit Miller Sketch.")

A. This is a cross-section taken through the supporting rods, looking down on the face of the lower head of the Busch press, from a

point at the upper end of the press.

Q. 55. I observe that the number and arrangement of the small holes in the upper head of the signature press in the wood cut which has been produced and marked for identification differ from the number and arrangement of the small holes in the corresponding head of the model. Does the wood cut or the model correctly show the number and arrangement of the corresponding holes in the Busch press?

A. The arrangement of the model represents the Busch press, with the exception of the one hole. But the sketch that I have made is a description of the hole in the Busch press. The hole

marked X on the sketch was filled up when I was there.

E. S. B. MILLER.

Affirmed and subscribed before me, this 21st day of Sept., A. D. 1894.

FRANK E. ZIEGLER, Special Examiner.

tch i it

tly ferort

is p a or-

the

the ble ike

urts ress

ossthe

t I

LL:

h a ort ngs rith s of

rge en-

me

Complainants' counsel offer in evidence the paper heretofore marked for identification as "Wood cut of signature press," to be marked "Complainants' Exhibit Wood Cut of Seybold Signature Press."

Also offer in evidence the model testified to by the last witness,

to be marked "Complainants' Exhibit Model No. 1."

Also offer in evidence the printed sheets heretofore marked for identification respectively as "A 15," "A 15*," "B 15" and "B 15*," to be marked respectively "Complainants' Exhibits Printed Sheets A 15, A 15*, B 15 and B 15*,"

JOSHUA W. JONES, a witness on behalf of the complainants, being produced, sworn and examined, deposes and says:

Examined by Mr. Jacobs:

Q. 1. Please state your age, occupation and place of residence?

A. I am sixty-three years old; I have no special occupation at this present time; I served an apprenticeship at bookbinding and have a thorough knowledge of the art of printing, having managed one of the largest printing and binding establishments in central Pennsylvania, and have been interested in the same. I have been also the superintendent of public printing and binding of the State of Pennsylvania nine or ten years. Place of residence, Harrisburg,

Pennsylvania. Q. 2. Are you the same Joshua W. Jones to whom the letters patent here in suit were issued?

A. I am.

33

Q. 3. And one of the complainants in this case?

A. I am.

Q. 4. Have you ever visited the printing establishment of Clarence M. Busch, the defendant in this case?

A. I have.

Q. 5. Where is it and when did you first visit it?

- A. It is located on Herr street, between Third and Sixth streets. Harrisburg, Pa. I first visited it on the 28th day of November, 1893.
- Q. 6. Was any work going on at that time which particularly attracted your attention?

A. Yes, sir.

Q. 7. What was it?

A. It was the folding of sheets and the putting them through a dry press similar to a machine or press for which I have patents. I recognized the press as the Seybold from having seen cut of the same.

Q. 8. Please describe the dry press which you saw there as fully

as you can.

A. I found it was a machine. It was formed of rods, head and foot blocks having cross-ways in them, also large holes in said head and foot blocks through which you could pass the hand and fore-The top head was movable or adjustable by means of a crank, sprocket wheels and drive-chain. The lower or pressing block was moved by means of a screw and three toggle joints. The balance of the machine I did not particularly examine, except I noticed that it was driven by a belt or belts. I don't remember whether there was one or two belts. I also noticed the three adjustable rods, the same as in my machine used for centering the work when smaller or intermediate sizes of sheets, less in size than the trough formed by the large rods, are pressed. I also saw the operator place an end board in the trough of the machine, that is the rods forming the trough. He then proceeded to fill the trough with folded printed sheets—the entire space between the lower and upper blocks—and placed an end board at the top of the pile of sheets

between the sheets and the upper head block, when he put on 31 the power which drove the lower head block towards the upper. He then took a cord, such as comes around the paper from the mill, and proceeded to tie said sheets two ways, that is, cross-ways, crossing them on the ends of the bundles. This was done by taking the cord, which had a loop in one end and which was held in one hand, and the cord pushed by the hand and forearm through the opening in one of the heads, taken by the other hand and carried to the other head and in like manner pushed through the other hole in the other head, the cord then slipped through the loop on the end, the cord then brought through the large hole and passed over the bundle and through the large hole in the other block, then brought down to the other block and passed in the large opening and there looped around the cord, which had formed a junction, then tied, and the bundle immediately removed from the press. I saw them fill the press several times and go through the operation several times. The large holes through which passed the hand and forearm correspond with the cross-way openings where the cord ties over the ends of the bundles.

Recess until 2 p. m.

2 P. M.

Examination of Joshua W. Jones continued. Present: Same counsel.

Witness continues his answer to Q. 8:

A. The bundles of sheets were tied while the pressure was on them. The pressure was retained by means of the tie, the bundles removed from the press and set aside to complete the process of dry-pressing; that is, the smoothing of the sheets, and removing the indentations or impressions made in printing. Time becomes the factor in this case. The sheets or signatures were placed with the back folds resting on the two lower small rods, and the head folds against the small top back rod. These rods formed a right-angle trough or guides for placing the printed signatures, and were adjusted to center, or nearly so, the signatures with the cross-ways in the two heads. In running up the lower head these rods pushed up through the upper head in holes in said head. The rods at the lower end were screwed in holes in the lower head.

number of bundles of signatures lying near the press, which had end boards at top and bottom of them and cords around them and tied.

The work I saw done I know was tied under considerable pressure, as I tested it with the blade of a pocket-knife, and it took considerable force to push the point of the blade between the sheets of the bundle which was tied.

Q. 9. Please tell us the size of the boards used there.

A. Six and a half by ten—about. I didn't measure the board, but I know the boards are about six and a half by ten, and made out of about inch stuff, probably about seven-eighth- of an inch thick.

Q. 10. How did the boards compare in size with the folded sheets?

A. About the size of the work or nearly so. The boards had rounded outer edges, made in the same manner as boards that I furnish.

Q. 11. Please state whether or not the boards were included in the bundle when tied up.

A. They were. I think I have stated that.

Q. 12. How were they arranged in the bundle with reference to the folded sheets?

A. They were placed at the top and bottom of a bundle of sheets

one at each end.

Q. 13. In your answer to Q. 8 you speak of the top head being moveable or adjustable by means of a crank, sprocket wheel and drive-chain. Will you please state a little more particularly how the movement of that head was accomplished by the means you have mentioned?

A. I didn't examine that very particularly. I did notice that the three large rods forming the trough had screw-threads cut in them near the top, and probably about half the length between the bottom and top heads. The sprocket wheels, I presume, acted as nuts, they being driven by the drive-chain which was driven by the crank.

Q. 14. What was the condition of the three large rods from the

end of the screw-thread to the lower head?

A. Which end of the screw-thread do you refer to?

Q. 15. In your answer to question 13 you say, "that the three large rods forming the trough had screw-threads cut in them near the top, and probably half the length between the bottom and top heads." What I want to know is what was the condition of those rods the rost of their length between the body in the rost of their length between the rost of thei

rods the rest of their length between the heads?

A. They were smooth, turned or cold-rolled. Q. 16. Was their surface smooth or rough?

(Objected to as leading.)

A. Smooth.

36

Q. 17. How were the large rods arranged in the press with refer-

ence to each other, and with reference to the heads?

A. The two lower large rods were in a line with each other, parallel with the cross-opening across the head, running from back to front, and were on an incline from bottom to top. The large upper

back rod was through the upper back quarters of the heads and was set about an inch and a half back out of line of the lower back rod and acted as guides or slides for the heads and formed a right-angle trough or receptacle for the pressing of large-size work.

Q. 18. Was or was not the arrangement of the large rods such as to permit the placing of sheets in the press without the interposition

of the small rods or any of them?

(Question objected to as leading.)

A. Yes, sir. As I stated before, the large rods will serve for lodging large-sized work, such as folio and quarto sizes. It could, however, only be practically used by running the top head down to or nearly where the screw-threads begin. This for large work, such as folio or quarto sizes, would leave ample space for doing that class of work, as the bundles would be necessarily heavy and unwieldly to handle if they were made larger. Again, in quarto and folio work the signatures are not as thick, consequently it would be much harder to keep them regular by reason of the swell in the folds, which in a large bundle the number of sheets would cause the backs of the sheets to slip up out of line of the rods. This would give space for about the same number of signatures as for octavo or smaller sizes, there being usually only about eight pages to a signature of quarto and four to a folio, whilst an octavo would have sixteen.

Q. 19. If you have made any sketch showing the arrangement of the large rods in the Busch press with relation to each other and to either of the heads, will you please produce it?

A. I did and I have it here.

(Witness produces sketch.)

Q. 20. How does this sketch correspond in size with the Busch press?

A. It is the exact size of the upper head inside of the large rods, as I took it by folding the paper and making a perfect right angle and laid it on the inside face of one of the heads and took an impression of the head by rubbing with the hand.

Q. 21. Will you please letter the various parts of the sketch and

then describe it by reference to the letters?

A. A represents the upper front quarter of the head and foot blocks. B represents the upper back quarter of head and foot blocks. C represents the lower back quarter of the head blocks. D represents the lower front quarter of the head blocks. E represents the cross-ways or openings in the head blocks, where the cord is passed over the boards on the ends of the bundles. G represents the large rods. H represents in the upper head block the holes through which the small adjustible rods pass and corresponding holes in the lower head in which the other end of said rods are screwed. The sketch is full size and measures ten by fourteen and a half, and is large enough to do double the size of the work which I saw being done, which would be a royal quarto printed on twenty-eight by forty-two paper. Even larger work than this could be

done on it, as the pressure exerted over the back and head folds and the printed page would accomplish the work when put through the press and the pressure retained by means of tying. It will be readily seen by this sketch that the two lower rods G form a bed or rest for the back fold of the sheet, and rod G at the top forms a guide for the head fold of the sheet or signature.

(Complainants' counsel offer in evidence the sketch produced by the witness, to be marked "Complainants' Exhibit Jones Sketch.")

Q. 22. When you took the impression by which this sketch was made were the small rods in the machine?

A. I had them removed by the operator.

Q. 23. Please tell us now whether any machines made under your letters patent, No. 204,741, have been introduced into use, and if so, to what extent?

A. I have had a good many of these machines manufactured, as to the number, I am not prepared now to give it to you. I sold to the United States Government Printing Office fourteen or more.

They are in some of our largest printing and binding establishments of the United States, such as Theodore L. De Vinne

& Company, printers of the Scribner, now Century Magazine; Harper Brothers, A. S. Barnes, Green's, and a number of others of New York city; Houghton & Mifflin, Riverside press, Cambridge, Mass., and a number of printers and binders in the city of Boston, and some printers and binders at Cincinnati, St. Louis, Chicago, Akron, Ohio, Rochester, N. Y., and other cities of the United States. I can't recall all. I have sold some in England, Canada, Holland and the Dutch government in Batavia. I never kept special books in regard to the sales of these machines, as every transaction would close itself. It was not like running accounts. This was prior to the time when I licensed or contracted with the W. O. Hickok Manufacturing Company, giving them the sole right to manufacture and sell my machines. I have with the sale of each machine accompanied the same with a license to use said machine and the process of dry-pressing as set forth in claim five of said letters patent. I have a blank copy of the form of said license with me and offer this as evidence.

(Witness produces two papers, which are fastened together, and are offered in evidence by complainants' counsel to be marked "Complainants' Exhibit Jones Form of License."

The offering in evidence of the papers just referred to is objected to as being incompetent, irrelevant and immaterial to the issue in

controversy.)

Witness continues: I would further state that these licenses are furnished without additional cost of the price of the machine to the purchaser. I merely insert the nominal sum of one dollar consideration.

Q. 24. Where were the machines, to which you refer in your last answer as sold in foreign countries, manufactured?

A. They were manufactured in Harrisburg, by W. O. Hickok

Some of them were manufactured by the W. O. Hickok Manufacturing Co.

Q. 25. On whose account?

A. On my account. You are speaking of the foreign.

Q. 26. Since your contract with the W.O. Hickok Manufacturing Company, making it your sole licensee to manufacture and sell, have any of your machines been made and sold under said letters

patent?

A. Yes, sir. The W. O. Hickok Manufacturing Company has manufactured and sold quite a number of these machines; as to how many, I am not prepared to give the number. I know that I have issued quite a number of licenses and at various times have had settlements with them for machines sold. You will notice that I speak of these presses as machines. This is from habit.

Q. 27. Have you or not issued any licenses to use the process of dry-pressing claimed in the fifth claim of your letters patent, No. 204,741, upon any other machine or press than those manufactured and sold under your said letters by yourself or the W. O. Hickok

Manufacturing Company?

A. I think I have. I own the patent of Russell A. Hart, of Battle Creek, Michigan, and letters patent No. 394,977, dated December 30, 1888, were assigned to me by the said Russell A. Hart, February 18, 1890. He also transferred to me a number of his machines or presses. I had a case against him for infringement and the assignment of the letters patent and the surrender of the machines he had on hand were a part of the compromise of the case. Some of those machines have since been sold by the W. O. Hickok Manufacturing Company, and for which I issued licenses to use the process. Two of the machines were complete; others were in parts and were completed by the W. O. Hickok Manufacturing Company. I think there were about nine complete and incomplete, that is, in parts not put together.

Q. 28. Apart from these Hart machines, have you issued any licenses for the use of your process upon any other machines than

your own?

A. No, sir.

Adjourned to September 22d, 9 o'clock a. m.

SEPT. 22D—9 o'clock a. m.

Met pursuant to adjournment.

Present: Same counsel.

Examination of Joshua W. Jones continued.

Cross-examined by Mr. Hill:

X Q. 29. From your first answer I would infer that you have had considerable experience in the art of printing and bookbinding. Is this correct?

40 A. Yes, sir.

X Q. 30. When and where did you serve your apprenticeship? A. In Harrisburg; with W. O. Hickok, about from 1845 to 1851 X Q. 31. Where were you engaged and in what capacity after the latter date mentioned by you?

A. I was engaged in Richmond, Va., and Harrisburg. Those

were the only two places.

X Q. 32. How long were you with W. O. Hickok subsequent to 1851.

A. I was engaged with him in the fall of 1844 as an errand boy, and was with him continuous until after I finished my apprenticeship. I may say that when I first went there the firm consisted of Hickok and Cantine, printers, bookbinders and booksellers.

X Q. 33. Did you serve your apprenticeship as a printer or as a

bookbinder, or both?

A. I was bound apprentice to learn the art of bookbinding.

X Q. 34. Where were you engaged during the years from 1851 to 1860?

A. When I left the employment of W. O. Hickok I was engaged with Fenn and Sedgwick, State printers, Harrisburg.

X Q. 35. How long did you remain with them?

A. I can't just say, probably not very long, as I went to Richmond, Va., and was employed by Ritchie and Donavant, State printers of Virginia. On my return home, on a visit, Mr. A. Boyd Hamilton had obtained the contract for public printing of the State of Pennsylvania, and he prevailed upon me to enter into his employment as a foreman, and I have been continuously engaged on the public printing and binding under the various contractors in the capacities of foreman and general manager up to the year 1874. In July, 1874, I was appointed by Governor Hartranft superintendent of public printing. I was reappointed March, 1875. Again reappointed March, 1876. Again reappointed March, 1876, for the term of four years. I was again appointed in 1881, by Governor Hoyt, for the term of four years. I served up to August, 1883, when I resigned. I have not been in the printing or binding business since that time.

41 X Q. 36. In your first answer you speak of having managed one of the largest printing and binding establishments

in central Pennsylvania. To whom did you refer?

A. I have reference to the Singerly printing and binding establishment, in the city of Harrisburg.

X Q. 37. During what years were you with this latter establish-

ment?

A. I first engaged with Singerly and Meyers, State printers, in 1861. After the death of Mr. Meyers, Mr. Benjamin Singerly became the sole proprietor. I continued with him until his death in 1876. Part of that time I was a partner with him in private work, such as printing and binding Λ. H. English and Company's school books, and also in the publishing of the State Journal, a newspaper published in the city of Harrisburg.

X Q. 38. During the time you served your apprenticeship with W. O. Hickok, what means, if any, was employed for removing in-

dentations or impressions on printed matter?

(Objected to as not proper cross-examination.)

A. The sheets were taken after being printed and dried. The drying was done by laying them over a peel and hung up on poles near the ceiling of the room. They were then taken to a table and laid out flat, averaging from one to six sheets, and were laid between fuller or glazed boards alternately. They were then laid into a large screw-press in bunches about an inch and a half or two inches in thickness and then a cherry board was placed on them and so on alternately until the press was filled, when an old German would call downstairs "Boys, come schrewff die press," when the entire force, consisting probably of eight or ten persons, would go upstairs and put on the pressure by means of a long iron lever, onehalf the number on one side the lever pulling, the other half on the opposite side of the lever pushing. The sheets were then allowed to remain in the press over night and the press emptied the next morning in the same manner as it had been filled, that is, the sheets and fuller or glazed boards were piled up on a table and the operators proceeded to take out the flat-pressed sheets, laying them to one side the pile and laying the boards off on another pile. was all done before the folding of the sheets. 12

X Q. 39. What function did the fuller-boards perform in

the operation just described by you?

(Same objection.

In view of the fact that this witness in his direct examination testified as to his having served an apprenticeship, and having a thorough knowledge of the art of printing and bookbinding, it is submitted that the foregoing questions are perfectly proper and

legitimate.

Counsel for complainants call attention to the fact that this witness was not asked and did not testify, on his direct examination, concerning the state of the art prior to the date of his patent, and suggests that the matter now inquired about should come at a later stage of the case and be shown by the testimony of witnesses called by the defendant, if it is deemed important as a matter of defence. and is therefore not proper cross-examination.

Counsel for defendant call attention to the fact that this witness, in his direct examination, has referred to his letters patent No. 204,741 in suit, and as said patent purports to contain improvements over the prior state of the art, it is submitted that it is perfectly proper that this witness, being the patentee and inventor, should testify as to what his knowledge of the art was at the time he pro-

duced his alleged invention.)

A. The fuller-boards, probably more commonly known in the trade as glazed boards—they being a board about the thickness of a heavy card-board, and are made out of some very hard fibre and being a hard board with a finished surface—they act as a hard substance placed between two rough, soft, yielding substances, and the sheets being placed from one to six between said boards, it gives a comparatively solid surface interposed between the yielding surface

of the sheet, whereby by using pressure and allowing that pressure to remain continuously on the sheets and boards while in press from twelve to twenty-four hours, it smooths out the indentations or impressions made by printing on the sheets.

X Q. 40. In your direct examination and in your letters patent, No. 204,741, you have used the expression "dry press" and also "dry-pressing." Please explain what we are to understand by those

expressions.

A. One is the machine on which the initiatory work is The other is the fact of removing the indentations made by type; in other words, the impressions made on paper in printing, giving a smooth and even surface to the sheet; in other words, smoothing the sheets.

X Q. 41. In the art of bookbinding is there any such process to

your knowledge as "wet-pressing"?

(Objected to as irrelevant, immaterial, and not proper cross-examination.)

A. No.

X Q. 42. In answer seven you speak of the Busch press as being similar to one for which you have patents. How many patents have you on your press?

A. I have a number, but I can't just recall how many.

X Q. 43. Have you patents on said press, other than those set up in this issue, and if so, about how many?

(Objected to as irrelevant, immaterial, and not proper cross-examination.)

A. I have other patents, but, as I said before, I can't say how

many, without going and making an examination.

X Q. 44. In answer twenty-three you mention the names of several parties to whom you sold presses, made under your letters patent, No. 204,741. Were all of said presses constructed as shown in Fig. 1 of said patent, and as described in the specifications?

A. Substantially so, with other improvements added. Some were

screw and others were hydraulic power.

X Q. 45. Did vou furnish "a bulk compresser device" in connection with each machine sold by you?

A. I did not.

X Q. 46. In answer eight you speak of having seen an operator compress and tie several bundles of paper on the Busch patent. Upon what did said papers rest during the process of compressing and tying the bundles on said press?

A. The sheets which I saw being operated upon were about six and a half by ten inches when folded. It was necessary, to center that size with the cross-ways of the press, to rest them on the re-

movable small rods, and so I saw it done.

X Q. 47. Did you see any papers compressed and tied in the Busch press with said papers resting upon the large rods which support the head?

44 A. I did not.

X Q. 48. What are the dimensions of folio and quarto sizes,

respectively, when folded?

A. There was a time when the papers were made of regular dimensions or sizes. They were regular sizes, such as 24 x 36, 28 x 42, and so on. This is somewhat changed, as paper is now made of any size the printers or publishers wish to have it. The terms octavo, quarto and folio have to a certain extent been dropped. What I mean is approximately on a basis thus: A sheet 24 x 36 printed on both sides of sixteen-page work makes two signatures. This folded three times makes an octavo size. A quarto, taking the same sheet and printing eight pages on two sides, makes two signatures. This sheet cut in half and folded twice is a quarto. The same size sheet printed on four pages, both sides, makes two signatures. This sheet when cut in half and folded is a folio.

X Q. 49. In a sheet of the dimensions given by you what would be the size of the signatures when folded which you have men-

tioned?

A. Octavo would be 6 x 9; quarto, 9 x 12; and folio would be

12 x 18.

X Q. 50. In compressing a bundle of printed sheets on the Busch press which you saw, might not the edges of the signatures project out some distance from the small rods and yet produce a perfectly compressed bundle?

A. I do not understand the question.

X Q. 51. To assist you to understand my question, I will call your attention to the model marked "Complainants' Exhibit Model No. 1," and will ask you whether or not bundles of paper might not be compressed on the Busch press, said papers resting on the small rods, their outer edges projecting outward some distance beyond the lower outer small rod?

A. You mean by that the head and foot of the sheet. Yes, such is the practice of pressing all sizes less than the full size of the trough formed by the rods. The object of the small rods is to form a lodging for the back and head of the sheets and to get them even on the back and head, the rods forming a rest and guide. When large work is used which will centre or nearly so without the use of the small rods they can be dispensed with and the large rods can

be used for resting the sheets and as guides.

X Q. 52. I now call your attention to the sketch made by you and marked "Complainants' Exhibit Jones Sketch"—which you say represents the exact size of one of the heads in the Busch press,—and the number and location of the openings therein for the small rods which support the printed matter, and will ask you whether or not printed signatures might not be compressed on said press and having their outer edge projecting out some distance over the large rod G shown in the right hand of your sketch, the small rods being placed in the openings which I have designated in red ink by X, the papers resting on said small rods.

A. Will you please mark the rod G that you refer to with red

ink?

X Q. 53. I will, and I have marked it G².

A. Provided the end board were of the size of the sheet and of sufficient rigidity I think it might be done, but this would bring the tie out of centre and would in time make a very awkward bundle to handle, as to my mind it would retain the pressure lopsided.

X Q. 54. If the signatures were sufficiently large would not the

same disadvantage arise if placed upon the large rods G?

A. Yes, but not so much so having the same size sheet.

X Q. 55. I will now call your attention to your letters patent No. 204,741 and will ask you what would be the result if an operator, through forgetfulness or carelessness should leave a bundle in the press over night under pressure and tied. Would the printed signatures be damaged or injured in any way through this caretessness or forgetfulness?

(Objected to as not proper cross-examination.)

A. I think not.

1894.

X Q. 56. Is the press shown in your letters patent No. 204,741 capable of bundling and tying papers other than folded printed signatures?

(Objected to as not proper cross-examination, for the reason that the question is directed to matters not asked about or testified to on direct examination and because it is apparently an attempt to introduce matters of defence into complainants' prima facie case, and because, if not so intended, the matter sought to be brought out is

irrelevant and immaterial.

46 Counsel for defendant would state that the witness in his direct examination has referred to said letters patent and the invention therein set forth purports to be an invention for removing indentations from printed matter, the object of the question was to ascertain from the witness whether it was necessary for the success-

ful operation of his press that the sheets should be folded.

Counsel for complainants call attention to the fact that the witness on the stand was not asked to construe the letters patent in suit, but was called for two purposes, first, to testify to what he saw in defendant's establishment; and, second, to state the extent to which his invention had been put on sale and introduced into public use and that therefore the object of the question being as counsel for defendant has just stated it, the question is incompetent.)

A. It was not so intended. The limits of its capability I am not prepared to say.

JOSHUA W. JONES.

Sworn and subscribed before me, this 22d day of Sept., A. D.

FRANK E. ZIEGLER, Special Examiner. T. J. W. Robertson, a witness on behalf of complainants, being produced, sworn and examined, deposes and says:

Q. 1. State your age, occupation and place of residence.

Λ. 61. Patent solicitor and mechanical expert, Washington, D. C.

- (It is agreed by counsel for complainants and defendant that the witness is competent to testify as an expert witness in patent matters.)
- Q. 2. If, in addition to your general qualifications to testify as an expert witness in patent matters, you have any special qualification to testify as an expert witness in cases specially involving the art of printing, will you please state what it is?

A. In my younger days I followed the trade of a journeyman printer, during which time I familiarized myself somewhat with the business of bookbinding, it being often carried on in the same build-

ing and frequently in the same room with the type setting and letter-press printing, which last two were my particular branches of the printing business. I have at the present time a small printing office as an adjunct to my office in Washington, where blanks, cards and other matters are printed for my office use.

Q. 3. Have you examined and do you understand United States letters patent No. 204,741, granted to Joshua W. Jones, for "improvement in bookbinders' dry press and sheet tie," and introduced in evidence in this case as "Complainants' Exhibit Jones Patent No. 204,741"?

A. I have carefully examined it and I believe I do.

Q. 4. Will you now turn to said letters patent and state what you understand said improvement to be, as therein described and claimed, limiting yourself as far as possible to that part of the same covered by claims 1, 2, 4 and 5?

A. The invention described in said patent and illustrated in the drawings and covered by the claims referred to in the question is a process for treating folded printed sheets, whereby the impressions made in the letter-press printing process are flattened out, so that the paper will resume its original smoothness, or substantially so, which process is carried out in such a manner that the operator can be continually putting in the signatures or printed matter and removing them in tied-up bundles, whereby with one press a much larger number of signatures can be pressed and at a very much reduced cost for labor over that of the process previously employed. The improvement also consists in a means for carrying out this process, which means is shown in the drawing and more particularly in that part which is shown to the left hand of Fig. 1 and details in Fig. 3 and 4. Previous to the invention of Mr. Jones as described in said patent it was the custom to press printed sheets by inserting them between heavy paper boards, sometimes called "fuller-boards, but generally now called "glazed boards," and putting said boards with the printed papers between them into a powerful press, by which pressure was produced on said boards by various means,

to

he

or, he ig-

41 ig-

at on ois

is ie ig to is-

ss at dis d-

),

of

sometimes by means of screw pressure, sometimes by hydrauli pressure. After the pressure was produced on the paper it was continued by allowing the press to remain with its pressure on to it fullest extent for ten or twelve hours or more, say from one night to the next morning, when the pressure was removed, the

papers and boards taken from the press and separated by 48 removing the boards from the pile of combined boards and paper, and putting the boards on one side on one pile and making another pile of the printed papers. This was necessarily compara tively a slow process, inasmuch as with one press only as much printed paper as the press would hold when put between the board could be pressed in about ten or twelve hours, so that where much work had to be done a number of such presses were necessary. I was also costly as to labor, because the sheets had to be placed be tween the boards and removed therefrom afterwards, which tool much time, especially where, as in the case of fine work, only on sheet was placed between two boards; and when this was doncomparatively few sheets could be pressed at once because the board took up much more room than the paper did, they being quite thick.

By the process set forth in the patent the printed sheets are no allowed to remain in the press for any considerable length of time but only long enough for the operator to tie up the bundle, when they are immediately removed, the entire process of putting the paper into the press, tying it up in the bundle and removing i therefrom taking but a few minutes.

D

Recess until 2 o'clock p. m.

Sерт. 22b—2 o'clock р. m.

Examination of T. J. W. Robertson resumed by Mr. Jacobs

Witness continues his answer to Q. 4.

As the entire operation, so far as the use of the press is concerned only takes but a few minutes, which may be from two to five for each bundle, a large number of bundles may be pressed and tied up in the course of a day, and left tied up between the boards with the pressure upon them as long as is thought necessary to smooth out the impression produced by the printing press, or until the signatures may be wanted by the binder to complete the operation of making the book for which the signatures are printed. The printed paper or signatures are thus allowed to remain for a considerable time tied up in bundles, which time may be from twenty-four hours to three or four days, but may extend to a year or more, the longer the better, as it is upon the time in which the bundles remain tied up subject to pressure between the boards that

the smoothness of the printed paper depends, the mere pressure produced by the press in the short time the paper remains in it having comparatively little effect upon the impression produced by the printing press. The pressure of the press and the mere tying up would produce but little effect if the signatures were immediately untied as soon as they were removed from the press

and the long-continued pressure after the bundle has left the press is therefore an essential part of the process, and without which it would not be much of a success. There is one important difference between the old process and the new that I think has much to do with the success of the process set forth in the Jones patent, No. 204.741. In the old plan where two or more sheets were set between boards the convex side of the impression on one sheet came in contact with the concave side of the sheet above it, so that these sheets would have little or no effect upon each other in smoothing out the impressions produced by the printing press, and especially would this be the case where half a dozen or more sheets were placed between two boards. In the new process described in the Jones patent under consideration, the sheets when folded have the convex impression of one-half of a sheet brought in contact with the convex side of the other half of the sheet by the act of folding the sheet in two, provided the sheet when being folded had its convex side of the impression uppermost. If, on the contrary, the concave side of the impression were uppermost, the concave part of the sheet would be folded together, but on the second fold the convex sides would come together in the center of the fold, so that under any circumstances the convex part of the impression on one sheet would be pressed by or come in contact with the convex impression on the same sheet, or with the convex impression of another sheet coming next to it, and thus the convex impressions coming in contact with each other tend, when under pressure, to efface each other, and, as I believe I said before, the longer the pressure is continued by keeping the bundles tied up, the more the impression is effaced and the smoother the paper becomes, so that I regard it as important that, if the process is to be carried out successfully, the paper should be

folded so that the convex impressions should come in contact with other convex impressions, and that the bundles of the signatures when tied up should remain for a considerable period of time in the tied-up condition under the pressure imparted

to them by the press.

I have given at some length what I consider the main features of difference between the old and new processes, because in my opinion the process is one that is not easily understood at first, and very few would be likely to understand it unless the essential differences

between it and the old process were pointed out.

I will now proceed to refer to the claims of the patent, but before doing so I would premise that there are certain features in the drawing which form no part of the claims under controversy. I refer more particularly to that part of Fig. 1 in the drawing which is to the right hand of said figure, and is called a "bulk compressor," this part not being necessary to the carrying out of the invention, although it would be a convenience to use it. Referring to the first claim of the patent I find it to be as follows:

"1. In a printer's and bookbinder's dry press and sheet-tie, the compressing heads C D D' and B² F' F, constructed with cross-ways L² L², centrally arranged through them, substantially as and for

the purposes herein set forth."

This claim has a special reference to the parts between which the signatures are held and tied and is intended to cover compressing heads having cross-ways centrally through them, so arranged that the operator can readily tie the bundle of signatures by inserting his arm through to catch and pass the tie through the heads.

The second claim is as follows:

"2. The inclined press bed, H H², provided with longitudinal slots, H¹ H¹, in its sides, in combination with the press heads, B² F' F and C D D', having through them the cross-ways, L² L², correspondingly arranged with said slots, substantially as and for the purpose set forth."

This claim in my opinion covers an inclined press bed, provided with openings in its sides, combined with the press heads covered in claim 1, whereby a series of signatures can be placed in the bed

without danger of the falling over of said signatures before 51 the press is put into operation, and the signatures conveniently tied up in a bundle after the pressure has been produced upon them and held under such pressure.

The fourth claim is as follows:

"4. In combination with the dry-press bed, II H2, the device of a set of removal ledges f, or a set of adjustable guide-rods, m, ar-

ranged as and for the purpose set forth."

This claim in my opinion covers the combination of a dry-press bed with devices intended to be used as a support for signatures of smaller size than those which the press is capable of pressing when such devices are not used. These devices are shown in two forms, one of which is shown best in Fig. 4, and are indicated by the letter f. These are strips which are set into grooves in the press bed, forming ledges on which the signatures would rest instead of resting on the press bed itself, as they would, if the ledges were not there. The other form of this device is shown best in Fig. 1, where it is indicated by the letter m, and consists of rods which pass through holes in the head indicated by the letter V in Fig. 4. These two parts are substantially equivalent to each other and either can be used for the purpose of supporting the signatures with equal facility.

The fifth claim is as follows:

"5. The process herein described for treating folded printed sheets of paper in dry-pressing, the same consisting of subjecting a collection of such sheets to pressure without the use of fuller-boards, and while under such pressure tying them into compact bundles with end boards, then removing them immediately from the press, and allowing them to remain tied sufficiently long

to fix and complete dry-pressing."

I have heretofore in the first part of this answer, set forth at considerable length in what this process consists, but I may sum it up by saying that it covers the process of pressing folded sheets or signatures by first subjecting them to pressure, then tying them between boards in a compact bundle and removing them from the press and allowing them to remain tied a sufficient length of time to efface the impressions produced by printing.

Q. 5. Have you examined the model offered in evidence in this case as "Complainants' Exhibit Model No. 1," and do you understand it?

A. I have and do.

Q. 6. Have you also examined Complainants' Exhibits "Wood Cut of Seybold Signature Press," "Miller Sketch," and "Jones Sketch," and do you understand them?

A. I have examined them and I believe I understand them all.

Q. 7. Assuming a machine made like the model and having operative mechanism for moving the lower and upper heads, such as is shown in Exhibit "Wood Cut of Seybold Signature Press," and having its three large rods arranged with reference to each other and the two heads as shown in Complainants' Exhibit "Jones Sketch," would you understand the designed operation and use of such a machine?

A. I should and I do.

53

Q. 8. Will you now compare Complainants' Exhibit "Model No. 1," assuming the operative mechanism and the arrangement of the large rods, as stated in my last question, with the Jones letters patent, No. 204,741, pointing out any resemblances or similarities you may discover and stating whether or not the invention set forth in said patent and covered by claims Nos. 1, 2, and 4, or either of them, is embodied in such machine, giving, if you please, at length your

reasons for your opinions upon the subject?

A. I have compared the model with the first claim of said patent and considering it to be as you mentioned, and find such claim to be embodied in said model. Said claim, as I have before stated, covers compressing heads having cross-ways centrally arranged through them, so arranged that the operator can readily tie the bundles of signatures by inserting his arm through them to catch and pass the tie through the head. These heads are shown in the Jones patent as composed of different parts, as clearly shown in Fig. 3, which represents the moveable head. Each of said heads, as shown in the figure referred to, consists of a square base carrying pedestals which are indicated by the letter D, on which are secured sections of the moveable head which are indicated by the letter D'. These parts marked D' form the acting face of the heads, that is, they come in contact with the boards used at each end of the . bundle of signatures and press upon the same. These various parts of the head C D' and D form in effect one solid piece

with cross-shaped openings in the face and large openings back of the face adapted to receive the arm of the operator. On examining the model I find that the heads there shown are made to represent one piece for each head, but they are to all intents and purposes practically the same as the heads shown in the Jones patent so far as the first claim thereof is concerned. The face of the blocks in the model correspond to the parts marked D' in Fig. 3, and the back of the blocks correspond to the part marked C in the same figure, while the small parts between the face and the back correspond to the pedestals marked D in said figure, 36 are, therefore, practically the same as the heads claimed in the first

claim and perform the same function in substantially the same way as the heads set forth in the Jones patent, No. 204,741, and covered by the first claim thereof. Referring to the second claim I find a difference in construction between the inclined bed shown by the Jones patent and the inclined bed shown in the model. and function of the bed in the Jones patent is to support the heads and the signatures to be pressed, and to form guides for the same. but the claim is limited to such a construction as will admit of not only those functions being performed, but it must admit of the tying of the bundles when pressed. This is accomplished in the Jones apparatus by slots cut in the sides of the bed, while in the model before me the bed is formed of stiff rods which can be used for the same function as the bed of the Jones press. I do not regard this difference as essential, inasmuch as it is simply a question of how much metal should be employed in the bed. In the Jones bed there is a narrow opening or slot between the parts forming the side of the bed, while in the model there is a large opening. This is merely a question of convenience for the maker. I should imagine that the model or press from which the drawing of the Jones press was made had a wooden bed and it was therefore more convenient to make it with a slot instead of the open space shown in the model, in which the round rods forming the bed of the press, I understand, represent iron. In view of this and what I before stated as to the heads of said model I am clearly of the opinion that the second claim of said patent is embodied in the model under consideration, assuming it to be of the form indicated by the Jones

sketch. As to the fourth claim, which covers "the device of a set of removable ledges" or "a set of adjustable guiderods," I find the latter plainly embodied in the small round rods in said model, and the other element of the claim, the press bed, that is, as I before stated, found in the large rods which support the heads. In view of this I am of the opinion that both elements of the fourth claim of the Jones patent under consideration are substantially found in the model referred to in the question.

Adjourned to Sept. 24th, at 9 o'clock a. m.

SEPT. 24тн, 1894—9 o'clock a. m.

Met pursuant to adjournment. Present: Same counsel.

Examination of T. J. W. Robertson resumed by Mr. Jacobs:

Q. 9. Were you present here during the taking of the testimony of William Hayes Grier, E. S. B. Miller and Joshua W. Jones, witnesses called by the complainants in this suit, and did you hear them testify?

A. I was and I did.

Q. 10. I now call your attention to the testimony of William Hayes Grier, beginning with answer to Q. 11 and ending with answer to Q. 18, that of E. S. B. Miller, beginning with answer to Q. 22 and ending with answer to Q. 35, and that of Joshua W. Jones, begin-

ning with answer to Q. 8 and ending with answer to Q. 12, and ask you to compare the process therein described with the process described and claimed in the Jones patent, No. 204,741, to point out any similarities and differences between the two which you may discover, and to state whether or not the process described by said witnesses is covered by the fifth claim of said patent, giving your reasons for any opinion you may express at such length as you may deem proper for a clear understanding of the matter.

A. I have carefully considered the testimony which I heard given by the said witnesses and have read their testimony, at least so much thereof as is referred to in the questions you have mentioned, and am clearly of the opinion that the process of dry-pressing described by said witnesses is covered by the fifth claim of the Jones patent

referred to in the question. I find that in the process described by the witnesses and in that set forth in the patent 55 and in the fifth claim thereof, the collection of folded sheets is put into the press with end boards at each end of the collection or bundle and pressure is produced on said sheets by the operation of the press; that while the bundle of signatures or folded sheets is still under pressure it is securely tied into a compact bundle with the end boards still on the bundle, after which it is removed immediately from the press and allowed to remain tied sufficiently long to fix and complete the dry-pressing. The process described by the witnesses and the process set forth in the patent are therefore in my opinion identical. The fact that the presses employed are of different construction makes no difference so far as the process itself is concerned, for the process is not limited to the use of any particular kind of press, but even if it were, the two presses are very similar in mechanical construction, if the equivalency of the parts are considered. In each case there is a trough or bed provided with openings in its sides and set in an inclined position, having heads with cross-ways in them to enable the operator to readily tie the bundle when pressed, and end boards are employed which are interposed between the bundles of signatures and the press heads, and a screw is employed to produce the pressure, so that mechanically considered there is not much difference between the presses employed in both processes; that is to say, the process of pressing the signatures as described by the witnesses referred to in your question and that set forth in the patent in the fifth claim thereof.

In my previous testimony in this case I referred to the end boards, but do not think I have dwelt sufficiently upon their importance to the success of the process, as such end boards are very important. If there were no end boards the pressing would be very imperfect, inasmuch as the bundle would become round at the ends after it was removed from the press and thus there would not be so much pressure at such rounded parts. Moreover the cross-openings in the heads would produce corresponding marks on the end sheets. It is therefore important that such end boards should be employed in the process of dry-pressing and that they should be tolerably smooth

and of an even surface on their acting faces.

Q. 11. What function, if any, is performed by the end boards in

the process of dry-pressing?

56 A. They serve in the first instance to transfer the pressure of the press to the signatures, and afterwards serve to prevent the cords with which the bundle is tied from injuring the end sheets of the bundle; but their main function is to retain the signatures under the pressure imparted to them by the press, whereby the impression produced by the printing press is effaced. They also serve to some extent as a protection to the end sheets in carrying the bundles from place to place and whilst the bundles are stored away.

Q. 12. Has the fact of the end boards being of substantially the same size as that of the folded signatures anything to do with the

performance of their function?

A. It has, for if they were not of substantially as large a size as the folded signatures the marks of their edges would be left on the sheets at the end of the press, and the projecting edges of the sheets would be damaged by the cords.

Q. 13. What I am trying to get at is whether or not the end boards have anything to do with the distribution of the pressure over the sheets in the bundle, and if so, whether that is a matter of

any importance in the matter of dry-pressing?

A. The end boards do have to do with the distribution of the pressure over the sheets in the bundle, and I find it stated so in the specification of the patent, where it is stated, referring to the end boards, "They are used on the ends of the bundle of the paper under treatment to distribute the pressure over the whole area of the ends of the bundle, and also to prevent cutting or marring of the paper by the twine or other tving material. Said end boards are made of any suitable material affording strength and rigidity at little cost, and of suitable size to nearly match the size of the folded work." I fully agree with this statement of the functions, as I consider they do distribute the pressure over the whole area of the ends of the bundle, which is an important feature in the process of dry-pressing, and is necessary in doing perfect work.

Q. 14. In your answer to Q. 4, near the end of the third paragraph thereof, you say that you "regard it as important that, if the process is to be carried out successfully the paper should be so folded that the convex impression would come in contact with other convex

impressions." Will you please state what is the fact in the 57 usual operation of printing and folding with respect to bringing the faces of the paper against each other?

(Question objected to as involving a process in the art of folding printed matter which is not involved in the process in issue.)

A. In my answer referred to in the question, I dwelt considerably on this point, because I considered it important to point out the differences between the old and new processes. In the usual operation of printing sheets and folding the same with which I am well acquainted, the convex impression always comes in contact with other convex impressions, either wholly or in part, in each sheet, and when the folded signatures are set in a bundle in the press in

the manner described in the patent the convex impressions act upon each other. It may happen, however, that if the convex side of the impression is underneath that on the first fold the concave sides will come together, but with the second fold the convex sides will again come together between the second fold.

Cross-examination by Mr. Hill:

X Q. 15. To what extent did you familiarize yourself with the

business of bookbinding?

A. I merely observed the processes carried on during the time that I was engaged in the printing business. I never actively engaged in bookbinding, except to occasionally repair the binding of books of my own, or books that I had bought in bad condition.

X Q. 16. During what years were you engaged in the printing business and what class of work was done by you while engaged in

that business?

A. I first began my practice in the art of printing in London, England, about 1850, after which I came to New York, worked for a time in a book office there, after that I went to Staten island, where I practiced all parts of the printing business and did a little of everything in that line. It was a small country printing office, where the running of a country newspaper was combined with job printing, book-selling and the running of a country post-office, in all of which I took my share of the work, but especially the printing part, where I filled the offices, as occasion required, of printer's devil, roller boy, pressman, reporter, editor, folder and carrier of the

papers after they were printed. After working there a year and a half or two years I again went to New York, where I

worked in various offices, among others, in the Tribune building, at the office of Baker and Godwin, which was then one of the finest offices of that day, where all kinds of work was done connected with the printing business; after that I was foreman of the New York Ledger, and in 1853 I went down to Washington, where I worked on the Congressional Globe, the precursor of the Congressional Record of today; shortly after that I returned to New York, where I worked on a magazine called the People's Journal, also on the New York Herald and the Scientific American; and about this time I became interested in sewing machines and dropped the printing business for a time, but occasionally did a little work. The last time I worked as a journeyman printer was in 1862.

X Q. 17. It was during the period, then, from 1850 to 1862, that you had occasion to observe the processes carried on in the art of

bookbinding, was it?

A. It was.

X Q. 18. During that time it was customary, was it not, to remove indentations from printed matter?

A. It was.

X Q. 19. Please state the various means employed during that time for this purpose, as observed by you.

A. The only processes that I ever observed were substantially that described by the witness Jones, namely, the insertion of the

printed sheets, generally one at a time, between boards, such as described by him, setting a bundle of such combined paper and boards into a press, producing pressure on such bundle by means of a screw or hydraulic power, and allowing the pressure to remain on the paper in the press for a lengthy period of ten or twelve hours or so and then removing the bundle from the press and separating the paper from the boards. That was the only process I remember to have witnessed, but I knew from information of others that papers were sometimes pressed to remove indentations previously produced by printing by subjecting said papers to a process called hot-pressing, but with the details of such process I was not acquainted.

X Q. 20. Did you ever observe more than one sheet having been placed between the boards in the process just described by you?

A. It was usually the practice to set in one sheet at a time, especially where fine work was done, but occasionally more than one was set in, where there was a great hurry and the work was not of the finest quality.

X Q. 21. What became of the sheets subsequent to being pressed and prior to being bound into book form, during this period from

1850 to 1862?

A. They were usually folded ready for the binder, carried to the binders' tables, where they were sewed and bound, if they were for book work.

X Q. 22. Did you ever observe any of said folded sheets tied to-

gether in the form of a bundle after having been pressed?

A. I have seen them tied, but not very often.

X Q. 23. Did you ever see any one tying them into bundle form?

A. I can't call to mind now any instance of seeing the bundles

being tied up, but I may have done so.

X Q. 24. In the bundles of folded printed sheets, which you say you have seen tied, were the ends of said bundles protected by means of stiff card-board, or other kind of board, to protect the paper from

the action of the string used in tying the bundles?

A. My impression is at this time that there were, on each side edge, pieces of thin pasteboard bent over the sides at the corners of the two opposite side edges, at about the center of said side edges, where the tving cords passed around the bundle, which was done only at that place, that is, crosswise of the folded sheet and not lengthwise, the object being simply to keep the bundle of sheets together, or for convenience for transporting them from one part of the building to another, and not with the intention of producing any pressure upon them to efface the impressions, as such impressions had already been removed by the action of the hydraulic or screw press before referred to in the previous answer.

X Q. 25. Are you positive you never saw such bundles tied and provided with card-board extending entirely over the two ends of

the bundles?

A. I should not like to say at this distance of time that I never have, but I have no recollection of it.

60 X Q. 26. Did you ever have occasion to observe any such bundles of folded printed matter from 1862 to 1874?

A. No, sir.

X Q. 27. So far as you know, was the process described in your former answer 19 successful for the purpose of removing indentations from printed matter?

A. It was.

X Q. 28. From your previous description of the invention set forth in the Jones patent, No. 204,741, I infer that in your opinion the primary feature of the invention therein set forth consists of the process as claimed for the bundling and tying of printed sheets, for the purpose of removing the indentations therefrom. Is this correct?

A. I consider the process set forth in the fifth claim as the primary

feature of the invention disclosed in said patent.

X Q. 29. You will please explain more fully what we are to understand you to mean by the expression "concave" and "convex" side of a printed sheet, which terms you have frequently used in your

direct testimony?

A. I used the words "concave" and "convex" in connection with the impression and not with the sheet itself, at least that was my intention, although I may have used it in the latter connection. By "concave" I meant the hollow or sunken impressions produced by the pressure of the type, when the sheet was going through the printing operation, and by "convex" I meant the raised surface produced by the same operation; one side of the sheet, to wit, that with which the type came in contact the last time it went through the press, having the hollow or sunken impressions, or "concave," as I have called them, while the opposite side had the raised impressions.

X Q. 30. In case a sheet of paper be printed on both sides, what would be the result as to these concave and convex portions?

A. Taking a sheet of paper and passing it through a printing press an impression is produced which on the second impression printed on the opposite side is partly effaced by said second impression, but this second impression remains until it has been effaced by some process, such as we have been considering, leaving concave and convex impressions the same as if the sheet had only been printed

once

61 X Q. 31. In case the second impression should not come on a line directly opposite that of the first impression, would

there not be convex portions on each side of the sheet?

A. There would; but in the days when I was engaged in the printing business, and I believe it is the same now, it was always an object to make the line on one side of the page come exactly on a line with the line on the other side of the page; or, in other words, what the printers call "register." This was for two reasons, one was that one impression partly effaced the other, and the other reason was that the paper between the lines looked whiter, thus producing a better effect than it would if the lines on one page came between the lines on the next page.

X Q. 32. Is it a fact that by having the lines on opposite sides of the page "register" that the second impression will wholly remove

the depressions made by the first impression?

A. Not entirely.

Recess until 2 p. m.

SEPTEMBER 24тн-2 o'clock p. m.

Cross-examination of T. J. W. Robertson resumed by Mr. Hill:

X Q. 33. If you can recollect, please give us the name of the place and the date, as nearly as you can recollect, of the incident alluded

to by you in your answer to X Q. 22?

A. I cannot just now. There were three or four places where it might have occurred; one was at a place in Pearl street, New York; I think it was near Wall street. The name has entirely escaped my memory. I only worked there a short time, shortly after my arrival in New York, and it might have been at Baker and Godwin's. It might also have been at an old printing office which I have not mentioned heretofore in my deposition, which was on Nassau street near Beekman, near where the first Herald office stood, which I believe printed some kind of magazine which was sent away in bundles. At this length of time my memory somewhat fails me as to what I saw in those days, although the fact remains in my memory of having seen such bundles. The date must have been somewhere between 1851 and 1854.

X Q. 35. I now call attention to "Complainants' Exhibit B 15*," pages 458 and 459, and will ask you whether or not you find on both of said pages what you have termed "convex im-

pressions"?

A. I do.

X Q. 36. From the manner in which this signature is folded, please state whether or not the convex impressions on one side register with the convex impressions on the opposite page when folded together, that is, do the convex impressions formed by one line of type on one page register with the convex impressions formed by the lines of type on the opposite page, as the sheet is now folded?

A. Before answering your question, I would like to ask if you

mean by "opposite pages" the pages numbered 458 and 459?

X Q. 37. 1 do.

A. They do not. The register and folding is not perfect; but I think you are under the wrong impression as to my use of the word "register." I use that word, as generally understood in the printing business, as meaning the so arranging of printed matter that the lines on one side of the page will be exactly in line with the lines on the page immediately back of it.

X Q.38. Please examine said pages 458 and 459 of this Exhibit "Printed Sheet B 15*," and state whether or not the convex impressions on the one page came into contact with the convex impressions on the opposite page, when the sheet is folded, as in this

exhibit?

A. In some cases they do and in some cases they do not. The sheet under consideration is what is known in the trade as "rule-and-figure work," and is about the worst style of work that could be

got up to illustrate the point of "register." If the printed matter thereon was ordinary reading matter, the effect would be very different and the registration would probably be much better.

X Q. 39. The figures on each of said pages are arranged in line

across the page, are they not?

A. They are.

Mr.

ree

led

it.

rk:

mv

val

It

eet be-

III-

to

rv

ere

* "

nd

m-

ed,

egled

of

by

ou

t I

ord

ng

the

nes

bit

m-

mhis

he

ıle-

be

X Q. 40. What function did the boards perform in the device

which you described in your answer to X Q. 19?

A. They were for two purposes, to prevent the set-off of the printed matter on one sheet upon the sheet next to it, and also to 63 help efface the impressions produced by the printing. Ordinarily the sheets are laid one upon the other, as they come from the printing press, with their concave impressions lying over or upon the convex impressions, one to a certain extent fitting in the other, instead of convex impressions lying against the convex, as in the process claimed in the Jones patent. The interposition of the boards broke up this arrangement and the sheets were thus

more readily made smooth by the power of the press.

X Q. 41. Is any mention made in the Jones patent with regard to

the "convex impression laying against the convex"?

A. There is not.

X Q. 42. Did not the boards described by you in answer to X Q. 19 assist to evenly distribute the pressure over the whole surface of

the bundle of printed matter?

A. I suppose they had some effect that way, but they were too thin to be of much service in producing an even impression over the entire surface. I am referring now to the glazed boards set between the sheets of the bundle. If a bundle composed of printed sheets and such boards were simply tied up, even after being put in the press, they would produce little or no effect in distributing the pressure over the entire sheet.

X Q. 43. In this process described by you in answer to X Q. 19, were there any other boards used excepting the glazed boards?

A. There were usually other boards used at the top and bottom

of the bundle and sometimes others at intervals.

X Q. 44. Were these boards used at the top and bottom of the bundle comparatively stiff and rigid ones?

A. They were.

X Q. 45. What function did they perform?

A. They were used to transfer the power of the press to the sheets being pressed, and if the sheets were larger than the bed or head of the press they would serve to distribute the power of the press evenly over the surface of the sheets. My remembrance is rather vague on this point as to the size of the head of the press; that is, whether it was small enough to require the stiff boards to transmit its power evenly, or not. My impression is, however, that the heads of the

presses I have seen were usually large enough to distribute their pressure themselves, that is to say, they were as large or larger than the sheets which were pressed under them.

X Q. 46. In either event the pressure would be upon the boards

and that pressure would be transmitted through the medium of the boards upon the printed matter, would it not?

A. That is correct.

X Q. 47. In your answer to Q. 11, in speaking of the end boards used in the process described by Mr. Jones in his patent, you say with reference to the functions of said boards, "but their main function is to retain the signatures under the pressure imparted to them by the press, whereby the impression produced by the printing press is effaced." Are we to understand from this that said boards are the medium by which the pressure is retained?

A. It is the means by which the pressure is retained in an even condition. If the boards were not there, but with the bundle simply tied without the boards, the pressure would not be maintained evenly. Of course, some means must be used to hold the boards

and bundle into the compressed condition.

X Q. 48. In your opinion in compressing and tying a bundle of printed papers, say twenty inches high, with end boards, would it not increase the rigidity of said bundle when tied if a third board be inserted therein midway between the two end boards, and of the same size as the latter?

A. I cannot see what good it would do in this respect. It might serve as some kind of protection to the center of the bundle in case a blow was given it about where the board would be, but I cannot see that it would add much to the rigidity of the bundle when tied.

X Q. 49. In your opinion would the insertion of such a third board destroy the efficacy of the process set forth in the Jones patent?

A. I do not think it would.

X Q. 50. Suppose a third or fourth board should be inserted and properly distributed throughout the bundle, would that fact, in your opinion, destroy the efficacy of the process claimed in the Jones patent?

A. I think not. It would, however, be unnecessary work to put the boards in the bundles, the bundles would take up more room in

the storing away and would be heavier to move around. It would take more cord to tie the bundles up and require more boards than the present plan, and would therefore be objectionable.

X Q. 51. In your opinion, would the efficacy of the Jones process be destroyed if one or more glazed or fuller boards should be in-

serted within the bundle between the two end boards.

A. I do not think the success of the process would be destroyed by the insertion of one or more fuller-boards, but the process would not be so successful as with the fuller-boards left out, for the reason that the boards would take time to be put in place, and if many of them were employed, a less number of signatures would have to go in the press, so that each bundle would contain a less number of signatures, and the final result would be that less work would be done by the operator than would be the case were such boards left out of the bundle.

X Q. 52. With reference to claim five, as contained in the Jones patent, No. 204,741, in your opinion, are all the steps therein recited

essential and necessary for the purpose of successfully carrying out the invention of Mr. Jones?

A. To carry it out to the greatest advantage all the steps described

in said claim should be taken.

X Q. 53. According to the wording of said claim, when must the bundles be removed from the press, after having been tied?

A. Immediately after tying.

X Q. 54. In your opinion, according to the wording of the claim, what length of time should intervene between the tying of the bundle

and removing it from the press?

A. I think the time might be varied without avoiding the claim. The word "immediately" in the claim I think is intended to distinguish the process referred to in the claim from the process of drypressing where the printed sheets necessarily stay for a long period, say ten or twelve hours, in the press before removal therefrom.

X Q. 55. What construction do you place upon that step in the fifth claim which reads as follows: "The same consisting of subjecting a collection of such sheets to pressure without the use of fuller-

boards"?

A. I think that the latter part of said sentence, "without the use of fuller-boards," is entirely superfluous, and might as well have been left out, but, as the sentence stands, it means that one of the steps of the process consisted in putting folded sheets into the press in contact with each other instead of setting the sheets in unfolded condition between fuller-boards, as in the old process.

X Q. 56. In your opinion, is claim one of letters patent No. 204,741 to be broadly construed to cover a press having two compression heads, with cross-ways through them, for the purpose of tying the

bundles?

A. If the Jones patent is the first to show such cross-ways, he would be entitled to have his first claim construed broadly as you stated it

X Q.57. In comparing the model marked "Complainants' Exhibit Model No. 1" with the second claim of the Jones patent, you have assumed that the large screw-rods in the Busch press upon which the heads are mounted are used for the purpose of supporting the printed signatures while being subjected to pressure, have you not?

A. I have assumed them capable of such use, or of being used for

that purpose.

X Q. 58. If said rods were never designed for such purpose, and were never used for such purpose, would your comparison thereof, with reference to the second claim of the Jones patent, as set forth in answer to Q. 8, be a proper construction?

A. I think so, for the fact would still remain that such rods were in the press and could be used at any time for the purposes of supporting signatures, should the owner of the press desire to do so.

X Q. 59. Would a press constructed as shown in Complainants' Exhibit "Wood Cut of Seybold Signature Press," in your opinion, be practical for the purpose of compressing a large bundle of signatures, the same resting upon the outer large screw-rods shown in said cut?

7 - 96

ls

ny ncm ss re

n ly

ls of it

rd re ht

se ot d.

d d

es ut in It

re css

oy ot at m

ie es, ie

es ed A. This cut is somewhat misleading, owing to the perspective. It would appear from it that the two farther screw-rods had but a very short smooth surface, and that the screw-threads ran nearly

to the lower end of one of them, while I understand that, as a matter of fact, the screw-threads do not extend more than half way between the two heads when said heads are at their greatest distance apart, thus leaving about half the length of the rods between the heads quite smooth. With such a length of smooth rods as I believe to be the fact and practice, such a press would be very useful for pressing quarto sheets, as bundles of quarto sheets sufficiently large to be conveniently handled could be pressed on such a press with the upper head run down and permanently fixed at the end of the smooth part of the rod.

X Q. 60. Would the fact of said large rods being kept properly lubricated detract any from their usefulness for the purpose just

stated in your last answer?

A. Lubrication would be objectionable in such case, if such lubrication consisted of oil or grease freely applied, but means can be found for producing sufficient lubrication on such rods that would not be objectionable.

X Q. 61. Claim two of letters patent No. 204,741 is specifically and restrictively worded, is it not, and each of the parts referred to

by reference letters?

A. The claim is somewhat limited in its form and it has, as you say, reference letters in it, but an inventor who is the pioneer in an art is not limited to the exact construction shown, even if he employs reference letters to indicate the parts.

X Q. 62. The press shown and described in patent No. 204,741 is capable of compressing and having tied therein matter other than

that of folded printed signatures, is it not?

A. It is.

X Q. 63. It would be capable of compressing between its heads and having tied therein in bundle form various articles, other than that of folded printed signatures, would it not?

A. It could.

X Q. 64. The removable ledges f, specified in claim four, are set in the sides of the trough, are they not?

A. They are.

X Q. 65. The set of adjustable guide-rods m, also specified in claim four, are mounted in the heads of the press, are they not?

A. They are.

68 XQ.66. Are the ledges f and guide-rods m specified in claim four, capable of simultaneous and conjoint use for the purposes specified?

A. No, they are not.

XQ. 67. If the sheets of paper rest upon the removable ledges f, the rods m could not be used, could they, at the same time?

A. No. sir.

X Q. 68. If the papers rested upon the adjustable guide-rods m, the removable ledges f would perform no function, would they?

A. They would not ordinarily, but it is possible that if the clips

shown in Fig. 4 and marked G were removed, that said ledges f

would serve as guides for the movable head.

X Q. 69. Referring to the "model No. 1" and to the wood cut of Seybold signature press, please designate the portion therein shown which is the equivalent, in your opinion, of the longitudinal slots II¹, in the sides of the press bed as specified in claim two of the Jones patent?

A. I consider the space between the two back rods as the equivalent for the slot in the back of the press, and the space between the front rod and the back lower rod as the equivalent of the slot shown in the near side of the bed in the drawing of the Jones patent,

in Fig. 1 thereof.

X Q. 70. Could you construct a press and mount the heads as shown in this model without producing the intervening spaces between the rods?

A. I could not.

X Q. 71. Could you construct a press on the order shown in the Jones patent, Fig. 1, having a trough with heads mounted therein, without at the same time forming therein the slots in the sides of the trough?

Λ. Of course, if I made a press like the Jones press, as shown in his patent, I must make slots therein, if it was intended to use the press for the same purpose as the Jones press is used and to conveniently

tie the bundles therein.

X Q. 72. Would said slots be formed as the result of mounting the heads in the trough as shown, or would said slots have to be specially formed in the sides of the trough?

A. No, to the first part of your question, and yes, to the last, X Q. 73. In your constructions of claims one, two, four and

five of the Jones patent, you have considered said claims in the light of Mr. Jones being a pioneer, have you not, both in the construction of the press and in the process therein set forth?

A. I have.

Redirect examination by Mr. Jacobs:

Q. 74. Please state a little more fully what you mean by your answer to X Q. 73.

A. I consider him the pioneer because he made a distinct advancement in the process of dry-pressing and a distinct advancement in the art of making presses for that purpose. I consider it a new departure in the art of press-making for pressing paper and also in the process for pressing printed signatures.

Q. 75. Is it necessary that he should be what is technically known as a pioneer in order to support your construction of the first, second

and fourth claims of his patent?

A. Not necessarily so. Unless equivalent constructions of earlier date can be found he is entitled to a broad construction of his claims, whether a pioneer or not.

Q. 76. Would the fact that he was not such pioneer disturb the

conclusions expressed by you in your answer to Q. 8?

A. It would not.

Q. 77. Is it necessary that he should be such pioneer in order support your construction of the fifth claim of his patent?

A. No. Q. 78. Would the fact that he was not such pioneer disturb conclusion expressed by you in your answer to Q. 10?

A. It would not.

Q. 79. Has anything been developed in your cross-examinat which would lead to change your construction of his several clair as expressed by you in your answer to Q. 4?

A. There has not.

Q. 80. Or the conclusions expressed by you in your answers questions 8 and 10?

A. No, sir.

Q. 81. Referring to your answer to X Q. 70, please explain w you could not "construct a press and mount the heads as shown i "Complainants' Exhibit Model No. 1" "without producing the

tervening space between the rods"?

- 70 A. If I made a press and mounted the heads as in the mo referred to, there must necessarily be intervening spaces tween the rods, as otherwise the heads could not be mounted as sho in the model.
- Q. 82. Referring to your answer to X questions 59 and 60, assu ing that it was desired to dry-press a considerable amount of she of the size mentioned by you in your answer to Q. 59, at a giv time, would any considerable amount of lubrication of the lar rods be necessary?

A. No, sir.

Q. 83. Would any lubrication which would interfere with the a of the rods as a bed to receive the signatures be necessary, ev assuming that oil or grease were used?

A. It would not. Sufficient lubrication might be obtained

anointing the surfaces of the rods and wiping them off.

Recross-examination by Mr. Hill:

X Q. 84. What do you consider to be the mechanical equivale of the elements specified in the claim of a letters patent?

A. A combination of devices which perform the same function

substantially the same way.

X Q. 85. If said combination of elements be capable of perfor ing the same function as the elements specified in a claim, is such combination, in your opinion, the mechanical equivalent of the e

ments specified in the claim?

A. If the elements referred to were known equivalents at the tir of the invention referred to, and had been used in the same com nation and capable of operating substantially the same way, sucl combination would, in my opinion, be the mechanical equivalent the combination covered by the claim.

X Q. 86. I have reference solely to the elements being capable performing the same functions, whether or not they had former been used in a combination similar to or performing function

analogous to those set up in the claim of a patent?

(Objected to, for the reason that the question calls for a matter purely of law, which is for the court and not the subject of expert testimony.

Counsel for the defendant deems the question a proper one, inasmuch as the witness has assumed that certain elements shown in the "model No. 1" were the equivalent of certain elements.

- 71 in the "model No. 1" were the equivalent of certain elements specified in claim two of the Jones patent, basing his assumption upon the mere fact that the large rods were capable of being used as a trough for the printed matter.)
- A. I believe as a rule it is understood that to meet a combination claim, a combination of elements must be found which were known as equivalents for the elements of the claim under consideration.

X Q. 87. What do you mean by known equivalents?

A. I mean devices that are commonly known as capable of performing the function of those for which they are substituted.

X Q. 88. Then, in your opinion, an element or combination of elements, which are capable of performing the same function of an element or elements specified in a claim, are the mechanical equivalents thereof?

A. If they were known equivalents and performed the same func-

tions in substantially the same way.

X Q. 89. Would the large rods in the "Exhibit Wood Cut Seybold Signature Press" be practical for compressing bundles of signatures resting upon the screw-threaded portion of said rods?

A. I should say not, unless the threads were filled in with some substance to make a smooth surface, which might readily be done.

X Q. 90. That would hardly be practical, would it?

Λ. I see no reason why it should not be, provided the upper head was kept in a fixed position.

X Q. 91. Is the outer head shown in the cut designed to be kept

in a fixed position?

to

he

ne

IS.

to

11-

el

e-9

'n

n-

ts

11

re

111

it

11

1-

a

6-

e

i-

a

of

of y is A. I believe it is intended to be kept so while the press is in operation.

X Q. 92. And how otherwise?

A. I believe it is intended to be movable for the purposes of ad-

justment simply.

X Q. 93. That is a function performed through the medium of the screw-threads cut on said rods in conjunction with the driving sprockets, is it not?

A. I believe so.

T. J. W. ROBERTSON.

72 Sworn and subscribed before me this 24th day of Sept., A. D. 1894.

FRANK E. ZIEGLER, Special Examiner.

Plaintiffs' Evidence in Rebuttal.

New York, July 22nd, 1895.

Testimony taken and proceedings had in the above-stated case, the office of Messrs. Theo. L. De Vinne & Co., 12 Lafayette pla New York city, by stipulation of counsel and in pursuance notice, before Samuel R. Bell, notary public and special examin

Appearances.

M. W. Jacobs, for complainants. George J. Murray, for defendant.

Theo. L. De Vinne, a witness on behalf of complainants, bei produced, sworn, and examined, deposes and says:

Examined by Mr. Jacobs:

Q. 1. State your age, residence, and occupation.

A. My age is 66; my residence is in New York city; I am printer.

Q. 2. How long and to what extent have you been engaged in t

art of printing?

A. As far as my recollection serves, I began in 1843. I began an apprentice on the "Newburgh Gazette," New York, learning corposition and press-work. Afterwards I was proof-reader, forema and junior partner in the firm of Francis Hart & Co. Since t

death of Mr. Hart in 1877, I have had the entire management of the business. I may add that previous to this

worked in various book and news offices in this city. As foreman and employer I have had considerable experience, both job and book work. The business that I now conduct prints t "Century Magazine," the "Century Dictionary" and all the pub cations of the Century Company. I also do much work for oth publishers. Our pay-roll for some years back averages about fo hundred names per week.

Q. 3. Prior to October, 1877, what was the state of the art wirespect to dry-pressing, or removing the type indentations from

printed sheets?

(Question is objected to unless limited to the establishments the witness was employed in, or had charge of. Question wit drawn.)

Q. 3. Were you acquainted with the general state of the art wi respect to dry-pressing, or the removal of type indentations fro printed sheets as it existed at and prior to October 24th, 1877?

A. I was acquainted then with the processes used. It was a part

my business to know all useful processes for dry-pressing.

Q. 4. Will you please tell us what the state of the art was in a spect to this matter, giving such details as you consider necessal for a proper understanding of the subject?

A. It was the usual method in all printing offices that did book and pamphlet work, and in many cases where there was fine job work, to wet down the paper and print it in a damp state, and afterwards to press the sheets between what are known as "press-boards." This was done in a small office by means of a screw-press; in larger offices by means of a hydraulic press.

(). 5. What were the press-boards to which you refer?

A. I hardly know how to define the constituents of the pressboards. They vary in different offices and different manufactories, but it is a thin, very hard, highly calendered and very compact mixture of textile rubbish, of which oakum is a very large constituent.

(). 6. Were they ordinarily or sometimes known as "fuller-boards"?

A. I never heard them called by that name here. They are generally defined here as press-boards. When the work was very fine and exact, one printed sheet was laid between these press-boards. When it was not so exact, two or three sheets were

put between the boards after being thoroughly dried.

Q. 7. How were the sheets dried for this purpose?
 A. By hanging on poles at the top of the ceiling.

Q. 8. How long were the sheets allowed to remain in the press

when this process was used?

A. The usual method was to keep them in over night; to fill the press in the afternoon, screw it down or pump it up, and keep them under pressure until the next morning.

Q. 9. Did it require much or little labor to charge the press in

this process?

A. It took much labor. To fill the press would always take a man and a boy, sometimes a man and two boys a day.

Q. 10. How about taking the sheets out of the press; was much

labor required there or not?

A. Allow me to correct the previous answer. I should have said

to fill and unfill a press.

Q. 11. How many sheets per day could be dry-pressed by this process, with a hydraulic press of the size ordinarily used in large

printing establishments?

- A. I cannot answer that question with definiteness because the capacity of hydraulic presses differ widely; some of them have but two or three feet above the platen, others have much more. It depends upon the height of the ceiling. The press has got to be made to fit that.
- Q. 12. About how much space in a hydraulic press would it require to press 5,000 sheets of the "Century Magazine"?
- A. I would hardly undertake to say how much space it ought to take. I should say that 1,750 sheets were about as much as could be put in a press at one time.

Q. 13. By whom was the dry-pressing done by this process? By

the printer or by the bookbinder?

A. It was always done by the printer. The publisher of books made it a part of the business of the printer to deliver sheets pressed to the binder.

75

Q. 14. Were they delivered to the binder flat or folded?

A. Always flat.

Q. 15. Are you acquainted with the process of dry-pressing printe sheets as set forth in the fifth claim of United States letters pater No. 204,741, June 11th, 1878, to J. W. Jones, a copy of which I no hand you?

A. I am acquainted with the process.

Q. 16. Have you used it in your work?

A. I have; our house has two of these machines. One of there

has been in use since 1879; the other since 1885 or 1886.
Q. 17. To what extent have you used these machines and this pro-

cess of dry-pressing in your establishment?

A. We use them for the pressing of the "Century Magazine," the "Century Dictionary," and other books of the Century Company We use them for all long editions of any work requiring dry-pressing

Q. 18. Have the Jones press and process been in continuous us

in your establishment since 1879?

A. They have.

Q. 19. Please state the results of the use of the Jones press an process as compared with the old method of dry-pressing describe in your preceding answers?

A. It does better work and at less cost. It saves waste of paper and allows pressed signatures to be stored and handled with greater

facility.

Q. 20. In what respect does it do better work?

A. The pressing is more uniform. In the old process of pressin by a screw or hydraulic press, it often happened that indentation in some corner were not thoroughly removed.

Q. 21. Are they thoroughly removed by the Jones press and pro-

cess?

76

A. They are. The pressure is uniform throughout.

Q. 22. Do you or not consider the Jones process an advance upo the processes in use prior to October 24th, 1877?

A. I do so consider it.

Q. 23. In what respect and to what extent? Please state as full

as you think proper.

A. It enables me to dry-press work which before was never dry pressed at all. When the "Century Magazine" had the comparatively small circulation of 60,000 copies a month, we wanted t dry-press it by hydraulic presses, at that time the best machines it use. We made calculation as to the number of presses that would be required and the amount of space that the presses would occupy and the cost of doing the work, and we gave up the project as bein

entirely impracticable. We got the Jones dry-presser at latter date because it seemed to us the only machine the

could do the work quickly, and with reasonable economy. We have also applied Jones' dry-presser to many other books. The workmanship done by it has always been satisfactory to binder an publisher. This machine has enabled us to do a great deal of work and do it well within little time.

Q. 24. In what, as you understand it, do the chief features of the

Jones process consist?

A. First—the novelty of pressing sheets in bulk after folding, without any press-board between to protect against set-off. I disbelieved in the possibility of the process until I was convinced by its practical working. Second—in the novel methods used for retaining pressure on these printed signatures after they left the press. These strike me as the most important features. There are other smaller matters, but I do not know that they are pertinent. I may add one, and that is his apparatus for keeping folded signatures in a gutter or channel, and directly in the line of resistance so that they will not spring or wobble under pressure.

(). 25. Was it possible by the methods in use prior to October 24th,

1877, to dry-press sheets in bulk after folding?

A. It was not possible. I have tried it many times to my sorrow

and spoiled the work.

Q. 26. Was it possible by the methods in use prior to that time to dispense with press-boards between the sheets in the process of dry-pressing?

(This line of examination is objected to unless limited to machines and devices within the knowledge of the witness.)

A. I never knew it to be done with success.

Q. 27. Had you or not prior to the date stated made any through

examination of the art so far as it related to dry-pressing?

A. I did make repeated examination of the processes in the houses of Harper & Brothers, Gray & Green, and other book printers of this city.

Q. 28. Were you or were you not acquainted with the literature

of the subject at that time?

A. I tried to be. I was a subscriber to and receiver of many of the leading typographical journals in this country and abroad.
 As one of the officials of the Typothetae I took much interest in everything that related to the development of the print-

ing art.
Q. 29. Have you yourself published any books or other publica-

tions on the subject of printing?

A. I have. I have written and published the "Printers' Pricelist," first edition 1869—a book intended for the use of job printers; another on the "Invention of Printing," 1876, and another, "Historic Printing Types," 1886, the substance of a paper read before the Grolier Club, of this city. I have published no other books, but I have frequently written on printing for trade journals in this country and in England, and have contributed some papers on books and engravings and printing methods for the Century Magazine.

Q. 30. What are the novel methods of retaining pressure upon the printed sheets after they have left the press in the Jones process as

referred to in your answer of question 24?

A. To me the novelty consists in tying up the pressed signatures between hardwood boards in such a manner that the pressure is not relaxed. Q. 31. Referring to your answer to question 24, do you look up the inclined trough of the Jones press as an essential feature of

apparatus?

A. I do. In that position it keeps the signatures straight and to the guides and side before pressure is applied. When pressure applied a gentle pressure on the part of the workman can keep signatures to be pressed in a line. If the sheets or signatures we placed upright without any defense or protection on either side, the would spring and wobble, and I do not see how it could be possite to keep them straight or in the line of resistance.

Q. 32. In using the press are the sheets reversed or are the ba-

laid all one way?

A. We keep them one way.

Q. 33. Is there any advantage in this?

A. Yes; it presses or flattens out the fold of the paper better.

Q. 34. Are the adjustable guide-rods in the press of any impance?

(This line of examination is objected to, and a motion will be ma to suppress the testimony as not being proper at this stage the case, it being testimony-in-chief and not in rebuttal of a evidence offered by defendants.)

A. They are of importance.

Q. 35. If you have at hand any cuts fairly representing the of ation of dry-pressing of the sheets according to the old process

scribed by you, will you please produce them?

A. The illustration on page 126 of the "Harper's establishmen dated 1855, is a fair representation of the old method of dry-pressisheets. I have a distinct recollection of seeing this process in the place as shown in the cut about the year 1858.

Q. 36. And is that substantially the same method which cont

ued in use down to and including the year 1877?

A. I know it to be, and believe it to be, the same process.

(The cut referred to by the witness offered in evidence to marked "Complainants' Exhibit Hydraulic Presses.")

Q. 37. Will you look at the cut I now hand you and state whethor not it represents the Jones signature press, which you now have in operation in your establishment, or one of them?

A. It is a fair representation of the general construction of press we now use. I cannot undertake to be minute or specific about the construction of the general construc

every particular.

(Cut offered in evidence and marked "Complainants' Exhibit of Jones Signature Press Used in the 'De Vinne Press.'")

Q. 38. Will you please look at Fig. 5 of the cut which I now ha you and state whether or not it fairly represents the bundle printed signatures after being passed through the Jones press in your establishment?

A. It is a fair representation of it.

(Cut offered in evidence to be marked "Complainants' Exhibit Cut of Jones' Bundle of Printed Signatures.")

Q. 39. If you can furnish us with a small piece of press-board, such as you say was used in the old process of dry-pressing, will you please do so?

(Piece of press-board produced by the witness to be marked Complainants' Exhibit "Sample of Press-board.")

Defendant's counsel, not waiving the objections above noted, but relying upon the same, proceeds to cross-examination:

X Q. 40. For what purpose do you now use the press-board, a

sample of which you produce?

A. For the pressing of small sheets, chiefly of job work, that have to be delivered flat.

X Q. 41. Do you use them on the Jones press?
Λ. I do not. They are used on the hydraulic press.

X Q. 42. In pressing signatures by the old process were not wood boards used at top and bottom?

A. Always.

X Q. 43. After the signatures have been in the press over night, as you say, and taken out in the morning, were they tied in bundles?

A. No. Not to my knowledge. We never tied them in this house, and I do not know or believe that they were tied in any other house.

X Q. 44. You never heard or knew of the signature press that employed platens with cross-groves for twine, and in which signatures were pressed and tied, before the pressure was removed, prior to the press which you say you put in your house in 1878 or 1879; is this correct?

A. I never knew that such a process was used in any office or on any machine before the Jones dry-presser.

THEO. L. DE VINNE.

CITY, COUNTY, AND STATE OF NEW YORK, 88:

I, Samuel R. Bell, a notary public, in and for the State of New York, do hereby certify that the above-named witness, Theodore L. De Vinne, was produced before me at the time and place above stated, was duly sworn according to law before testifying, that his deposition has been read over by him before signing, and that he has signed the same this day in my presence.

Witness my hand and official seal this 22d day of July, in the

year 1895. [SEAL.]

SAMUEL R. BELL, Notary Public, Kings Co.

(Cert. filed in N. Y. county.)

Testimony taken and proceedings had in the above-stated case, at the Hotel Hanover, 12th and Arch streets, Philadelphia, Pa., by stipulation of counsel and in pursuance of notice, before Theo. H. McCalla, notary public, as special examiner.

Appearances.

M. W. Jacobs, Esq., for complainants. George J. Murray, Esq., for defendant.

James B. Nicholson, a witness called on behalf of the complainants, being produced, sworn, and examined, deposes and says:

Examined by Mr. JACOBS:

Q. 1. State your age, occupation, and place of residence.

A. Age, 75; residence, Philadelphia; occupation, grand secretary of grand lodge of Odd Fellows.

Q. 2. What was your occupation prior to your present one?

A. Bookbinder.

Q. 3. Harrison B. Hood, a witness called by defendant to testify as an expert, during the course of his deposition referred to and introduced into the record a number of extracts from a book "published in 1856 by Henry C. Baird, entitled, 'Manual of the Art of Bookbinding,' by James B. Nicholson." Are you the James B. Nicholson who wrote that book?

A. I am.

Q. 4. Mr. Hood quoted, from the book referred to, a passage from page 41, under the title "Beating, Pressing, etc.," beginning with the words, "The first operation," etc. Will you please state whether the process of beating referred to, had any connection whatever with removal of type indentations from printed sheets?

A. None whatever.

Q. 5. Were you at the time you wrote that book or at any subsequent time, aware that the process of beating with a hammer had ever been used for the purpose of removing such type indentations?

A. I was not.

81 Q. 6. In your judgment, would that be a practicable method of removing such indentations?

A. I do not think it would; I never had any practical test of that,

a

r

a

as the sheets always came from the printer already pressed.

Q. 7. Was it at the time your book was written, or at any subsequent time while you remained engaged in the bookbinding, the work of the bookbinder to remove the type indentations from the printed sheets?

A. It was not.

Q. 8. By whom was it done?

A. It was done—or attempted to be done—by the printer.

Q. 9. Mr. Hood further quotes from page 43 of your book, beginning with the words, "A rolling machine has been invented as a

substitute for the beating which books require previous to being bound," and again, from page 44, beginning with the words, "a powerful embossing press, technically called a 'smasher,' has lately been employed to great advantage," and again, from page 45, beginning with the words, "In some binderies a hydraulic press is relied upon for compressing the sheets without their undergoing the beating or rolling process." Were any of the processes described in these passages for the removal of type indentations?

(Objected to by defendant's counsel as the passages speak for themselves and it is immaterial what this witness's opinion — regarding the process intended, so long as the means described is sufficient to accomplish the result.)

A. They were not.

Q. 10. Please state for what purpose these several processes as well as the beating described in the previous passage were used in the art of bookbinding?

(Question objected to as immaterial.)

A. Until the requisite degree of solidity was obtained. They were designed to make the book solid by driving out all the air that was in or between the sheets.

Q. 11. Were the processes of beating and rolling, etc., applied to

all kinds of work that came into the bindery?

A. I don't think that they were; simply for fine, good books.

Publishers' work was merely pressed in a standing or hydraulic press. Cheap or low-priced books could not bear the expense.

Q. 12. Did the book while passing through the bindery

undergo more than one pressing?

(Objected to as leading.)

- A. It did; the sheets were pressed or run through the rolling machine or smasher before it was sewed. It was then pressed after being laced in by the forwarder; it was pressed again slightly when finished.
- Q. 13. In any of these operations was the book or were the sheets while under pressure tied in such manner as to retain the pressure thereon?

A. They were not.

- Q. 14. Mr. Hood in his answer to cross-questions 15 and 16 of his deposition says that gathering and collating are the same process; is that correct?
- A. It is not; they are entirely different and distinct processes. In gathering the sheets, the sheets are laid out upon a gathering board or table; a pile of the sheets of each signature being placed side by side the whole length of the board or table. A girl passes along and draws one sheet from the top of each pile; they are then placed upon another table, and the gathering process is completed. Then the sheetman or a girl takes the gathered book by the top right-hand corner and with her left hand she goes over each sheet and sees that it is in its proper place. That is collating. The pro-

cess of collating is described on pages 39 and 40 of the manual Sometimes in the gathering, two sheets are picked up by the gath erer; this is corrected in the collation. Sometimes the gathere omits to draw a sheet from its place, and the collator detects and rectifies the mistake.

Q. 15. In what form were the sheets delivered by the printer to the binder at the time your manual was written, and subsequently so far as you know? Were they flat or folded?

A. They were flat.

Q. 16. What was the first operation performed by the binder after the sheets were delivered to him?

A. To fold the sheets.

Cross-examined by Mr. MURRAY:

X Q. 17. In your opinion how much pressure would be required to remove type indentations from a pile of signatures?

(Objected to as new matter and not proper cross-examination.)

A. I do not know; I have had no experience in printing X Q. 18. But you have had experience in bookbinding, have 83 you not?

A. I have.

X Q. 19. By what process, if you know, was it that type indenta tions were removed from the manual you have been testifying about?

A. I suppose it was done by the printer; by pressing the sheet

between fuller-boards.

X Q. 20. If it had not been done by the printer as you describe but the signatures had been put together and sewed as you hav described them and then subjected to pressure of 50 to 80 tons, d you think that pressure would have removed the type indenta tions?

A. A book could not have been submitted to that pressure afte

it had been sewed.

X Q. 21. Assume that it had been subjected to that pressur before it had been sewed, and answer the question under tha assumption?

A. I do not know whether it would remove the type indenta tions; it might partially, perhaps; we never pressed a book for tha

purpose.

X Q. 22. After you had folded the sheets into signatures wha was the next operation?

A. Gathering them.

X Q. 23. And after they were gathered and collated, what next A. They were beaten, rolled or smashed: if they were good books

X Q. 24. And if not good books, what then?

A. If not a good, if they were cheap, low-priced, or publishers

books, they were simply pressed in the standing press.

X Q. 25. When good books were made how long did you subject the signatures to pressure; I mean a bundle of signatures sufficient to form a book?

nual^{*} gathherer s and

er to ntly,

after

nired

ting, have

entalying heets

ribe, have is, do enta-

after ssure that

entathat what

next? ooks.

shers' object icient A. When the book was subjected to a smasher they were not then submitted to a press; books that were rolled were put in a press to take the curl out of the books, so the sheets would lie together. Books that were beaten would not require as much pressure, if they

were evenly beaten. The tendency was to beat them too thin around the edges except by an expert beater. Publishers' work was generally pressed over night, the press changed in the morning and remained during the day.

JAMES B. NICHOLSON.

Sworn and subscribed before me this 23d day of July, A. D. 1895, THEO. H. McCALLA, Notary Public.

STATE OF PENNSYLVANIA, City and County of Philadelphia, ss:

I. Theo. Hill McCalla, a notary public in the aforesaid State, city, and county, do hereby certify that the above deposition of the above-named witness, James B. Nicholson, was taken at the time and place above named, the witness having been first sworn by me before testifying; that his deposition was read to him before signing, and that he signed the same in my presence.

Witness my hand and official seal this twenty-third day of July,

A. D. 1895.

[SEAL.]

THEO. H. McCALLA, Notary Public.

Washington, D. C., July 24, 1895.

Testimony taken and proceedings had in the above-stated case, at the office of T. J. W. Robertson, No. 605 Seventh street, Washington, D. C., by stipulation of counsel and in pursuance of notice, before G. Dittmar, notary public, as special examiner.

Appearances.

M. W. Jacobs, Esq., for complainants. George J. Murray, Esq., for defendant.

Thomas B. Penicks, a witness on behalf of complainants, being produced, sworn, and examined, deposes and says:

85 Examined by Mr. Jacobs:

Q. 1. State your age, occupation, and place of residence.

A. Age, 54; place of residence, Washington, D. C.; occupation, bookbinder, Government Printing Office.

Q. 2. Were you formerly employed in the Government Printing Office in any other official capacity; if so, state in what capacity and for what length of time?

A. Yes; superintendent of the folding-room of the Government Printing Office 25 years; from 1866 to 1887, and from 1889 to 1894. Q. 3. What was the nature of the work under your supervision as

superintendent of the folding-room?

A. All the work was printed in the press-room, then forwarded to the drying-rooms for dry-pressing, then came to the folding-room, where the work was cut, folded, tied up in bundles of five hundred each; these bundles were tied up with a simple piece of paper top and bottom or a piece of pasteboard, then a rope was passed around the bundle, a man then put his left arm on the top of the bundle and drawed the cord around the bundle as tight as possible, then knotted the rope; these bundles were then removed to the warehouses and remained until the work of the different signatures were all completed and ready for gathering into books; the work was then removed from the warehouse to the gathering tables, and placed on the gathering table for gathering; the work was then tied up again by hand in the same manner as the bundle of signatures were and then stored subject to the orders of the bindery. Everything that was made into book form passed through the folding-room in my superintendency, except blank work which had to be done.

Q. 4. What method of dry-pressing was used there when you took

charge of the folding-room?

A. The ponderous old style,—pressing sheets between fuller-

boards.

Q. 5. If any other method of dry-pressing was subsequently introduced, please state what it was in your own way, how it came to be introduced and all about it.

A. In the year 1878 the Hon. John Defrees was public printer. He sent for me and Mr. Oliver Reed, who was then foreman of the press-room, and said to us: "There is a man by the

name of J. W. Jones, who has invented a machine for removing the indentations of type from sheets after they are folded. has this machine running at the State printing office, at Harrisburg, Pennsylvania. I want you to act as a committee and go to Harrisburg, see this machine in operation and investigate the work." We felt very skeptical about the claims of Mr. Jones for removing the indentations of type in signatures after they were folded, so we thought we would take some of the work that was printed in the Government Printing Office. We were not willing to go there and see work that was printed by them and pressed. We took five hundred octavo sheets and five hundred quarto sheets. These signatures were given a heavy dose of ink for this especial purpose, and at the time I thought we were putting up a job on the Jones press, and that it would be impossible for them to remove the indentations of type from these thousand signatures, and there would be no set-off So we went to Harrisburg, carried the thousand sheets to the State printing office, examined the working of the Jones signature press, saw our thousand sheets pressed. We then sealed the bundles for fear that some one might tamper with them in our absence. These sheets were pressed at noon. The next morning we went to the State printing office and found the seals of the bundles We opened the bundles, examined the sheets carefully, and to our astonishment the indentations of type were removed, and

there was no set-off of color, and the sheets were perfectly smooth. We then returned to Washington with the thousand sheets, showed them to the public printer, and made a favorable report upon the work done by the Jones signature press. We recommended to him that he purchase one machine on trial.

Q. 6. Were any of these machines purchased and put to work in

the Government Printing Office?

as

to

m.

ed

op

nd

lle

en

e-9°

re

as

ed

re

in

ok

r-

11-

to

r.

ın

10

V-

le

g,

S-

e

10

re

ie

d

11-

es

ie

d

of

ff

0

1-

le

)-

9

1.

d

A. They were at different times by John Defrees, public printer, and A. M. Clapp, public printer, and S. P. Rounds, public printer, there being at times fourteen hydraulic machines that had been purchased under the administration of the public printers just named.

Q. 7. What results were obtained by the use of these machines as compared with the "ponderous old style, pressing sheets between fuller-boards?" Please state in your own way and

as fully as you think necessary.

A. There was a great improvement in the appearance of the work, the indentations were removed uniformly, and there was a glossy surface produced by the signature press that was not obtainable from the old style of hydraulic pressing. The work pressed by these machines was advantageous, there being no waste of signatures that necessarily came from handling by the old process, and the large saving by the process made the saving to the Government the cost of the work comparatively nothing.

Q. 8. Did you or not consider the Jones press and process an ad-

vance in the art?

A. Most undoubtedly. It is one of the best pieces of machinery that was ever introduced into the printing and bookbinding trades.

Q. 9. In what, as you understand it, did the novelty of the Jones

process consist?

A. The novel part of it to me was the fact that you could remove the indentations of type after the signatures had been been folded, something that was never heard of before in my experience in the trade; also the uniform manner in which the signatures were pressed, removing all the swell in the head, back, and front of the sheets which necessarily occurs in folding; and the solidity of the bundles for books, making the signatures and bundles after being pressed as hard almost as a rock.

Q. 10. In what respects were the Jones press and process an ad-

vance in the art?

A. Well, for perfection of removal of indentations of type, and for rapidity in the quantity of work produced by them, and for the great advantages of security to the work after being pressed for storing purposes, for the saving of storage and on account of the protection against fire. The signatures of the work tied up and stored until completion of the work under the old system of tying up necessarily made a large loss of the signatures from the fact of the paper being wet when tied by hand and stored away, the paper would dry,

the bundles become loose from contraction, the piles of signatures careened and leaned over to such an extent that it became necessary to often take the piles of signatures down and

9-96

retie them and repile them; also the cord used in tying up the bu dles by hand would crease and kink the sheets to such an exte that many of the signatures top and bottom of the bundles were stroyed, often necessitating reprinting of signatures at consideral cost for the completion of the work.

Q. 11. How many sheets per day could be dry-pressed by the Jor

process upon a single machine?

A. Well, of course that depends a great deal upon the adepth of the hydraulic pressman who manipulates the machine. Some can do more than others. I have known some men in raci on the machine to do one hundred and fifty bundles, each bund containing five hundred signatures, in eight hours, making seven five thousand signatures in eight hours. No man should be allow to operate one of the hydraulic pressing machines who does less th fifty thousand signatures in eight hours.

Recess.

Q. 12. In what do you consider that the differences consist between the old process referred to by you and the Jones process of d pressing?

A. In the old process the sheets were laid between fuller-boa for removing the indentations of type; this naturally from print of the sheet would make them all concave, and this pressure was l after sheets were removed from the old hydraulic presses. Wher from the Jones pressing machines the sheets being folded, the prin matter would make convex against convex and concave against c cave, and then having solid blocks at the end of each bundle of tributes the pressure uniform over the signatures, and when the we is pressed to the capacity on the machine it is desired, the tying the bundles retains the pressure of the machine on the signatu printed, and the longer the pressure thus retained on the bund leaving the machine the more advantageous is the work.

Q. 13. In the old process were the sheets laid concave against c

cave or concave against convex?

A. They were all laid one way, being concave against convex.

Q. 14. Will you look at U. S. letters patent No. 181,3 to J. B. Archer, and state whether the operation of dry-pr 89 ing could be conducted by the end frame shown in Fig.

(Question objected to for the reason that it does not appear so that the witness is qualified to testify as an expert in relation patents for mechanical devices of any kind.)

A. I don't think it possible to remove the indentations of type the frames here described, for the reason the pressure on signatu printed could only cover that portion where the frame was, leav in the center of the sheets without any pressure that is required remove the indentations of type. Whereas in the block used the Jones machine for pressing it covers the entire surface of

Q. 15. In the Jones machine did the inclined trough perform:

special function? If so, please state what it was.

(Objection repeated.)

A. Yes, the incline of the trough allowed the trough to be filled with signatures with the backs all one way, and the heads all one way, which otherwise could not be done by one person in an upright machine, as it would be almost impossible to pile up sheets a foot high with backs and heads all one way.

Q. 16. Was there any advantage in having the sheets with the

heads all one way?

A. Yes, if the heads and backs were not laid all one way in pressing, the sheets would undoubtedly slip and the heads or backs of the sheets would be twisted and kinked, and by the sheets all lying one way it brings all the printed matter exactly over printed matter and thereby the indentations of type are more easily removed.

Q. 17. From your experience can you say whether or not a quick or sudden blow by a hammer would remove the impressions of type

on paper?

A. No, it would not. The sudden blow would break or destroy the fiber of the paper, whereas if the pressure is gradual and even you can get the desired result. A quick, sudden blow would not give the desired result.

Q. 18. Do bookbinders hammer books after they have been

printed: and, if so, for what purpose?

A. Yes, it's a common thing for bookbinders to hammer books after the work has been printed and made into books. This hammering is done to remove the swell in the backs of books from sewing and to make them as solid as possible for cutting.

Q. 19. Was this hammering done in your experience for the

purpose of removing type indentations?

A. No, the hammering is not done to remove the indentations of type, and what was often hammered all over the book, sometimes in addition to the hammering just stated, was for the purpose of removing creases or kinks in the paper produced by tying up the sheets before they were made into books.

Q. 20. In your experience, prior to the Jones press and process, was any method used for removing type indentations except the ponderous method of pressing sheets between fuller-boards in a hydraulic

press to which you have referred?

A. No, I never heard of any machine prior to the Jones signature press that would remove the indentations of type except the old process of laying the sheets between fuller-boards and pressing them.

Q. 21. Where did you work prior to entering the employment of the Government?

A. Worked in the city of Philadelphia, Pa.

Q. 22. Can you give us any idea of the saving to the Government by reason of the introduction of the Jones presses and process?

(Question objected to as it does not appear what process was used before the introduction of the so-called Jones press, nor does it appear that the process used prior to the introduction of such presses or the machines used for accomplishing the same purposes used by the Government were the best machines upon the market prior to 1878.)

A. Well, the capacity for dry-pressing on the old-style hydraulic pressing machines was about fifteen hundred fuller-boards containing four sheets between each fuller-board, which makes six thousand sheets, and these sheets being cut in half would make twelve thousand copies. That number of sheets with the fuller-boards and wooden boards which were put in to steady the sheets and fuller-boards was a pressful. These presses were allowed to press these sheets about four hours, that being two presses for eight hours, the

working time of the employees of the Government Printing
Office. That would make twenty-four thousand copies pressed

in the eight hours by the old hydraulic system. There was employed six men to each press, including their work of trucking, racking, placing the signatures between the fuller-boards, piling them up in the presses and again removing them after being pressed. The pay of these men was two dollars (\$2) per day. That would make twelve dollars (\$12) per day for the twenty-four thousand sheets pressed by the old system. Whereas, on the Jones signature press for the removal of indentations of type, fifty thousand sheets is an ordinary day's work of eight hours. The man who operates the Jones hydraulic press in the Government Printing Office receives \$2.40 (two dollars and forty cents) per day for the pressing of the fifty thousand sheets, thereby doing more than double of the amount of work done by one of the old hydraulic pressing machines, and a difference in wages of twelve dollars (\$12) for six men and two dollars and forty cents (\$2.40) for the pressman on the Jones hydraulic machine, that being a saving of nine dollars and sixty cents (\$9.60) in money alone on one machine. Then there are other advantages in the saving of signatures that from the new process over the old, in the handling of the sheets from the old hydraulic presses, from the tying up by hand, from the waste in storage,—would be another large item in saving to the Government.

Q. 23. Referring to your answer to question 19, were there any creases or kinks in the paper produced in the Jones process which

required to be hammered out?

A. No; it is impossible for there to be any creases or kinks in the work pressed on the Jones machine, from the fact of the immense pressure and the uniformity of the pressure, and there being no ropes that touches the bottom, top, or ends of the sheets, thereby preventing the kinks or creases that were caused in the old way of tying up signatures.

Q. 24. How were the signatures tied in the Jones machine or

process?

92

A. In the inclined, rectangular trough you placed a pressing board in the lower end of the trough against the lower platen connected to the piston. The signatures were then placed against the block,—

heads against the outer side of the trough, and the backs against the lower side of the trough,—until the trough contained five hundred signatures; then another end-pressing block was placed at the upper end of the bundle of signatures near the upper stationary platen in the trough; then the pressure was applied and the work in the trough was gradually pressed up to the upper platen of the trough until the amount of pressure required was obtained, these platens, top and bottom, being split crosswise, and the large opening admitting of the arm. The rope was then passed through these openings around the bundle of the work with the pressure on, and securely tied. After the bundles are securely tied, the pressure is removed from the signatures in the trough. The work can then be removed from the pressing machine for storage purposes with the pressure still retained.

Q. 25. Did the open crossways admitting the hand and forearm

perform any function in this operation?

A. Yes, necessarily. It would be almost impossible to tie the rope around the bundles all the way unless these openings were in these cross-heads, as they admit, especially the large opening in the platen, of passing the arm through the large opening in the platen, then through the opening in the head crosswise section to the opening in the lower bed of the press, then around the large opening in the lower crosswise section, to the opening in the back, then around again to where it is tied.

Q. 26. I now hand you several letters having reference to the use of the Jones press and process in the Government Printing Office, and ask you whether they are signed by you, and whether they correctly state the facts as they existed at the time the letters were

written.

A. They do, and they are correctly signed by me.

(Letters offered in evidence to be marked "Complainants' Exhibit Thomas B. Penicks' Letters of February 25th, 1879, and February 5th, 1880, and August 3d, 1886.")

Q. 27. Referring to your letter of February 5th, 1880, what do you mean by "I now press all books after being gathered"?

A. In answer to that question I would state that it is impossible for the Government bindery to receive the work as fast as completed by the printing office, and it became necessary to store this

work away in the warehouses until the bindery was ready to receive it. These books often remained in the warehouses for weeks and months, subject to the order of the bindery. It became necessary for the preservation of the work to again tie them up into the bundles of books to preserve them, otherwise if the bindery could have taken this work as fast as it was gathered it would not have been necessary to repress the books for binding.

Q. 28. Then it was only for the purpose of retaining the sheets in bundles and not for the purpose of dry-pressing that they were pressed after gathering? Is that correct?

A. That is correct. The indentations had already been removed with the first pressing of the sheets.

(The introduction of the letters is objected to and the whole of the

foregoing deposition, except question and answer 14, for the reason that it is testimony-in-chief and not properly testimony in rebuttal

Cross-examination by George J. Murray, Esq.:

X Q. 29. In your answer to question 14, you say that the Archepatent would not remove type indentations for the reason that the pressure would only cover that portion where the frame was. A suming that the frame was substituted for boards, what would be your opinion?

A. Well, as far as this drawing is concerned, it shows the drawing of a bale of manure or other substances, and I do not think the you can bale sheets to remove the indentations of the type like the drawing of the bale described in the patent and specification.

J. B. Archer.

X Q. 30. I asked you to assume that the frame of the J. B. Archepatent was substituted by a solid board at each end. To be more explicit, assume that the bars marked "A" in the drawing of the Archer patent were replaced by a solid board extending across the bale, and that signatures were subjected to pressure between two such end pieces and tied in the manner while under pressure, a described in the Archer patent. Would such process remove the type indentations? And if not, why not?

(Question objected to as not proper cross-examination and for the reason that it assumes matters which do not appear in the patent equestion.)

A. From the appearance of the drawing, being a large bale, it would seem to me there would be a promiscuous pring of sheets in the bale described by J. B. Archer's paten it would not admit of the removal of the indentations of type from the assumed question asked, and as the patent therein describe simply shows a frame partially around the bale, and then tied to an unknown pressure to me, I therefore think it impracticable remove the indentations of type.

X Q. 31. What removes the indentation of type in the Jone

press?

A. The gradual pressure on the sheets and convexing and cocaving of type coming together, and the immense retained pressurremoves the indentations of type.

X Q. 32. What removes the indentations of type under the oponderous process you have spoken about on the intermediate shee

between the fuller-boards?

A. The convexing and concaving of the indentations of the ir mediate sheets between the fuller-boards, and the fuller-boards for ing an even, hard substance with the pressure of the hydraulic m chines forces the fiber of the paper which has been disturbed by the indentations of type again back to its place.

X Q. 33. What prevented the offsetting in the intermediate shee

in the old ponderous process?

A. The theory of that is that after the work is printed, there some chemical atmospheric change, or, as it would be, an invisib

film over the paper, and as long as this film or invisible covering is

unbroken there will be no set-off of the intermediate sheets.

X Q. 34. Then the same chemical agency which prevented offsetting of the intermediate sheets in the old ponderous process, also prevents the offsetting in what you understand to be the Jones process; is that correct?

A. I believe so.

X Q. 35. In the Archer process the bands which are secured around the frames retain whatever pressure the bale may have been subjected to in press after the press platens have been separated, do they not?

A. It may, where the bands are on the bale.

X Q. 36. Why do you say "may"? Don't you know that they will, if the frames are strong enough to resist strain after the pressure is removed?

95 A. I do not.

X Q. 37. Have you any opinion as to whether they will or not, if the frames are rigid enough to prevent springing after the bands have been tightened and the pressure of the platen removed?

A. My opinion is,—from observation in baled goods,—that there is always a bulge in space left open for the want of uniformity of pressure.

X Q. 38. Well, a bundle of signatures tied up by the Jones pro-

cess is baled goods, is it not?

Λ. It is baled but not in the sense of the bale shown in the Archer patent.

X Q. 39. The difference is that in the Archer patent frames are employed, while in the Jones so-called process end boards are employed. If there is any other difference, please state what it is.

A. Well, as I said before, the bale shown here is not a bale of signatures, but apparently a square bale with a large quantity of substances promiscuously thrown into baling machines. The Jones machine, having the solid blocks top and bottom to the bundles, and the signatures all laid exact over each other, the heads, backs and tails of the sheets folded, with a gradual pressure of the machine, would, in my estimation, be entirely different from the bale shown and supposed by me to press in the ordinary baling machine.

X Q. 40. I don't think you have answered the question. Perhaps I have not made myself understood. Assume that the Archer bale is compressed in an ordinary hydraulic or screw-press, in each of which the pressure is necessarily gradual, and under this assump-

tion answer the question.

A. Well, being an assumed proposition, I again assert that I have

answered the question intelligently.

X Q. 41. You don't think, then, that material such as described or suggested in the Archer patent could be compressed and the pressure held in the Jones press?

A. No, I don't think that the Jones machines would bale manure

or any substances like manure.

X Q. 42. Why?

A. Because in the proposed baling machine, as is used by Mr.

Archer, substances thrown in the square box with the sub-96 stance thrown in the same machine is protected by the box in the baling machine, and the matter therein compressed together, and the matter being of a soft nature, as manure and similar substances will adhere together and make a square bale; whereas, in the Jones machine-if you should put manure into the Jones machines—just as soon as the pressure was put on the machines, from the fact of there not being a square box to hold the receptacle, and no boards at the tail of the machine, where the tail sheets come, the matter pressed, as manure and soft substance-, by the Archer machine, would squash out from the Jones machine from the want of the tail protection.

X Q. 43. Do you think it would require any more pressure to remove type indentations than it would to remove kinks in the paper

which you say was removed by hammering?

A. Yes, or I could never in hammering a book remove the kinks or creases made in it, nor get the power of thirty-five tons pressure

from my arms.

X Q. 44. Do you think if the sheets after printing were dried and then folded into signatures, and a pile of these signatures subjected to the old ponderous press you have spoken about, that the type indentations would be removed?

A. I do not.

X Q. 45. Why?

A. It would be impossible, from the fact that the old hydraulic pressing machines were about six or seven feet high from platen to platen, and you could not pile folded sheets in one of these old hydraulic pressing machines with the heads all one way and backs all one way. You could not press them—they would not remain on account of the press being perpendicular. As soon as the pressure would be put on, the sheets would all squash out, and the desired object of removing the indentations of type could not be accomplished.

X Q. 46. If the signatures were put in press alternately head and

tail instead of being all placed one way, how then?

A. You would not get the desired result then.

X Q. 47. Why not?

A. Because the turning of the head towards the tail of the sheet and the back towards the front of the folded sheet would throw the printed matter entirely out of the convex or concave. 97

X Q. 48. What difference would that make?

A. It would make the difference of either a flat surface coming against a convex, or a concave coming against a flat surface.

X Q. 49. Well, what of that? Didn't the concave and convex surfaces come against flat surfaces when fuller-boards were used?

A. Not entirely.

X Q. 50. Do you mean to say that when fuller-boards were used, that the type indentations were not as completely removed from the outer as they were from the intermediate sheets?

A. I do.

X Q. 51. It was well known then that the intermediate sheets in the old process had the type indentations more perfectly removed from them than they were removed from the outer sheets which

came in contact with the fuller-boards?

A. The inner sheets always had a better appearance, were smooth and better in every respect as printed matter, from the fact that the glazed fuller-boards on the lower and top sheets seemed to mash the indentations of type out.

THOMAS B. PENICKS.

Adjourned until July 25th, at 10 a. m.

JULY 25, 1895.

Proceedings resumed pursuant to adjournment. Present: Same counsel as yesterday.

- T. J. W. Robertson, a witness who was formerly sworn and testified, being recalled on behalf of the complainants, deposes and says:
- Q. 1. Have you read and do you understand the letters patent offered in evidence in this case by the defendant?

A. I have and I do.

- Q. 2. Have you read the testimony of Harrison B. Hood, called by the defendant to testify as an expert witness in this case, and do you agree with him in the conclusions stated in his deposition?
- 98 A. I have read the testimony referred to, and while I agree with him in one or two points, I disagree with most of his conclusions.

Q. 3. Please state what conclusions you disagree with, giving

your reasons fully therefor.

A. I find on referring to his testimony that he cites quotations from two printed works describing the art of bookbinding, one of which is "A Manual of the Art of Bookbinding" by James B. Nicholson, while the other is a book entitled "The English Cyclopædia, Arts and Sciences." The extracts given by Mr. Hood from these books refer to an entirely different process from that of dry-pressing. and which is performed after the paper has already been dry-pressed, and is most generally performed by a different set of operators than is the operation of dry-pressing; the latter being a part of the printer's duties, while the pressing described in the books cited by Mr. Hood is a part of the bookbinder's duties, and has nothing to do with the object for which dry-pressing is performed, namely, the removing of indentations made by the type in the act of printing, nor would it be practicable to remove indentations in that manner. To remove indentations, such as are produced in the type-printing process, it is necessary that the process shall be a long and continuous one, as otherwise the indentations will not be permanently removed. All that the processes, described in the books referred to, accomplished was simply the solidifying of the book, mostly by pressing out the air that was between the pages when being folded. I find nothing whatever in these processes that in anywise describes or suggests the process set forth in the fifth claim of the Jones patent in suit. Referring to the patents in the order in which Mr. Hood has mentioned them, I find that No. 181,389 issued to J. B. Archer, was for a patent for "baling manure and other substances." In said patent there is shown a bale held under compression by means of cross-ties, and an open frame at top and bottom, and which open frames are incapable of producing the result aimed at in the Jones patent, for instead of removing indentations from sheets of paper, it would produce much worse indentations or impressions than those produced by the act of printing. The same remarks apply to the patents Nos. 169,518 and 125,786.

The inventors, if they can be called such, of the bales shown in these three last-mentioned patents never had the least idea of tying up the material they used under pressure for the purpose of removing indentations, nor would these patents, in my opinion, suggest to any one such an idea. As a matter of fact, the matter put up in such bales, instead of being smoothed or the indentations removed from it, had a much greater number of indentations put into it by the pressure than it had before it went through the operation of pressing and tying. There is nothing in the patents just referred to, even when taken in connection with the extracts from the Nicholson work and cy-lopædia, that would in anywise suggest the discovery made by Mr. Jones, that indentations could be removed from printed matter by the process described in his patent.

Mr. Hood next refers to a series of patents showing grooves in the bed and platen thereof and slots in the sides of the box, in which the material to be pressed is placed to undergo the pressing operation, to wit: Nos. 119,195, 58779, 43523, and 9324, not one of which is designed to be used in the manner in which the Jones press is used, nor could it conveniently be used for the same purpose. He also refers to a press patented by W. R. Dingman October 20, 1863, and numbered 40336, which is designed for tying bundles of paper, and it appears to be the only patented press cited that is designed for tying paper into bundles, which is the main object of its invention; the pressing part of the operation of the press being simply an incidental matter designed to bring the bundle of paper into a small compass, and without any idea of removing indentations from the paper set in the press.

Mr. Hood next refers to the patent of Hardesty, No. 2113, which shows a press designed for pressing tobacco into a hogshead, and the only resemblance it has to Mr. Jones' invention is in the fact that it is of a trough-like form, has perforations in the side, and has the head moved by a screw. It is entirely unadapted for the purposes for which Mr. Jones' press is used, and is in nowise analogous either in construction or operation to the Jones press in the patent in suit.

Not one of the patents cited shows a press having cross-ways adapted to receive the arm of the operator so that a bundle may be

100 thr

pat

hav

direction of to be to continue to continue

are

fort

the

zon

its
inc
trot
reg
fou
the
far
bee
refe
pat
tion
pai

it bei on fice 1/2 the dra am

elin

141)

readily tied at right angles with a single tie, all of them, excepting the patent to Dingman showing only grooves through which the tying material would have to be passed or drawn through with an instrument such as is shown in Fig. 6 of the Cooley patent No. 58779. The Dingman patent, it is true, shows a press having openings through which the arm can be passed in one direction to allow of the string being readily passed through it, but there is no way shown in said press of tying the bundles crosswise of the ties shown in the drawing of said patent. Mr. Jones appears to have been the first to conceive the possibility of so arranging and constructing the heads of a press that a person could readily tie a bundle of papers in both directions with a single string. do this it is necessary that both the heads should have cross-ways at right angles to each other of sufficient size to readily insert the arms of the operator and draw the string through and manipulate the rope and secure the end of the string. This cannot conveniently be done with a mere groove, because it requires that, when a single tie is used to secure the package in both directions, the loop or noose at the end of the string or tie shall be arranged over the center of the end board when the tie is completed, which it is very difficult to do-if not impossible-when mere cross-grooves are used, such as are shown in the Cooley patent. In view of the reasons above set forth, I do not consider that any of the patents referred to anticipates the first claim of the Jones patent in suit.

Mr. Hood refers to the Hardesty patent as showing an open horizontal trough-shaped press bed with longitudinal slots or spaces in its sides, and states that, "I do not think it involved invention to incline the press bed, especially in view of the fact that inclined trough-shaped beds or receptacles arranged to receive and hold in regular order a series of folded sheets was a common construction found in folding machines for folding printed sheets." Not one of the patents cited by him, nor do any of the exhibits in this case, so far as I am aware, show a press having an inclined trough-shaped bed of earlier date than the Jones invention. I suppose Mr. Hood refers in the quotation I have just made from his evidence to the patent No. 186,309, which he mentions in his answer to cross-question 61, wherein he states that "the drawings in this patent show a pair of open trough-like boxes inclined at opposite angles." In

this, however, he is entirely mistaken. He has probably been misled by Fig. 3 of the drawing of the patent referred to. He has mistaken that figure for a vertical section when it is really a horizontal section, the small rollers marked "c³" being stated in the specification to be vertical rollers, as will be seen on referring to line 10 of the second column of page 3 of the specification. As these rollers are vertical, it follows that the troughs j³, k³ are arranged horizontally, and there is nothing to show that they are inclined at all, but on the contrary the other figures of the drawing show that they are horizontal. In view of this I think I am entitled to consider that Mr. Jones was the first to make an inclined press bed, and in view of the novelty and advantage of such an arrangement I believe that it required invention to conceive

the idea of such an inclined press bed and to embody the idea in a

working press, Mr. Hood to the contrary notwithstanding.

To sum up my answer to this question, I may state that I entirely disagree with Mr. Hood's answer to cross-question 59, in which he states substantially that he does not find any invention in the first. second, and fifth claims of the Jones patent in suit, as I regard each of said claims as covering matter that required invention and not anticipated by any of the patents or exhibits in suit. In looking over my testimony, I find I omitted any reference to Mr. Hood's conclusions in reference to the Palmer press. As I understand said press, it is simply used for making bundles of signatures after they have been folded, so that they could be conveniently stored, and was not designed or used for the purpose of taking out indentations, nor were the bundles capable of being tied up in the same manner as they could be in the Jones press. As stated by the witnesses who gave evidence as to the construction of said press, it was necessary to lay two strings across each other in the bottom of the press, which strings were tied separately after the pressing was completed, thus entailing two operations where one only is necessary in the Jones press. I do not believe that the process carried out by the Palmer press is the same process as that described in claim five of the Jones patent, for the process of dry-pressing had already been carried out

on the sheets before they were folded, as testified to by the witness Schrank in his answer to question 33, but inde-

pendently of this, as there were no rigid end boards used it is impossible that the process referred to in claim 5 could have been carried out, even if the press had been powerful enough to produce the necessary pressure, which I doubt, especially in view of the fact as stated by one of the witnesses who testified about the press, that when the bundles were crooked they could be straightened by striking them on the floor.

Q. 4. Do you find in the passage quoted by Mr. Hood from Nicholson's Manual, and the English Cyclopædia, any reference or relation whatever to the removal of type indentations from printed

sheets?

A. I do not; in fact, as the printed sheets had the indentations romoved in the printing office usually before they reached the binders, there were no indentations to be removed by the processes described in the books you have mentioned.

Q. 5. In the Jones machine does the inclined press bed perform

any special function?

A. It does; it has two purposes, one of which is to keep sheets from falling down when piled in the press without the assistance of any device for keeping them in place, such as is necessary when the trough is laid horizontal. The other purpose is to keep one of the heads in such a position that the operator can readily manipulate the tie in the cross-ways.

Q. 6. Do the open cross-ways in the Jones machine perform any

special function ?

A. They allow the insertion of the hand and part of the arm of the operator, whereby he can readily pass the cord around the bundle of signatures in both directions and manipulate the loop so as to bring it in the center of the end board when the tie is being

Q. 7. Please state the differences as you understand them between

the Jones process and the old-style fuller-board process.

A. In the old fuller-board process the printed sheets were laid in an open state unfolded between fuller-boards, which are comparatively thick sheets of paper or pasteboard, and the pile of printed sheets and fuller-boards was set in the press, generally either a screw press or hydraulic press, and thus great pressure produced upon them. This was generally done over 103

night so that the sheets could be under pressure all night long, and were removed from the press the next morning, so as to allow of the press being used for another lot of sheets to be pressed the next night. I should have stated that besides the fuller-boards there were a number of wooden boards set at intervals in the pile, and as there were frequently nearly as many fuller-boards as sheets of printed paper, comparatively few sheets could be pressed at a time in a large press. As a consequence many presses were required n a large establishment, and many employes required to fill and

empty the press.

In the Jones process the sheets are folded ready for the binder, and are then inserted in the bed of the press with the folded edges ll in line, and with end boards at top and bottom of the bundle, fter which the press is set in motion until the requisite pressure has sen produced, when the operator passes the tie-string around the aundle in one direction and then in the opposite direction and ecures the end of the tie. The pressure is removed by running the ead of the press away from the bundle and the latter removed for torage or carried to the binder, as desired, after which another lot f signatures is set in the press and pressed and tied as before, so that ith one press a very large number of sheets could be dry-pressed nd tied in bundles in a very short time, and with even better results s to removing indentations than when the sheets are pressed bereen fuller-boards in a hydraulic press. These better results are ne mainly to the fact that in the old-fashioned process, when two more sheets were set between each two fuller-boards, the concave art of one impressed sheet would rest upon the convex part of other; whereas in the Jones process one-half of the impressed conx indentations came into contact with corresponding convex inntations on the adjacent pages, whereby each convex indentation ted upon the convex indentation on the other page, and thus aded to flatten each other out. Besides the advantage of the periority of the work over the old-fashioned process of dry-pressg, the Jones process left the signatures tied up in bundles convenient storage or for carrying from room to room, whereas by the old-

fashioned fuller-board process, if it was necessary to store away the folded signatures, it was necessary to put them through some such process as that described by the witnesses who tesed about the Palmer press.

Adjourned until July 26th, at ten o'clock a.m.

Examination resumed pursuant to adjournment. Present: Same counsel as before.

Q. 8. Would it be possible to accomplish the process of dry-presing in the Palmer press, as its construction and use is described by defendant's witnesses?

A. It would be practically impossible for the reason that to carr out such process in a practical manner it would be necessary for a the sheets to be set in the same order in the press, that is to say, wit the folded edges in line with each other, instead of being "piled u back and front" or "head and tail," as described by the witnes Schrank. If an attempt were made to arrange the folded edges of the sheets all under each other, owing to the increased thickness du to the folds, the pile would topple over or the signatures slide off of each other; and if it were practicable to set them in the press wit their folded edges in line by one person holding them while anothe person filled the press, as soon as the pressure was applied ther would be a tendency for them to slide more or less out of line, an the result would be that some of the folded edges would project over other of the folded edges and have creases formed in them near th edges, while the projecting folds themselves would not be properl pressed or creased. This would be the case even if end boards, suc as are used in the Jones press, were employed, but, as I understand the testimony of the witnesses referred to, rigid end boards were no employed on the Palmer press, which, as I understand the proces described in the 5th claim of the Jones patent in suit, is a featur essential to success in the process described.

Q. 9. Was the press shown and described in the Dingman pater

intended to be used on printed or unprinted paper?

A. It was intended to be used in a paper mill on unprinted paper and simply is a convenient way of tying up the unprinted paper in bundles.

105 Cross-examination by George J. Murray, Esq.:

X Q. 10. If the fuller-boards were omitted from the pile of sheet in the old process, would the type indentations be removed or not

A. I do not think they would, for the reason that the concav impressions would as a rule overlay the convex impressions of the sheet under it and thus form a kind of matrix for them which would prevent the indentations or impressions being properly removed.

X Q.11. The witness, Mr. Penicks, who is a practical bookbinder testified that the type indentations were more perfectly remove from the intermediate sheets which did not come in contact with the fuller-boards than they were from sheets which did come is contact with the fuller-boards. Do you think he is mistaken?

A. Mr Penicks, being a practical binder at the present time ought to be able to testify as to the question whether intermediate or outer, sheets were the better pressed; but I must say that I do not quite understand how the facts can be as he has stated then

My experience in the printing office is so many years old that I have no recollection at the present time as to whether intermediate

or outer sheets were the better pressed.

X Q. 12. Well, if it were true, as Mr. Penicks states, then it would follow, would it not, that you are mistaken about the concave impressions overlaying convex impressions of the sheets in the old process, as stated in your answer to question 10?

A. I do not think so.

X Q. 13. Mr. Penicks has also testified in cross-question 32 that "the convexing and concaving of the indentations of the intermediate sheets between the fuller-boards, and the fuller-boards forming an even, hard substance with the pressure of the hydraulic machines forces the fiber of the paper which has been disturbed by the indentations of type again back to its place," under the old ponderous process. Then you think Mr. Penicks was mistaken in this matter, do vou?

A. I do not think that the convexing and concaving of the indentations has anything to do with the success of the process of removing indentations of type by the hydraulic press; on the contrary, I think that if the convex sides of both sheets 1(16) were put together, instead of the convex fitting into the con-

cave, that the impressions would be easily removed.

At this point the deposition of T. J. W. Robertson — suspended by consent of counsel for the purpose of recalling Thomas B. Penicks.

Examined by Mr. Jacobs:

Q. I. In my examination the other day, I omitted to ask whether in the old process of dry-pressing the sheets required to be dried before pressing, and whether or not the same was the case in the

Jones process. Will you please state how it is?

A. In the old process the sheets after leaving the printing press, the paper being wet, it became necessary to dry them. There was immense long racks with rods on, which slided in and out of the room heated by steam. These wet sheets were then slung across the rods in the racks. After the racks being filled up with the wet sheets they were then shoved back into the drying-room, and allowed to remain there under the heat of steam until they were dry. It would take three or four hours to dry them in the racks just described. In the Jones process the sheets do not have to go through the process of drying, but are folded wet as taken from the press and pressed wet.

Q. 2. Am I to understand you, then, that in the Jones process the sheets are taken directly from the printing press, folded, and put

into the dry press? A. They are.

Q. 3. And, therefore, drying of the sheets before submitting them to pressing is dispensed with in the Jones process, is it? A. It is.

(Testimony objected to as not proper rebuttal testimony, as be irrelevant and immaterial to any issue in this case.)

THOS. B. PENICK

107 Cross-examination of T. J. W. Robertson by Mr. Mur. resumed:

X Q. 14. I do not understand your last answer. What do mean by "convexing and concaving," as used in your last answer.

A. I used the words "convexing and concaving" because t were used by M. Penicks. What I meant was, that the raised pression on one sheet would come in contact with the sunken pressions with the sheets above it or below it as the case might

X Q. 15. Are you not mistaken as to the use that Mr. Peni made of the term "convexing and concaving"? I understand fi his cross-questions 31 and 32 that what he meant by it was, putt the concave surface to concave surface and convex surface to covex surface. Read his answer to question 31, in which he stathat the convexing and concaving of type coming together remothe type indentations in the Jones press; and in the next answithat the same concaving and convexing removed the type indentations.

tions by the old process. Now which is right?

A. At the time I answered that question I had not read the cution 31, but I had only seen the question 32 as quoted in your question 13, and I do not now quite understand what Mr. Penicks me by "convexing and concaving of the indentations," as used in answer to question 32. As I read your question 13 I understood? Penicks to mean by the term "convexing and concaving" that sheets were laid with the convex impressions or the convex sides the sheets in contact with the concave sides of the sheets above the or below them, as the case might be, that being the usual mode laying sheets in a hydraulic press, instead of having the conviside of the impressions in contact with the convex side of the op site page, as in the Jones process.

X Q. 16. But Mr. Penicks states that the concave and convex s faces come together in the same manner in the one process as in other, does he not, and that it is that convexing and concaving the

other, does he not, and that it is that convexing and concav removes the type indentations when subjected to pressure?

A. I do not understand Mr. Penicks to testify "that the conceand convex surfaces come together in the same manner the one process as in the other;" he simply refers to the covexing and concaving without stating that they came

gether in the same manner in the two processes.

X Q. 17. Well, if the concave surface of one sheet came oppose the convex surface of the adjacent sheet in the old process, how you account for the fact as testified to by Mr. Penicks that the intendiate sheets in the old process had the type indentations may perfectly removed from them than they were removed from to outer sheets which came in contact with the fuller-boards, und the assumption of your former questions, that convex face comit

against convex face was one of the great advantages of the so-called

Jones process?

A. I am unable to understand how the intermediate sheets in the old process can have the indentations more perfectly removed from them than from the sheets that came in contact with the fuller-boards. It is possible that the harsh surface of the fuller-board may have some effect on the other sheets that the softer material of the sheets would not have on each other. This, however, is mere theory, and I cannot state positively that such would be the case.

X Q. 18. Didn't the fuller-boards have glazed surfaces, and were they not more commonly called "glazed boards" than "fuller-

boards "?

ng

Y

ou

r?

ev

m-

n-

e.

ks

m

19

n-

es

ed

er,

a-

18-

38-

nt

1e

Ir.

10

of

m

of

X

10-

r-

ne

at

ve

in

11-

te

lo

r-

re

he

er

ng

A. The surfaces originally were perfectly smooth, and were sometimes called "glazed boards." I do not know that they were oftener called "glazed boards" than "fuller-boards;" I generally heard them simply called "boards."

X Q. 19. There is no suggestion in the Jones patent in suit as to any advantages the supposed invention attains by reason of the so-

called convexing and concaving, is there?

A. I believe not.

X Q. 20. Is there any suggestion in the patent that one string instead of two may be used?

A. There is not.

X Q. 21. The process described in the 5th claim would be the same process whether one or two strings were used, would it not?

A. It would.

X Q. 22. So far as your examination of the arts has gone, was there any device or machine prior to the Jones invention, by which

the process of his 5th claim was carried out?

A. Now that the process has been invented and patented,

I think it possible that the process has been invented and patented, I think it possible that the process might be carried out imperfectly in some other presses that have been patented; but I am not acquainted with any press patented or invented prior to the Jones invention described in the patent in suit that could be used to practically carry out the process described in the 5th claim of the Jones patent. By "practically" I mean commercially practically.

X Q. 23. Can the process of the 5th claim be carried out independently of the press described in the Jones patent or any press

having similar functions?

A. To carry out the process there must be some means employed for putting the sheets under pressure, but the press need not have the construction nor all the functions shown in the patent in suit.

X Q. 24. What function could you omit from the Jones press and

carry out the process?

A. Well, instead of having a screw to press the heads together, the heads might be moved by means of hydraulic machinery, or by a system or levers. As a matter of fact, I believe that in most large establishments the head is now moved by hydraulic power.

X Q. 25. What function of the press shown in the Jones patent is

omitted by the changes indicated by your last answer?

A. I do not know, strictly speaking, that there would be any 11-96

function omitted by simply changing the screw of the Jones or substituting therefor hydraulic or other power, but if in add to that change such a press were set horizontal instead of inclinit would not have the function referred to in my answer to out to 5.

X Q. 26. Do you mean that, if the press of the Jones patent set horizontally or vertically, that the process of the 5th claim of

not be carried out on that account?

A. I do not, for I believe the process could be carried out press set horizontally, but not with the same facility as with one inclined.

X Q. 27. Could the process be carried out if the press were vertically instead of inclined?

A. I do not think it would be commercially practicable to co

out the process on a vertical press.

X Q. 28. Why?

A. It would be difficult to pile the signatures in the proorder in a vertical press.

X Q. 29. State why it would be difficult.

A. The reason is that sheets when folded and before they pressed are much thicker at their folded edges than at the unfol edges, so that in attempting to pile them in a vertical press t would be apt to slide off, and it would be very difficult to de any means to keep the folded edges in line with each other, whit is very necessary to do in the operation of dry-pressing.

X Q. 30. Wouldn't the difficulty you have spoken of be overed if the folded signatures were subjected to the action of a smar

before placed between the platens of a press?

A. I do not think that the action of a smasher would be suffic to prevent their folded edges being thicker than the unfolded o as the pressure is not retained on them long enough in a smash press.

X Q. 31. How long would the pressure have to be maintained

press the folded edges flat?

A. I have no means of knowing how long it would take, by should suppose it would take very nearly as long as it would to remove the impressions out of the paper in the old-fashion

fuller-board process.

X Q. 32. Is it in your opinion that the twine or ties used in Jones process put any additional pressure on the pile or has a thing to do with removing type impressions any more than to tain the pressure of the press until the fiber of the paper becomes the pressure of t

A. It is not.

X Q. 33. It's a fact then, is it not, that the pressure exerted moves the type impressions, and the ties only prevent the paper suming, partially, at least, the condition the paper was in bef pressure was applied?

A. That is my understanding of the process.

X Q. 34. If the bundle of signatures were removed from Jones press without being tied, how long do you think it wo take for the type indentations which had been pressed out to reappear?

A. I have never noticed paper under those circumstances, but should imagine that the impression would reappear immediately to some extent.

X Q. 35. Whether the signatures were separated or not?

A. Yes, if they were not kept under pressure.

X Q. 36. In the Jones patent in suit, the bulk compressor at the right of Fig. 1, is said by the patentee to be for the purpose of taking the swell out of the sheets, which, when first folded, are large at their heads. Was the patentee mistaken in supposing that the

smasher would press the folds flat?

A. Such a smasher would undoubtedly take out a good part of the swell, but in its ordinary operation it would still leave the folded edges rather thicker than the unfolded ones, as the fibers would not be set as they would be afterwards in the dry press, which forms the main feature of the patent, and the subsequent treatment to which the sheet would be subjected by being tied up for a lengthened period.

X Q. 37. What keeps the pile of signatures in proper position to prevent them from sliding or slipping one from the other in the bulk compressor or smasher shown in the Jones patent, which is a

vertical press?

A. There is nothing shown or described in the patent for that

purpose.

d

t

t

r

X Q. 38. If the bulk of signatures after being compressed in the smasher or bulk compressor shown in the Jones patent were placed between the platens of a vertical press and the platens brought together, do you think the type indentations would be removed from the signatures if the pressure was left on long enough?

A. If the platens were brought together with sufficient force and the pressure retained long enough, I see no reason why the type in-

dentations would not be removed.

X Q. 39. Well, if the same bundle were put in the Palmer press and pressure applied and the bundle tied to retain the pressure, why wouldn't the type indentations be removed if the bundles remained tied long enough?

Λ. If sufficient pressure could be produced on the Palmer press, the bundle enclosed in proper end boards, and the bundles tied and kept tied long enough, I believe the type impressions would be removed; but at the same time there would most probably be

imperfections in the bundle of signatures so pressed, inasmuch as it would be very difficult to keep all the folded edges of the sheets in line, and the result would be that some of the folded edges would overlap the folded edges of the others and thus the sheets would be imperfectly pressed, although the indentations might possibly be removed if great care were exercised in setting the bundle of signatures in the press.

X Q. 40. In view of the fact that it was quite common in the state of the art long prior to the Jones invention to provide guides for properly arranging sheets of paper and other material, one upon

the other, in power presses, do you think it would require invent to provide back or side guides for the Palmer press to retain bundle in proper position? Your attention is called to the Diman patent as as an example of a prior patent in which rear guiare provided, and the Kellogg patent having slotted guides around the platen; to the Stibbs patent, and to many other pate you have referred to in your direct examination.

(Question objected to as assuming a state of the art which has appeared.)

A. I do not think it would require invention to provide Palmer press with back or side guides, but even if it were proviwith such back or side guides it would not even then, in my or ion, be commercially practicable to carry out the Jones process it, because to carry out said process commercially it would be a essary that the signatures should be retained in a perfectly e position along the two folded edges, that is to say, the edges form the top and back of the book when completed. This could not done conveniently in the Palmer press, even with back and s guides, because there would be a tendency to slide one signature the other, owing to the thickness of the folded edges. Such gui as are shown in the patents referred to in the question would keep the sheets in proper position, even if the press had guides around, as in the Kellogg patent, for it would be necessary that space inclosed by the guides or sides of the press should be rat larger than the folded signatures, because some of the sheets in fe ing are not folded perfectly true; hence some of them have a lar surface when folded than others. There would thus be

trouble, which I have before referred to, of the folded ed of some of the sheets overlapping the others, and theref

being imperfectly pressed.

X Q. 41. By "commercially practical," I suppose you mean, t the process carried out on the Palmer press or on the other pres you have referred to could not be economically carried out. An right?

A. Generally speaking, that is the way I wish to be understo

X Q. 42. In criticising Mr. Hood's testimony you say that not of the patents he refers to was "designed to be used" in the man in which the Jones press is to be used. What difference would make, in a patentable sense, what a machine is designed for so leas it accomplishes a particular result?

A. It would make no difference.

X Q. 43. What advantage has either shown, described, or dicated in the Jones patent with relation to his machine aside from the process of his 5th claim that is not as fully shown, described a stated in the Dingman patent No. 40336? By the process I me the removal of type indentations only.

A. I consider the inclined position of the trough or bed as advantage, and the cross-ways as another, neither of which

shown in the Dingman patent.

X Q. 44. The Dingman patent combines in one machine be

JULY 27, 1895.

the press and table tie. It effects a great saving of time and labor, the paper is pressed uniform in thickness, no part of the ream can be moved out of its place by the process of tying, and by his process the bundles need not lie loose about the mill and be wasted, as is often the case. What other advantages has the Jones press except

the removal of the type indentations?

A. The inclined position of the bed has the advantage of allowing the folded edges of the signatures to assume their proper position, and to prevent the signatures from falling over, and besides this the cross-ways in the heads admit of the bundle of signatures being tied crosswise or with the ties at right angles. None of these advantages is shown in the Dingman patent.

Adjourned until July 27, 1895, at 10 a.m.

114

Proceedings resumed pursuant to adjournment. Present: Same counsel as before.

Cross-examination of T. J. W. Robertson resumed.

Examined by Mr. MURRAY:

X Q. 45. Do you consider claim 1 of the Dingman patent to refer

to a process or specific mechanism?

A. It seems to be a combination of the two, both process and specific mechanism. In somewhat similar claims to that in the Dingman patent the courts have construed them to be for the mechanism employed, if I recollect the decisions right.

X Q. 46. The claim is informal, but considering it as a claim for

the mechanism, as follows:

"In a paper press and tying engine, the combination of a series of jaws or corresponding upper and nether metallic plates, all disconnected, so that while the paper is being subjected to the required pressure it may be easily tied into reams or bundles." Would you

consider the Jones press to contain such invention?

A. If the broad construction usually given to a pioneer in an art were given to this claim, I believe that the Jones press would come under that description; but it may be that in view of the particular specific description of the parts contained in the claim the courts would limit it to the construction shown in the drawing, which the Jones patent does not show.

X Q. 47. Suppose it be limited to the specific elements of a claim

like the following:

In a press and tying engine, the combination of the frame, the stationary bed plate consisting of a series of metallic plates disconnected from each other, the movable platen consisting of a series of metallic plates arranged opposite the metallic plates in the stationary bed, and means substantially such as shown to move the upper platen or to form the stationary bed for the purpose of compressing a bundle of sheets and holding the pressure while the bundle is tied.

Would the Jones press contain such invention?

A. I believe such a claim would cover the Jones machine shown in his patent.

X Q. 48. Assuming the 1st claim of the Dingman pa to be for a process, and, removing the informalities, to r

The process herein described for treating sheets of paper, same consisting of subjecting a collection of such sheets to pres and while under such pressure tying them into compact burn and then removing them immediately from the press.

Would the practice of the Jones process as described in the pa

in suit be within the terms of that claim?

X Q. 49. Do you consider that the pressure heads shown in cut on the last page or back of Complainants' Exhibit "Cu Jones Bundle of Printed Signatures," to be a patentable imp ment over the pressure heads shown in the Jones patent in sui

A. I should hardly say so; it seems to me that they are only chanical equivalents of the devices shown in the Jones patent in

for the same purpose.

X Q 50. Do you consider the adjustable clamp shown in Fi 6 and 7 on the first page of the exhibit above referred to, to patentable improvement over the string or chain ties shown i other figures on the same sheet and also in the Jones patent?

A. So far as I can see, it is only an ordinary clamp, and wh may contain some feature in the details of construction not no parent to me which would render the same patentable, I do no sider that, considered simply as a substitute for the tie, it wou an improvement over the cross-tie shown in Fig. 5, because the pressure on the boards came in the center of each one, would be a tendency for the pressure of the paper to ben boards outwards at their ends, and therefore for the purpose moving indentations I should consider it an inferior device cross-ties shown in Fig. 5, as the pressure on the boards is ea all directions when the cross-tie is used.

X Q. 51. Would your opinion be the same if two clamp

used, one near each end of the bundle?

A. I think the pressure would be more equable under the cumstances, as there would not be the same tendency to be

board at the end.

X Q. 52. Would the employment of either one or these clamps, instead of the cross-tie, be an evasion 116 5th claim of the Jones patent?

A. I think not. $m X \, \, Q. \, \, 53. \, \, In \, \, the \, employment \, of \, either \, one \, or \, two \, of \, these \, cl$ would not be necessary to have cross-grooves in the pressurwould it?

A. It would not. X Q. 54. Is there any substantial difference between the heads shown on the back page of this exhibit, and the heads shown in the Cooley patent, No. 58779, except in the are five grooves or ways in the Cooley pressure heads, whi are but two in the exhibit referred to? You may also refer to the hand press on the preceding page of this exhibit in answering the question.

A. I consider that there is an essential difference between them, and this difference results from the use of the cross-ways shown in the presses illustrated on the exhibit, which are of such character as to allow of the introduction of the hand and forearm of the operator to allow him to readily tie the bundle of signatures in both directions with one tie, which is an important feature in the rapid working press. The grooves in the Cooley press I do not consider an equivalent of the cross-ways in the Jones press, for the reason that they are not adapted to be used in the same way, as, irrespective of the difference in the position of the grooves, they are too small to allow of the ties being readily passed through without the use of some such instrument as is shown in Fig. 6 of the patent; and even if a tie could be as readily passed through the groove in the Cooley press as it could through the cross-ways in the Jones press, their small size would prevent the ready manipulation of the loop which is necessary in the tying of a single tie crossing the bundle at right

X Q. 55. The grooves in the patent and in the illustration referred to are the same shape in cross-section and are arranged at right angles to each other, are they not?

A. They are, to both parts of the question.

X Q. 56. And the slots in the sides and ends of the press box are arranged in line with the grooves in the Cooley patent, are they not?

117 A. They are.

X Q. 57. In the Craig patent, No. 48523, there is shown in Fig. 3 a bale held compressed by two clamp ties passing over boards at each end of the bale to hold the pressure of the press. Is there any substantial difference between the method of holding the pressure illustrated in the Craig patent, and in Figs. 6 and 7 of the Complainants' Exhibit "Cut of Jones' Bundle of Printed Signatures"?

A. No. sir.

ent

ad

the

ire

es.

ent

he

of

ve-

ne-

uit

. 3,

e a

he

it

11)-

on-

be

all

ere

the

re-

the

m

ere

eir-

the

of

the

s, it

ids,

ure

ure

ere

X Q. 58. If instead of the side pieces A in the Archer patent, a single board was used, and printed sheets were baled in the same manner that the substances referred to in the patent were employed, would the practicing of such process be within the 5th claim of the Jones patent?

A. If the boards used were rigid end boards similar to the end boards referred to in the Jones patent, one at the top and one at the bottom of the bale, and the bale were allowed to remain bound sufficiently long to remove the indentations from the printed paper, I should consider that such process would be within the 5th claim of the Jones patent.

X Q. 59. The Palmer device as represented by Respondent's Exhibit "Sketch of Palmer Press," is a bookbinder's press and sheet-tie having compressing heads constructed with cross-ways centrally



CARD 2

arranged through them for the purpose of tying bundles of folded

signatures while under pressure, is it not?

A. Broadly speaking, that is correct, but not in the sense of the 1st claim of the Jones patent in suit. The claim is to the special "cross-ways L² L²" constructed to—as stated in about the middle of the first column of page 1 of the specification—"afforded access through them to readily insert and manipulate the twine, and to tie the bundles of paper while held compressed, thus securing the bundle together by a powerful tie." Such cross-ways are not shown in the Palmer press.

X Q. 60. The cross-ways L² L² are centrally arranged through the compressing heads of the Jones patent for the purpose of allowing the strings to pass through them to tie the bundle while under pressure. Isn't the same true of the cross-heads on the Palmer press?

A. If I correctly remember the testimony of the witnesses who have testified about said press, two strings are used in tying up a

bundle, which are laid in the grooves in the bed of the press before the paper is put in, and, after the paper is put in and pressed, the strings are passed through the grooves in the top block and tied; whereas by the construction of large-sized cross-ways, such as are referred to in the 1st claim of the Jones patent, a single string is used which is tied cross-wise of the bundle of signatures, so that it would take less time, probably, to tie the bundles both ways with a single tie than it would take to tie a single string by the method employed in the Palmer press.

X Q. 61. Is it anywhere stated in the specification of the Jones patent that one string instead of two strings is employed in tying up

bundles?

A. Not in those precise words, but I find in the first column of page 2 of the specification two references to the tie, in each of which the word "tie" is used in the singular, and nowhere do I find it referred to in the plural. I also find in a number of other places in the specification that the word "tie" is used in the singular.

X Q. 62. Is there anything in the drawing of the Jones patent to

indicate whether two strings or one string is used?

A. There is not.

X Q. 63. Would it require any invention to change the ways in the Palmer press to the shape of the ways shown in the Cooley patent?

A. It would not, but even then such ways would not be the equiv-

alents of the cross-ways of the Jones patent.


X Q. 64. Not even if the circular openings were made large to

pass the hand and arm of the operator through them?

A. If they were made large enough to pass the hand and arm of the operator through them, they would then be the same practically as the cross-ways in the Jones patent.

Redirect by Mr. Jacobs:

R. D. Q. 65. You have been asked somewhat about the Dingman press. Was it anything but a mere machine for loosely bundling unprinted paper?




APPENDIX.

COMPLAINANTS' EXHIBITS.

"Complainants' Exhibit Miller Sketch."

(Offered in evidence page 15.)




Susch p121




"Complainants' Exhibit Wood cut of Seybold Signature Press."

> (Marked for identification page 10. Offered in evidence page 16.)



Mo 96 } Busch \ p 122 Jone etal "Complainants' Exhibit Jones Sketch."

(Offered in evidence page 21.)




No 96) Nouseh p 123 Jourselal



"Complainants' Exhibit Jones Form of License."

(Offered in evidence page 22.)

ILLUSTRATING PATENT PROCESS DRY PRESSING AND SHEET-TYING.




3. Adjustable clamp. 4, 5, 6, 7, 8 and 9. Bundles of signatures, books, or paper, illustrating Patented Process, Dry-Pressing, Sheet-Tying, Smashing, Tableting. Nore.-The clamp is used for lifting the work out of the press when smashed, and firmly holding the same until it is passed over the saws, or to the sewing machine, and also to hold firmly 1. Rounded outer edges End Board. 2 and 10. Chain and rope ties. paper or sheets for gluing tablets, pamphlets, &c. LETTERS PATENT No. 204,741. - "Claim 5. The process herein described for treating folded printed sheets of paper in dry-pressing, the same consisting of subjecting a collection of such sheets to pressure without the use of fuller boards, and while under such pressure tying them into compact bundles with end boards, then removing them immediately from the press and allowing them to remain tied sufficiently long (Continued on next page.) to fix and complete dry-pressing.

Mogle Splay

**Complainants' Exhibit Hydraulic Presses."

Illustrating the old process of pressing between fuller boards.

(Offered.in evidence page 62.)




From " The Harper Establishment "

Copyright, 1855, by Harper & Brothers.

No. 96 Busch \ p/26 "Complainants' Exhibit Cut of Jones Signature Press used in the De Vinne Press."


Offered in evidence page 62.)



Jourselas Sp / My

"Jones' Steam Screw-Power Signature Press."


(Referred to by Defendant's Counsel, Plaintiffs' printed record pages 99-100.)



Jonesch Sp. 131

"Jones' Steam Screw-Power Signature Press."


(Referred to by Defendant's Counsel, Plaintiffs' printed record pages 99-100.)



Busch Sp. 131

"Jones' Hand Power Signature Press."

(Referred to by Defendant's Counsel, Plaintiffs' printed record page 100.)



Mo 96 Busch & p /32 Jones etal A. That is all, and from the construction of the mechanism for raising and lowering the upper plates it would seem to be incapable of producing much pressure.

R. D. Q. 66. Is it your understanding of the Jones process that the type indentations are removed by the exertion of

the pressure in the machine or by the retention of the press-

ure on the bundles?

A. By the retention of the pressure in the bundles, because if after a bundle has been pressed it is immediately opened the indentations will still appear; this is further proved by the fact that the longer the bundles stay tied up the better are the impressions removed.

R. D. Q. 67. Referring to your answer to cross-question 43, are

not the adjustable guide-rods another advantage?

A. They are.

T. J. W. ROBERTSON.

Complainants give notice that they have closed their testimony. Certificate of notary waived by defendant's counsel.

120 (Here follow diagrams marked pp. 121, 122, 123, & 124.)

125 Office of J. W. Jones patented process signature press for drypressing, sheet-tying, smashing, and tableting.

No. of press, —; style —; No. of license, —.

License.

In consideration of the sum of — dollars to me in hand paid, by — , of the city of — , in the county of — and State of — , the receipt whereof is hereby acknowledged, I do hereby license and empower the said — — to use in said city of — at shop situate — , and nowhere else, on machine style — , No. — , my improved process of dry-pressing and sheet-tying as described in the specification and pointed out in the fifth claim of my patent, No. 204,741, granted to me on the 11th day of June, 1878, from the time this license is made to the end of the term for which said letters patents are granted.

And for the same consideration, I hereby agree, in case of removal or sale by the said licensee, to transfer the right to use said process

to the new shop or the bargainee as the case may be.

Accompanying license No. -.

Bearing even date herewith.

Signed at Harrisburg, in the county of Dauphin and State of Pennsylvania, this — day of ——, 18—.

———, Patentee. [L. S.]

(Here follow diagrams marked pp. 126 & 127.)

"Complainants' Exhibit Cut of Jones Bundle of Printed Signatures," offered in evidence page 62, is the same as the cut at the head of "Complainants' Exhibit Jones Form of License," supra. Page 108.

"Complainants' Exhibit Thomas B. Penicks' Letter of February 25, 1879."

(Offered in evidence, page 77.)

Office of Public Printer, Washington, February 25th, 1879.

Mr. John D. Defrees, public printer.

SIR: Your note of the 23d inst., asking my opinion of the advantages and value of J. W. Jones' patent hydraulic printers and binders' pressing machine, is at hand.

I am pleased to have the opportunity of bearing testimony to the worth of these valuable machines. The three octavo and one quarto machines have been in operation several months. I have made

daily examinations of the work pressed.

There has not been a single instance of set-off. The work is equal, if not superior, to the old style of pressing, and is done with great rapidity. We have pressed and tied up 500 octavo sheets in 24 minutes. I think a fair average would be 6,000 sheets per hour. One of the greatest advantages of the machine is the solidity of the bundles for storage purposes. These machines will in a short time pay for themselves, alone, in the saving of sheets, soiled by the old style of pressing and tieing up. The longer I use the machines the better I like them, and I should dislike very much to do without them.

Respectfully, &c.,

THOS. B. PENICKS, Sup't Folding Room.

129 "Complainants' Exhibit Thomas B. Penicks' Letter of February 5th, 1880."

(Offered in evidence, page 77.)

Government Printing Office, February 5th, 1880.

Hon. John D. Defrees, public printer:

In reply to your letter of inquiry relative to the merits of J. W. Jones' hydraulic pressing machine and process, I can only say, that a year's experience confirms a previous testimonial in behalf of these machines. With our seven machines, we can press and the up, hourly, 52,500 octavo 16-page sheets. The indentations of the

type are entirely removed; I have yet to find a single instance of set-off. For rapidity in pressing and compactness of the sheets, the machines have no equal. I now press all books after being gathered. This is a great advantage to the binder, as it makes the books all regular, more solid, ready for sewing, and invaluable for storing.

Respectfully, &c.,

THOS. B. PENICKS, Superintendent.

"Complainants' Exhibit Thomas B. Penicks' Letter of August 3rd, 1886."

(Offered in evidence, page 77.)

Government Printing Office, Folding-room, Washington, D. C., August 3d, 1886.

Hon. S. P. Rounds, public printer.

Dear Sir: The hydraulic pressing machines of J. W. Jones, of Harrisburg, Pa., were introduced in this office in the year 1878. We, like most all other printing establishments, used the ponderous dry-pressing machine, pressing the sheets between fuller-boards. This process was slow and expensive. After introducing the first four of Jones' hydraulic pressing machines, the pay-rolls of the drying-room was reduced about \$68.00 per day. We have now in use fourteen machines, 9 octavos and 5 quartos. These

pressing machines remove all the indentations of the type from printing. I have given this process the severest test on plate-work, and as yet, I have been unable to discover any set-off. After the work is pressed in bundles it still retains the pressure. This is a great advantage to the work, and also for storing purposes. This office uses 32,000 square feet for storing pressed sheets and books. Were it not for the use of these machines, we would require double of our present storing capacity. The pressed work, also, lessens the chance of destruction by fire. All books gathered are pressed; they are then ready for sewing. This does away with the old process of smashing or pressing in standing presses by the binder. These hydraulic pressing machines are invaluable to this office; and I believe for economy, perfection of work, and labor-saving, the best piece of machinery ever introduced in the trades of printing and binding.

Respectfully, &c.,

THOS. B. PENICKS, Supt. of Folding-room.

Other exhibits were offered in evidence by complainants, viz: "Complainants' Exhibit Model No. 1" (printed Record, page 16). "Complainants' Exhibits Printed Sheets A 15, A 15*, B 15, B 15*" (printed Record, pages 5 and 16).

"Complainants' Exhibit Sample of Press-board" (printed Record,

page 62).

(Here follow diagrams marked pp. 131 & 132.)

135-137 In the Court of Appeals of the District of Columbia.

CLARENCE M. Busch, Appellant,

J. W. Jones and The W. O. Hickok Manufacturing Company, Appellees.

No. 903, October Term, 1899.

It is hereby stipulated and agreed by and between counsel for the parties hereto that there is no question concerning the incorporation of The W. O. Hickok Manufacturing Company, one of the appellees, and that printing of "Complainants' Exhibit Certified Copy of Articles of the W. O. Hickok Manufacturing Company" may be dispensed with. It is further stipulated and agreed that a copy of "Complainants' Exhibit Contract of Jones and Hickok Manufacturing Company" and a copy of the specification of U. 8. patent No. 9324, dated October 12, 1852, to Kellogg, may be printed in their proper places in the transcript of record for this court.

CHAS. E. RIORDON,
Of Counsel for Appellant,
M. W. JACOBS,

Of Counsel for Appellees.

August 31, 1899.


(Endorsed:) Court of Appeals, D. C., October term, 1899. No. 903. Clarence M. Busch, appellant, vs. Joshua W. Jones et al. Stipulation of counsel. Court of Appeals, District of Columbia. Filed Sep. 6, 1899. Robert Willett, clerk.



J. W. JONES. Book-Binders' Dry-Press and Sheet-Tie.

No. 204,741.

Patented June 11, 1878.



UNITED STATES PATENT OFFICE.

Joshua W. Jones, of Harrisburg, Pennsylvania.

Improvement in Bookbinder's Dry-press and Sheet-tie.

Specification forming part of Letters Patent No. 204,741, dated June 11, 1878. Application filed October 24, 1877.

To all whom it may concern:

Be it known that I, Joshua W. Jones, of the city of Harrisburg, in the county of Dauphin and State of Pennsylvania, have invented a new and useful improvement in bookbinder's dry-press and sheet-tie, which improvement is fully set forth in the following specification and accompanying drawing, in which—

(Here follows diagram marked p. 138.)

Figure 1 is a perspective view of my invention, exhibiting a bundle of sheets in the press tied and ready for removal therefrom. Fig. 2 is a perspective view of a bundle of sheets tied and ready for setting aside, as by my process of treating printed papers or sheets to remove therefrom the indentations of types. Fig. 3 is a perspective view of my divided press plunger or follower. Fig. 4 is a cross-sectional view of my press-frame and the divided follower applied thereto, the view being taken at indicated line x, Fig. 1.

The object of my invention is, first, to furnish a bulk-compressor device, to be used to prepare the matter properly before it is inserted in the dry-press proper, thus saving time or repeated travel by the latter, before the operation of tying; second, to furnish a dry-press proper in which the compressing parts or heads-that is, the base and plunger-are constructed dividedly, or with ways through them, to afford access through them to readily insert and manipulate the twine, and to tie the bundles of paper while held compressed, thus securing the bundle together by a powerful tie, which, when they are removed from the press, retains its force ad libitum; third, a press-frame, having sides peculiarly set and arranged, and provided with longitudinal slots therein corresponding with the ways in the press-heads, above referred to, and for the same purpose, as well as to rightly lodge and center the paper with relation to the middle of the press-heads; fourth, certain ledges in the said press-frame and guides on the plunger thereof, to properly center different-sized sheets in press to secure the tie at the middle of the bundles both ways; fifth, a new process for treating printed and folded sheets of paper in dry-pressing, consisting of subjecting a collection of such sheets to pressure without the use of fullerboards, and while under such pressure tying them into compact bundles, with end boards thereon; then removing them immediately from the press, and allowing them to remain tied sufficiently long to fix and complete the dry-pressing.

My bulk-compressor (shown at right of Fig. 1 in drawing) consists of uprights K K², transverse parts K¹S W′, the treadle M, connected by link N P to lever Q, which, by being pivoted to bracket R, operates the plunger T W, to which it is also pivoted. The folded sheets, which are swelled or large at their heads when first folded are placed upon the base W′ and smashed—that is, the swell is taken out of them—by the plunger W, to bring the bulk into manageable compass for ready insertion into the dry-press and sheet-tie proper, so that about five hundred folded sheets may be pressed and tied at one operation, that number of sheets being usually put into one bundle. The said compressor device is therefore connectedly arranged with or near to the said dry-press device, that work may be readily transferred from the former into the latter.

The left part of Fig. 1 in drawing represents my improved dry.

press and sheet-tie device.

The operations of dry-pressing and sheet-tying are accomplished by the same device. It consists of a bed, H H², mounted upon uprights E and K, in such manner that it has a downward inclination from the former to the latter upright, as shown in Fig. 1, and the sides of said bed H H² are set laterally inclined, trough form, so that the folded paper may securely lodge and carry therein while being operated on. The sides H and H² of said bed are longitudinally slotted at H¹ to correspond with the open ways L² L² of the press-heads, as shown in Fig. 4, to afford access to the work while in the press to tie into bundles, as shown in Figs. 1 and 2.

In the trough of said bed H H² are firmly attached thereto the blocks B¹ B², in position as shown. Block B² is the base of the divided head F F F′, constructed with openings or ways L², similar to the plunger-head shown in Figs. 3 and 4. The divisions F F of said head are supported, either on pedestals F′ or on the frames H and H², at suitable distance from base B², to enable the operator to pass the hand between said parts while applying the tie.

Block B¹ is, in the present illustration, shown to be a stationary nut, in which the serew B serves to operate the plunger or follower C D D', which is connected by swivel to said screw, and the screw is provided with handles a a' about its head A. It is, however, evident that said follower may be actuated by other mechanical means; also, that two such followers may be made to act in conjunction. I do not therefore limit myself to screw-power, nor to a single follower, as in practice both heads of the press may be made movable, and other than screw-power may be employed, the more definite limits of my invention being in the make of the heads, they being slotted or thorough-channeled by cross-ways L² L², corresponding with slots H¹ of the bed.

The follower or plunger head shown in Fig. 3 consists of the base C, pedestals D, and bearing-divisions D', disposed oppositely about the central cross-ways L² L², as shown, the plan being similar to that of the stationary or opposite head B² F' F; and the bundle of sheets L is inserted between said heads, as shown in Fig. 1, it being cross-tied over end boards L³ by twine L¹, as shown in Fig. 2.

It may be noticed that the bodies or bundles of the folded sheets

are so located in the press-trough H H² that the middle part of the ends of said bundles may come under or opposite the middle part of the press-heads—that is, in right position before the ways L² L²—

to secure the tie over the middle of bundles both ways.

When large work is being pressed and tied, no special adjustment of the press is needed to locate the work centrally, as described; but when intermediate and small-sized work is operated on, it is kept properly distanced from the press-sides H H², either by removable ledges f lodged in grooves in said sides H H², as shown, or by sliding adjustable rods m, removably attached to the plunger-divisions D' at v, and allowed to pass freely through the parts F, B², and K. (Shown in Fig. 1.) That said plunger D D' C may not be sprung out of its true line of travel, owing to the pile of folded sheets canting, it is stayed laterally to the press-sides H H² by clips G G, made to embrace and slide along them, as shown in Figs. 1 and 4.

In my improved process of dry-pressing, the end boards on the bundles referred to are shown in Fig. 2 in position on the bundle, immediately under or subject to the tie. They are used on the ends of the bundle of the paper under treatment to distribute the pressure over the whole area of the ends of the bundle, and also to prevent cutting or marring of the paper by the twine or other tying material. Said end boards are made of any suitable material affording strength and rigidity at little cost, and of suitable size to nearly match the

size of the folded work.

Besides the advantage attained by my improvement in rendering v-pressing speedier, less laborious, and less expensive than by the rocesses heretofore employed, it also makes the work more convenient to handle and rank up until required for binding, and avoids the not infrequent mishap of tumbled and scattered work on the floor of the bindery, and consequently lessens the risk from fire.

Having thus described my invention, what I desire to secure by

letters patent is embraced in the following claims:

 In a printer's and bookbinder's dry-press and sheet-tie, the compressing-heads C D D' and B² F' F, constructed with cross-ways L² L², centrally arranged through them, substantially as and for the

purposes herein set forth.

2. The inclined press-bed H H², provided with longitudinal slots H¹ H¹ in its sides, in combination with the press-heads B² F′ F and C D D′, having through them the cross-ways L² L², correspondingly arranged with said slots, substantially as and for the purpose set forth.

3. The press-head C D D', connected by swivel with screw B A a a', and made to travel as a plunger in the nut or block B', in combination with bed H H² and clips G G, substantially as and for the purpose set forth.

4. In combination with the dry-press bed H H², the device of a set of removable ledges, f, or a set of adjustable guide-rods, m, ar-

ranged as and for the purpose set forth.

5. The process herein described for treating folded printed sheets of paper in dry-pressing, the same consisting of subjecting a collec-

tion of such sheets to pressure without the use of fuller-boards, and while under such pressure tying them into compact bundles with end boards, then removing them immediately from the press, and allowing them to remain tied sufficiently long to fix and complete dry-pressing.

In testimony that I claim the foregoing as my invention I have hereunto set my hand and seal this 20th day of October, 1877.

JOSHUA W. JONES. [L. s.]

Witnesses:

THOMAS McCAMANT. W. H. SMITH.

141 Complainants' Exhibit Contract of Jones and Hickor Manufacturing Company.

Articles of agreement, made the 27th day of December, 1889, by and between Joshua W. Jones, of the city of Harrisburg, State of Pennsylvania, of the first part, and the W. O. Hickok Manufacturing Company, a corporation doing business under the laws of the State of Pennsylvania and located in said city of Harrisburg, of the second part.

Whereas, the said party of the first part has invented certain new and useful improvements in the method or process of dry-press as set forth in letters patent No. 204,741, granted to him on the tanday of June, 1878, and certain improvements in mechanappliances for carrying out said method or process as said letters patent No. 204,741, in letters patent numbers as follows: Nos. 212,977, M'ch 4, 1879; 219,73′ 9; 223,355, Jan. 6, 1880; 224,696, Feb. 17, 1880 pt. 20, 1881; 9598, reissued M'ch, 1881; and in certain consum on file in the U. S. Patent Office; and

Whereas, the said party of the first part has made of caused to be made divers valuable patterns of whereas the said party of the first part has created a decrease of said machine and the right to use the process of dry-pressing and sheet-tying and whereas the said party of the second part is desirous of acquiring a license as sole licensee from said party of the first part to manufacture and sell said machines and appliances together with the right to use said patterns in making said machines and appliances, and also of acquiring the business established by said party of the first part in the particular branch of the art to which said inventions pertain, upon terms mutually advantageous to both of said parties, it is therefore agreed by and between said parties as follows; that is to say:

The said party of the first part, for the considerations hereinafter named, does hereby agree to empower and license and does by these presents empower and license the said party of the second part to manufacture and sell the several machines, articles and appliances

covered by the letters patent already obtained and those which may hereafter be obtained by himself or others in the manner hereinafter mentioned or by assignment; and does also for the said considerations agree to transfer and turn over to the said party of the second part all business that he now has relating to said machines, articles and appliances, together with all patterns, with the right to use the same, now owned or used by him in the manufacture of said machines, articles and appliances or any of them, and any cuts or other articles which may or will assist the said party of the second part in placing the said business before the public.

The said party of the first part further agrees that the license hereinbefore provided for shall be an exclusive one, and that he will not, during the lifetime of this contract, give or grant any other license or right to manufacture or sell said machines, articles and appliances or any of them, to any other corpora-

tion, person or party whatsoever.

In consideration whereof, the said party of the second part doth

hereby agree:

1. To pay to the said party of the first part, his heirs or assigns, a royalty of twenty-five per centum on the selling price of all machines manufactured and sold, and ten per centum on all supplies and appliances used in connection with such machinery, and sup-

plied by the said party of the second part.

2. To keep a strict and proper account of all sales; to render to the said party of the first part a full and true statement of said sales, and the royalties herein reserved quarterly on the first day of January, April, July and October in each year, during the lifetime of this contract, which royalties shall become due and payable within thirty days thereafter, and to give to the said party of the first part free access to the books of the said party of the second part, at all reasonable times, to enable him to examine the same and verify

such statements, if he should so desire.

3. The royalties payable to the said party of the first part under this contract shall be held to apply to all machines, appliances or articles manufactured and sold by the said party of the second part, its successors and assigns, and containing any of the processes, improvements or devices covered by said letters patent or any of them, or by any patents which may hereafter be issued to the said party of the first part or be owned by him, relating to the process of drypressing and sheet-tying, whether some or any of said letters patent shall have expired or not, but this contract shall not preclude or prevent the said party of the second part from manufacturing and selling other machines, appliances or articles designed to accomplish the same results, which do not in whole or in part contain any of the processes, devices or improvements covered by any existing or expired letters patent then owned by the said party of the first part; provided, however, that if at any time during the lifetime of this contract, by reason of the expiration or invalidity of one or more of the patents now owned or hereafter obtained or acquired by the said party of the first part, other corporations or parties shall be enabled to manufacture and sell said machines, appliances or articles, or those similar thereto and capable of accomplishing the same results, so that the said party of the second part cannot compete therewith in the open market at the royalties hereinbefore provided, then and in that case there shall be such a re-rating or readjustment of said royalties as will admit of such competition and be then mutually agreed upon, to the end that the interests of both parties to this contract shall be fully protected, and the purpose thereof be fully carried out to the full end of the term thereof. And provided further, that if the said parties cannot agree as to the royalties, so as to be re-rated and readjusted, then and in that case each party shall select one disinterested person who shall

thereupon re-rate and readjust said royalties, and if the persons so chosen cannot agree they shall in turn choose a third person as an additional arbitrator and the decision of the three persons so chosen as to the royalties aforesaid shall be final and bind-

ing upon both of said parties.

4. That if said party of the second part or any of its agents or workmen should at any time, during the existence of this contract, make or discover any improvements to the said machines, articles or appliances, or any of them, whether patentable or not, the same shall be considered the property of the said party of the first part and if any letters patent be obtained therefor by the said party of the second part or in its behalf, such letters patent shall be assigned to the said party of the first part without further consideration, and if in the opinion of the said party of the first part the improvement is patentable or worthy of a patent, the said party of the second part will execute or have executed all the necessary papers to secure proper letters patent or patents and the issuance of the same to the said party of the first part as its assignee, at his expense.

The said party of the second part further agrees to make all reasonable efforts to create and stimulate a market for said machines, appliances and articles, and generally to push the said business for

the mutual benefit and advantage of both parties hereto.

It is also mutually agreed and understood, without further consideration, that the said party of the first part does not by this contract assign or agree to assign any of his right, title or interest in said invention patented now or to be patented hereafter, except that the said party of the second part shall be the sole licensee while this contract exists.

It is also mutually agreed and understood, without further consideration, that this contract shall run for twenty years and so long thereafter as the said party of the second part, its successors or assigns, shall manufacture or sell or procure others to manufacture and sell any machines, supplies or appliances for carrying out the process of dry-pressing or sheet-tying set forth in said patents now existing or to be procured hereafter or any of them, subject, however, to the stipulations and provisions hereinbefore contained and reserved in clause three (3).

It is also mutually agreed and understood, without further consideration, that this contract covers the manufacture and selling by said party of the second part whether it be done in its own shops of

at the shops of other parties with the consent and allowance of said

party of the second part.

It is also mutually agreed and understood, without further consideration, that this contract binds said party of the first part his heirs or assigns and said party of the second part its successors or assigns for the full period for which the same has to run under the terms and conditions hereinbefore specified and contained.

It is further agreed that the said party of the first part shall turn over and assign to the said party of the second part all complete machines and appliances heretofore made for him since April 1st,

1889, and remaining unsold, and also all circulars, cuts and
printing matter or material, used or owned by him in advertising the said business, and in consideration thereof the said
party of the second part agrees to pay to him in cash the sum of
\$68,00, for circulars, envelopes, etc., and on all unsold machines and
appliances in stock to pay when sold the royalties provided for in
clause one (1) of this agreement.

In witness whereof, the said party of the first part hath hereunto set his hand and seal and the said party of the second part hath caused to be hereunto affixed its corporate seal attended by the

signature of its secretary this 27th day of December, 1889, in duplicate.

J. W. JONES. [SEAL.] THE W. O. HICKOK MFG. CO., By ROBERT SNODGRASS.

For the President.

Attest: LUCIUS S. BIGELOW, Secretary.

Deposition of Harrison P. Hood. Filed October 7, 1895.

Supreme Court of the District of Columbia, Sitting in Equity.

Joshua W. Jones and The W. O. Hickor Manufacturing Company vs. Clarence M. Busch.

Taking of testimony and offering of evidence in the above-entitled cause before David S. Oliver, notary public, No. 28 Wiggins block, Cincinnati, Ohio, commencing Thursday, June 13th, 1895, on behalf of respondent, pursuant of agreement of parties.

Present: M. W. Jacobs on behalf of complainant-, and George J. Murray on behalf of respondent.

Harrison P. Hood, witness produced on behalf of respondent, being first duly sworn, deposes and says, in answer to interrogatories propounded to him by Mr. Murray, as follows:

Q. 1. State your name, age, residence and occupation.

A. Harrison P. Hood; 54; Indianapolis, Indiana; patent solicitor and expert.

Q. 2. Please state what, if any, experience you have had as a practical mechanic, and also what experience you have had in reading and interpreting letters patent or mechanical inventions that would enable you to testify as an expert in suits brought for infringement of letters patent.

A. For more than twenty years past I have been engaged in preparing and prosecuting applications for patents for new inventions. During the greater portion of this time I have carried on in connection with my office, a workshop where, under my direction, models

of new inventions have been made, experimental machinery has been constructed, and I have made a business of putting

into practical shape the ideas of the inventors. I have also been frequently called upon to testify as expert in patent causes in which were involved the examination of mechanical devices and the reading and construing the letters patent in connection therewith.

Q. 3. Have you examined letters patent of the United States No. 204,741, dated June 11, 1878, upon which this suit is founded, said patent being identified in the record as "Complainants' Exhibit Jones Patent No. 204,741," and do you understand the same?

A. I have examined Complainants' Exhibit "Jones Patent No.

204,741," and I do understand it.

Q. 4. Please state what you understand the invention to be that is described in this patent and pointed out in the claims, your attention being called particularly to claims 1, 2, 4 and 5 of the said patent, and, in order to make your answer clear, you may refer to the letters patent and publications before you, identifying each as you refer to it, and give your reasons for any opinion you may ex-

Dress

A. The invention shown and described in the Jones patent No. 204.741, relates to a means for removing from printed sheets the type indentations and elevations made during the process of printing whereby a smooth surface is given to the back side of the printed sheet. One of the methods in common use for accomplishing this result, at the time of the filing of the application of the Jones patent was as follows: A pile was formed of printed sheets and hard glazed boards, called fuller-boards, arranged alternately, one on the other. The pile thus formed was placed between the platen and the follower of a suitable press and a powerful pressure applied. The pile being allowed to remain under pressure for several hours. The purpose of the Jones invention appears to be to save this great expenditure of time and to dispense with the use of the fuller-boards. To this end Jones conceived the idea of retaining the pressure communicated by the press to the pile after the pile had been removed from the press. For this purpose he contrived a press in which the pile of printed sheets, made up without fuller-boards, might be placed a stiff board of substantially the same size as the printed sheets, being placed at each end of the pile and the platen and follower of the press being so constructed that cords might be conveniently passed around the package formed of the printed sheets and end boards, and securely tied while the pile was still in the press. A package was thus formed which, when removed from the press, would retain the printed sheets under pressure any length of time desired and leave the press free for use in forming other packages. In his drawings and specification Jones illustrates two forms of press. One a vertical press, having a follower which is actuated by a series of lever- and used for the purpose of smoothing out or straightening folded sheets, forming book signatures, so that they might be conveniently piled and occupy but a small space, and this press is used simply to prepare matter for the other press, and is not claimed as any part of his patented invention. The press in which the 146 packages are formed consists of a trough-like structure formed of two boards or plates secured together to form a right angle and supported by standards, with the open side of the trough upwards, one of the standards being shorter than the other, so that the

and supported by standards, with the open side of the trough upwards, one of the standards being shorter than the other, so that the bed occupies the position slightly inclined from the horizontal. Near the end of this trough-like structure are rigidly secured a pair of rectangular blocks. One of these blocks serves as a foot or platen of the press; the other one serves as a nut for the pressure serew. Attached to the pressure screw by a swivel connection is a rectangular follower which is guided by the sides of the press and is adapted to be moved along the press bed by the screw. The opposed faces of the platen and the follower are each provided with a pair of straight open ways, crossing each other at right angles and intercepting at points substantially in line with the axis of the pressure serew. The two sides of the press bed are provided each with a longitudinal slot which registers with one of these ways in the follower and the platen, the whole construction being such that a package contained under pressure between the follower and the platen may be bound by cords passing through the open ways and the slotted sides of the press. The intention is that the binding cords shall cross each other centrally of the end boards of the package, and the inventor explains that "when large work is being pressed and tied, no special adjustment of the press is needed to locate the work centrally, as described; but when intermediate and small-sized work is operated on, it is kept properly distanced from the press sides, H. H², either by removable ledges, 1, lodged in grooves in said sides Π and Π^2 , as shown, or by sliding adjustable rods, m, removably attached to the plunger divisions, D' at v, and allowed to pass freely through the parts F, B^o and K.

Of the claims which you have mentioned in your question, Nos. 1, 2 and 4 relate to the construction of the press and claim 5 relates to the process for treating the folded sheets. Claim 1 includes simply the particular construction of the platen and follower termed the compressing heads," whereby they are adapted to permit the insertion of the binding cord while the package is under pressure. The second claim includes, in addition to the construction of the compression heads, the particular form of the press bed. Claim 4 is for the combination with the press bed of two alternative forms of guides for centering the sheets in the press. Claim 5 is in the

following words:

"The process herein described for treating folded printed sheets of paper in dry-pressing, the same consisting of subjecting a collection of such sheets to pressure without the use of fuller-board while under such pressure tying them into compact bundle end boards, then removing them immediately from the preallowing them to remain tied sufficiently long to fix and codry-pressing."

In determining what was new in this process at the till Jones application was filed, it will be interesting to know m before practiced in this particular art in the art of bookbi

As pertinent to this subject, I quote from a book pul in 1856 by Henry G. Baird, entitled "A Manual of the Bookbinding," by James B. Nicholson. I quote first

page 41, under the title "Beating, pressing, &c.":

"The operation is commenced by shaking the volume ustone by the back and head, so as to make the whole even a facilitate the division of it into as many equal parts, which called searching or beatings, as may be judged necessary accepted to the fitness and other circumstances. A section is then take well beaten over, drawing it in the hand towards the body so bring the various parts successfully under the hammer, and fully avoiding striking more blows in one part than in the except giving the edges a slight extra tap round."

Quoting again from page 43, in the same book:

"A rolling machine has been invented as a substitute for beating which books require previous to being bound. The is divided into parts, according to the thickness of the books part is then placed between tins, or pieces of silver; the rolled then put in motion and the part passed through. This is required the requisite degree of solidity is obtained."

Again quoting from page 44:

"A powerful embossing press, technically called a smashe lately been employed to great advantage. A book is placed be tins, a platen is adjusted to a proper height, and a large fly-set in motion. The platen descends in a perpendicular mathen, upon its ascending, by means of a small hammer the disbetween the platens is decreased; the wheel still continuing ition, the book, upon the descent of the platen, is compressed forcibly than at first. The operation is repeated until the book experienced the whole power of the press. It has been caled that by this process a single volume will, if necessary, undepressure equal to a weight of from 50 to 80 tons."

Page 45:

"In some binderies a hydraulic press is relied upon for coming the sheets, without their undergoing the beating or reprocess. For publishers' work it has been found to answer purpose for which it is employed, as the press can be filled or placing books in layers of from one to four or eight, according their size, between iron plates; and the immense power of the is thus evenly distributed through a large quantity of sheets a same time."

Again I quote from a book entitled "The English Cyclop Arts and Sciences," volume 2, published in London, by Brad and Evans, in 1859. On page 267, under "Bookbinding," in the left-hand section of the page, near the top, I find the following state-

"If the sheets thus folded, gather- and collated, are to be put into boards, they are sewn in the next process; but if they are to be bound, and therefore finished in a more careful manner, they are beaten or pressed before being sewn, as a means of bringing them to a more compact and smooth state. Until a recent period this process used to be affected by means of the hammer—the volume

being divided into parcels of a few sheets; and these parcels, held flat on a smooth stone, being beaten with a heavy ham-

mer. But the rolling press has greatly improved the mode of This press consists of two smooth steel rollers, rotating nearly in contact; the parcels of the volume are placed between tin plates and then passed between the rollers, the action of which gives then a more effective and expeditious pressure than the hammer. Sometimes, however, the ink becomes transferred to the opposite page by this process, when not properly conducted—to the great disfigurement of the book."

It is evident from these quotations that it was a matter of common knowledge and practice in the art of bookbinding, at the time of filing the Jones application, to subject an assemblage of printed sheets forming a pile, without the use of fuller-boards, to heavy pressure for the purpose of solidifying and smoothing them. It is also evident that when a package of printed sheets forming a pile of book signatures was to be subjected to pressure, that the placing of rigid boards or plates at the ends of the pile would operate to evenly distribute the pressure over the surface of the sheets. It is evident therefore that we must look for the novelty of this process to that step in the process which consists in "tying them (the collection of sheets) into compact bundles * * * then removing them immediately from the press, and allowing them to remain tied sufficiently long to fix and complete dry-pressing.

As bearing upon this phase of the subject, I will refer to the following U.S. patents, copies of which have been placed in my hands

as exhibits in this case.

No. 2113, issued May 29, 1841, to Thomas G. Hardesty, for improvement in tobacco presses.

No. 9324, issued October 12, 1852, to Daniel Kellogg, for improvement in presses for binding flocculent and other substances.

No. 40336, issued October 20, 1863, to William R. Dingman, for

improvement in paper presses.

No. 48523, issued July 4, 1865, to Oliver P. Craig, for improvement in bailing presses.

No. 58779, issued October 16, 1866, to Solon Cooley, for improvement in wool presses.

No. 119,195, issued September 19, 1871, to Thomas Stibbs for improvement in presses for pressing yarn, &c.

No. 125,786, issued April 16, 1872, to Charles Brown for improvement in baling short-cut hay or straw.

No. 169,518, issued November 2, 1875, to Charles Brown for improvement in baling short-cut hay.

No. 181,389, issued August 27, 1876, to James B. Archer for im-

provement in baling manure and other substances.

Of these patents No. 181,389 shows a bale formed supposedly of a mass of stale manure confined between two light frames formed as follows:

"The two frames are each composed of side pieces A, A, and end pieces B, B, consisting of wooden slabs, the said side pieces being of a length equal to the length of the bale, and the said end pieces being of a length equal to the width of the bale. These side

and end pieces are nailed or otherwise secured together at the ends to form the frames, which are thus made of a size

the ends to form the frames, which are thus made of a size and form to cover the edges of the two opposite sides of the bale to which they are tied. * * * The frames A, B having been made, the bale is formed in a baling press of suitable size by first placing one of the frames on the bottom of the box of the press, then filling in upon it the requisite quantity of the material to be baled, afterward putting on the top frame, and then subjecting the contents of the bale between the frames to a suitable pressure. The bands having been applied at a suitable stage in the operation, have their ends fastened while the bale is subject to pressure, and after they have been fastened the box of the press is opened and the bale turned out."

Substituting for the material mentioned in this patent as forming the bale, folded printed sheets of paper, we have the entire process of Jones as claimed in claim 5. The steps are taken in the same order and would, in my opinion, produce the same result.

In patent No. 169,518, a bale somewhat similar to the last-described bale is shown, the difference being in the particular construction of the end boards or frames. The process is the same. One of the end frames is laid in the press, the material is then filled in above it and the other end board is put on top.

"Pressure is then applied to the mass thus bound and protected, and when sufficiently compacted, bands, cords, ropes, or wires, D D, are passed and fastened around the compressed mass of short-cut hay or straw, with or without feed, and around the sticks or binders, A, A¹, and slats C, C¹, to retain the bale in its compact form.

In patent No. 125,786, we have illustrated another example of a bale formed between end boards and bound while under pressure. In this case the form of the bale is cylindrical with plain ends. I

quote from the specification:

"To press the short-cut hay or straw, A, into the form of a hollow cylinder, as shown, said material may be suitably piled or packed in a box of cylindrical shape, open at its ends, and resting on a grooved base for passage of the binding ropes, cords, or wires, said base also carrying a mandril for forming the passage b in or through the bale and the follower of the press, which works within the box, being grooved like the base, also made hollow to receive the mandril through it. The box itself should be made to open down its side, either by means of hinges or otherwise, so that when opened

it may be removed, whereby the bale is left wholly exposed at its sides for the convenience of hooping or binding it, the hoops, ropes, or wires, c, being passed through grooves in the base and follower in planes parallel with the axis of the base, and over segmental wooden strips, d, arranged to lie one upon the other, so as to brace the ends of the bale without impairing the ventilation."

Adjourned to Friday, June 14, 1895, at 10 o'clock a. m.

150 Met, pursuant to adjournment, Friday, June 14, 1895. Present: Same parties as before.

Witness continues his answer:

The examination of these three last-mentioned patents makes it evident that the idea of tying a package protected by end boards while under pressure was not first discovered by Mr. Jones. It seems to me the process claimed in claim 5 is without an element of patentable novelty. Neither of these patents just mentioned show- any machine for communicating the pressure to the bale, but they all imply such a construction of the press as renders the tying of the bale possible while under pressure. Examining further into the state of the art, we find shown in patent No. 119,195 a press for forming yarn into packages. This press consists essentially of a base having a series of grooves across its upper surface, a pair of vertical sides rising from the opposite edges of the base and proyided with open slots which register with the grooves in the base, brackets extending from these vertical sides to form a support for a plate carrying a pressure serew to which a follower is attached by a swivel joint and the under face of this follower is provided with a series of grooves corresponding with the grooves in the base. The plate carrying the pressure screw and its follower is arranged to slide upon its support and upon the upper edges of the vertical sides of the press, so that the follower may be brought into position over the base or may be pushed to one side so as to leave the top of the press open. In forming the packages, the tie-ropes are first passed through the grooves in the base and the material is then piled into the press, the vertical sides of the press forming guides for the orderly arrangement of the material. The follower is then brought into position and the mass is compressed, after which the free ends of the binding cords are passed through the vertical slots, through the grooves in the follower and is then tied while the package is under pressure. Packages like those formed in the press shown in the Jones patent might be easily and conveniently formed in this press, the only difference being that the cords would pass about the package in one direction only.

In patent No. 58779 is shown a press for making wool fleeces into compact packages. The press consists essentially of a bottom board or base to the sides of which are hinged side and end pieces arranged in such a manner that they may be opened out into the same plane with the bottom board, or may be raised vertically to form therewith a square box, open at the top. A follower adapted to fit loosely into the box thus formed is provided with dogs which engage ratchet

14-96

bars, which are secured to the sides, so that the follower when pushed down, is retained in position. The opposed faces of the bottom board and the follower are each provided with two series of grooves crossing each other at right angles, and registering with vertical slots formed in the sides of the press. These grooves, which are formed in the bottom board and in the follower, form intersecting open ways for the passage of the binding cord, and they each open into an enlarged space immediately back of the groove.

which permits the easy introduction of the binding cord.

They are in this respect the complete counterpart of the cross-ways L², L², of the Jones patent. In using this press, after the material has been compressed, the cords are drawn through the grooves in the bottom boards of the press, and are then passed about the package in opposite directions, and tied while the package is still under pressure, thus forming the package bound with cords in the

same manner as the package shown in the Jones patent.

Patent No. 48523 shows a press in which the baling box is raised to a vertical position for filling, and is then put in a horizontal position for the process of pressing. The baling box is provided on opposite sides with removable doors, and the manner of baling is as follows: A pair of slats are provided of about the size of the interior diameter of the press, having grooves upon one face for the insertion of binding hoops, and grooves upon the opposite face for the insertion of binding clamps, there being one at each end of the slats. The manner of forming the bale in this press is as follows: I quote from the specification:

"Before the commencing of the pressing the upper and outer slab, K¹, is inserted, so that the bale is confined on opposite sides by slabs corresponding in area to the length and breadth of the bale, which slabs intervening between the clamp bars and the hay confine the latter to its proper shape and dimensions for hooping. Grooves k in the inner faces of the slabs K, K¹, enable the insertion of the hoops after the removal of the clamped hay from the press."

The binding clamps consists of a pair of straight bars each pivoted at one end to a short connecting bar and provided at the other end with tenons which enter mortises in another connecting bar of similar length. In using the clamp, the mortised connecting bar is removed, and the clamp is applied to the package formed of the material pressed, and the end boards or slabs K and K¹, while the package is under pressure, so that a package may be retained under

pressure after its removal from the press.

In patent No. 9334 there is shown a vertical press in which the lower platen is pivoted to the frame, so as to turn in a horizontal plane, the upper face of the platen is grooved transversely and longitudinally for the passage of binding cords. A rectangular pressing box open at both ends, and having in its vertical walls longitudinal slots, which register with the grooves in the platen, is mounted on the lower platen and serves as a guide in placing the material to be pressed. An upper platen or follower is pivoted at the lower end of the vertically moving rack-bar, so as to register with the lower platen and the press box. The under face of the

said follower is grooved to correspond with the platen. The material being placed in the press box is compressed between the platens, cords are passed through the slots in the sides of the press box and along the grooves in the platens, and are tied around the compressed package while it is under pressure, the cords crossing each other at

right angles. End boards and folded printed sheets being placed in the press box and subjected to pressure, and tied as described, the resulting package would be a duplicate of that

shown and described in the Jones patent.

In patent No. 40236 to Dingman, there is shown a press for pressing and tying paper. The lower platen consists of a series of plates of metal arranged in the same horizontal plane, and supported upon a series of standards or pedestals, which rise from a common support, the arrangement being such that there is a space between the edges of adjacent plates. The follower or upper platen consists of a similar series of metallic plates which are attached to rods which rise from a sliding frame common to all, the arrangement being such that the plates forming the upper platen are arranged opposite those of the lower platen, and have similar spaces between their edges. In operating this press, the loose paper in sheets or bundles as it comes from the machine is deposited on the lower section of the bed plate, resting on all the sections. Pressure is then applied to the bundle of sheets by bringing the upper platen down upon the package. Cords are then passed around the package in the spaces between the sections forming the platens, such spaces forming open ways for the passage of the cord to which free access may be had from all sides. After the cords have been secured the package of tied sheets is removed from the press. The inventor says, in relation to the object of his invention:

"The process of pressing and tying paper now generally employed requires a large and somewhat expensive press, which is located in some corner of the finishing-room, and as the paper comes from the machine it is carried to the finishing table, there counted and folded, and when sufficient is obtained to fill the press, it is conveyed to the press and placed therein, and pressed for about twelve hours, or during a night. It is then removed and conveyed to the tie-table and there tied into reams. * * * This operation is laborious and tedious, occupies much time, requires strong twine, and unavoidably draws the ream away or the paper out of place. The following, on the other hand, are some of the advantages I claim for my press and my mode of tying: 'It effects a great saving of time

and labor.' 'The paper is pressed uniform in thickness.' "

We have in this press another example of open ways to which free access may be had, formed in the "compressing heads" for the purpose of permitting of the tying of the package while under pressure.

In patent No. 2113 there is shown a trough-shaped horizontal press box, having open or longitudinally slotted sides, which serve to hold in proper alignment the material to be pressed. The press consists of two end pieces or standards which are connected by longitudinal strips or bars arranged in pairs in two sets, one above

the other, the lower set of parallel bars being nearer together than the upper set, thus forming suitable guides to hold in alignment the series of cylindrical receptacles, and a hogshead into which the material is forced from the cylindrical receptacles by followers which

are arranged to traverse the trough-like press bed.

In view of the state of the art, as illustrated by the above. 153 described patents. I think that at the time the Jones application was filed there was no patentable invention in the combinations claimed in claims 1 and 2 of the Jones patent. The cross-ways L2 and L2 of claim 1 are found in Kellogg No. 9324, in Cooley No. 58779, similar ways extending across the follower and the platen in one direction only are found in Craig, in Dingman and in Stibbs. The particular construction of the compressing heads comprising the base portion, the series of pedestals or standards erected on said base portion, and the series of disconnected plates forming the working surface of the head, and arranged with open spaces between them for the passage of the binding cords are found in Dingman, the only difference between the two devices being that in Dingman the plates with their standards are arranged to form a series of successive open ways, and in Jones the same parts are arranged to form intersecting open ways. Claim 2 includes, in addition to the elements of claim 1, the press bed inclined and provided with longitudinal slots in its sides. We have in the patent to Hardesty the open horizontal trough-shaped press bed, with longitudinal slots or spaces in its sides. I do not think it involved invention to incline the press bed, especially in view of the fact that inclined trough-shaped beds or receptacles, arranged to receive and hold in regular order a series of folded sheets, was a common construction found in folding machines for folding printed sheets.

With regard to claim 4, the device of a set of removable ledges or a set of adjustable guide-boxes for centering the sheets does not appear to be found in any of the exhibits. It appears to me, however, that it is not clear from the claim which device is to be used.

the claim being for an alternative construction.

Q. 4. Will you please examine the sketch which I now hand you, marked "Respondent's Exhibit Sketch of Palmer Press," and the testimony of the witnesses Schrank, McKee, and Davis, describing the machine from which this sketch was made and the means of operating it, your attention being particularly called to answer to questions 22 and 40 of Schrank, and compare the device represented by said sketch with the device shown, described, and particularly referred to in claims 1, 2, and 4 of the Jones patent in suit, and also state how the process of pressing and tying bundles upon this press as described by the witnesses compares with or varies from the process set forth in claim 5 of the Jones patent.

A. The device illustrated in the sketch "Palmer's press," referred to in your question, consists of a rectangular frame carrying upon one of its cross-bars a block secured centrally to the cross-bar and provided with a pair of intersecting open grooves in its upper surface. The other cross-bar carries a nut in which is mounted a screwthreaded plunger, — the lower end of which — attached a second

grooved block corresponding in size with the block first described, the whole forming a press in which a pile of printed sheets might be compressed and tied in a package while under pressure by cords crossing each other at the centers of the ends of the package. Comparing this device with that shown in the Jones patent contained

in claims 1, 2, and 4, the grooved blocks of the device shown in the sketch correspond with the compressing heads con-

structed with cross-ways in claims 1 and 2, and the process used in connection with the press shown in the Palmer sketch and described by the witness Schrank in his answer to question 22 is the same process as that described in claim 5 in the Jones patent. I do not find anything in the device shown in the sketch which corresponds to the combination called for in claim 4.

Q.6. Please examine the wood cut "Complainants' Exhibit Wood Cut of Seybold's Signature Press," and state if you understand the construction and operation of the machine of which that is a per-

spective view.

A. I have examined the exhibit which you mention in your question and I understand from the cut there shown the general construction and manner of operation of the machine illustrated.

Q. 7. Compare the machine illustrated by this wood cut with the Jones patent, referring particularly to claims 1, 2, 4 and 5, and state wherein you find the elements of the said claims and the elements of the machine referred to to correspond or differ the one from the other. And also wherein the elements of the Jones patent and of the structure represented by the wood cut compare with or differ from the preceding state of the art as illustrated in the patent you have heretofore referred to, and in Respondent's Exhibit Sketch of Palmer Press.

A. The machine illustrated in the cut before me consists essenfially of a pair of uprights carrying three guide-rods extending at an angle therefrom and forming inclined ways on which are mounted a fixed head or platen. It is, however, adjustably secured in position upon the rod and a corresponding movable head arranged to traverse the rod or ways. The removable head is actuated by a pair of toggle-jointed levers which are pivoted to arms projecting from the head and from one of the uprights in which the rods are supported. The toggle levers are connected by a link with a nut which is mounted upon and arranged to traverse a screwthreaded shaft which is mounted in bearings in the uprights. The mechanism is provided apparently for driving the screw-threaded shaft in opposite directions, the details of which do not appear in the cut. The fixed head and removable head or follower are provided in their opposed faces with open cross-ways through which cords might be passed. These cross-ways open into a cylindrical enlarged passageway formed in the body of the head, and similar in appearance to those found in the compressing heads of the Cooley patent No. 58779, which I have before referred to. A pair of light rods appear in the cut as connecting the two heads, one of which shows a series of small openings adapted to receive the rods and would indicate that the rods were adjustably in position and were

for the purpose of supporting the signatures when placed between the heads. This machine is similar to that shown in Jones' patent in that it shows an inclined trough-like press bed, upon which are mounted a fixed head and a movable head, in which are formed open cross-ways communicating with a large opening formed

155 in the heads beneath it. There are also found in the machine illustrated in the cut the adjustable rods for supporting the signatures in a centered position relative to the cross-ways. The points of difference between the device illustrated in the cut and

that shown in the Jones patent are:

1st. The press bed or ways which the movable head traverses is formed of rods instead of planks, as in the Jones device; the compressing heads instead of being built up of a series of blocks and connecting standards are apparently formed in one piece. The movable head, instead of being directly actuated by the screw is actuated by the straightening of the toggle lever above described Comparing the device shown in the cut with the claims of the Jones patent, I find compressing heads which answer the same purpose as the compressing heads called for in the claim and they are provided with the cross-ways, centrally arranged through them. Referring to claim 2, I find the inclined press bed provided with longitudinal openings in its sides and the press heads having through them cross-ways correspondingly arranged with said slots Referring to claim 4, I find, in combination with the press bed, of the set of adjustable guideways, but I do not find the set of removable ledges called for in the claim. In relation to claim 5, the press illustrated in the cut appears to be adapted to the carrying out of the process described in said claim. Comparing the machine illustrated in the cut with the previous state of the art, as heretofore described, I find that it has in the opposed faces of the compressing heads open cross-ways for the introduction of binding cords for tying packages in the press, which was a common device well known in this class of machines. I also find a circular enlarged opening formed through the body of the head and communicating with the cross-ways to be an old device illustrated in the patent to Cooley. before mentioned. I also find the open trough-like form of the press bed to be an old device, as shown in the patent to Hardesty. the construction shown in the cut being more like that shown in Hardesty than that shown in Jones' device. The previous state of the art shows the purpose of the construction shown in this class of devices, viz: the adaptation to the tying of packages while under pressure, to be very old.

Defendant's counsel herewith offers in evidence the patents referred to by the witness in his foregoing deposition and requests the officer to appropriately mark the same as respondent's exhibits:

"Hardesty patent, No. 2113, May 29, 1841."
"Kellogg patent, No. 9324, October 12, 1852."
"Dingman patent, No. 40336, October 20, 1863."

"Craig patent, No. 48523, July 4, 1865."

"Cowley patent, No. 58779, October 16, 1866."
"Stibbs patent, No. 119,195, September 19, 1871."

"Brown patent, No. 125,786, April 16, 1872."

⁶ Brown patent, No. 169,518, November 2, 1875."

" Archer patent, No. 181,389, August 27, 1876."

Also the abstracts from the publications "Manual of the Art of Bookbinding" and the English Cyclopædia set forth in the answer herein and quoted by the witness in his testimonv.

It is agreed by complainants' counsel that the abstracts printed in the record may be taken as correct abstracts from the works referred to, subject to correction by copies of the works referred to,

if request be made for the same prior to the hearing.

Also Patent Office copy of specification and drawing of patent to Hart, No. 334,977, December 25, 1888, which patent was referred to

by the witness Jones in his deposition in this case.

Defendant's counsel also gives notice upon the record that he will reserve the right to introduce and use at the hearing any patents referred to in the answer as illustrating the state of the art, and not here introduced in evidence, upon proper notice to the opposite side that he intends to use such evidence.

Adjourned to Saturday, June 15, 1895, at 10 o'clock a. m.

Met, pursuant to adjournment, Saturday, June 15, 1895. Present: Same parties as before.

Cross-examination by M. W. Jacobs:

X Q. S. What practical experience, if any, have you had in the art of printing?

ìİ.

A. I have had no experience as a practical printer. Simply have a general knowledge of the subject, as gathered from observation and reading

X Q. 9. What practical experience, if any, have you in the art of bookbinding?

A. I have none.

X Q. 10. What special means of observation have you had in

A. My office and workshop were for many years in the same building with a printing office and bookbindery. I have also had some experience in putting into practical shape machinery for folding newspapers as they came from the press.

X Q. 11. In the folding of newspapers, is there any necessity or occasion for dry-pressing or the removal of the type indentations

from printed sheets?

A. No. sir.

X Q. 12. Have you ever in practice witnessed the operation of dry-pressing?

A. I have not, that I took any special notice of.

X Q. 13. Your testimony in this case has been based wholly upon the papers which were submitted to you and to which you have referred, and not upon your practical knowledge of either of the arts of printing or bookbinding. Is that correct?

A. It is, except that I have gained some information from other

publications not shown in this record.

X Q. 14. Will you please describe the various steps in the process of making a book from the time the copy is placed in the hands of the printer until the completion of the book, stating by whom 157 the various steps are taken and, as far as you can, the tech-

nical names of the same.

A. The copy is put in the hands of the compositor or compositors and is set up in type. The types when set up are assembled and locked up in forms containing usually several pages of the work Papier-maché matrices are then formed upon the type. When these matrice plates of type metal are cast, thus forming stereotyped plates, from which the sheets which are to form the book are printed In the process of printing, slight indentations are made by the types in the paper, thus causing slight elevations on the opposite side of the printed sheet. After printing, the sheets are folded twice, four or eight times, as the case may be, each of these folded sheets being numbered or lettered in succession as they are to stand in the book This number or mark — termed a signature, and the same term is also applied to the folded sheet. In the process of bookbinding several book signatures are connected in one package and are taken to the dry press where they are subjected to heavy pressure to remove the impressions and elevations caused by the type and to smooth and solidify the several signatures and sheets. After removal from the dry press the several successive signatures which go to form a single book are arranged in successive order, which operation is termed collating. When thus arranged they are tied to gether and taken to the sewing table where several cuts are made across the edge of the book which is to form the back. Into the cuts thus made short strips of twine are secured, the ends of such pieces of twine being left projecting a short distance from the sides of the book, which ends are secured to the inner surfaces of the boards, forming the covers of the book. The preparation of the covers and the particular steps taken in their completion and ornamentation, I am unable to describe.

X Q. 15. What do you understand by collating and by whom is

it done?

A. Usually, I believe, by girls employed for that purpose. I understand by collating, the arrangement of the several signatures or folded sheets going to form a book in their regular order of sequence.

X Q. 16. What is "gathering"?

A. It is the same process.

X Q. 17. What is dry-pressing and by whom is it done?

A. I don't know that it is done by any special class of employees except those whose duty it is to run the presses. Dry-pressing is the pressing of the dry sheets to smooth and solidify them.

X Q. 18. Prior to the Jones patent was the dry-pressing done by

the printer or the bookbinder?

A. By the bookbinder, I think.

X Q. 19. In your answer to question 17, what do you mean by solidifying sheets?

A. Giving them an even and solid appearance and flattening out

folded sheets so that they will lie closely together.

X Q. 20. Was that one of the objects of dry-pressing prior to Jones' patent?

A. It was, I think.

X Q. 21. How was the dry-pressing done at that time?

A. First by beating with a hammer, then by rolling between rollers and later by pressing into a hydraulic press. I do not mean by this that these are successive steps, used at any time upon one mass of signatures, but that they represent stages in the development of the art.

X Q. 22. How was it done in the hydraulic press?

A. Several books or masses of signatures were piled upon the platen of the press, iron plates being introduced at the ends and at intervals along the pile to evenly distribute the pressure. The plunger of the press was then brought down upon the mass or pile, subjecting it to heavy pressure.

X Q. 23. That operation you understand as dry-pressing, do you?

A. Yes, sir.

158

X Q. 24. Was that operation intended for the removal of the in-

dentations of the type made in printing?

A. I think that was one of the objects of the operation. It is cited as later development of the art to which the old art or process of beating with a hammer pertained.

X Q. 25. Where, if anywhere, do you find it stated that the operation described by you in your answer to cross-question 22, was intended for the removal of the indentations of the type made in

printing?

A. In the book entitled "Manual of Bookbinding," by Nicholson, heretofore referred to in my testimony under the article or heading "Beating and pressing," commencing on page 41, which first describes the operation of beating with a hammer, and then of rolling, and on page 45 it states: "In some binderies a hydraulic press is relied upon for compressing the sheets, without their undergoing the beating or rolling process." The article does not state specifically the entire object of the operation to be the removal of the type impressions, but that, according to my opinion, would be included under the general object stated, namely: "To secure the first great requisite of bookbinding, solidity."

X Q. 26. That operation was conducted in the bookbindery, I

believe?

A. I thiak it was.

X Q. 27. You never saw it done, did you?

A. No, sir.

X Q. 28. Now, as a matter of fact, at the time to which we have been referring, was not the smoothing out of the type indentations, technically termed dry-pressing or smooth-pressing, done by the printer before delivering the sheets to the binder?

A. I do not know.

X Q. 29. Where, if anywhere, do you find it stated that the process of beating with a hammer was used for the purpose of removing type indentations?

A. On page 41 of Nicholson's Manual, from which I have quoted before, which, as I have heretofore stated, does not specifically state

the object of the operation to be the removal of the type impressions, but the object appears to be the smoothing of the sheets, and the operation described would, in my opinion, result in removing the roughness occasioned by the type indentations

X Q. 30. Please quote upon the record any passage you may find which at all indicates that the object of the operation was the

removal of type indentations.

A. At the foot of page 40, I quote:

"The book, being found correct, will be ready for the beating stone, which, although it has been almost entirely superceded by the introduction of machinery, will always be invaluable to a binder of limited means; and the amateur will find it to be an essential process to secure the first great requisite of good binding.

solidity.

"The first operation is commenced by shaking the volume upon the stone by the back and head, so as to make the whole even and facilitate the division of it into as many equal parts, which are called sections or beatings, as may be judged necessary according to the thickness and other circumstances. A section is then taken and well beaten over, drawing it with the hand towards the body, so as to bring the various parts successively under the hammer, and carefully avoiding striking more blows in one part than the other, except giving the edges a slight extra tap round."

As I have before stated, the removal of the type indentations was included in the term "solidity," and would be a necessary result of

the operation described.

X Q. 31. Do you mean to say that the beating of perfectly fresh sheets with a hammer would be a practical way of removing type indentations?

A. I do not think it would be so considered at this day.

X Q. 32. Was it at that day?

A. So far as I am informed, it was the best way they had at that day.

X Q. 33. What, in your opinion, would have been the effect upon the opposite page of beating with a hammer to remove type inden-

tations from freshly printed sheets?

A. The effect would be to offset the printing of one sheet upon the other, and the users of this process are especially instructed by the writer to be careful to see that the sheets are dry. I quote page 42: "Before beating a book, care should be taken to observe, if it has been recently printed, for, if so, it would set off by being beaten too much. This will be easily ascertained by referring to the date at the foot of the title, or by smelling the ink it has been printed with, which, being composed partly of oil, will not have got perfectly dry." X Q. 34. Now, upon further reflection, do you not find this to be the fact, that the passages to which you have referred on your direct examination have relation exclusively to the manipulation of the sheets in the bindery for the purpose of putting them into book form, and have no relation at all to the removal of the type indentations which, at that time, was customarily done by the printer be-

fore the sheets were delivered to the binder?

160 A. The passages to which I have referred are undoubtedly for the instruction of the bookbinder, and if it is a fact that the printed sheets came to him with the type indentations removed, then the processes described do not necessarily include removal of the type indentations.

X Q. 35. There is nothing in the passages referred to, so far as you have been able to find, which indicates that the process therein described was intended for the removal of the type indentations, is

there?

A. There is no such indication except indirectly, as I have before

stated.

X Q. 36. In your answer to question 4 you speak of the trough of the Jones press being slightly inclined from the horizontal. Will you look at the drawing accompanying the patent to him, and having measured the standards Λ and E with the measure which I now hand you, if you care to do so, say whether you have not rather

understated the inclination in describing it as slight.

A. It is possible that "slightly inclined" does not quite express it. The drawing is in perspective, and rather bad perspective at that. By actual measurement of the standards in the drawing, one is nearly three times as long as the other, but to suppose that that represents the inclination of the bed, would be to exaggerate it quite as much as I have slighted it. I should say that the bed in the drawing formed an angle with the horizon of 20 or 25 degrees.

X Q. 37. What is the purpose, as you understand it, of having the

bed of the press inclined?

A. To cause the signatures, as placed between the compressing heads, to have a slight inclination towards the foot of the press, so that they will steady while in the press.

X Q. 38. We find the same or substantially the same inclination in the Seybold press, as represented in "Complainants' Exhibit

Wood Cut of Seybold Signature Press," do we not?

A. Yes, sir: it is substantially the same. The direction of the inclination is, however reversed. The Seybold press being lowest at the follower end or head of the press.

X Q. 39. What practical difference does that make, if any, in the

operation of the machine?

A. No difference of particular importance; in the Jones machine the pile of signatures would remain in place while the follower moved up against it. In the Seybold machine the pile of signatures would lie against the follower and would be moved along with it at the starting of the press.

X Q. 40. In your answer to question 4, in describing the method of removing type indentations by means of fuller-boards under

pressure, you say that the pile was allowed to remain under pressure for several hours. Have you not somewhat understated the time? Was it not the practice to turn out two pressful/s in 24 hours; or, in other words, to allow the sheets to remain under pressure twelve hours on an average?

A. I think it was the practice to allow the signatures to remain under pressure over night, which would presumably be about twelve hours. I meant to express by the term several hours a considerable length of time, but did not think it necessary

to state the exact number of hours.

X Q. 41. What was the size of the presses generally used for the fuller-board process of smoothing out indentations?

A. I do not know, and I have no data for determining. X Q. 42. You never saw the process carried out, did you?

A. No, sir.

X Q. 43. What is a fuller-board?

A. I understand it to be a glazed sheet of hard material and of moderate thickness.

X Q. 44. Of what material and of what thickness?

A. I believe they were usually made of pasteboard or analogous paper material having a hard, smooth surface. As to thickness, I should suppose them to be anywhere from 2 to 1 of an inch thick.

X Q. 45. How many sheets could be put in a press between fuller-

boards in this process of smoothing out indentations?

A. I could not tell how many without making a calculation involving the distance between the compressing heads of the press and the thickness of the printed sheets, but I should say that perhaps one-tenth as many printed sheets could be pressed at one time when fuller-boards were used as could be pressed at one time when the fuller-boards were dispensed with.

X Q. 46. Dispensed with in what process or machine?

A. In the same press.

X Q. 47. Prior to the date of the Jones press, were the fullerboards dispensed with in the process of removing indentations from printed sheets?

A. I think they were. No mention is made of fuller-boards in the printed publications of 1856 and 1859, which I have already

referred to, so far as I am aware.

X Q. 48. What kind of a press was the operation there described

conducted in?

A. The hydraulic press mentioned in Nicholson's Manual, as illustrated on page 46. It is constructed apparently with metallic head and foot plates which were connected by four metallic pillars or rods, which served as guides for the follower. In the base the pressure cylinder was formed, and into this the piston which depends from the follower was fitted. No dimensions of this press are given.

X Q. 49. Where, if at all, in that publication do you read that fuller-boards were dispensed with in the process of smoothing out

type indentations?

A. Nowhere, except by implication, as I have several times ex-

plained. By implication, I mean that in the various processes described no fuller-boards are mentioned, and consequently I infer from that that none were used.

X Q. 50. Neither is the process of smoothing out type indenta-

tions there mentioned, is it?

162 A. No, except by implication, as I have several times explained.

X Q.51. As a matter of fact, you do not know whether or not fuller-loards were dispensed with in that process, do you?

A. Certainly not, from personal observation.

X Q. 52. And your entire knowledge on that subject is derived from the printed publications to which you have referred, is it?

A. It is.

X Q. 53. In your answer to question 4, you speak of the use by Jones of "a stiff board of substantially the same size as the printed sheets." That board was not only stiff but rigid, was it not, according to his specification?

A. It was. I supposed the terms stiff and rigid to be substantially

synonymous.

X Q. 54. What, as you understand it, was the function of that

rigid board in the Jones patent?

A. It is to distribute the pressure over the whole area of the ends of the package, and also to prevent cutting or marring the pages

with the twine used in binding or tying the package.

X Q. 55. Of the various patents to which you have referred on your direct examination, and which have been offered in evidence, which do you consider to be the best reference for the first claim of

the Jones patent here in suit?

A. Dingman, taken in connection with Cooley.

X Q. 56. Please explain what you mean by your last answer.

A. I mean that the patent to Dingman shows a platen or pressing head which is constructed in three parts, viz: the cross-beam, I: the series of metallic standards, 1; and the series of metallic plates, J, which are mounted upon said standards in such a manner as to leave open ways between them for the passage of the binding twine. Of these parts, the beam, I, corresponds to the block, B2, of the Jones press: the standards, 11, correspond to the standards, F', and the plates J correspond to the blocks or plates F. The other compressing head, containing the parts C, D and D' of the claim, is but a duplication of the parts just described, and the spaces between the plates J correspond to the cross-ways L2 of the claim, only they are differently arranged, being arranged in a series so that the package when pressed can be tied in one direction only, while in the Jones patent the ways are arranged to cross each other so that the package can be tied in both directions. This particular arrangement of open ways for the passage of the binding cord is found in the platen and follower of the press shown in the patent to Cooley.

X Q. 57. Which do you consider the best reference for the second

claim?

A. The patents to Dingman and Cooley, before cited, taken in con-

nection with the patent to Hardesty. In claim 2, the additional elements to those of claim 1, are the inclined press bed, H H², provided with longitudinal slots H¹, in its side. The horizontal trough-

like press bed, having longitudinal slots in its side, is found in Hardesty. Longitudinal slots in the press bed arranged

to register with the open ways of the platen and follower is found in Cooley. There is no invention, in my opinion, in tilting the press bed, so that the material to be packed rests to a greater or less extent upon the platen.

X Q. 58. Which do you consider the best reference for the fourth

claim?

A. I do not find any.

X Q. 59. As I understand your deposition, in view of the state of the art, as you understand it, you do not find any invention in the matters claimed in the first, second and fifth claims; is that correct?

A. That is correct.

X Q. 60. In the next to the last paragraph in your answer to question 3, you speak of the series of disconnected plates forming the working surface of the head. What do you understand to be the purpose of those plates erected on standards, as you have described them?

A. To form open ways for the passage of the binding cord, the pedestals being for the purpose of easy access to the ways while tying the package and for the introduction of the binding twine.

X Q. 61. In the concluding sentence of the next to the last paragraph of your answer to question 3, you refer to folding machines having inclined trough-shaped bed. What machines of that character which were in existence at the date of the Jones patent do you have in mind?

A. Such a trough-like structure for the reception of folded sheets is found in the United States patent No. 186,309. I have no memoranda of the date of this patent, but its number shows it to have been issued a considerable time previous to the filing of the Jones application. The drawings in this patent show a pair of open trough-like boxes inclined at opposite angles and arranged to receive the folded sheets as they come from the machine. The folded sheets standing on edge are brought into orderly arrangement to form a package by the sides of the box. Similar troughlike structures for the same purpose are found in U. S. patents No. 147,052, 141,490, 141,486. In these cases, however, I believe the trough is not inclined, but lies horizontal.

HARRISON P. HOOD.

Defendant gives notice on the record that the testimony for the defense is closed.



Busch Sp. 165


RESPONDENTS EXHIBIT.

SKETCH OF PALMER PRESS.

WILLIAM M. STEWART.

April 26th, 1895.

Notary Public.



119

164 Supreme Court of the District of Columbia, Sitting in Equity.

Joshua W. Jones and The W. O. Hickok Manufacturing Company vs. Clarence M. Busch.

United States of America,
State of Ohio, Hamilton County, 88:

I, David S. Oliver, a notary public in and for the county of Hamilton. State of Ohio, by consent of counsel acting special examiner in the above cause, do hereby certify that the foregoing deposition of Harrison P. Hood was taken on behalf of the respondent, pursuant to agreement of parties, beginning June 13th, 1895, and concluding June 15th, 1895; that the said witness was duly sworn and examined and the deposition of said witness was reduced to writing in his presence and by him subscribed in my presence; that the several exhibits referred to in said evidence were introduced into evidence and identified by my signature; that George J. Murray appeared on behalf of respondent and M. W. Jacobs on behalf of complainant-; that I am not connected by blood or marriage with either of said parties nor interested directly or indirectly in the matter in controversy.

In witness whereof, I have hereunto set my hand this 15th day

of June, 1895.

DAVID S. OLIVER, Notary Public, Hamilton County, O.

(Here follows diagram marked p. 165.)

167

DANIEL KELLOGG.

Improvement in Presses for Bundling Flocculent and Other Substances,

Specification forming part of Letters Patent No. 9324, dated Oct. 12, 1852.

To all whom it may concern:

Be it known that I, Daniel Kellogg of Pittsfield in the county of Washtenaw and State of Michigan, have invented certain new and useful improvements in presses for bundling flocculent and other substances, of which the following is a full, clear and exact description, reference being had to the accompanying drawings—

(Here follows diagram marked p. 166.)

which form part of this specification and in which, figure 1 is a view in perspective of the press and other devices or arrangements connected with it; figure 2, a vertical section of the same; figure 3, a view in perspective of a fleece pressed and bundled; figure 4 an interior face view of the pressing bed, detached.

My invention consists of a peculiar construction and arrangement of the press box, bed and platen, whereby the substance being pressed, may be single and double or cross-bound while under pressure.

The framing A of the press may be constructed in any suitable manner and various mechanical arrangements adopted for operating the platen C which, as represented in the drawings, is made to fall and rise by a rack D operated by a spiral worm-wheel F turned

through a handle p.


The platen C is so attached to the rack D that it is capable of being turned or revolved horizontally and of being disconnected when required to attach a different platen, that represented in the drawings being designed for pressing fleeces of wool, for which purpose the pressing box E and bed B are also adapted, the construction and arrangement of these latter parts being as follows,—the pressing box E is square and made with vertical slots e through either side: it sits loosely on a plate f to which is secured the bed B that projects slightly within the pressing box; the bed B or its plate f is so connected by a swivel, with the cross-tie of the frame that, together with the pressing box, it is capable of being turned or revolved horizontally similar to the specified capability of the platen to turn by its connection, through a swivel, with the rack D; both the under face of the platen and top surface of the bed have channels or creases a cut in them corresponding as regards situation and direction, to lines drawn through the slots e of the opposite sides of the pressing box. The fleece to be pressed is put into the box E (situate as in figures 1 and 2) the platen in producing the pressure descending within the The fleece, thus pressed by the descent of the platen, is said box. then bound, while under pressure, by passing a needle and cord


Busch Sp 166

П. Kellogg, Wool Press,

Nº 9,3R4, Pat

Patented 011.12, 1852.





through each pair of opposite slots e in the box and through the corresponding creases a of the platen and of the bed, and 168 knotting or looping the cord. The fleece being thus bound in one direction, that is by a series of cords passing along the several creases a which are parallel or form channels connecting the slots ein the opposite sides of the box,-the pressing box, fleece, platen and bed are then turned partly round and the fleece is bound by a secand series of cords at right angles to the first, by simply passing the needle and cord and knotting the latter successively through the slots of the other two opposite sides of the box and along the corresponding channels in the bed and platen. Thus the fleece is bundled as represented in figure 3, it being both single and double and cross-bound, and as this is done while the fleece is under pressure, the fleece will be formed into such compact bundles as to greatly facilitate their transportation to market.

The turning horizontally of the pressing box and platen while the fleece is under pressure greatly facilitates the operation of binding as the fleece can be bound with equal case in both directions. It has been before stated that the pressing box E, though of square shape may be of any other desired form,—say a parallelogram so as to give length and breadth to the bundle, according to the substance to be pressed,—any alteration in the shape of the box involves a corresponding one in the bed and platen. The slots in the box and channels in the bed and platen may be arranged so as to cross the

cords in other directions than at right angles.

For pressing fleeces this press will be of great utility to the farmer, but to extend its usefulness to him, it is proposed to vary its application, by making it a cheese or general press. For pressing cheese, the platen C, box E and bed B are removed, a suitable round platen attached to the rack D, the cheese laid in its cloth, the perforated tub, and the whey pan, then put on the lower tie-timber of the press which forms a bed, the platen brought down to the necessary pressure and retained for the required length of time to discharge the whey, by affixing a weighted lever to the shaft of the wheel F. It is further proposed, for the increased convenience of the farmer, to attach an apple or other grinding mill at the back of the press, I being the feed-hopper, J the rotary toothed grinder, K the toothed concave set up to its required proximity with the grinder by a screw l and spring L; m, the handle for revolving the grinder by pinions n and o; a platform extends under the mill from, and on the same level as, the lower cross-tie forming the bed of the press.

In grinding apples for the production of cider, a perforated tub covered by a loose cloth and resting in a cider vat is placed on the platform to catch the pomace and juice as they fall from the mill, the ends of the cloth are then thrown over the pomace in the perforated tub which, by sliding the vat that carries it, forward, is brought under the platen of the press that serves to squeeze the pomace for the extraction of the juice which is forced through the cloth and

perforated tub into the receiving vat.

Again, it is proposed for the accommodation of the farmer, to con-

nect, at one side of the mill, a rotary disc corn-sheller, the said disc being toothed and working in combination with a stationary but adjustable toothed disc set parallel,

or at a slight inclination, to the movable disc.

Having thus described my improved press, what I claim as new therein and desire to secure by letters patent, is—The combination of the pressing box made with openings in its sides, with the platen and bed turning on swivels and formed with channels so arranged as to admit of the passage of the needle and cord through the pressing box for the purpose of singly and doubly binding fleeces of wool, or other substances, while under pressure.

In testimony whereof I have hereunto subscribed my name.

DANIEL KELLOGG.

Witnesses:

F. G. FONTAINE. P. H. WATSON.

W. R. DINGMAN. PAPER PRESS.

No. 40.336.

Patented Oct. 20, 1863.

We Posymon

172

UNITED STATES PATENT OFFICE.

WM. R. DINGMAN, of Stuyvesant, New York.

Improvement in Paper-presses.

Specification forming part of Letters Patent No. 40336, dated October 20, 1863; antedated October 11, 1863.

To all whom it may concern:

Be it known that I, Wm. R. Dingman, of the town of Stuyvesant, in the county of Columbia and State of New York, have invented a new and useful machine for combining and facilitating the operations of pressing and tying paper into reams or bundles, which I call the "combination paper-press and tying-engine," and I do hereby declare that the following is a full, clear, and exact description of the construction and operation of the same, reference being had to the annexed drawings, making a part of this specification, in which—

(Here follows diagram marked p. 171.)

Figure 1 is a perspective view; Fig. 2, a front elevation, and Fig.

3 a plan or bird's-eye view.

Letter A is the frame of the press; B, the vertical sliding frame; C.C. guide beams; D, hand or capstan wheel; E, hand-wheel shaft; F, crank-shaft at right angles to E; G G', cross-beams supporting the bevel-gear; H, connecting-rod or pitman; I, cross-beam secured to frame A for supporting the lower jaws or bed-plates of the press; JJJJJ, metallic plates or jaws forming lower part or bed of the press; K, cross-bar secured to the sliding frame B, and provided with journals at each end; L L L L L, plates or jaws supported by the metallic rods k k k k k, forming the upper or active part of the press; M, ratchet-wheel secured to hand-wheel shaft; N, pawl to hold the press while the paper is being tied; O, yoke-bar; P, spring to operate yoke-bar; e, bevel-pinion on end of shaft E; f, bevel-gear wheel on end of crank-shaft F, worked by pinion e; g, crank secured to end of crank-shaft F, and connected with and operating the sliding frame B by means of the connecting-rod H; i i i i, metallic standards supported by cross-beam I; k k k k, metallic standards supported by cross-bar K in sliding frame B.

To enable those skilled in the art to make and use my invention,

I will proceed to describe its construction and operation.

The frame A may be made of hard wood or metal of any required dimensions. For common straw wrapping-paper I use one which is three feet long by two feet wide and three feet in height. These proportions as also the size of the press, may be varied, as required.

Within the frame A is placed the transverse sliding frame B, of such breadth as to slide easily up and down in the guide-beams C.C. This sliding frame is operated by the hand-wheel D. I will

here suggest that this hand-wheel may be omitted and a pulley and belt be substituted, to be operated by the motive power of the mill. Hand-wheel D and ratchet M are secured to shaft E. This shaft revolves in bearings attached to the frame A, and has the bevelpinion e, secured to its opposite end. This pinion gears into bevelwheel f, attached to the end of shaft F, which latter revolves in bearings secured to frame A and at right angles to shaft E.

To the end of shaft F is secured the crank g, by means of which and the connecting-bar H, the sliding frame B is operated. This connecting-bar is adjustable, its length being varied by having holes at different distances from the crank-pin, through which the bolt connecting its lower end with the lower cross-beam of the sliding frame may be inserted. On this bolt the connecting rod or bar H is of course movable—can vibrate or revolve freely as the sliding frame moves up and down. At its upper end this connecting-bar is connected with the crank g by a bolt on which the latter revolves, forming a toggle or hinge joint. The combined length or angle of connection of crank and connecting-rod may thus be varied to correspond with the degree of pressure required.

To the beam I, which is bolted firmly across the frame A, is secured a series of metallic standards i i i i i, supporting metallic plates J J J J at their upper ends, which form the lower half or bed of the press. To the cross-bar K of the sliding frame B is also secured another series of standards k k k k, which extend up behind and a little above the former, and to which are attached the corresponding plates, L L L L L, forming the upper jaws or active part of the press. These plates are separate, and sufficiently disconnected to allow the string or cord used for tying the paper to pass

hotwoon

I would suggest that the operation of this press may be varied by making the pressure upward instead of downward; but I do not think it advisable. The cross-bar K is provided with journals at each end, so as to allow it end-play. The yoke-bar O, which in its ordinary position rests against the standards k k k k, and keeps

them upright and in place when it is thrown back against the spring P, allows the standards when elevated to drop back, the bar K rolling on its journals, so as to make the space between the upper and lower jaws larger, if required. When the standards begin to descend with the sliding frame, the yoke-bar comes in contact with the spring P, which throws it over against the standards and forces them back again into their original upright position. The pawl N is employed upon the ratchet-wheel M to hold the press while the paper is being tied. After this it is removed, and, if necessary, is cut into ordinary or single crown-reams. The spring P is secured to the cross-beam G'. (See Fig. 3.)

The operation of my press is evident from the foregoing description of its construction. By means of the hand-wheel D, operating the bevel-gears e f, the crank g, and the connecting-rod H, the sliding frame B, carrying the rolling-bar K, with the standards k k k k and their several jaws, are elevated. The loose paper, in sheets or bundles as it comes from the machine, is deposited on the lower

jaws or bed of the press. This being done, the hand-wheel is revolved backward toward the operator, causing the jaws L L L L L to descend upon the paper and to compress it to the degree required. The pawl N, being hooked, drops into the ratchets on wheel M and holds the press down until the paper is tied. By a reverse movement of the hand-wheel, the pawl being raised, the pressure is re-

lieved and the paper removed.

The process of pressing and tying paper now generally employed requires a large and somewhat expensive press, which is located in some corner of the finishing-room, and as the paper comes from the machine it is carried to the finishing-table, there counted and folded, and when sufficient is obtained to fill the press (usually about one hundred reams) it is conveyed to the press and placed therein, and, by means of a large screw and follower, pressed for about twelve hours, or during the night. It is then removed and conveyed to the tie-table and there tied into reams. After this (it being, when it comes from the machine, usually double-crown, or double the length of the ordinary ream of wrapping-paper) it is cut into two reams or single-crown. The usual mode of tying paper is by passing a strong cord or twine around the ream, with a noose or loop at the end, through which the other end is passed and then drawn upon with the hand until the loose ream or bundle is sufficiently compressed. This operation is laborious and tedious, occupies much time, requires strong twine, and unavoidably draws the ream away or the paper out of place.

The following, on the other hand, are some of the advantages I

claim for my press and my mode of tying:

First. It combines in one machine both the press and the tie-table, and occupies much less space than the old press alone, and can be

easily conveyed from place to place, to suit convenience.

Second. It effects a great saving of time and labor, requiring no longer to take the paper from the finishing-table, press, and tie it in this machine than it does to remove it from the ordinary press to the tie-table alone. The tying process with my press, instead of being laborious, is simple and easy, requiring comparatively light cord or twine, and leaves the ream perfectly square.

Third. The paper is pressed uniform in thickness, and no part of the ream can be moved out of its place by the process of tying, since

it is held firmly while this is being done.

Fourth. Ordinarily, now, a full press of paper is made before any part of it is pressed. With my machine it can be pressed about as fast as it is made, so that it need not lie loose about the mill and be wasted, as it often is in the ordinary process.

Fifth. Instead of requiring a man, as it does for the old process, effecting comparatively little work, a boy, or even a girl, is sufficient to press and tie with my machine, and does more work and does it

better.

What I claim as my invention, and desire to secure by letters

patent, is-

 Constructing and employing a press with a series of jaws or corresponding upper and nether metallic plates, J J J J J and L L L L L, all disconnected, so that while the paper is being subjected to the required pressure it may be easily tied into reams or bundles.

2. The arrangement of the standards k k k k with their plates L L L L operating in combination with i i i i, with their respective plates J J J J J, substantially in the manner and for the purpose herein set forth.


3. The combination and arrangement of the several parts and devices employed to operate the sliding frame B, or their equiva-

lents, substantially as and for the purpose herein set forth.

· WM. R. DINGMAN.

Witnesses:

JACOB TEN BROECK. H. TAPPAN.





Ro 96 Busch p 174 Romes Letal.


S. Cooley, Wool Press,

NR 58,779,

Patented Oct. 16, 1866.







Malon too

Inventor Bookey Mesen of Attorney

UNITED STATES PATENT OFFICE.

Solon Cooley, of Oakwood, Michigan.

Improvement in Wool-presses.

Specification forming part of Letters Patent No. 58779, dated October 16, 1866.

To all whom it may concern:

Be it known that I, Solon Cooley, of Oakwood, in the county of Oakwood and State of Michigan, have invented new and useful improvements in wool-presses; and I do hereby declare that the following is a full, clear, and exact description thereof, which will enable others skilled in the art to make and use the same, reference being had to the accompanying drawings, forming part of this specification.

The present invention consists, principally, in a novel construction and arrangement of the press whereby, after the fleece has been pressed therein, it can be securely bound or tied before removing it from the press, and without relieving the pressure upon it; also in the use, in combination with the sides of the press-box, of a follower of such a construction and arrangement that it will hold itself at any degree of depression to which, by means of weight, it may have been brought to bear against the wool.

(Here follows diagram marked p. 174.)

In accompanying plate of drawings my improvements in wool-presses are illustrated, figure 1 being a plan or top view of the press with the sides swung down; Fig. 2, a plan or top view of the press with its sides swung up; Fig. 3, a central longitudinal vertical section, taken in the plane of the line x x, Fig. 2; Fig. 4, a transverse vertical section, taken in the plane of the line y y, Fig. 2; Fig. 5, an end view of a bale of wool pressed in my improved press; Fig. 6, a detail view.

Similar letters of reference indicate like parts.

A in the drawings represents the bottom boards of the press, to the sides of which are hinged the side and end pieces or boards, B B, and C C, of the press-box, so that they can be swung up or down, the sides and ends, when in a vertical position, forming a perfect square-shaped box, in which position they are secured by means of hooks D D, hung upon one side piece and interlocking with the notch a in the other, extending across the width of the box outside of the upper ends of the end boards, C C.

The bottom board, A, of the press-box has a series of grooves, b b and c c, extending entirely across its width in both directions and at right angles to each other, continuations of which grooves are made in the form of slots d and f in both the side and end boards, B B and C C, of the box, which slots, when the side and end boards are

swung up into a vertical position, extend in directions at right angles

to the grooves in the bottom board, A.

Upon the inside face, at the center of each end piece C of the box, and in a vertical direction, are secured toothed or ratchet rack-bars F F, one to each end board, with the teeth of which engage the spring-arms G upon the upper side of the follower H, made of suitable size to fit within the press-box, as such follower is depressed or pressed down by weighting it in any suitable manner, thereby preventing the follower from rising or being lifted until said arms are disengaged by the swinging down of the end pieces, or in any other proper manner.

The use of my improved press, constructed and arranged as above described, is as follows: First, place the fleece upon the bottom board of the press, when roll it up upon each side, and then raise the side boards, BB, securing them in position by properly fastening either one of the two hooks D over and across from one to the other; then roll up either one of the two ends of the fleece, and, swinging up the end board at such end, the proper hook D is fastened across from one side of the press to the other, to hold the end board in such position, when the other end of the fleece is rolled up and its end board swung up and secured as explained for the opposite end. The follower is then placed in the top of the box, and weighted in any suitable manner, so as to press down the fleece with any desired degree of pressure, its spring-arms, by interlocking with the rackbars of the end-boards, preventing the follower from moving upward, and thus holding it in its depressed position, when the cords which are to be used to bind the compressed fleece being drawn through the grooves in the bottom board of the press, are then passed up and around one side and end of the bale through the grooves

g g in the under side of the follower, and down the opposite side and end, where, meeting the other ends of the cords, they are tied together and about the bale, firmly and tightly binding the same together; after which the sides and ends are swung down, relieving the follower and leaving the bale free to be removed at pleasure.


I claim as new and desire to secure by letters patent-

The arrangement of the bottom board, A, the sides BB, and ends CC, as constructed with the follower H, spring-arms GG, rack-bars F, and hooks DD, substantially as and for the purpose herein specified.

SOLON COOLEY.


Witnesses:

W. L. BAINES. E. BARLING.



THOMAS STIBBS:

Improvement in Press for Pressing Yarn, &c.



119,195.

UNITED STATES PATENT OFFICE.

THOMAS STIBBS, of Wooster, Ohio.

Improvement in Presses for Pressing Yarn, &c.

Specification forming part of Letters Patent No. 119,195, dated September 19, 1871.

To all whom it may concern:

Be it known that I, Thomas Stibbs, of Wooster, in the county of Wayne and State of Ohio, have invented a new and improved press, which is especially designed for pressing yarn but may be employed for other purposes; and I do hereby declare that the following is a full and exact description thereof, reference being had to the accompanying drawing which forms a portion of this specification, of which—

(Here follows diagram marked p. 177.)

Figures 1 and 2 are side elevations, representing different positions of the laterally movable as well as vertically movable platen of the press; Fig. 3, an end view of said press; and Fig. 4, a top view of the same.

An open frame-work, of the shape shown in the drawing, constitutes the body of my said improved press. Said frame-work consists of the base platform a, the vertical uprights or ribs b b b b b' and cece', which rise from opposite sides of said platform, and the horizontal arms or ways dd, which project outwardly from the uprights b' c', as shown in Fig. 1. The upper ends of the uprights or ribs b b, c c, &c., are all brought to the same horizontal plane with the upper edges of the arms or ways dd; and the respective series of said uprights are also in line with the arm d, which projects from the right-hand upright of each of said series. A metallic carriage, e. of such a shape that its sides will rest upon and pass a short distance within the inner sides of the upper ends of the respective series of uprights b b, c c, &c., is placed upon the frame of the press, and may be freely moved to and from the various positions represented in the drawing. A vertical screw-aperture in the central portion of the carriage ϵ receives the screw f, whose lower end is swiveled to the platen q, which platen works freely between the inner sides of the series of frame uprights or ribs b b, c c, &c., as shown in Fig. 3.

I prepare my improved press for the free reception of the yarn to be pressed by first screwing the platen g up to its highest position; then running the carriage e and the platen g out upon the arms or ways d d to about the position shown in Fig. 2; and then placing the tieropes g g through the open spaces between the uprights or ribs b b c c into the transverse grooves in the platform a. After the

requisite quantity of yarn has been placed within the space above the platform a the requisite tie-ropes are placed transversely above the same through the spaces between the respective uprights b b, &c. and cc, &c., and then the carriage c and the platen g are run inward until the lugs h h, which laterally project from opposite sides of said carriage, are carried under the retaining heads of the hold-fasts or hooks i i, which hold-fasts rise from and are secured to or form a portion of the central uprights or ribs b c of the frame-work of the press, as shown in Figs. 1 and 2; then, when thus prepared the platen q is forced downward by the application of the requisite degree of power to the rotation of the screw f. After attaining the requisite degree of pressure upon the contents of the press, and after properly securing the ends of the tie-ropes to each other, the platen g is moved upward by a reverse movement of the screw f, and is then run outward upon the arms or ways d d preparatory to the removal of the pressed bale and the reception of the requisite material for the formation of another bale or package by a repetition of the same operation as that above set forth. The lugs jj, that rise from the outer ends of the frame arms d d, serve as guards to prevent the carriage q from being run out too far upon said arms.

I propose to sometimes elongate the frame-work, swivel, and multiply the hold-fasts *i* i of my improved press to such an extent as shall enable the press to receive two or more distinct charges of yarm or other material, to be pressed one after the other by one and the

same platen.

I claim as my invention-

 The open body of the within-described press, consisting of the platform a, the uprights or ribs b b' c c', the hold-fasts or hooks i i, and the horizontal arms or ways d d, arranged substantially as and

for the purpose set forth.

2. The combination of the jointly acting carriage c provided with lugs h, the screw f, and the platen g with the uprights or ribs b b' c c', horizontal arms or ways d d, and the hold-fasts or hooks i i, of the body portion of the press, substantially as and for the purpose set forth.

In testimony that the foregoing is a full and clear specification of my new and improved press for compressing yarn, &c., I hereunto subscribe my name.

THOS. STIBBS.

Witnesses:


A. J. DE WITT. S. R. BOUNITZ.



W. P. CRAIG. BALING PRESS.

No. 48.523.

Patented July 4, 1865.



UNITED STATES PATENT OFFICE.

WALDO P. CRAIG, of Milton, Kentucky.

Improvement in Baling-presses.

Specification forming part of Letters Patent No. 48523, dated July 4, 1865.

To all whom it may concern:

Be it known that I, Waldo P. Craig, of Milton, Triable county, and State of Kentucky, have invented certain new and useful improvements in baling-presses; and I do hereby declare the following to be a full, clear, and exact description thereof, reference being had to the accompanying drawings, making part of this specification.

My improvement relates, in part, to a provision whereby the advantages of tramping are secured in a portable baling-press, and also, in part, to an arrangement which enables the hooping of the bale to be effected outside of the press.

(Here follows diagram marked p. 179.)

Figure 1 is a side elevation of my machine in condition for tramping. Fig. 2 is a longitudinal section through the same represented in the act of pressing. Fig. 3 shows the bale after being pressed and before it has been hooped. Fig. 4 is a view of the clamp and tie-bar detached.

A represents a horizontal bed, from which rises a vertical frame, B, whose transom C contains a journal-bearing for the upper end of the screw D. The screw D has also a bearing in the frame A, and has attached to its lower extremity the sweep O. The bed A supports on friction-rollers a a' a" the carriage E, having two stout abutments, E' E", to one of which, E", the outer arm, F', of the toggle F F' is hinged, the inner arm, F, of said toggle being hinged

to the follower G, which runs on the friction-rollers g g'.

I render my press available for tramping by means of a device which I call the "tumbling-box," and which is arranged and operated as follows: The vertical sides of the carriage E contains two horizontal slots, e, to receive the trunnions h of the tumbling-box H, which box, when liberated so as to revolve on its trunnions, assumes the vertical position, as shown in Fig. 1. The slots e permit the strain to be brought to bear against the abutment E and relieve the trunnions h of any strain whatever during the time the pressing is being effected. The tumbling-box H having been allowed to assume the vertical position, a slab, K, is deposited in its lower end, and the door L (of which there is one on each side of the tumbling-box H) being closed, the charging and tramping is commenced at the open end H' of the tumbling-box. The external faces of both of the slabs K K' are grooved at J to receive the rectangular clamp-

bars M M', which, being inserted when the hay has become sufficiently compressed and their ends secured from separation by the tiebars N N', enable the removal of the bale. Before the commencement of the pressing the upper and outer slab, K', is inserted, so that the bale is confined on opposite sides by slabs corresponding in area to the length and breadth of the bale, which slabs, intervening between the clamp-bars and the hay, confine the latter to its proper shape and dimensions for hooping. Grooves k in the inner faces of the slabs K K' enable the insertion of the hoops after the removal of the clamped hay from the press. In the act of pressing the bottom (now inner end) of the tumbling-box H bears firmly against the abutment E' of the carriage, and the pressing is effected by the simultaneous approach of the abutment E' and follower G.

P is a floor or platform on which the press stands, and the sweep O may either revolve under the floor, as shown in Fig. 1, or it may be attached to the upper end of the screw D, and be operated in a

room above that in which the press is situated.

I claim herein as new and of my invention—

1. The tumbling-box H, substantially as described and set forth.

2. The arrangement of tumbling box or trunk II, trunnions h,

slots e, and abutment E', substantially as set forth.

3. While disclaiming the general idea of hooping bales outside the press, I claim the combination of the U-formed clamp-irons M M', tie-bars N N', and grooved clamp-boards or slabs K K', when constructed and employed as specified.

In testimony of which invention I hereunto set my hand.

W. P. CRAIG.

Witnesses:


GEO. H. KNIGHT. JAMES H. LAYMAN.



Sund St. 181 T. J. Hardesty

Tobacco Press.

Patented May 29,1841.



182

UNITED STATES PATENT OFFICE.

Thos. G. Hardesty, of Tracy's Landing, Maryland.

Improvement in Tobacco-presses.

Specification forming part of Letters Patent No. 2113, dated May 29, 1841.

To all whom it may concern:

Be it known that I, Thomas G. Hardesty, of Tracy's Landing, in the county of Anne Arundel, in the State of Maryland, have invented a new and improved apparatus or press for pressing tobacco into hogsheads; and I do hereby declare that the following is a full

and exact description thereof.

In my improved tobacco-press the hogshead into which the tobacco is to be pressed has both heads removed, and it is placed horizontally upon the frame of the press, resting upon two longitudinal pieces of timber, near the ground, prepared to receive it: and two false hogsheads or receiving-cylinders, the same in diameter, or nearly so, with the hogshead, are placed upon the same longitudinal pieces in a line with it, said hogshead being situated between them. The hogshead and the two false hogsheads are to be filled with tobacco by hand, and may be made to contain the whole quantity that is required to be packed in the hogshead. When thus prepared, pressure is to be made at each end of the apparatus by means of two screws, which force up two followers, said followers entering and passing through the false hogsheads and forcing all the tobacco which had been placed in them for that purpose into the hogshead situated between them. The false hogsheads are so constructed as to admit of their being removed from the press without its being necessary to retract the pressing-screws; and this I effect by uniting the staves which constitute the false hogsheads to bands or hoops of iron, which are clasped together at their ends, and when unclasped are to spring open sufficiently far to admit of the escape of the false hogsheads over the shaft of the screw. The same end may be attained by making one of the staves of each of the false hogsheads removable, and affixing it in place, when in use for packing, by means of loops and wedges confining it to the iron bands or hoops of the false hogsheads.

In the accompanying drawings-

(Here follows diagram marked p. 181.)

Figure 1 is a perspective representation of my press, with the hogshead that is to be packed and one of the false hogsheads placed upon its lower longitudinal pieces or sills; and Fig. 2 is one of the false hogsheads removed from the press and sprung open.

A is the hogshead to be packed, and B B' are the false hogs-

heads.

lowers.

C C are the lower longitudinal pieces or sills of the press.

D D are the upper longitudinal pieces, which are firmly connected to the two iron end or head pieces, E E, of the press. One or both of the pieces D D is to be made removable, to admit of the rolling of the hogshead and false hogsheads onto and off from the sills C C.

F F are two screws, which turn in boxes G, said screw-boxes being firmly attached to the power-wheels H H, and swiveling, by means of collars, in the iron head-pieces E E. Each of these screws carries a follower, I, on its inner end, and the screws must be of such length as to carry the followers entirely through the false hogsheads, and cause them to enter the ends of the hogshead A and to occupy the place which is to receive the heads.

The false hogshead, Fig. 2, is shown as sprung open.

a a are staples or eyes, which receive the catches b b on the ends of the hoops or bands J J. When sprung open, the false hogsheads may be readily removed, while the followers I are within the hogshead A; and the same may be effected, as before remarked, by making one of the staves of B B removable, and providing it with

iron straps, by which it can be keyed onto the bands J J.

When this press is to be used, the two screws are to be turned back, so that the followers I will be in contact with the head-pieces E E. The hogshead and the false hogsheads, filled with tobacco by hand, are then to be placed in a range on the sills C C. The followers are now to be brought up to press upon it at both ends. In doing this the screws may at first be turned by means of a winch on their outer ends until the resistance is too great for this mode of proceeding. The power-wheels H H may then be turned by means of the rounds or handles c c c, by which means all the requisite force may be obtained and applied. When the pressure has been thus completed and the false hogsheads have been removed, the followers are to be so far withdrawn as to allow of the insertion of the heads between them and the tobacco. The heads are then to be forced up and secured in place.

183 It will be manifest that other means may be adopted of forcing up the followers, and that the screws F F may be dispensed with, while the false hogshead and the general arrangement in other respects may remain substantially as described. Thus, for example, racks and pinions may take the place of the screws and boxes, and the required power be thus applied. Although I prefer the screws, believing them to be the best arrangement, I do not intend, therefore, to limit or confine myself to their use, but to employ racks and pinions or other known means of forcing up the fol-

Having thus fully described the nature of my press for pressing tobacco into hogsheads and shown how the same operates, what I claim therein, and desire to secure by letters patent, is—

1. The manner in which I construct and employ the two false hogsheads by placing them horizontally in a range with the hogshead to be packed and pressing simultaneously from each end, as set forth.

2. The so arranging of the parts of the press as that two followers may be forced up, one from each end thereof by means of the pressing-screws operated by female screws or boxes attached to the power-wheels.

THOMAS G. HARDESTY.

Witnesses:

THOS. P. JONES. ALEX. DUVALL.

UNITED STATES PATENT OFFICE.

James B. Archer, of Yonkers, New York.

Improvement in Baling Manure and Other Substances.

Specification forming part of letters patent No. 181,389, dated August 22, 1876; application filed July 20, 1876.

To all whom it may concern:

Be it known that I, James B. Archer, of Yonkers, in the county of Westchester and State of New York, have invented a new and useful improvement in baling manure and other substances; and I do hereby declare that the following is a full, clear, and exact description of the same, reference being had to the accompanying drawing, forming part of this specification.

(Here follows diagram marked p. 184.)

This invention is more especially designed for the baling of stable manure, in which it has heretofore been found difficult to meet all the requirements of properly confining the material in all parts of the bale, and yet to provide desirable ventilation. It is also applicable to the baling of hay and other substances or materials.

The improvement consists in the combination of two complete frames applied to opposite sides of the bale, and of a form and size to extend all along the edges, and to the corners of said sides, with bands which pass over the said frames and around the bale, and confine the material of bale between the said frames in such manner that the said frames form clamps to clamp said material firmly.

Figure 1 in the drawings is a perspective view of a bale illustrating my invention. Fig. 2 is a perspective view of one of the frames

Similar letters of reference indicate corresponding parts in both

The two frames are each composed of side pieces Λ Λ and end pieces B B, consisting of wooden slats, the said side pieces being of a length equal to the length of the bale, and the said end pieces being of a length equal to the width of the bale. These side and end pieces are nailed or otherwise secured together at the ends to form the frames, which are thus made of a size and form to cover the edges and corners of the two opposite sides of the bale to which they are applied.

The bands C C, of which there may be any number, may be of hoop-iron, wire, or other material, and may be fastened around the bale over the said frames by any suitable fastenings; but I prefer to provide them with hooks a a and eyes b b, two or more eyes in each band, so that some time after the bale has been com-


J. B. ARCHER.


BALING MANURE AND OTHER SUBSTANCES.

No. 181,389.


Patented Aug. 22, 1876.

Fig.1.





Witnesses John Boomer



pressed and the material in it has shrunk by drying, it may be re-

compressed and the bands tightened up.

The frames A B having been made, the bale is formed in a bailing-press of suitable size by first placing one of the frames on the bottom of the box of the press, then filling in upon it the requisite quantity of the material to be baled, afterward putting on the top frame, and then subjecting the contents of the bale between the frames to a suitable pressure. The bands having been applied at a suitable stage in the operation, have their ends fastened while the bale is subject to pressure, and after they have been fastened the box of the press is opened and the bale turned out.

The bale thus formed confines and protects the material most effectively; but the contents may be still further protected at the corners or other parts by placing cleats across the bale from one

frame to the other, and nailing them to the two frames.

What I claim as my invention is-

The combination, with a bale, of the clamping-frames A B A B, applied to opposite sides of the bale, and the bands C C, passing over the said frames and around the bale, substantially as herein described.

J. B. ARCHER.

Witnesses:

BENJAMIN W. HOFFMAN. FRED. HAYNES.

187

UNITED STATES PATENT OFFICE.

CHARLES BROWN, of New York, N. Y.

Improvement in Baling Short-cut Hay.

Specification forming part of Letters Patent No. 169,518, dated November 2, 1875; application filed September 28, 1875.

To all whom it may concern:

Be it known that I, Charles Brown, of the city, county, and State of New York, have invented a new and useful improvement in baling short-cut hay and straw, with or without feed; and I do hereby declare that the following is a full clear, and exact description of the same, reference being had to the accompanying drawing, which forms part of this specification.

Long hay is usually baled on or convenient to the place upon which it is produced, and the same afterward sent to market for future use, either by working it up into short-cut hay, or otherwise.

In baling long hay it is customary to use four or six heavy sticks arranged lengthwise upon the exterior of the bale, and these sticks, after the bale has been broken or used, have had but little if any value.

One of the objects of my invention is to use these sticks in the baling of short-cut hay or straw, with or without feed; and although place is immaterial, this can, generally, be done most economically in the market towns or cities where the long hay has been sold.

In baling short-cut hay or straw, with or without feed, however, a different and much closer arrangement of the binders is necessary; and my invention consists in a novel combination of cross-edge and longitudinal-edge sticks and separated slats applied to opposite sides of the bale, the whole being bound together, with the compacted contents of the bale, by bands, cords, ropes, or wires, substantially as hereinafter described, and whereby I am not only enabled to use the sticks previously employed in baling long hay or other rough sticks, but am able to bale the short-cut hay or straw, with or without feed, in a most economical, complete, and solid manner, and so that the contents of the bale are protected alike from heating and from injury by exposure to the weather.

The drawing represents a view in perspective of a bale of shortcut hay or straw, with or without feed, put up in accordance with my invention.

(Here follows diagram marked p. 186.)

A A and B B are four sticks, which may have been previously used in baling long hay; or they may be specially made for baling short-cut hay or straw, with or without feed. These sticks A A and B B are placed in the cut-hay press before the loose and uncompacted short-cut hay or straw, with or without feed, is filled into the


C. BROWN.

BALING SHORT CUT HAY.

No. 169,518.

Patented Nov. 2, 1875.

Quech p. 186



Wilnesses John Becker Juit Hayne, Charles From Somey. Brown & Allen



press, and so that the binders A A will underlap at their ends the hinders B B, thus binding four of the edges of the bale. the loose and uncompacted short-cut hay or straw, with or without feed, is put into the press, and four more sticks, A' A' B' B', are placed in a corresponding relation with the other sticks A A B B. on or along the four edges of the upper or opposite side of the loose or uncompacted masss, or uncompressed contents of the bale. There are also placed between the longitudinal or side-edge sticks A A and A' A', on the upper and lower or opposite sides of said loose mass or unpressed contents of the bale, two or more thin wood slats, C C and C'C', separated from each other, respectively, and with their ends also resting on or lying over the cross-sticks B B B' B'. These slats may be arranged at a distance of two or three inches apart, more or less. Pressure is then applied to the mass thus bound and protected, and when sufficiently compacted, bands, cords, ropes, or wires D D are passed and fastened around the compressed mass of short-cut hav or straw, with or without feed, and around the sticks or binders A A' and slats C C', to retain the bale in its compacted form.

By the combination of the cross-edge sticks B B' with the longitudinal-edge sticks A A' the bale is bound on eight of its edges by the sticks, thus preventing the spreading of both the sides and ends of the bale, and preventing the contents of the bale from becoming loosened and wasted during handling or transportation of the bale. This retaining of the compactness of the bale at its sides and ends

resists the effects of dampness and wet.

By the combination of the separated slats C C' with the sticks A A' and B B', not only is the bale more firmly braced or held together, but any wet or dampness which the bale has contracted by long or severe exposure to the weather will escape by evaporation on suitably exposing the bale to the air or sun, whereas a close cov-

ering on the same sides of the bale causes the wet or dampness to be retained in the bale, so that the contents of the latter are seriously injured or made worthless by heating and

rotting.

I claim-

The combination of the longitudinal and separated slats C C' with the cross-edge sticks B B B' B', the longitudinal-edge sticks Λ A Λ' A', applied to opposite sides of the bale, and the binding bands, cords, ropes, or wires D, substantially as shown and described, and for the purposes herein set forth.

CHARLES BROWN.

Witnesses:

MICHAEL RYAN, HENRY T. BROWN. 190

125,786.

UNITED STATES PATENT OFFICE.

CHARLES BROWN, of New York, N. Y.

Improvement in Baling Short-cut Hay or Straw.

Specification forming part of Letters Patent No. 125,786, dated April 16, 1872.

Specification describing an improvement in baling short-cut hay or straw, the invention of Charles Brown, of the city, county, and State of New York.

This invention relates to the putting up of short-cut hay or straw in compact bales of convenient size, shape, and weight for handling, transportation, sale, and use as feed for horses or cattle, and for other purposes. The invention consists in putting up short-cut hav or straw in packages, each of which constitutes a hollow bale, formed by a passage arranged to extend through the bale, and the walls of which are composed of the contents of the bale, whereby a more perfect ventilation is effected, so that the hay or straw may be put up greener than when baled so as to present only an outside exposure, and whereby increased facility is afforded for handling the bale or for lifting it from place to place, especially over mud or dirt. Such hollow or ventilated bale I prefer to make of cylindrical form, for the purpose of further facilitating transportation by rolling, and whereby that loss or waste which is incidental to square-shaped bales is avoided, both in moving the bale about and in detaching it for feed, by reason of the bale presenting no sharp edges or angles up its sides, and the greater convenience with which it may be chipped off as required. The invention also consists in a hollow cylindrical bale, braced at its ends by segmental wooden strips and hoops, cords, or wires, arranged to extend across the strips and down the sides of the bale in planes parallel to the axis of the latter, whereby said hollow bale is very effectually bound without impairing its ventilation; and long hay or straw may be used for partly covering the ends of the bale to hold the contents in place and to provide for ventilating the same.

In the accompanying drawing-

(Here follows diagram marked p. 189.)

which forms part of this specification, figure 1 represents a longitudinal outside view of a bale of short-cut hay or straw put up in accordance with the invention; Fig. 2, an end view of the same; and Fig. 3, a longitudinal section thereof.

To press the short-cut hay or straw A into the form of a hollow cylinder, as shown, said material may be suitably piled or packed

CHARLES BROWN.

Improvement in Baling Short Cut Straw or Hay.

No. 125,786. Patented April 16, 1872.

Tous us 189




Fig: 3

Milnegeses: Dustrame Plasame Sharler Snown per Brom Combotton



in a box of cylindrical shape, open at its ends, and resting on a grooved base for passage of the binding-hoops, cords, or wires, said base also carrying a mandrel for forming the passage b in or through the bale and the follower of the press, which works within the box, being grooved like the base, also made hollow to receive the mandrel through it. The box itself should be made to open down its sides, either by hinges or otherwise, and so that when open it may be removed, whereby the bale is left wholly exposed at its sides for the convenience of hooping or binding it, the hoops, ropes, or wires ccbeing passed through the grooves in the base and follower in planes parallel with the axis of the bale, and over segmental wooden strips d d, arranged to lie one upon the other, so as to brace the ends of the bale without impairing the ventilation. Long hay or straw f may also be arranged over or at the ends of the bale to act, conjointly with the strips, to hold the contents of the bale in place, and to provide for the ventilation of the bale between the strips. The passage b through the bale, in addition to its ventilating purpose, may also be used, by insertion of a pole or stick through it, to carry the bale.

What is here claimed, and desired to be secured by letters patent,

1. A hollow bale of short-cut bay or straw, substantially as speci-

2. The combination, with a hollow cylindrical bale, A, of the segmental-shaped binding-strips d d at the ends of the bale and the hoops, cords, or wires, c c, arranged to cross said strips and to extend down the sides of the bale in planes at right angles to the axis of the latter, essentially as described.

CHARLES BROWN.

Witnesses:

HENRY T. BROWN. FRED. HAYNES.

192

UNITED STATES PATENT OFFICE.

RUSSELL A. HART, of Battle Creek, Michigan.

Signature-press.

Specification forming part of Letters Patent No. 394,977, dated December 25, 1888. Application filed September 3, 1887. Serial No. 248,669. (No model.)

To all whom it may concern:

Be it known that I, Russell A. Hart, a citizen of the United States, residing at Battle Creek, county of Calhoun, State of Michigan, have invented a new and useful signature-press, of which the following is a specification.

The objects of this invention will appear in the following descrip-

tion and claims.

One prominent object which may be mentioned is a construction and arrangement of parts whereby the press automatically stops when the bundle of printed pages is sufficiently compressed.

Another leading object consists in constructing the tray in which the pages are placed and the blocks between which the pages are compressed so that the Lundle of pages after being compressed can be readily tied with a strand of cord on each of the four sides and crossed at each end, and this while the compressed bundle is still in the press.

(Here follows diagram marked p. 191.)

In the drawings forming a part of this specification, figure 1 is a side elevation with parts removed, below described; Fig. 2, a plan; Fig. 3, end view of parts shown in Fig. 1, looking from a point at the left. Fig. 4 is a detail view, in elevation, from the same point of observation. Fig. 5 is a transverse section on line p p in Fig. 1. Fig. 6 is a detail view, in cross-section, of elements y, u, and r in Fig. 5 on line w w. Fig. 7 is a perspective view of a supplemental tray, hereinafter described; Fig. 8, a section on line 2 2, Fig. 1, looking from a point at the right; and Figs. 9 and 10 are enlarged views, in perspective, of blocks C and C', and Fig. 11 of frame A, shaft x, and plate z', all in Fig. 1.


Referring to the lettered parts of the drawings, A' is a V-shaped tray supported by standards T, these parts constituting a part of the frame A, in which the internally-threaded shaft x, with internal screw, c, is supported. The tray A' has slots c c' through each of its oblique sides and a V-slot, f, through one end, Fig. 3. The screw c has a head, o, against which the block C is placed cornerwise in the tray A'. The block C' is placed in the other end of the tray A'.

In Fig. 7 is shown a supplemental V-tray having one closed end and slots in the oblique sides, which slots register with the slots c c' in the main tray A'. The printed leaves are placed on their edges

(No Model.)

R. A. HART.

any-





cornerwise in the supplemental tray, Fig. 7, and the latter is placed with its contents in the tray A'. The blocks CC' are placed at the ends of the bundle of leaves in the supplemental tray. One of the bullevs CC' is then slid on the shaft CC' to engage with the dog CC' by

swinging the lever L.

The arrangement of the pulleys B, which revolve in opposite directions, and the dog n and screw c are not new, per se, and will be understood without details being given. Suffice it to say that when one of the pulleys engages the dog the screw c moves forward toward the left, as here shown, and when the other pulley engages the dog the screw moves back. When the screw moves forward, the leaves are compressed, the block C being carried along, as indicated

by the dotted position in Fig. 1.

When sufficient pressure is brought to bear, the block C' presses hard enough against the spring-actuated slide m to force it against the upper end of the pivoted lever F. This action moves the rod t, which is attached to the lower end of lever F and the lower end of the pivoted lever v, which operates the left-hand pulley, and of course said pulley is by that means slid away from the dog n and the screw thus automatically stopped. The supplemental tray is also slid along and its open end extends out through the slot f of the tray A' and through the opening in top of lever F, Fig. 4, this slot and opening being made purposely to accommodate the supplemental tray. The sliding action of this tray is not illustrated, but will be understood, as the head o of the screw c slides it and the block C along at the same time; but the supplemental tray may be dispensed with, if desired, and the leaves be placed directly in the tray A'.

The blocks C' C are so constructed on their inner faces (one having transverse grooves e' e'', Fig. 9, and the other a three-cornered mortise, e, each corner opening through the edge of the block, and a groove, J, leading from the other edge of the block into the mortise or recess e, Fig. 10) that by the use of a large needle the compressed bundle can be tied with a cord, so there will be a strand on each of the four sides of the bundle and crossing at the ends,

the same as a package can be tied when held in the hands.
By this means when the screw c is run back releasing the bundle it is ready to be taken out of the press, and is firmly held in

its compressed condition.

The plan of tying is not here illustrated, but the following will make it clear. A loop is made in one end of the cord and caught over a stud or the like to hold it. The other end is put through one of the channels of block C', thence along one of the oblique sides of the bundle, and then passed obliquely through the recess c of block C—as, for instance, from 1 to 2. At 2 the cord is caught over a stud, (not shown.) from thence along the second side of the bundle and through the other groove of block C', back along the third side of the bundle and through groove J, and up through the loop which was left at 2, and thence from 2 to 3 and along the fourth side of the bundle to the place of starting. The cord is then caught through the first-named loop, and then by releasing the loop at 2 and draw-

ing the cord tight and tying it the bundle is bound at the sides and ends, as before stated. The recess e, Fig. 10, allows the loop, which was at 2, to be drawn to the center of the end of the bundle. The crossed cord in Fig. 8 shows the appearance at this end of the

bundle—left-hand end in Fig. 1.

The lever L, Fig. 5, is pivoted to a bracket, y, which bracket is attached to the frame in Fig. 1, but is not shown in said latternamed figure. The lever L engages a lug, S', and as the other end of said lever enters the groove a' of one of the pulleys, the left pulley is locked in proper position to move the screw c forward. u is a sliding wedge, Figs. I and 5, to which a rod, S, is attached. The other end of rod S is attached to the upper end of the centrally. pivoted lever d, and the lower end of this lever is attached to the rod t. By this means when the end lever, F, operates by the pressure of the block C on the slide m the wedge is drawn forward, pressing down on the end of the lever l, Fig. 5. This lever is shown in cross-section in Fig. 1. At z, Fig. 5, is a spring-actuated plunger. which is carried upward by the lever l when the wedge u tilts said lever, and this raises the lever L, unlocking it from the lug S', so that the lever v can slide the left-hand pulley B out of engagement with the dog n. The lever L is shown clearly in the plan in Fig. 2. The head o of the screw has a projection, u', through the slot c' of the trav A. Should the screw c be started by accident or meddlesome design when the projection u' comes in contact with the head v' of the rod r, Fig. 1, the wedge u, to which said rod is attached will be drawn forward, unlocking the lever L, and as the rod Sis also attached to the wedge the lever v (by means of the hereinbeforedescribed construction) will be tilted and the movement of the screw c will be automatically stopped.

It should have been stated that the registering elongated slots in the oblique sides of the two trays enables the cord-needle to be inserted into the grooves of the blocks C' C, as before explained.

In Fig. 11 I have shown a broken portion of the frame A and the shaft x in perspective, showing also grooves S" in the shaft x, near the bearings, into which groove a semicircular plate, z', is inserted edgewise beneath the shaft, and is secured to the face of the bearing, which in Fig. 11 is the end of the frame A. The object of this plate is to keep the oil from unduly running out of the bearings. One of these plates may be employed on each side, and they may be at each end of the shaft, or, rather, at each bearing of the shaft.

The screw is automatically stopped from running too far back by means of a sliding bar, i, Fig. 1, right-angled at each end. One end enters the groove a of the right-hand pulley B, and the other end passes up through a slot in the tray Λ to contact with the head a of the screw, which contact throws the pulley to the right, disengaging

it from the $\log n$.

Having thus described my invention, what I claim is—

1. The combination of the main tray having the slotted sides with the blocks having crossing-grooves in one and the three-cornered recess and the groove in the other, and means for compressing the bundle between said blocks, substantially as set forth.

2. The combination of the main tray having the side slots and the V end slot, the slotted supplemental tray, the grooved and recessed blocks for placing at the ends of the bundle in the latternamed tray, and means for compressing the bundle between the

blocks, substantially as set forth.

3. The combination of the main tray, the blocks for placing at the ends of the bundle, the screw, dog, and sliding pulley, a springactuated slide which is operated by pressure of one of the blocks, a pivoted lever operated by said slide, a pivoted lever for operating the sliding pulley, and a rod connecting the ends of said pivoted

levers, substantially as set forth.

4. The combination of the frame, the press screw and dog, the sliding pulley, the hand-lever engaging the lock-lug, the sliding wedge, a pivoted lever operated by said wedge, the spring-actuated plunger for lifting the hand-lever to unlock the same, the headed rod projecting from the wedge, a projection on the head of the screw to contact with the head of said rod, a lever for operating the sliding pulley and rods, and a pivoted lever connecting the pulley, lever, and wedge, whereby when the wedge is drawn forward the hand-lever is unlocked and the pulley is disengaged from the dog. substantially as set forth.

5. The combination of the frame, the traveling screw, a dog on said screw, a sliding pulley adapted to engage said dog to cause the screw to recode, and the sliding bar right-angled at the ends, one

end being in position to be brought in contact with the head of the screw and the other end in the groove of the sliding pulley, whereby the receding screw is automatically stopped. substantially as set forth.

6. The combination of the frame, the shaft having the grooves, and the semicircular plates inserted in said grooves, substantially as

RUSSELL A. HART.

In testimony of the foregoing I have hereunto subscribed my name in presence of two witnesses.

Witnesses:

195

A. R. HENRY. M. B. DUFFIE.

Remarks of Justice Hagner as to Decree.

Filed January 30, 1896.

In the Supreme Court of the District of Columbia.

Jones and The Hickok Man'r'G Co. No. 15391. Equity. CLARENCE M. Busch.

My examination of this cause has satisfied me the complainants are entitled to a decree for an account and for an injunction, as prayed.

The complainants' counsel may prepare a decree accordingly.

A. B. HAGNER,

Asso. Justice.

Jan'y 30, 1896.

Interlocutory Decree.

Filed February 11, 1896.

In the Supreme Court of the District of Columbia.

J. W. Jones and W. O. Hickok Manufacturing Company

1. Equity. No. 15391,
2. Docket 36.

Clarence M. Busch.

This cause coming on to be heard upon pleadings and proofs and having been argued by counsel for the respective parties and having been fully considered by the court, it is hereby, this 11th day of February, 1896, by the court, ordered, adjudged, and decreed as follows, viz:

That letters patent of the United States No. 204,741, granted to the plaintiff, Joshua W. Jones, on the 11th day of June, 1878, for bookbinders' dry-press and sheet-tie, are good and valid in law.

That Joshua W. Jones was the original and first inventor of the invention described and claimed in said letters patent; that the legal title to said patent and to the invention described and claimed therein is vested in the said Joshua W. Jones, one of the plaintiffs herein; that the said W. O. Hickok Manufacturing Company, the other plaintiff herein, is the exclusive licensee to manufacture and sell, to be used by others throughout the United States, machines containing the inventions or discoveries described and claimed in said letters patent; that the defendant has infringed the said letters patent and the exclusive rights of the plaintiffs thereunder by making, using, and vending within the United States machines embodying the improvements specified in said letters patent and particu-

larly claimed in the 1st, 2nd, and 4th claims of said letters patent, and also by practicing the process embodying the improvement specified and particularly claimed in the 5th claim

of said letters patent.

And it is further ordered, adjudged, and decreed that plaintiffs do recover from the defendant the profits, gains, and advantages which said defendant has received or made or which have arisen and accrued to him by reason of any infringement by said defendant of the said first, second, fourth, or fifth claims of said letters patent No. 204,741 since the date of said letters patent, and also the damages which the plaintiffs have sustained by reason of said infringement to be assessed as provided by statute.

And it is further ordered, adjudged, and decreed that this cause be referred to the auditor of this court to ascertain, take, state, and report an account of the gains, profits, and advantages which the said defendant has received or which have arisen or accrued to him from the manufacture, use, or sale of machines or the practicing of said process described and claimed in claims one, two, four, and five of said letters patent No. 204,741, and also to assess the damages suffered by the plaintiffs herein by reason of said infringement.

It is further ordered, adjudged, and decreed that the plaintiffs on such accounting have the right to cause an examination of said defendant ore tenus or otherwise, and also the production of the books, vouchers, and documents of said defendant, and that the said defendant attend for such purpose before said auditor from

time to time as said auditor shall direct.

And it is further ordered, adjudged, and decreed that a perpetual injunction issue in this cause against the defendant, Clarence M. Busch, his servants, attorneys, workmen, employees, and representatives, and each of them, perpetually enjoining and restraining him and them from directly or indirectly using, vending, or offering for sale any machine embodying the improvements specified in claims one, two, or four of said letters patent made prior to the expiration of said letters patent.

And it is further ordered, adjudged, and decreed that the plaintiffs do recover of the defendant their costs, charges, and disburse-

ments in this suit, to be taxed by the clerk of this court.

A. B. HAGNER, Asso. Justice,

Final Report of Auditor. Filed March 26, 1897.

In the Supreme Court of the District of Columbia.

J. W. Jones and W. A. Hickok Manufacturing Company vs. Clarence W. Busch.

No. 15391, Equity Doc. 36.

By a decree passed on the 11th of February, 1896, this cause was referred to me to ascertain, take, state, and report an account 197 of the gains, profits, and advantages which the defendant has received or which have arisen or accrued to him from the manufacture, use, or sale of machines or the practicing of the process described and claimed in claims 1, 2, 4, and 5 of said letters patent No. 204,741, and to assess the damages suffered by the plaintiffs by reason of said infringement. This cause was moved in this office in December, 1896, and, upon notice, was set for hearing for Tuesday, the 22d day of December, at which time the counsel for the plaintiffs and the defendant respectively appeared and submitted and filed testimony for the plaintiffs, taken in Harrisburg, Pennsylvania, together with a stipulation of the said counsel that the testimony of witnesses in this accounting might be taken before any officer competent to administer oaths with the same effect as if regularly taken before the auditor. This testimony is marked "auditor's

way of distinction from the printed records containing, respectively, the evidence submitted by the parties prior to the granting of the decree. The subject-matters of the reference were then argued by counsel and a brief filed by the counsel for the plaintiffs. Upon leave granted for that purpose the counsel for the defendants subsequently transmitted, to be filed, a brief in behalf of the defendant, and these briefs are returned with this report.

The patent in question contains four specific claims illustrated by the drawings attached to the patent, and in the fifth claim a description of the process. As bearing upon the question of accounting.

quote the fifth claim in full, as follows:

"The process herein described for treating folded printed sheets of paper in dry-pressing, the same consisting of subjecting a collection of such sheets to pressure without the use of fuller-boards, and while under such pressure tying them into compact bundles with end boards, then removing them immediately from the press and allowing them to remain tied sufficiently long to fix and complete

dry-pressing.

It is established in proof that the defendant used the infringing machine from September, 1893, to the 10th of February, 1895, when it was destroyed by fire; that during the said period the defendant was the public printer for the State of Pennsylvania, and in the performance of the work done by him as such public printer he used the infringing machines during the period named. It will be seen that the subject of an accounting in such a case is not to show what profits as such were made by the use of the infringing machine. It is alleged that by its use the defendant made savings in the cost of the work performed with the machine, and that these savings are included under the terms of the decree as constituting gains and advantages which have accrued to the defendant from the use of the infringing machine or the practicing of the process described in the sustained claims.

In the case of Tilghman v. Proctor, 125 U. S., p. 136, the Supreme Court held that, if the unauthorized use by the defendant of a patented process produced a distinct saving in the cost of manufacture,

he must account to the patentee for the amount so saved: 198 The court in that case having adjudged that Tilghman's patent was a valid one for a process; that the apparatus described could be operated to produce a beneficial result, and that the defendants had infringed the complainant's patent, the master to whom the case was referred found from the evidence that the complainant had derived no profit from the invention otherwise than by granting licenses to others to use the same; that for several years the respondents held such a license, but terminated the same, refusing to pay the license fees after a certain period, although continuing to use the process until the expiration of the patent, between four and five years afterward. The master reported that as to the profits, gains, savings, and advantages which had accrued to the defendants the process described in the patent was more advantageous than any other process open to public use at the time in question, and re-

ported the defendants' savings in certain material and their gain in a product, setting off against this their loss in another direction, and thus showing the net gains and savings. After drawing a distinction between the extent of a recovery for the infringement of a patent at law and under a bill in equity and holding that in the latter proceeding the owner of the patent is entitled to recover the amount of gains and profits that the defendant has made by the use of the invention, the court announces the rule to be that the profits for which the infringer must account are the fruits of the advantage which he derived from the use of the invention over what he would have had in using other means then open to the public and adequate to enable him to obtain an equally beneficial result. In that case the defendants contended that the plaintiff, having established license fees for the use of his patent, was not entitled to any gains and profits accruing to the defendants in excess of those fees, but the court held the plaintiff had the right and was entitled to have a de-

cree for profits.

It appears that the printing law of Pennsylvania required that all of the work should be dry-pressed, and the defendant, testifying on page 5 of the auditor's record, states as his reason for purchasing the infringing machine that the printing law of 1876 provided for such dry-pressing and to avoid any possible objection to the use of any other process than what was known as dry-pressing. The dry-pressing spoken of seems to be a technical name for the character and result of the process. It appears that the impression of the type in printing leaves upon the page next the press the impression of the type in concave form, while on the opposite side of the sheet those impressions appear in convex form. In the use of the machine and process of the plaintiff the sheets containing respectively the concave and convex characters were placed against or upon each other so as to register the lines as fully as practicable, and as a result of the process the convex and concave features were removed and the printing given a smooth, regular appearance. It also appears that by reason of the admission of a current of air between the sheets at a period of the process any dampness of the ink was removed, 199

this feature tending to some extent to justify the designation

of the process as that of dry-pressing.

In order to ascertain the savings to the defendant resulting from the use of the invention, it becomes necessary to inquire what other means were then open to the public and adequate to obtain an equally beneficial result. In pursuing this branch of the inquiry it will be convenient to describe first the process of the plaintiffs' invention. T. J. W. Robertson, a witness produced on behalf of the complainants, and whose deposition is begun on page 30 of the plaintiffs' printed record, and who it was agreed by counsel for both parties was competent to testify as an expert witness in patent matters, testifies that he had examined the letters patent in question here, and describes the improvement covered by claims 1, 2, 4, and 5 as a process for treating folded printed sheets whereby the impressions made in the letter-press printing process are flattened out so that the paper will assume its original smoothness or substan-

tially so, which process is carried out in such a manuer that the operator can be continually putting in the signatures or printed matter and removing them in tied-up bundles, whereby with one press a much larger number of signatures can be pressed and at a much reduced cost for labor over that of the process previously em-The witness refers to the means for carrying out this process, as shown in the drawings attached to the patent, and proceeds to state that prior to this invention it was the custom to press printed sheets by inserting them between heavy paper boards-sometimes called fuller-boards; also called glazed boards-and putting said boards, with the printed papers between them, into a powerful press, pressure being produced on said boards sometimes by screw and sometimes hydraulic pressure; that this pressure was continued by allowing the press to remain with such pressure on to its fullest extent for ten or twelve hours or more, when the papers and boards were taken from the press and separated by removing the boards from the pile of combined boards and paper and putting the boards on one pile and the printed papers on another; that by the process of this invention the printed sheets are allowed to remain only long enough for the operator to tie up the bundle, when they are immediately removed, the entire process of putting the paper into the press, tying it up in the bundle, and removing it therefrom taking but a few minutes: that the signatures, meaning the sheets of printed matter, are thus allowed to remain tied up in bundles for a time, which may be from twenty-four hours to three or four days, or may be extended longer, and that the long-continued pressure after the bundle has left the press is therefore an essential part of the process. Referring to the difference between the old or prior process and that set forth in the Jones patent, this witness proceeds to state that in the old plan, where two or more sheets were set between the boards the convex side of the impression on one sheet came in contact with the concave side of the sheet above it, so that these sheets would have little or no effect upon each other in smoothing out the impressions. while in the process of the Jones patent the sheets when folded

have the convex impression of one-half of a sheet brought in contact with the convex side of the other half of the sheet. This witness proceeds with considerable detail to describe the entire operation of this so-called dry-pressing process, and refers particularly to the claims 1, 2, and 4 and the drawings or figures illustrating these claims. He then concludes by saying as to the fifth claim that this claim covers the process of pressing folded sheets or signatures by first subjecting them to pressure, then tving them between boards in a compact bundle and removing them from the press and allowing them to remain tied a sufficient length of time to efface the impressions produced by printing. It may serve to enlighten the comparison to be made between the process of this invention and other processes relied upon by defendant's counsel as being in existence, open to the public, and adequate to obtain an equally beneficial result if I refer to the process described by many, if not all, of the witnesses who testified on that subject here as generally in use prior to the patenting of the Jones process—that is, what was known or designated as the fuller-board process. The witness Suydam, produced in behalf of the plaintiff, and whose testimony will be found on page 9 and the following pages of the auditor's record, being a booklinder by trade and having served as foreman of the State bindery of Pennsylvania for ten or eleven years, states that there were two methods of accomplishing what was known as dry-pressing used in the said State bindery, one being the old method of dry-pressing with fuller-boards and what was known as a standing hydraulic press, and the other the Jones dry-pressing system, which was introduced some time in the seventies. This witness, on page 14 of the auditor's record, describes the two processes or operations by way of

comparison, first giving the fuller-board process as follows:

"The sheets were taken from the press-room direct to the sheetroom; they were there hung upon rods to dry. After they were dried
they were taken off the rods; brought down into the folding-room;
they were then placed between fuller-boards, three or four sheets at
a time; from there they were placed in the hydraulic standing
press; the press was then run up tight by hydraulic pressure.
After being pressed, as a rule, over night the pressure was taken off
the sheets, the press emptied of fullers-boards and sheets, and the
sheets taken out from between the boards. The sheets were then
folded and tied up in bundles of five hundred; the same process
gone through with each signature until the book was completed.
The sheets were then gathered into book form, taken to the smashing machine and smashed, and the book was then ready for sewing.

"In the Jones process the sheets came from the sheet-room direct to the folding machine; when they were folded they were placed in the Jones machine, five hundred signatures at a time, with smooth-finished oak boards of an inch thickness placed at each end, the outside edges of the boards being rounded off. The pressure was then applied, the required amount being obtained; a heavy cord was placed both ways around the five hundred signatures, the

201 pressure relieved, and the signatures stored away until the completion of the book, thus doing away with the hanging of the sheets and all of the handling as described in the process with

fullers-boards and standing press."

The defendant, being examined as a witness, states, on page 3 of the auditor's record, that in his business from 1883 to 1893 he employed a smashing machine to do the work which, after September, 1893, he did upon the infringing machine, and states in the same connection that there was but little saving in money by the use of the latter over the former, but considerably greater in convenience, owing to the greater case in handling the machine-compressed bundles over those tied by hand. On page 6 of the auditor's record the same witness states that a smasher is used in the operations of binding after the sheets have been gathered and collated into books, and described the manner in which a smasher is operated and used as follows:

"The bunch of sheets are placed on a large board of pasteboard and another pasteboard placed on top of the bunch, and the combination is slid in between the rising bed and stationary head of the machine, and receives a pressure at each revolution of from thirty to one hundred tons, being allowed to receive two or three of these pressures generally and then removed, the length of each pressure being about three or four seconds and not exceeding a

quarter of a minute."

The witness Suydam testifies in relation to the use of the smashing machine, and, among other things, on page 22 of the auditor's record he testifies that if the sheets were folded, gathered, tied up in bundles in the old way until ready for use, and then subjected to the action of the smasher that the type indentations would not be removed, and gives his reasons for that statement. He also, on page 24½ of the auditor's record, states that, in his judgment, based upon his experience, his knowledge of the use of such machines, and of what is necessary for the removal of type indentations, that he is positive that a smasher is not a practically operative machine for such purpose.

The plaintiff Jones, examined as a witness, testifies, on page 28 of the auditor's record, that the removal of type indentations from printed sheets by use of a smasher is an utter impossibility; that he is familiar with the use of a smasher, and states the details of that familiarity, and then proceeds in reply to question 14 to state why a smasher would not perform the work of removing type indenta-

tions from printed sheets.

It is contended that what was known as the Palmer press was, during the period covered by this accounting, open to the public use and was adequate to produce a result equally beneficial and advantageous with that of the Jones invention. It appears from the proof that this press was not capable of dry-pressing; that it was useful in the bindery for bundling and storage of sheets which had already been through the operation of dry-pressing, and that the packages or bundles made by the use of that press were not in the convenient, safe, and protected form as the result of the opera-

tion of the Jones process.

202 It is also contended and appears in proof that during the period covered by the accounting there was in existence a press known as the Gordon press, which to a certain extent was capable of performing some of the material operations of the Jones invention, but it also appears that this press was not capable of use for such printing as was required from the defendant as public printer for the State, the Gordon press being only useful for light printing, such as letter-heads, circulars, and similar printing.

It is testified to by several of the witnesses that the only process known generally prior to the Jones signature press that would remove the indentations of type was the old process of laying the sheets between fuller-boards and pressing them. This statement is made by the witness Thomas B. Penicks, a bookbinder in the Government Printing Office, who was superintendent of the folding-room of the Government Printing Office for 25 years. On page 74 of the plaintiffs' printed record his testimony on this point will be found.

The plaintiff Jones also testifies on this point, commencing on

page 26 of the auditor's record. Having already testified to his means of knowledge of the printing and bookbinding arts during the period from 1844 to 1883, he states in reply to a further question that he has kept up since the latter date his knowledge of the said arts by visiting establishments and through trade publications to which he subscribes, in both of which directions he kept up continual watchfulness to ascertain whether any new process was discovered for the operation of removing type indentations or, as so called, dry-pressing; that he was continuously taking the principal journals of the book trade published in this country and those of England; that he had found no process mentioned nor had he seen any other process excepting the pressing between fuller-boards, as before described, and his own: that there was but one modern process, which was the pressing of the sheets between fuller-boards, and no older processes as cheap and practicable as that.

It is abundantly shown that what was known as the fuller-board process was the operation or method generally used down to the time of the Jones invention, and, exclusive of the use of that invention, the process generally used during the period covered by this accounting. The plaintiff having established this fact satisfactorily, I hold it to be incumbent upon the defendant to assume the burden of proving that there were other processes or means open to public use and adequate to obtain results equally beneficial with those obtained by the use of the plaintiff's invention; this the defendant

has failed to do.

I therefore find that the only means open to the public during the period from September, 1893, to February 10, 1895, and adequate to obtain results equally beneficial with those obtained by the use of the plaintiff's invention was the process known as the

fuller-boards process, described more in detail as follows:

When the printed sheets taken from the press reached the drying-room they were hung upon rods for drying. When dry they were taken down and brought into the folding-room and placed between fuller-boards three or four sheets at a time, then placed under the hydraulic stamping press, and that press run up to its full capacity, the sheets remaining in that pressure usually during the night, after which the pressure was taken off, the press emptied of fuller-boards and sheets, the sheets taken out from between the fuller-boards, then taken to the folding machine, and, after being folded, tied up in bundles of 500, the same process being gone through with each signature until the entire book was completed, when the sheets were placed on the table and gathered into book form; from there taken to the smashing machine, and after being smashed the books were ready for sewing.

I next proceed to ascertain whether the use of the plaintiff's invention resulted in a saving of cost as compared with the said fuller-board process. I find from the evidence that the work of the latter process, as I have above described it, required the labor of five different persons—one for hanging up and taking down the sheets, two for placing them on the fullers-boards, one for tying them in

bundles of 500 each, and one for mashing and running up the hy-This enumeration of the labor is exclusive of the work of folding and gathering. See the testimony of Suydam, on pp. 10 and 11 of the Aud. Rec. The same witness, on page 11, in reply to a question as to the cost of the operation of dry-pressing printed sheets by the fuller-board process, states that, estimating the wages of the persons employed at the rate of \$3 per week for each the cost would reach 29 cents per thousand signatures. On pp. 29 and 30 of the Aud. Rec., the plaintiff Jones, testifying, states that taking into consideration the extremely low rate of wages paid and the cheap class of labor used in the process, the dry-pressing by fullers-boards, including the smashing, would cost about 27 cents per thousand sheets, and he proceeds to give in detail the calculation through which he reaches that result. Comparing this calculation with the other evidence as to the amount of labor required in the processes through which the paper passes in being so dry-pressed. I find his detail calculation correct, and without repeating it here adopt it as the basis of my finding, that the dry-pressing by means of the fuller-board process cost not less than 27 cents per thousand

Calculating the 10,500,000 sheets treated by the defendant by the means of the infringing machine at the rate of 27 cents per thousand, I have the actual cost of the entire work if it had been performed by means of the fuller-board process. As against this I put the actual cost of the labor employed in operating the Jones process and reaching the same results of dry-pressing, being, as is testified to by the defendant, one-fifth of the service of a boy whose wages were \$3.50 per week. I find the period covered by this accounting taken as of the 1st of September, 1893, and ending on the 10th of February, 1895, to be 75 weeks. As the time of the boy other than

the one-fifth appropriated to the Jones machine was devoted to other of the defendant's work, I take one-fifth of these 204 wages as the cost of operating the infringing machine. Deducting this amount from the entire cost as ascertained above. I

have the net saving to the defendant by the use of the infringing machine.

The plaintiff claims a further advantage gained by the defendant by the use of the infringing machine in the item of the saving of waste paper. It appears that the State in furnishing to the defendant paper for its printing allowed 28 sheets per thousand extra for waste, and that any saving out of this allowance became the property of the defendant under his contract. It appears in proof that the waste by the fuller-board process was about 10 sheets per thousand, while by the Jones process it did not exceed one sheet per thousand, a saving of 9 sheets per thousand, or, as the evidence further shows, a total of 11,820 pounds, treating the paper as 60 pounds to the ream, and its market price, as testified to by R. A. Johnston. paper dealer, as 6 to 7 cents per pound, the apparent saving to the defendant would be the quantity as above stated in weight at the rate of at least 6 cents per pound.

In the absence of any express proof showing whether the defend-

ant made sale of this paper so saved, I am compelled to assume that there was a saving to him or gain at the rate of 9 sheets per thousand, aggregating the weight of 11,820 pounds, which were of value

to him of at least six cents per pound.

A further contention of the plaintiff is that there was to the defendant a saving in machinery; that the work accomplished by him in the operation of dry-pressing these printed sheets, if performed by the process described as the fuller-board process, would have required the service of at leave five presses during the period of this accounting; that presses of the required capacity, including the pumps and exclusing other connections, would have cost in 1893 \$960 each, aggregating for the five presses the sum of \$4,800. It is claimed by the plaintiffs that as the work if done and performed by that process would have required an investment of this sum of money, which was saved to the defendant by the use of the infringing machine, he is properly and lawfully chargeable with the interest on that sum during the period covered by the account.

I am unable to agree with the counsel for the complainant in this contention. The rule as laid down uniformly by the courts in cases of accounting for gains, profits, and advantages derived by the infringer by the use of the infringing machine or process is that the gains, profits, or advantages must be established by affirmative proof produced by the plaintiff; that this proof must be definite and precise, with nothing left to implication or intendment. There are several defects in the proof offered to establish the assertion of the plaintiff on the point under consideration. It does not satisfactorily appear that the work of dry-pressing the 10,500,000 printed sheets by the fuller-board process would have required the number of machines asserted by the plaintiff, and even if it was, it does not appear that the defendant would have been compelled to pur-

205 chase five machines or pay for them in money the amount estimated. In short, the testimony is not such as I think the rule laid down by the courts requires to authorize me to charge the defendant with the interest on this sum of \$4,800 as a saving or ad-

vantage.

In the schedule hereto annexed I have stated the savings of the defendant by the use of the Jones process by the infringing machine as compared with the only other means then open to the public and adequate to obtain an equally beneficial result, being the two items I have above described, the saving in cost of labor and in the waste of paper.

I find that the defendant has realized advantage in the way of savings by the use of the machine and process described in claims 1, 2, 4, and 5 of the letters patent No. 204,741 as savings in cost of labor, \$2,782.50, and as savings in waste of paper, \$709.20, being a

total savings of \$3,491.70.

I do not find in the cause evidence sufficient to enable me to assess the damages suffered by the plaintiffs by reason of the defendant's infringement. Plaintiff has produced evidence tending to show the selling price of the Jones machine or press and the cost of labor and material employed in the construction of such machine.

206

It is contended by the defendant that this is not sufficient; that the cost of the machine or press includes not only the value of the labor and material, but its fair proportion of the expenses of the plaintiff's business, as to which there is no proof in the cause. In the recent case of The Fenton Metallic Manufacturing Co. v. The Office Specialty Manufacturing Co. I have had occasion to consider this question and to hold that upon the authorities the business expenses of the plaintiff should be included in the item of cost of the patented article. This rule is laid down by Robinson on Patents repeatedly and is sustained by a number of cases in the Federal Reports. In the condition of the proof here I am unable to report damages suffered by the plaintiffs.

JAS. G. PAYNE, Auditor.

SCHEDULE A.

Account of Gains, Profits, and Advantages which have Accrued to the Defendant from the Use of the Machine or Practicing of the Process Described in Claims One, Two, Four, and Five of the Letters Patent.

Cost of dry-pressing by the fuller-board process:

10,500,000 sheets at 27 cents per thousand....... \$2,835.00

Cost of said operation by the process of the said patent—labor of one boy onefifth of the time for 75 weeks at wages of \$3.50 per week:

Saving in waste of paper, 9 sheets per thousand, 197 reams, 11,820 pounds, at 6 cents per pound.

Saving in cost of labor...... \$2,782.50

JAS. G. PAYNE, Auditor.

7,709.20

Exceptions to Auditor's Report.

Filed April 8, 1897.

In the Supreme Court of the District of Columbia.

J. W. Jones and The W. O. Hickok Manufacturing Company
vs.
Clarence M. Busch.

In Equity. No. 15391, Docket 36.

Exceptions to auditor's report.

Exceptions taken by the defendant to the report made herein by James G. Payne, auditor, to whom this cause was referred.

First. For that the auditor has disregarded the order of the court referring the case to him, and the patent in suit, so far as the fifth claim is concerned, by considering testimony and basing his conclusions upon a process wholly outside of the patent.

Second. For that the auditor has assumed that the fifth claim of the patent, which is "for treating folded sheets," includes also other

steps not specified in the claim, to wit:

1. The step of hanging the unfolded, wet, printed sheets.

Removing said sheets from the drying poles and placing them between fuller-boards.

Placing such sheets and fuller-boards in an hydraulic press.
 Subjecting said unfolded sheets to pressure and allowing them to remain for a certain number of hours in the press.

Removing the sheets and fuller-boards from the press and separating the fuller-boards from the sheets.

6. Folding the dry sheets.

none of which steps are specified in the claim or referred to in the patent.

Third. For that the auditor has reported a saving of paper and of handling wet printed sheets and preparing them for the folding machine, whereas the fifth claim of the patent has only to do with folded sheets.

Fourth. For that the auditor reports savings by the use of the process of the fifth claim over processes in use prior to Jones' invention, and disregards the testimony of the witnesses Busch, Grier and Suydam that during the time of the alleged infringement no fuller-boards were necessary in dry-pressing and no savings made by the use of the Jones process.

Fifth. For that the auditor has assumed, without proof, that the "dry-pressing" referred to in claim 5 means removing type indentations, instead of, as the claim specifies, to fix

and keep the pressed sheets smooth.

Sixth. For that the auditor has based his report upon the assumption that the process of the fifth claim is a mere function of the ma.

chine shown in the patent in suit and the other later patents, which were improvements upon the machine shown in the patent.

Seventh. For that the auditor has reported more than nominal damages, as he should have done, the complainant having failed to apportion the advantages derived from the use of the machines in carrying out the process, the comparison, from the evidence, being with the improved hydraulic machine, which is the subject of sereral patents to the complainant, and the defendant's machine, which is also an improvement upon all of the Jones machines, and, as such, patented.

Eighth. For that the auditor disregarded the testimony of complainant and his witnesses to the effect that no damages would have accrued to either of the complainants had defendant bought the Jones machine, which carried with it a license to use the process, instead of the infringing machine, the difference in the cost being but \$100.00 for a machine, including the improvements of later

patents than that upon which this suit is brought.

Ninth. For that the report is based upon the ruling in Tilghman rs. Proctor, 125 U. S., page 136, in which the process was a purely chemical process, irrespective of mechanical appliances, while the steps in the Jones patent, as set forth in the patent and testified to by the witnesses, is purely mechanical.

GEO. J. MURRAY. Solicitor for Defendant.

(Endorsed:) In equity. No. 15391, docket 36. Sup. court, Dist. of Columbia. J. W. Jones et al. vs. Clarence M. Busch. Exceptions to auditor's report.

Decree.

Filed January 19, 1899.

In the Supreme Court of the District of Columbia.

This cause came on to be heard upon the exceptions of the defendant filed on the 16th day of February, 1897, and on the 8th day of April, 1897, to the report of the auditor, filed herein on the 26th day of March, 1897, and on the defendant's motion filed on the 19th day of December, 1898, to vacate the interlocutory decree passed herein on the 11th day of February, 1896, and the same were argued by the respective counsel and considered by the court. 208

It is therefore this 19th day of January, 1899, by this court and the authority thereof adjudged, ordered, and decreed that the said-exceptions and the said motion be, and the same are hereby,

overruled, and the said report of the auditor be, and the same hereby is, finally ratified and confirmed.

A. B. HAGNER, Associate Justice.

Final Decree.

Filed April 4, 1899.

In the Supreme Court of the District of Columbia.

J. W. Jones and The W. O. Hickok Manufacturing Company
es.
Clarence M. Busch.

No. 15391, Equity
Doc. 37.

Final decree.

This cause having heretofore come on to be heard upon the exceptions of the defendant, filed on the 16th day of February, 1897, and on the 8th day of April, 1897, to the report of the auditor, filed herein on the 26th day of March, 1897, and on the defendant's notion, filed on the 19th day of December, 1898, to vacate the interlocutory decree passed herein on the 11th day of February, 1896, so far as the fifth claim of the patent in suit is concerned, and an order having been entered on the 19th day of January, 1899, by this court, in which it was adjudged, ordered, and decreed that the said exceptions and the said motion be overruled and the report of the auditor be finally ratified and confirmed, and the case now coming on for final decree this 4th day of April, 1899—

It is ordered, adjudged, and decreed that the said decree of February 11th, 1896, and said order of January 19th, 1899, be, and the same are hereby, confirmed and made final, and that the said defendant pay to the complainants the sum of \$3,491.70, with interest from the 26th day of March, 1897, the date when said report was

submitted to the court.

It is further ordered, adjudged, and decreed that the said defendant pay to the complainants the costs in this suit, amounting to \$293.05, and that said complainants have judgment and execution for such costs and for the sum above decreed, with interest to be paid by the defendant to complainants aforesaid.

> A. B. HAGNER, Associate Justice.

(Endorsed:) Jones et al. vs. Busch. Final decree (amended).

209

Petition for Appeal.

Filed April 19, 1899.

In the Supreme Court of the District of Columbia.

J. W. Jones and W. O. Hickok Manufacturing Company, Complainants,

In Equity. No. 15391.

CLARENCE M. Busch, Defendant.

Petition for appeal.

To the honorable the judge of the supreme court of the District of Columbia:

The above-named defendant, Clarence M. Busch, conceiving himself aggrieved by the interlocutory decree entered on or about the 11th day of February, 1896, in accordance with a decision filed on or about January 30, 1896, the order signed January 19, 1899, and the final decree entered on April 4th, 1899, in the above-entitled cause, does hereby appeal to the Court of Appeals of the District of Columbia from said decree, and prays that this his appeal may be allowed; that a proper citation may be issued and served upon the complainants in said cause or their solicitors, and that a transcript of the record, proceedings, and evidence in said cause upon which said decree was founded, duly authenticated, may be transmitted with this appeal to the said Court of Appeals.

GEO. J. MURRAY,

Defendant's Solicitor.

CHAS. E. RIORDON, Of Counsel.

Appeal allowed and bond for costs fixed at \$500,

A. B. HAGNER, Justice Sup. Ct., D. of C.

Assignment of Errors.

Filed April 19, 1899.

In the Supreme Court of the District of Columbia.

J. W. Jones and W. O. HICKOK MANUfacturing Company, Complainants,

In Equity. No. 15391.

CLARENCE M. Busch, Defendant.

And now comes the above-named defendant, by his solicitor, and presents, with his accompanying petition for an appeal from the final decree rendered in this cause, the following assignment of errors:

First. The findings of the court are against the clear weight of

the evidence, and the decree based thereon is against the law and the facts and is inequitable and unjust for the reasons hereinafter stated and for other reasons apparent on the face

of the record.

Second. The court erred in holding on interlocutory decree that the letters patent, No. 204,741, granted to complainant Jones June 11, 1878, being the patent in suit, were good and valid in law, and that the legal title to said patent was vested in said Jones and his co-complainant, The W. O. Hickok Manufacturing Company.

Third. The court erred in finding and holding that the defendant infringed the 1st, 2nd, and 4th claims of said letters patent by the use of one machine used by him, and by further finding that the defendant infringed the 5th claim of said patent by practicing the process set forth therein on the machine covered by the 1st, 2nd, and 4th claims of said patent.

Fourth. The court erred in granting a perpetual injunction against the defendant, a mere user of one machine, eight months

after the expiration of the patent in suit.

Fifth. The court erred in overruling the motion to vacate the interlocutory decree after the auditor had reported that the complainants had suffered no damage by reason of the defendant having purchased his machine from another instead of from the complainants, when the undisputed testimony before the auditor showed that every machine purchased from the complainants carried with the sale of the machine a license to use the process of the 5th claim of the patent free of royalty.

Sixth. The court erred in overruling the exceptions to the auditor's report awarding as profits and damages \$3,491.70 by the use of the machine covered by claims 1, 2, and 4 of the said letters patent No. 204,741 and the process practiced on said machine and covered by claim 5, when the auditor reported no damages by reason of defendant's infringement in purchasing the alleged infringing

machine.

Finally. The court erred in holding that complainants were entitled to interest on the amount of damages found by the auditor from the date of submission by the auditor of his report to the

court.

Wherefore the appellant, Clarence M. Busch, prays that the Court of Appeals of the District of Columbia will proceed to hear the said cause anew, and that the said decree of the supreme court of the District of Columbia and every part thereof may be reversed and a decree made reversing said decree with costs or such other decree as to the said Court of Appeals may seem fit.

GEO. J. MURRAY,

Solicitor for Appellant.

CHAS. E. RIORDON, Of Counsel.

(Endorsed:) Copy. Petition for appeal & assignment of errors.

Memorandum.

April 19, 1899.—Bond for appeal filed. 21—96 211

Copy.

Waiver of Citation.

Filed May 18, 1899.

In the Supreme Court of the District of Columbia.

J. W. Jones and W. O. Hickok Manufacturing Company, Complainants, In Equity. No. 15391. Clarence M. Busch, Defendant.

In the above-entitled cause appeal having been taken to the Court of Appeals of the District of Columbia by the defendant, Clarence M. Busch, from a decree against him in the supreme court of the District of Columbia, I, in behalf of the complainants, hereby waive service of citation in re said appeal.

M. W. JACOBS. Attorney for Complainants,

May 17th, 1899,

(Endorsed:) Copy. In equity. No. 15391. Jones et al. vs. Busch. Waiver of citation

Supreme Court of the District of Columbia.

UNITED STATES OF AMERICA, 88:

I, John R. Young, clerk of the supreme court of the District of Columbia, do hereby certify the foregoing pages, numbered from 1 to 155, inclusive, to be a true and correct transcript of the record, as prescribed by rule 5 of the Court of Appeals of the District of Columbia, in cause No. 15391, in equity, wherein Joshua W. Jones et al. are complainants and Clarence M. Busch is defendant, as the same remains upon the files and of record in said court.

In testimony whereof I hereunto subscribe Seal Supreme Court my name and affix the seal of said court, at of the District of the city of Washington, in said District, this Columbia. 20th day of May, A. D. 1899.

JOHN R. YOUNG, Clerk.

Endorsed on cover: District of Columbia supreme court. No. 903. Clarence M. Busch, appellant, vs. Joshua W. Jones et al. Court of Appeals, District of Columbia. Filed May 22, 1899. Robert Willett, clerk.

212

Addition to Record per Stipulation of Counsel.

Court of Appeals, District of Columbia, October Term, 1899.

CLARENCE M. Busch, Appellant,

**JOSHUA W. JONES and THE W. O. HICKOK MANUFACTuring Company.

No. 903.

Filed September 21, 1899.

213 In the Court of Appeals of the District of Columbia.

Clarence M. Busch, Appellant, rs.

Joshua W. Jones et al.

Court of Appeals, District of Columbia, October Term, 1899.

Clarence M. Busch, Appellant,
vs.
J. W. Jones and The W. O. Hickok Mfg. Co., Appellees.

It is hereby stipulated and agreed by and between counsel for the parties hereto that the accompanying pages, 8 to 26, of defendant's (appellant's) printed record, in the supreme court of the District of Columbia, may be printed and form part of the transcript of record for this court, the same having been inadvertently omitted from the transcript furnished, said pages covering stipulations, testimony of Charles G. Schrank, Edmund H. McKee, Francis E. Davis, and Alexander Stewart, and the notary's certificate.

CHAS. E. RIORDON,
Of Counsel for Appellant.
M. W. JACOBS,
Counsel for Appellees.

September 19, 1899.

In the Supreme Court of the District of Columbia, Sitting in Equity.

Joshua W. Jones and The W. O. Hickok Manufacturing Co. vs. Clarence M. Busch.

It is hereby stipulated and agreed by and between the parties hereto, that the testimony and proofs to be taken on behalf of both parties hereto may be taken orally before any duly qualified notary public, with the same force and effect as though taken before a regular examiner of this court, and an order may be entered at any time by either party upon filing this stipulation, appointing such notary public or notaries public as may act as special examiners.

Office copies of all letters patent offered in evidence by either party hereto may be received, marked and read with the same force and effect as though the same were duly certified copies.

Dated September 12, 1894.

M. W. JACOBS, Solicitor for Complainant, O. M. HILL, Solicitor for Defendant,

The Supreme Court of the District of Columbia, Sitting in Equity,

Joshua W. Jones and The W. O. Hickok Manufacturing Co. vs. Clarence M. Busch.

It is hereby stipulated and agreed by and between the parties hereto that the records in the above-stated case, and also the exhibits offered in evidence therein, may remain in the custody of the respective counsel, to be filed, however, upon the request of the opposite party; and exhibits to be loaned to either side, for the purposes of this case, upon reasonable notice.

Dated September 24, 1894.

M. W. JACOBS, Solicitor and Counsel for Complainants. O. M. H1LL, Solicitor and Counsel for Defendant.

Supreme Court of the District of Columbia, Sitting in Equity.

JOSHUA W. JONES and THE W. O. HICKOK
Manufacturing Company
18.
CLARENCE M. BUSCH.

No. 15391, Doc. 36.

Taking of testimony, offering evidence in the above-entitled cause before William M. Stewart, Jr., No. 400 Chestnut street, Philadelphia, Pennsylvania, commencing Friday, April the 26th, A. D. 1895, on behalf of respondent-, pursuant to agreement of parties.

Present: M. W. Jacobs on behalf of the complainant, and George J. Murray on behalf of respondents.

Charles G. Schrank, a witness produced on behalf of respondent-, being first duly sworn, deposes and says in answer to interrogatories propounded to him by Mr. Murray, as follows:

Q. 1. State your name, age, residence and occupation.

A. Age 63: 1303 Moore street, Philadelphia; occupation, at present, book agent.

Q. 2. Please state how you were employed during the year 1874, and prior thereto.

A. I was employed in the year 1874 as a bookbinder. I 215 was in the employ of John Palmer, the man I served my apprenticeship with.

Q. 3. How long prior to 1874 were you in the employ of John Palmer? Where was his place of business when you were first employed by him?

A. I was employed by him first in 1848 at 517 Minor street,

Q. 4. State how long you were continuously employed by him, and

where his place of business, if he had different places.

A. From 1848 up; I was 37 years in his employ, but not constantly. He moved from 517 Minor to the northwest corner of Sixth and Minor streets. Then afterwards moved from there to the southwest corner of Sixth and Walnut streets, from there to the Tatham building, Nos. 224, 226, 228, S. Fifth, then across the street to the Wiler building on the east side of Fifth street, from there I assisted in the removal of the machinery to the Tatham building again on the 19th of May.

Q. 5. Will you please state what means was employed by Mr. Palmer, or in his establishment, for pressing, bundling or tying up

signatures while you were in his employ?

A. They had a press there with a screw in it of about an inch and a quarter with blocks with slots in for the purpose of taking up the slack of the strings after the pressure was applied.

Q. 6. State when that press, such as you have described, was first

put in use by Mr. Palmer, if you know.

A. He had the press made when I was out of his employ in the year 1873, but I had used the process on another press, that is blocks previous to that, which I had seen in use at another place of Mr. George W. Story, who carried on the process of folding books at the northwest corner of Third and Walnut streets. When I was about 15 years of age I was errand boy for John Palmer. I introduced it into Mr. Palmer's shop in 1863.

(So much of the foregoing answer as relates to the use of the alleged process or press in the establishment of George W. Story, objected to because not set up in the answer.)

Q. 7. State how you come to introduce that press in the establishment of Mr. Palmer, in 1863?

A. I used it in tying up those signatures and bundles of books. I found I could not tie them tight enough with the process he had, and I proposed to him to have these blocks made, that I had seen in use in Story's place. I had them made about 6 x 10 inches, and one inch and a half thick, with a grooved slot in them so that the slack of the twine could be taken up after the pressure had been applied, and the cause of it was that the bundle would be tight.

Q. 8. Were those blocks used on a press the same, or different

from the one that was employed in 1873?

A. They were used on a press called the single-screw Stuart press, a press similar only with heavier screws.

Q. 9. How recently have you seen the press which you say was used by Mr. Palmer in 1873 or 1874?

A. I think it was last Thursday, April the 18th, 1895, in Russell &

Bates' bindery at 509 Locust street, Philadelphia.

Q. 10. State whether it was in the same condition when you saw it last as in the year 1873 or 1874, and if there was any changes, describe them.

A. I think the bottom cast-iron block was broken, and they are now and have been using one of the original blocks of wood.

Q. 11. Please examine this sketch I now hand you, and state what it represents.

A. It represents the press that was used for that purpose.

Q. 12. Do you notice any differences between the sketch and the press now at Russell & Bates' place, 509 Locust street?

A. It is the same press which I have removed twice. I removed it first from the Wiler building into the Tatham building in 1874, and in 1880 we removed it into the annex of the Tatham building.

(The sketch referred to is herewith offered in evidence, and marked as "Respondent's Exhibit Sketch of Palmer Press.")

Q. 13. What time was this press that was used at the Palmer bindery, and represented by this sketch as the Palmer press, fitted with iron blocks as spoken about?

A. About the year 1873, when he had it built.

Q. 14. How are you enabled to state positively that this press was made in 1873, and moved into the Tatham building in May, 1874?

A. I went back to Mr. Palmer's employ in February, 1874, and on the 19th of May he started to move the bindery to the Tatham building out of the Wiler building. On the afternoon of the 20th of May, in moving one of the presses I slipped on the floor and fell, and cut my cheek which gave me a black eye. On that night my mother died, 20th of May, 1874; I had to go to the funeral with a black eye, which I did not like to do, but I had to do it.

Q. 15. How long after 1874 did you continue to work for Palmer? A. I think in 1882 or 1883 he died, and I then worked for his

widow up to 1888.

Q. 16. How extensively was this press used in the bindery while

you were employed there?

A. It was employed for two or three days in the week, and then would stand idle for a day or so.

Cross-examined by Mr. JACOBS:

Q. 17. Please state a little more particularly than you have done the construction of the Palmer press, giving the dimensions of the several parts as nearly as you can recollect them.

A. I think it is about 8 feet high on the side pieces and about 10 inches wide and the side timbers are about 2 inches thick. The cross-pieces are about 5 feet, about the same width and thick-

217 ness of the side pieces, with a screw of about one inch and a quarter. At the end of the screw there is attached an iron

block, 6 or 7 inches wide by 10 or 11 in length, with slots in it for the twine to slip through, and a block similar at the bottom to take the place of an iron one that was broken. There was a bar with a hall on each end to run the screw down with, which I think was about three feet in length, but I never measured it.

0.18. Was the lower block fixed or removable?

A. It was removable.

Q. 19. What were the dimensions of the slots to which you have referred?

A. I think they were about 3 of an inch wide; I know they were not a full half inch. I think they are about 1 of an inch in depth.

Q. 20. Apart from the slotted blocks, the press was an ordinary upright press, was it not?

A. It was used for no other purpose than tying up.

Q. 21. Apart from the purpose for which it was used, and the fact that it contained slotted blocks, it was an ordinary upright, handscrew press, was it not?

A. It was an ordinary press, and was never used except for

tving up.

Q. 22. Please describe now the manner in which the press was used.

A. First in using it, the strings were laid in the bottom block or platen, a piece of paper laid on top of the string, a piece of pasteboard laid on top of the paper, and the gathered books or signatures piled up in bundles of ten, and a piece of pasteboard on top and a heavy paper on top again; string was then brought over the top of the pile; the top block was then screwed down and the pressure applied. The slack of string was then taken up and the bundle tied and removed.

Q. 23. For what purpose were the pieces of pasteboard placed at

the top and bottom of the bundle?

A. To keep the books straight and to prevent the twine from cutting into the signatures and destroying them.

Q. 24. The sheets were gathered in books before being placed in the press, were they?

A. They were.

Q. 25. How were the books arranged in the bundle with reference to each other?

A. They were piled up back and front or "head and tail," as we use the expression in the book trade, so that they could be easily

Q. 26. Would it have been just as easy and convenient to have piled them all one way?

A. No. SIL.

Q. 27. Why not?

A. One side of the bundle would have been so much higher than the other on account of the fold and they would not have made a straight bundle. 218

Q. 28. Were any guides of any kind used for piling the

books in the press?

A. We only used our eye in piting, and we would set the block

under the other one as near as we could, and when the bundle was removed we would straighten it up by knocking it down on the floor.

Q. 29. Did the bundle straighten easily by being knocked on the

floor?

A. It did when I tied them.

Q. 30. The bundles then were not tied so tightly as to refuse to vield when knocked on the floor?

A. They were not.

Q. 31. Was the top platen held by any means from following the

screw when the latter was turned?

A. As far as I understand Mr. Jacobs' question, it was held with one of the hands. You would start the ball around and hold it. It was a crude affair at first.

Q. 32. For what purpose were the books put into bundles in the

Palmer establishment, as you have described?

A. For their preservation and to save space in storage until they went to be bound and delivered to the publishers, and they stored them in their store-rooms. Among whom were the firm of T. & J. W. Johnson, law publishers, 535 Chestnut street, Messrs. Kay & Bro., on Samson street, between 7th and 8th streets, on the south side, and then we stored some for W. & O. H. Morrison, on the sixth floor of the Tatham building.

Q. 33. How were the sheets delivered at the bindery?

A. They were tied up in bundles and had been pressed by the regular printers' process through fullers-boards or printers' boards.

The printers used a hydraulic press.

Q. 34. This pressing between fuller or printers' boards by means of hydraulic pressure, of which you speak, was for the purpose of removing the indentations, was it?

A. Yes, sir, the indentations of the type.

Q. 35. And this was done, as I understand you, by the printers before the sheets were delivered at the bindery?

A. Yes, sir.

Q. 36. The Palmer press then was not used for the purpose of removing indentations, but merely for the purpose of bundling the sheets for storage. Is that correct?

A. Yes, sir, just for making a neat bundle out of it for storage. Q. 37. What kind of pasteboard was used on the ends of the

bundles?

A. They were principally backs of old books, which had been sent there to be rebound and the leather was attached to them, and also

in the regular binder boards.

Q. 38. I suppose you used any kind of pasteboard that was conveniently at hand and would protect the sheets from cutting by the cord ?

A. That is right.

(Recess from 12.30 to 1.30 p. m.)

219 Redirect by Mr. MURRAY:

Q. 39. Have you since recess measured the press you have been testifying about at the establishment of Russell and Bates, 509 Locust street?

A. I have.

Q. 40. Please give the measurements of the different parts, and to make your answer more clear will you please refer to the Exhibit "Sketch of Palmer Press," and indicate on said sketch by reference

letters the parts you refer to in your answer.

A. The height of the sides which I have marked "A" are 7 feet 11 inches; thickness is 2 inches; width between uprights of crosspieces, which I have marked "B," are 44 inches, inside measurement; width of uprights, 8½ inches; width of cross-pieces, same, except the top cross-piece, which is 11 inches wide and 3½ inches thick; width of cross-slot in the iron platen, one-half inch; slot in wood block, ¾ of an inch; the screw is a scant 1¼ inch; the length of bar is 38 inches; the size of platens, 11½ long by 7¾ inches in width. The abovementioned bar is taken from out to out of the balls.

Q. 41. After having again examined the machine and having the sketch before you do you notice any differences between the machine and the sketch excepting that the top bar is broken away

in the sketch to expose the nut?

A. That is the only difference.

Q. 42. Will you state the depth as well as the width of the crossslots in the upper and lower platens?

A. The depth in the iron slot, which is the upper, is \(\frac{2}{3} \) of an inch. The lower one, which is of wood, is about a half an inch.

Recross-examination by Mr. Jacobs:

Q. 43. The lower platen which you examined and measured today

is not the same that was on the machine in 1874, is it?

A. No, sir. It is not. The original one was broken and was made of iron, and the one that is on today is not the one which was on when I made use of the press.

Re-redirect by Mr. MURRAY:

Q. 44. State how the lower platen which you say is on the machine today corresponds with or differs from the platen which you say you used upon the same machine in 1873 and 1874.

A. It differs in being wood and the slot being larger than it was

in the original, which was iron.

Q. 45. Then, as I understand you, both platens were iron when you used it, and can you state whether or not they were cast from the same pattern?

A. They were to the best of my knowledge.

Re-recross-examination by Mr. Jacobs:

Q. Of your own knowledge, I suppose you are not able to say anything about the casting of the platens or the patterns from which they were east, are you?

220 A. I cannot, as I was not in Mr. Palmer's employ when the castings were made, and afterwards came in his employ and saw the press complete.

CHAS. G. SCHRANK.

Sworn and subscribed to before me this 26th day of April, 1895. WM. M. STEWART, Jr.,

Notary Public.

And Edmund H. McKee, being duly sworn, deposes and says, on being examined by Mr. Murray:

Q. 1. State your name, age, residence, and occupation.

A. Edmund H. McKee, Prospect street, Roxborough; age, 74 years; bookbinder by trade.

Q. 2. How were you employed, and for whom, during the years

1873 and 1874 and prior thereto?

A. I was employed in the finishing department of the Palmer bindery. To explain that more definitely, by finishing is doing the gold-work, the lettering of books and such things as that, that you may see on the various kinds of books, law books, morocco books or on all books, although the real name is known as bookbinder. Prior I was employed by Mr. Palmer, when he had his bindery on Minor street below Sixth. From there I went to the corner of Sixth and Minor with him, when he moved there. From there to the S. E. corner of 5th and Walnut Sts. From there to Mr. Tatham's large building on Fifth street above Locust street. From there to Mr. Wiler's building, which at that time was the firm of Wiler and Moss, the stair-rod manufacturer-, which was on Fifth street opposite to what is called Adelphi street. From there we went to Mr. Tatham's building again. From there into what I would suppose you would call the annex, at 509 Locust street. During all these years I was engaged by Mr. Palmer as a finisher. I have described the modes of finisher. I remained in the establishment until the death of Mr. Palmer. After his death Mrs. Palmer, the widow of the late John Palmer, took charge of the business, together with the son, but finally from disagreement she took charge of the business and carried on the same herself. I was still retained under her proprietorship as a finisher, and after she sold out I was still retained to do what job finishing there was to be done by the present proprietors, Russell & Bates, and still work there when there is anything to do. which is very seldom.

Q. 3. Are you familiar with a press for bundling and tying up signatures used by Mr. Palmer, and still in the establishment of Russell

and Bates?

A. I have seen the press, believing it is the same press that was formerly occupied by Mr. Palmer in tying up signatures and books after the gathering of the books and then collating them, because it is necessary that books tied into bundles should be gathered so that after the book is gathered it has to be collated. The collating is in order to show that the book is complete by having all the signatures in that book.

Q. 4. Please describe the press that was used for bundling

and tving up these books and signatures briefly.

A. It is a plain structure of two uprights of heavy planking, of a top piece, and then a lower planking across. These planking crosswise are to strengthen the uprights. The screw, as far as I know, that took hold on the middle piece between the uprights; the screw. looking at it occasionally, I was not able to see that as if I had been working at the tying up, as I had nothing to do with that process at all: it consists of a screw and the platen is attached to the screw and after the books are got between, papers are first laid on the bottom. and then a piece of pasteboard, and then the books are laid on top of this and another piece of paper on the top; then if they could find old sides enough of old books that were torn from books, for instance, books that were sent just for being rebound, they were saved for this purpose and put on top of the paper. After placing these on the top, this block was placed on the top of that, and the cords put through, and then they turned what I call the lever, but you call it the bar. As it neared the bundle it had to be guided by the hand so as to bring it down, in bringing it down, or they could bring it down square on the tops of the bundles. Then the pressure was put on, whatever pressure was deemed necessary, cords run through them tight and then were tied at the ends. Whatever little slack there might be there as the pressure was taken, the pressure being taken off, the books would rise, leaving the bundle tightened.

Q. 5. Please examine the sketch I now hand you marked "Respondent's Exhibit Sketch of Palmer's Press" and state how it corresponds with or differs from the press you have been describing.

A. This seems to correspond, except that the top is broken away and I suppose is to let the screw show, but that looks like the orig-

inal press.

Q. 6. Can you state when this press that is now at the bindery of Russell and Bates was first put up and used at the bindery of John Palmer?

A. To the best of my knowledge and belief it was originally there in 1873 or 1874, I am not positive. I cannot be positive about that question; as to the best of my knowledge and belief.

Q. 7. Can you state whether or not this press was in use in Palmer's bindery before Mr. Palmer moved into the Tatham build-

ing?

A. My knowledge is that it was introduced when they were in the Tatham building, while he was in the Tatham building—to the best of my knowledge and belief.

Q. 8. Do you mean the first time that Mr. Palmer was in the

Tatham building, or the second time?

A. I think it was the first time, but I cannot be positive.

Cross-examined by Mr. Jacobs:

Q. 9. When were you first employed by Mr. Palmer at his bindery?

A. I went to Mr. Palmer between 1849 and 1850. He then had his bindery on Sansom street, No. 517, I think.

Q. 10. And you continued in the employ of Palmer and his suc-

cessors until a few months ago; is that correct?

A. I think during the period I was away for a year or two, when I worked for the Government, and then went back again, but since that time I have been off and on when there was any finishing to do, until last year, when I was sick for about three months. I am still engaged there when there is anything to do, with the parties who have the establishment.

Q. 11. Can you tell the date of the removal of Mr. Palmer's bindery from Minor street, below 6th, to the corner of 6th and

Minor?

A. I cannot tell positively; it was about 1863, but it may have been a little later; outside of the machine here I could not say

positive, as my memory is not as bright as it was.

Q. 12. As I understand it, the press, concerning which you have been testifying, was used merely for the purpose of tying up and bundling books after the sheets had been gathered and collated; is that right?

A. Yes, sir; I have never seen it used for any other purpose.

Q. 13. Can you give the date when Mr. Palmer moved to his bindery from the corner of Sixth and Minor streets to the corner of Fifth and Walnut streets?

A. I cannot give you the date.

Q. 14. Can you give the date when he moved from Fifth and

Walnut streets to the Tatham building?

A. I cannot. I have never had any data. I never took any data. I never thought that anything would transpire to cause anything like this kind that would call for my memory of the bindery. I never charged my memory with it.

Q. 15. I suppose you do not know either when he moved to the

Wiler building or to the Tatham building the second time?

A. I have nothing that I could give you to base any data upon, but I will state here that I never bothered about these things, and never had any cause to bother about them.

Q. 16. Can you give about the year that any of the movings oc-

curred?

A. Could not say; I might come very early or very late; as I said, my mind was never charged with anything of that kind, as I never thought of having to use anything like this.

EDMUND H. McKEE.

Sworn and subscribed to before me this 26th day of April, 1895. WM. M. STEWART, Jr., Notary Public.

Adjourned until 10 o'clock a. m. April 27th, 1895.

223 Met pursuant to adjournment, April 27th, 10 a. m. Present, the same parties as yesterday.

Francis E. Davis, a witness produced on behalf respondent, being duly sworn, deposes and says, in answer to interrogatories propounded to him by Mr. Murray, as follows:

0. 1. State your name, age, residence and occupation.

A. Francis E. Davis, 58 years of age; residence, 2154 North 27th street; occupation, bookbinder.

Q. 2. State how you were employed, and where, during the years

1870 to 1878?

A. From 1870 to 1872, I was foreman for John F. Bush, bookbinder, located Jayne's building, on Carter's alley, below Third, from that time to May, 1872; he was burned out at that time. After that we took a room on the fifth floor of Tatham's building, 5th street, above Locust street. We were there all that time from 1872 to 1878.

Q. 3. During the time that you were working for Mr. Bush in the Tatham building, where was the bindery of John Palmer located?

A. When we first went into Tatham's building, Mr. Palmer's bindery was on the other side of the street, but I do not know what the number was. As near as I can recollect, about 1874, we occupied the south side of the fifth floor, and about that time we moved in on the north side; and Mr. Palmer took the room we vacated. I could not say how long he was there; I know it was a year or two.

Q. 4. What, if any, means did Mr. Palmer have in his place for pressing and tying up signatures at the time he moved into the Tatham building, and during the time he was occupying rooms in

that building?

A. He had a standing press that worked with an iron bar with two arms on it. They would fill that press with a certain number of sheets, a board on top and bottom, and tie the ropes around them two ways, and let up the press and take the sheets out.

Q.5. Describe the lower platen upon which the pile of signatures rested and the upper platen which was brought down to compress

the pile in that press?

A. I could not do that, I never knew it.

Q. 6. How did they get the strings around the pile to tie up the bundle?

A. I never examined the machine at all.

Q. 7. But you do know that the signatures were put in the press and the platen brought down to compress the pile of signatures, and then strings tied around the pile to hold it compressed when the upper platen was withdrawn, do you not?

(Objected — as leading.)

A. I do.

Q. 8. How recently have you seen that machine?

A. I have not seen it since they moved out of the building, it was there all the time Mr. Palmer and Mr. Busch occupied the building.

Q. 9. Do you think you would recognize the machine or a drawing of it if you were to see it now?

A. Well, I think I would.

Q. 10. I now hand you a sketch marked Exhibit of Palmer Press. Will you please examine that and state whether it is similar to or differs from the press used by Mr. Palmer at the time when he was in the Tathem building?

(Objected to as leading and because the proper ground has not been laid.) $\label{eq:condition}$

A. Well, the standing of the press, it seems to me, is about as his was, and the mode of screwing down is exactly the same, but the blocks, top and bottom, I could not say anything about.

Q. 11. Do you know what the purpose of the slots of the top and

bottom blocks in a press of this kind were used for?

(Objected to because the proper ground has not been laid for the question.)

A. To put a rope through for tying the bundle. It could not be tied any other way unless the slot was there.

Q. 12. You saw the press of Mr. Palmer used while he was in the

Tatham building, did you not?

A. I did. We had to pass through his room to go to the elevator; he had a sawing-out machine between our door and this press; nearly every day I had to pass through there to go to the elevator, and saw a may tying up sheets there, and I would see the boy take the sheets from the press and take them to the sixth floor.

Q. 13. These were tied up while the bundles were in the press, were they not?

A. They were.

Q. 14. And you say that they could not be tied up unless the cross-slots were in the upper and lower blocks. Did you notice when the bundles were removed to be carried to the sixth story whether these blocks had cross-slots in them or not?

(Objected to as leading.)

A. That was my opinion, I did not notice it.

Q. 15. Have you seen a press for tying up signatures since the time you moved out of the Tatham building, which had blocks between which the bundles are compressed, which blocks are provided with cross-slots like these in the sketch shown you?

A. I have not.

Q. 16. Have you not one in your own establishment with the same kind of blocks for tying up signatures which was made under your order?

(Objected to as leading.)

A. I have a wooden one made under my order, which has but one slot, that is cross-wise of the sheet, and ties but one way with one rope.

Q. 17. What suggested the idea to you of making that press with the slotted blocks and single cords for tying up bundles?

(Objected - as immaterial and irrelevant.)

A. I had the idea that we could not tie the rope sufficiently tight

unless there was a slot in the block to let it slide through.

Q. 18. Did you get that idea from the press you saw at the Palmer place which you say strings were drawn through and tied tightly after the bundles had been compressed?

(Objected — as leading and assuming.)

A. Never did; never thought anything about his press.

Cross-examined by Mr. Jacobs:

Q. 19. How long were you working for Mr. John F. Busch?

A. About ten years.

Q. 20. From when to what time?

A. I think it was about 1870 when I went to work for him, I am not positive about it, I worked for him from that time until he died.

Q. 21. When did he die?

- A. I worked for him that time until he died, I think it was about 1880.
- Q. 22. For what purpose was the press concerning which you have testified used in the Palmer bindery?

A. Used for tying up folded sheets.

Q. 23. Was it used for dry-pressing or taking out the type indentations from the sheets?

A. It was not used for either.

Q. 24. Was the press, in your opinion, capable of being used for that purpose?

A. It was not.

- Q. 25. How was dry-pressing or smooth-pressing done at that time in the trade?
 - A. I never saw any done in a bookbindery.

Q. 26. Where was it done?

A. It is usually done in a printing office.

Q. 27. How, at that time?

A. By hydraulic pressure, single sheet between two boards, and is done in the same manner now up here at 10th and Cherry streets, at Sherman's printing-house.

Q. 28. The two boards referred to in your last answer were fuller-

boards, were they?

A. They were.

Q. 29. And the sheet was placed unfolded between them, was it?

A. Flat as it came off the printing press.

Q. 30. The press in the Palmer bindery was used merely for bundling gathered books for the purpose of storage, was it not?

A. I could not say they could bundle gathered sheets as

A. I could not say they could bundle gathered sheets as well as books, whether they were all one signature or gathered books it is all the one thing; I never examined the work that was doing in the press, whether they were bundles of signatures only, or whether they were gathered books.

Q. 31. In your answer to the fourth question on your direct examination, you speak of a board on top and bottom. What kind of a board was it that was used?

A. A binder's board to protect the sheets from being soiled. Paper would answer just as well.

Q. 32. Pasteboard, was it?

A. Yes, pasteboard or binder's board, the same thing as is put on books.

Redirect by Mr. MURRAY:

Q. 33. Can you give a brief description of the manner employed by the workmen who worked on this press in Mr. Palmer's place, to place the sheets in position in the press, tie the bundles, and re-

move the tied bundles from the press?

A. Well, I can give you a description of the way in which we do it. We take the sheets from the folding machine, count them off in twenty-five, and put six twenty-fives in the press, and then put the pressure on, tie the rope, take the pressure off, and take the bundle out. It is the same way he did them at that time, only they had hand folding, but that was the same principle exactly.

Q. 34. Were the strings that tied the bundles placed in position

for tying before the pressure was put on in both cases?

A. They are in our case.

Q. 35. How was it in the Palmer case?

A. I could not say; I never noticed; I could guess at it; there is one thing certain, they could not put the string on after the pressure is on.

Q. 36. But you know the bundles were tied in the Palmer press before the pressure was taken off, do you not?

(Objected to as leading.)

A. They certainly were, as that is the object of the press to make

a bundle as compact as possible.

Q. 37. Then, as I understand you it would be impossible to place the string and tie the bundles, unless the top and bottom blocks were grooved as shown in this sketch?

Sketch of Palmer press.

(Objected to as leading and assuming.)

A. I think it would be.

FRANCIS E. DAVIS.

Sworn and subscribed to before me this 27th day of April, 1895.

[SEAL.] WILLIAM M. STEWART, Jr., Notary Public.

(Recess was taken from 12 m. to 1 p. m.)

227 ALEXANDER STEWART, a witness produced on behalf of the respondent, being duly sworn, testifies in answer to interrogatories put to him by Mr. Murray as follows:

Q. 1. State your name, age, residence, and occupation.

A. Alexander Stewart; 226 South Fifth street; book-keeper for Tatham & Bros.

Q. 2. How long have you been book-keeper for Tatham & Bros.?

A. About 40 years, I guess.

Q. 3. Do you remember that John Palmer had a bindery in the Tatham building, 224 South Fifth?

A. Yes.

Q. 4. Can you state when he moved into that building?

A. Yes, on or about the 15th day of May, 1874.

ALEX. STEWART.

Sworn and subscribed to before me this 27th day of April, 1895.

[SEAL.] WILLIAM M. STEWART, JR.,

Notary Public.

Adjournment until further notice.

STATE OF PENNSYLVANIA, City and County of Philadelphia, \} 88:

I, William M. Stewart, Jr., notary public in and for the said city and county, do hereby certify that in pursuance of agreement by counsel, the depositions hereto attached were taken down upon the typewriter in my presence, and from the oral statements of the witnesses in answer to the interrogations and cross-interrogations hereto attached, propounded to them by counsel at the time and place designated in the caption above, and after being so reduced to writing, were subscribed by the witnesses in my presence; the witnesses having been by me first sworn to testify the truth, the whole truth and nothing but the truth, touching the matters at issue in said cause.

I further certify that I am not of counsel for any of the parties to said cause, or in any way interested therein; that the fee \$13.00 for taking said depositions has been charged to the defendant, and the same is just and reasonable.

WILLIAM M. STEWART, Jr., Notary Public.

Endorsed on cover: No. 903. Clarence M. Busch, appellant, vs. Joshua W. Jones et al. Addition to record per stipulation of counsel. Court of Appeals, District of Columbia. Filed Sep. 21, 1899. Robert Willett, clerk.

228 Second Addition to Record per Stipulation of Counsel.

Court of Appeals, District of Columbia, October Term, 1899.

CLARENCE M. Busch, Appellant,
vs.

Joshua W. Jones and The W. O. Hickok Manufacturing Company.

Filed October 2, 1899.

229 In the Court of Appeals of the District of Columbia.

Clarence M. Busch, Appellant, rs.
Joshua W. Jones et al.

Court of Appeals, District of Columbia, April Term, 1899.

CLARENCE M. Busch, Appellant,

188.

JOSHUA W. JONES and THE W. O. HICKOK MANUFACTURING Company, Appellees.

No. 903.

It is hereby stipulated and agreed by and between counsel for the parties hereto that the accompanying depositions, taken in the accounting under the interlocutory decree of the supreme court of the District of Columbia in the above-entitled cause, may be printed and taken as part of the transcript of record for use in this court.

CHAS. E. RIORDON, Of Counsel for Appellant, M. W. JACOBS, Counsel for Appellees.

Sept. 27, 1899.

Endorsed: Court of Appeals, D. C., April term, 1899. No. 903. Clarence M. Busch, appellant, vs. Joshua W. Jones et al. Stipulation of counsel as to second addition to record. Court of Appeals, District of Columbia. Filed Oct. 2, 1899. Robert Willett, clerk. n the Supreme Court of the District of Columbia. In Equity.

W. Jones and The W. O. Hickok Manufacturing Company

rs.

Clarence M. Busch.

No. 15391, Docket
No. 36.

Testimony for Plaintiff before Frederick M. Ott, Notary Public, Harrisburg, Penn.

in the Supreme Court of the District of Columbia. In Equity. No. 15391, Docket No. 36.

Accounting before the Auditor under Interlocutory Decree of the Court.

It is hereby stipulated and agreed by counsel for the plaintiffs and counsel for the defendant that the testimony of witnesses in the above accounting may be taken by either party before any officer competent to administer oaths (subject to objections made to the relevancy and competency thereof) with the same effect as if the same were regularly taken before the auditor.

Dated the 29th day of September, 1898.

M. W. JACOBS,

Of Counsel for Plaintiffs.
GEO. J. MÜRRAY,

Counsel for Defendant.

No. 222 Market Street, Harrisburg, September 29, 1896.

Testimony taken in the accounting under the interlocutory decree of the court in the above-stated case by agreement of counsel before Frederick M. Ott, Esq., notary public.

Present: M. W. Jacobs for plaintiffs and George J. Murray for defendant.

CLARENCE M. Busch, being called by plaintiffs for examination one tenus in accordance with the foregoing decree, being duly sworn, deposes and says as follows:

Q. 1. You are the defendant in this case?

A. Yes.

Q. 2. It has been testified that you have had in use at your printing establishment, in Harrisburg, a signature press, manufactured by the Scibold Machine Company of Dayton, Ohio. Please state when you purchased that press, when you began to use it, and how long you used it.

A I ordered it in the spring of 1893, received it in July, 1893, began to use it about September, 1893, and it was burned up Feb-

ruary 10, 1895.

Q. 3. You are now and were during that time, I believe, the contractor for the State printing of the State of Pennsylvania? Is that correct?

A. Yes.

Q. 4. When did your contract begin?

A. July 1, 1893.

Q. 5. Can you state approximately the number of sheets pressed upon the Seibold press, above referred to, while you had it?

A. About ten and a half million.

Q. 6. What kind of sheets?

A. Sixteen-page sheets.

Q. 7. Printed sheets, were they?A. Yes; printed sheets exclusively.

Q. 8. Will you look at the deposition of William Hayes Grier, taken in this case, and which I now hand you, and state whether

his answers to questions 11 to 17, inclusive, substantially state the manner in which you used the Seibold press in pressing the ten and a half million sheets of which you have spoken?

A. Yes; it does.

Q. 9. By whom was the press operated and at what cost?

A. By a boy; average wages, three dollars and a half a week; spending about one-fifth of his time.
 Q. 10. The remainder of his time was spent on other work.

was it?

A. Yes.

Q. 11. What was the size of the bundles pressed in the Seibold press and how many signatures did they contain?

A. About twenty-four inches and about nine hundred.

Q. 12. Please state by whom the paper used in your printing for the State is furnished to you.

A. By the State.

Q. 13. How much paper is furnished to you by the State for one thousand copies of any printed signature?

A. Five hundred and twenty-eight.

Q. 14. There being two copies to the sheet?

A. Yes.

Q. 15. What is the size and the weight of the paper used in the State printing?

A. Twenty-six by forty inches, sixty pounds to the ream.
Q. 16. Please state also the quality of the paper so used.

A. Supercalendered book.

Q. 17. Through what operations, if any, were the printed sheets put after leaving the printing press and before they were pressed into bundles, as described by Mr. Grier?

A. Folded only.

Q. 18. What average wages were paid in your establishment between September, 1893, and February, 1895, to girls who worked by the day or week?

A. Four dollars a week.

Q. 19. For what were the extra twenty-eight sheets allowed by the State in printing a thousand copies of any signature?

A. Allowed for waste.

Q. 20. And any saving out of the twenty-eight sheets, which you made, went to you under your contract, did it?

A. Yes.

(Decendant's counsel objects to the whole of the foregoing testimony as incompetent, irrelevant, and immaterial, and, without watving this objection, but relying upon it, proceeds to cross-examine.)

 \times Q. 22. How long were you engaged in printing and book-binding before you took the contract for printing for the State of Pennsylvania in July, 1893?

(Objected to by counsel for the plaintiffs as irrelevant and immaterial.)

A. I learned the bookbinding trade in my father's establishment from 1877 to 1880; succeeded him in business from 1880 to 1892; was put of business in 1893—from July, 1892, to July, 1893.

X Q. 23. In your business from 1883 to 1893, what kind of machines did you employ to do the work which you did after September 1893, on the Seibold machine?

(Same objection.)

A. A smashing machine.

X Q. 24. What, if any, saving was effected on the Seibold machine over the smashing machine which you had theretofore used?

(Same objection.)

A. Little, if any, in money, but considerably greater in convenience.

X Q. 25. In what did the convenience consist?

(Same objection.)

A. The greater ease of handling machine-compressed bundles over those tied up by hand.

X Q. 26. What did you pay for the Seibold machine? What was the price of it?

(Same objection.)

A. The price was four hundred dollars.

X Q. 27. At what price could you have bought one of the Jones machines for from the Hickok Manufacturing Company of the same size and to do the same work?

A. Mr. Bigelow said he would have sold me one to do the work

for five hundred dollars and saved me all this trouble.

X Q. 28. Was there any more waste in using the smashing machine you have spoken about than there is in using the Jones press or the Scibold press?

(Objected to for the reason that the use of the smashing machine has already been set up in this case as an anticipation of the process of dry-pressing covered by the patent in suit and has been substantially adjudicated by the court, and the defendant is therefore not entitled to reopen that question in this proceeding, which is merely one of accounting under the interlocutory decree of the court.

Defendant's counsel states that this being an accounting, the only question before the master is the amount of saving made under the decree over above what might have been made by the use of machines, whether they did or did not anticipate this patent.)

A. No waste at all in either.

X Q. 29. How extensively was the Jones press used, so far as you know, as compared with the smashing machines which were used for the same purpose?

(Same objection.)

A. About one to thirty, I should think; one Jones machine to thirty of the smashing machines.

233 X Q. 30. Then why did you purchase a Seybold machine instead of using the smashing machines, which you had theretofore used?

(Same objection.)

A. Because the printing law of 1876 provides for "dry-pressing," and to prevent my predecessor filing a possible objection to the use of any other process than what was known here as dry-pressing.

X Q. 31. Mr. Jones, one of the complainants herein, has testified in his answer to cross-question 41, on page 7 of complainants' record, that there was no such thing known in the bookbinder's art as wetpressing. Was he correct; and if he was, why is the bundling process used on the Jones machine denominated "dry-pressing"?

(Objected to for the foregoing reasons; also as irrelevant, immaterial, and incompetent at this stage of the case.)

A. In hydraulic fuller-board pressing of the flat sheets they were sometimes sprinkled with water before being pressed. This is wet-pressing, I suppose, although I never heard it called that. Why Mr. Jones called his dry-pressing I do not know, unless because no water is used with it.

X Q. 32. Is any water used in the process of pressing in a smash-

ing machine?

(Same objection.)

A. No.

X Q. 33. Is any water used for pressing folded signatures with any machine that you know of?

(Same objection.)

A No

— 34. Have the only machines that you have seen, manufactured by the Hickok Manufacturing Company, such as the one you used

after the Seybold machine was destroyed by fire, been hydraulic machines or screw-press machines?

(Objected to as immaterial and irrelevant.)

A. I have never seen anything but a cut of their screw-press machines. All the machines I have seen were hydraulic.

(Counsel for plaintiffs, without waiving objections, but relying upon the same, proceeds to cross-examine.)

Q. 35. As I understand your testimony, you were not engaged in the printing business prior to entering upon your contract with the State of Pennsylvania on July 1, 1893. Is that correct?

A. I never operated a printing establishment before that.

Q. 36. Did you learn the printer's trade?

A. No.

0.37. As I understand it, a smasher is used in the bookbinder's trade in one of the operations of binding after the sheets have been gathered and collated into books. Is that correct?

A. Generally, but not necessarily.

Q. 38. Please describe the manner in which a smasher is

operated and used.

A. The bunch of sheets are placed on a large board of pasteboard and another pasteboard placed on top of the bunch, and the combination is slid in between the rising bed and stationary head of the machine, and receives a pressure at each revolution of from thirty to one hundred tons. It is allowed to receive two or three of these pressures generally, and then removed. The length of each pressure is about three or four seconds.

Q. 39. What number of sheets are put into a smasher at a time, and what is the total length of time they are allowed to remain

A. A bunch from four to six inches thick, and not over a quarter of a minute.

Q. 40. By the use of the Jones or Seybold press the use of a smasher upon the sheets which have been put through either of those presses is dispensed with, is it not?

A. It is unnecessary.

Q. 41. What would be the cost of a smasher, such as would be required for the work of your establishment, if you did not use a signature press?

A. I sold one last May for a hundred and seventy-five dollars.

(Answer objected to as irresponsive.)

Q. 42. What I want to know is the cost of a new one.

A. About six hundred and fifty dollars.

Q. 43. The machine you sold for a hundr-d and seventy-five dollars was one which came into your possession in the purchase of Mr. Meyers' establishment after your fire, was it not?

A. I bought it in June, 1893, for two hundred and fifty dollars for use in another purpose. It was second hand then. It went through the fire. I rebuilt it and sold it, as stated.

Q. 44. When and where did you have the conversation with Mr. Bigelow in which you say he told you he would have sold you a Jones machine for five hundred dollars and saved you all this trouble?

A. He called at my office within a few days of the first notice of the suit, which was served on me, apologized for the matter, stating that the company were drawn into it because of their business relations with Mr. Jones; hoped it would not affect our very pleasant business relations prior to that, and said if he had only known of it in time or seen me before I bought the Seybold machine he could have sold me one of the new-style Jones presses almost as cheap as the Seybold. I told him what the Seybold had cost, and he said he could have sold me his for five hundred dollars and saved me all this trouble.

Q. 45. Didn't Mr. Bigelow tell you substantially that he was sorry you had to be sued, but that it was necessary to bring suit against some one to stop the infringement of the Jones patent by the Seybold Company, and that as you were the most convenient

the suit was brought against you?

(Objected to by counsel for defendant as leading.)

A. I remember very distinctly his stating that Mr. Jones had no feeling against me personally and about what you indicate, but that was from Mr. Jones' standpoint entirely. He said the Hickok Company really had no interest in the matter, except through their relations with Mr. Jones, which necessitated their being parties to the suit.

Q. 46. What kind of labor is employed to operate a smasher?

A. A boy; about the same wages as the Jones or Seybold machine.

Q. 47. Is it not a very dangerous machine for a boy to operate?

A. Yes; but they are nearly all operated by boys.

Q. 48. In what does the danger consist?

A. Catching the fingers or hand between the rising bed and the bunch of books.

Recross-examination by Mr. Murray:

X Q. 49. Are any fuller-boards used between the sheets for the purpose of removing the type indentations on a smashing machine?

(Objected to as assuming and for the reasons stated in objection to cross-question No. 28.)

A. No fuller-boards are used in connection with a smashing machine.

C. M. BUSCH.

Sworn to and subscribed to before me this twenty-ninth day of September, A. D. 1896.

[Seal of Frederick M. Ott, Notary Public, Harrisburg, Pa.]

FREDERICK M. OTT, Notary Public.

Adjourned to September 30, 1896, at ten o'clock a. m.

September 30, 1896—10 а. m.

Examination resumed pursuant to adjournment.

Present: Mr. Jacobs, for plaintiffs, and Mr. Murray, for defendant.

CHARLES A. SUYDAM, being produced, sworn, and examined, saith:

Examined by Mr. Jacobs:

Q. 1. State your age, occupation, and place of residence.

A. Fifty-three years of age; bookbinder by trade, and present place of residence, Philadelphia.

Q. 2. How long have you been engaged in the trade of book-

binding?

A. Thirty-nine years.

Q. 3. In what capacities?

A. Four years as an apprentice; then as a journeyman bookbinder with A. Boyd Hamilton, Singerly & Meyers, Benjamin Singerly, and Lane S. Hart, State printers, at Harrisburg, as a journeyman, from 1860 to 1868 or 1869, I think it was, and from that until 1880 as foreman of the State bindery.

Q. 4. Since 1880 what have you been engaged in?

A. As book-edge marbler for the J. B. Lippincot Company, Phila-

delphia.

236

Q.5. While you were foreman of the State bindery at Harrisburg. under the various State printers, what methods of dry-pressing were used in their establishments?

A. There were two methods. The one method was the old method known as dry-pressing with fuller-boards, and what was known as a standing hydraulic press, and the other was known as the Jones drypressing system.

Q. 6. When was the Jones dry-pressing system introduced there?

A. It was early in the seventies. I can't say the exact year, but the first machine made and used was at the State bindery, of which I then was the foreman.

Q. 7. While you were foreman, under whose supervision was the

dry-pressing of the establishment done?

A. Under my supervision.

A. 8. Was the printing of the sheets done in the same establishment or not?

A. Yes, sir.

Q. 9. Into whose hands did the sheets pass immediately upon

leaving the press?

A. They passed through my hands to the drying-room. I allude to the first process named, which was the fuller-board standing-

Q. 10. Please describe, now, the steps of that process until the sheets were ready for sewing, stating also the number of hands and kind of

labor required.

A. When the sheets reached the drying-room they were hung upon rods for drying. After they were dry they were taken down and brought into the folding-room; then placed between fuller's

237

boards, three or four sheets at a time, and then placed under the hydraulic standing press, and the press run up to its full capacity: I couldn't state the number of tons; remaining in that pressure, as a rule, over night; after which the press was emptied, the sheets taken to the folding machine, then, after being folded, tied up into bundles. Each signature was handled in this manner until the entire book was completed. The sheets were then placed on the gathering table; gathered into book form; from there to the smashing machine, and after being smashed the books were ready for being set up for sewing. This required the labor of five different persons, one person hanging up the sheets and taking the same down; two persons for placing the sheets on the fuller's boards; one

person tying them in bundles of five hundred each, and one person for -mashing and running up the hydraulic press. With the exception of the person who run- the -mashing machine and the pressure on the hydraulic press, the other labor was

performed by girls.

Q. 11. You speak of gathering and folding as two of the steps, but do not mention them in the latter part of your answer, when referring to the persons who performed the labor. Are we to understand that the persons who did the folding and gathering are included in the "five different persons" mentioned in your answer or not?

A. No. sir.

Q. 12. Please state now what steps mentioned in your answer to question 10, as required by the old process of fuller-board drypressing, are omitted under the Jones system of which you have spoken.

A. The hanging up and taking down of the sheets, of the two girls who place the sheets between the fuller's boards and take them

out; that is about all.

Q. 13. Is the smashing required in connection with the Jones system?

A. Not necessarily so.

Q. 14. For what purpose is a smasher or smashing machine used in a bookbindery, and at what stage of the progress of the work?

A. For the purpose of forcing the air from between the folds and creasing the sheets solidly at the head and back. This is done after the sheets have been gathered into book form.

Q. 15. Will you state now the cost of the operation of dry-pressing printed sheets by the fuller-board process, stating also the wages per week upon which you base your calculation and the kind of labor?

A. Twenty-nine cents per thousand signatures. At three dollars per week. I have already mentioned the labor employed in the process. What I mean by three dollars per week is three dollars per week for each person employed.

Q. 16. Will you state, in a general way, how you have reached

this conclusion?

A. By a practical knowledge acquired in the handling of the work by this method and the wages commonly paid in the city of Harrisburg for that kind of service.

Q. 17. The wages of which you speak, I presume, were those paid at the time you had charge of such work here and has no reference to the wages now paid; is that correct?

A. It is

Q. 18. Are you familiar with the fuller-board hydraulic press process as it is still practiced in large establishments?

A. Yes, sir.

Q. 19. State whether or not there is any difference in the amount of labor required or other items of cost in carrying it out between the process as it is now practiced and as it was practiced under your supervision in the State bindery.

A. The process is practically the same, but the cost very much greater over that, being the difference in the amount

of wages paid.

Q. 20. Then, as I understand you, the cost then an I now differs only in the amount of wages; is that correct?

A. That is correct.

Q. 21. In your answer to question 10, referring to the old fullerboard process, you spoke of the sheets being tied up into bundles.

Please state how they were tied.

A. Five hundred sheets were put into a pile, a couple of sheets of the same signature were placed at either end, the same being tied with a heavy cord, such as came around bundles of printing paper, wrapped around both ways, and the number of the signature marked on the outside of one of those sheets.

Q. 22. Was the tying done by machinery or by hand?

A. By hand.

Q. 23. How were the bundles tied with respect to looseness or solidity?

A. That depended entirely upon the amount of strength used by the girl who tied them up. They were simply tied in that manner to keep them in some kind of shape until ready for gathering.

Q. 24. In your answer to question 15 you state the cost of the operation of dry-pressing printed sheets by the fuller-board process to be "twenty-nine cents per thousand signatures." Will you please explain what you mean by thousand signatures, as you use the phrase in this connection?

A. A signature for an octavo is a sheet of sixteen pages, used in

this connection.

Q. 25. Was there any waste of paper in connection with the fuller-board or the Jones process of dry-pressing? And, if there was,

please state the comparative waste under the two systems.

A. By the fuller-board process there was considerable waste, probably ten signatures in a thousand, caused by the insecure manner in which they were tied up and handled, while by the Jones process there was comparatively none, as handled in the bindery.

(Recess from 1 to 2 p. m.)

Q. 26. Just as we were about taking the recess for dinner you

stated that you desired to make a correction of your testimony in

some respect. You may now do so.

A. I desire to add to the word-"State bindery," in answer to question 3, "excepting a period of two years while in the service of the United States as a volunteer soldier during the late rebellion."

I also desire to make a correction so as to have the answer to question 6 read: "It was in the fall of 1877;" and strike out "I can't say the exact year;" and the balance of the answer to read: "The first machine made and used was at the State bindery, of which I then was foreman."

I also desire to correct the answer to question 12—that is, that "all the steps mentioned in the answer to question 10 as required

by the old process of fuller-board dry-pressing are omitted," inasmuch as the process under the Jones system requires a

different manner of handling the sheets.

Q. 27. In view of the correction which you have just made to your answer to question 12, in order that the matter may clearly appear upon the record, I ask you to state the steps taken from the time the sheets leave the printing press until they are ready for sewing, first, under the old fuller-board process, and secondly, under the Jones process, and to indicate what operations, if any, under the Jones process are substituted for any operations under the fuller-board process which are omitted in that of Mr. Jones.

A. The first question I have already answered, from the sheets leaving the printing press until they are ready for the sewer. Do

you want that repeated?

Q. 28. Yes.

A The sheets were taken from the press-room direct to the sheet-room. They were there hung upon rods to dry. After they were dried they were taken off the rods, brought down into the folding-room. They were then placed between fuller's boards three or four sheets at a time. From there they were placed in the hydraulic standing press. The press was then run up tight by hydraulic pressure. After being pressed, as a rule, over night the pressure was taken off the sheets, the press emptied of fuller's boards and sheets, and the sheets taken out from between the boards. The sheets were then folded and tied up in bundles of five hundred. The same process gone through with each signature until the book was completed. The sheets were then gathered into book form, taken to the smashing machine and smashed, and the book was then ready for sewing.

In the Jones process, the sheets came from the sheet-room direct to the folding machine. When they were folded they were placed in the Jones machine, five hundred signatures at a time, with smooth-finished oak boards of an inch thickness placed at each end, the outside edges of the boards being rounded off. The pressure was then applied. The required amount being obtained, a heavy cord was placed both ways around the five hundred signatures, the pressure relieved, and the signatures stired away until the completion of the book, thus doing away with the hanging of the sheets

and all of the handling as described in the process with fuller's

boards and standing press.

When the last sheet has been printed and pressed as just described the sheets are then gathered into book form and are ready for the sewer.

Q.29. For the five different persons required for the various steps, exclusive of folding and gathering, under the fuller-board process, how many operatives are substituted under the Jones process?

A. One.

- (The same objection interposed by counsel for defendant to the testimony of the preceding witness is repeated here, and the 240 further objection that the comparison is between the old,
- antiquated process, which was out of use long prior to the date of the alleged infringement by defendant, instead of between the modern processes used for the last ten or fifteen years, and the Jones process, so called; but defendant's counsel, without waiving the objection, proceeds to cross-examine:)
- X Q. 30. Do you mean by your answer describing Jones' process that the sheets were brought directly from the press, without being first dried, to the folder?

A. Yes, sir.

X Q. 31. And then pressed, under the Jones process, while wet?

A. I didn't say so.

X Q. 32. What did you mean by saying "thus doing away with the hanging of the sheets," which you deemed necessary in the old fuller-board process?

A. Experience had shown us that the sheets could be taken direct from the press-room, folded, placed in the Jones machine, tied up

under hydraulic pressure, without danger of any set-off.

X Q. 33. Then they were not dry-pressed, were they—that is, they were not dried in the old manner before they went to the press?

A. Not by hanging on rods, as described in the fuller-board process.

X Q. 34. Describe how they were dried before going to the press. A. The sheets were not dried, in the term that the word is generally used, the Jones process not requiring that the sheets should be hung up in order that the ink should be set.

X Q. 35. Well, how were they dried, was the question you were

asked, if dried at all?

A. They were not dried, only so far as the action of the air might affect the ink in passing through the folding machine.

X Q. 36. Well, after they passed through the folding machine

were they wet or dry?

A. They were in a condition to produce satisfactory results, as claimed, in dry-pressing. I wish to add that the paper was not wet down, as had been customary at one time, and that the paper was run through the printing press as dry, and the only dampness was from the fresh ink.

X Q. 37. Then under the new process of printing it would not be

necessary to hang the sheets if they were pressed on the old hydraulic press, would it?

A. Yes, sir; that is my impression.

X Q. 38. Give us the reason for your impression.

A. For the reason that under the old system of pressing with fuller-boards, by placing the board known as the fuller's board between the sheets, a very compact mass of paper and board, not yielding any except so far as removing the impression was concerned, would cause the fresh ink to what I would call "break" and set off, while on the Jones machine, the papers having no hard fuller's board between them, the impression would yield gradually and there would be no set-off.

241 X Q. 39. Whether it yielded gradually or not would depend on the speed of the movable platen in either case or the

amount of the pressure applied, would it not?

A. I think not. X Q. 40. Why?

A. For the reason that I have saw sheets brought to the State bindery, where I was then in charge, given into my care, which were doubly charged with ink and prepared expressly to show that the Jones machine could not do the work claimed for it. I run the pressure on the machine and tied up those sheets and left the pressure on over night, and when opened in the morning the indentations of the type were entirely removed and no indications of a setoff, while some of the same class of sheets were placed in a standing press in a small quantity, the pressure applied, and when taken out next morning the reading was scarcely legible by reason of the set-off.

X Q. 41. Do you know how much pressure was applied in each

case?

A. I do not; for the reason that I have forgotten the number of tons pressure ordinarily used for the Jones machine, but it was very much in excess of that applied in the standing press. I would also say that after eighteen years my memory is not as vivid in regard to the number of tons pressure as it was when I had it in daily use.

 \vec{X} Q. 42. Mr. Thomas B. Penicks, a witness called in this case, has testified that it was well known that the intermediate sheets between the fuller-boards in the old process were smoother and better and had the type indentations more perfectly removed from them than from the sheets that came in contact with the fuller-boards.

Was that also your experience with the old process?

A. No, sir.

X Q. 43. The reverse of that was true, then, in your experience?

(Objected to by counsel for plaintiffs as irrelevant and immaterial.)

A. I never saw any difference. If anything, it was in favor of the sheets that were next to the fuller-boards.

X Q. 44. What is the distance between the platens in the old pon-

derous process you have spoken of as being in existence before the

Jones machine was used?

A. That varies. In some establishments I have seen them, I should judge, possibly six feet between the platens and the top of the press. The average of those that I have seen were possibly four and a half to five feet.

X Q. 45. How many sheets would be put in the press at a time?

A. I think about five thousand.

X Q. 46. How long would it take to fill the press, employing the two girls who you say did that work?

A. It would take two girls to fill and empty the press, including the putting on and taking off of the pressure, ten hours.

242 X Q. 47. What is the comparative pressure used in the Jones press and the machine you denominate a "smasher"?

A. I can't answer that question. The smasher should not be compared with the Jones machine, as the relative pressure of the smasher is very small.

X Q. 48. The Jones machine you speak about, I suppose, is the one that was used in the State printing office here while you were

there employed?

A. The machine I allude to was the one patented by Mr. Joshua W. Jones, of Harrisburg, Pa., in, I think, the year 1877.

X Q. 49. Please describe that machine.

A. I certainly can't use the technical terms in describing this machine. It was built of iron, with a trough sloping from the head to the foot, in which the sheets were placed with a stationary head and a movable platen moving on an incline. The pressure was applied by forcing water into a chamber, which forced what I call the plunger to move out of this chamber, pressing the sheets up against the head of this machine. There are openings in the side and bottom of the trough to admit of the free use of the hands of the operator in placing the cords around the bundle of signatures. It also had screw-holes in the top head and smooth holes in the platen, by which rods could be centered for the different sized sheets. There were two pumps, one large and one small one. The large one moved the platen up rapidly and the small pump for the additional pressure.

X Q. 50. That fairly describes the machine you worked on at the

State bindery here at Harrisburg, does it?

A. I think it does.

X Q. 51. Did you ever see any other kind of a machine than the one described in the preceding answer that was said to be made under the Jones patent?

A. I saw several that were made under the Joshua W. Jones

patent.

X Q. 52. Were they the same or different from the one you have

just described?

A. Practically the same, except an experimental machine made of wood, which, I believe, led to the invention of the present hydraulic machine.

X Q. 53. Are they using the Jones machine in the establishment you are engaged in now?

(Objected to as irrelevant and immaterial.)

A. No, sir.

X Q. 54. Do they still use the old, ponderous fuller-board process you have described above?

(Same objection.)

A. They do.

X Q. 55. Mr. Grier was superintendent of the State printing when you were employed in the State printing office, was he not?

A. No, sir; I think not; I am not so positive about that:

I think that he was appointed after I left there.

X Q. 56. Mr. Grier states in his answer to cross-question 49, on page 7 of his deposition taken in this case, that after he purchased a Gordon press it did the work without any necessity of removing impressions, and that he only used the fuller-board process for about three months and them abandoned it. You say that in your establishment you still use it. Do you in your establishment use the old-style printing presses?

(Objected to as irrelevant and immaterial and not proper crossexamination.)

A. I wish to say in regard to the first part of the interrogation that Mr. Hayes Grier was a newspaper and job printer, and it was very evident that he used one of the old style of presses that was worked by hand, as it was called, pulled by a bar, by which the indentations of the type on letter-heads and bill-heads, such as he mentions, were almost driven through the paper, and in order to turn out a job any way creditable he was compelled to use the fuller's-boards, placing them in singly, in order to turn out a creditable job. The use of the Gordon press renders it entirely unnecessary to go through that process after printing. In regard to the second interrogation, I wish to say that the same kind and style of presses are used in the establishment where I am now employed as were used by Mr. Benjamin Singerly and Mr. Lane S. Hart, State printers, while I was in their employ.

Redirect by Mr. Jacobs (without waiving objections):

Q. 57. What is a Gordon press, and for what kind of work is it used?

A. It is what is known as a job press. They are used for such things as bill-heads, circulars and letter-heads, and work of that description, and cards. It makes a very light impression.

Q. 58. Is it capable of use in printing signatures of books of any

such size as the work of the State of Pennsylvania?

A. Not as I understand signatures to be of the size of eight or sixteen pages, of the size used by the State of Pennsylvania.

Q. 59. Referring to your answer to cross-question 36, please state

whether or not the process of printing sheets dry and "without wetting down" had been introduced into the State printing office while you were still using the fuller-board process of dry-pressing.

A. Yes, sir.

Q. 60. Was it or not found necessary to put sheets thus printed dry and without wetting down through the operation of drying before subjecting them to the operation of dry-pressing between fuller-boards?

A. Yes, sir.

Q. 61. Are sheets thus printed still subjected to the preliminary operation of drying, where the fuller-board process of dry-pressing is used?

244 A. I couldn't answer that positively; not as to all the sheets being treated in that way in dry-pressing.

Q. 62. Please explain a little more fully what you mean by your

ast answer.

A. I have had but a limited opportunity to ascertain that fact,

but believe that all cut-work is so treated.

Q. 63. In your judgment, based upon your experience in the art, would or would it not be practicable to subject sheets thus printed to the operation of dry-pressing between fuller-boards without such preliminary drying?

A. My experience has been of such a character that I would not

like to risk it.

Recross-examination by Mr. MURRAY:

X Q. 64. If the sheets were printed dry and placed in an old hydraulic press without fuller-boards would the type indentations be removed without offsetting the ink?

A. In answering that question I would like to ask, were the

sheets hung up before being put in the press or not?

X Q. 65. No; they were to be put in the press in the same manner as in the old process, with fuller-boards, but without any pre-

liminary drying when the sheets were printed dry.

- A. In answer to that question, then, I would say that it is absurd to suppose a case of that kind, of filling up a press composed entirely of printed sheets such as we have been talking about here. It occurs to me that, so far as the pressing is concerned, it would be something like placing a huge sponge into a press of that kind and expecting to press it flat. So far as the question of offsetting is concerned, that could only be answered by an experiment of that kind.
- X Q. 66. Are flat printed sheets, piled one on top of the other any more spongey than the same sheets are when folded and piled one on top of the other?

A. They are, inasmuch as the flat sheets have the indentations of the type all one way, while in the folded sheets the type become opposite, as it were, and more readily yield to pressure.

X Q. 67. They have the indentations all one way when placed

between fuller-boards, have they not?

A. Yes, sir; but the fuller's boards are interspersed to give solidity in the pressing that could not otherwise be obtained in the flat sheets.

X Q. 68. But you say it is this solidity that would cause offsetting in the sheets which are printed dry and placed between fuller-boards without first being hung up, while if the same sheets were folded and subjected to pressure without fuller-boards, in Jones' process, the yielding of the sheets would prevent the offsetting. Will you please explain this apparent discrepancy?

A. I did not say that it was the solidity of the sheets that would cause the offsetting if placed between fuller-boards. Any one knows who has ever seen a printing press work that when the sheets

come from the press and are deposited by the fly one on top 245 of the other there is no possible chance of the air getting at the ink, and if taken direct from the press and put into fuller's boards is what would cause the set-off in the damp state of the ink, while in the Jones process, in passing through the folding machine. there is a current of air strikes both sides of the sheet, and in folding it retains considerable air, which prevents the sheet from lying closely together in its folded state, thereby causing a thin film to form on the ink, causing it to dry, and that air remains in those sheets until forced out by the pressure of his machine.

X Q. 69. If the sheets were folded, gathered, tied up in bundles in the old way until ready for use and then subjected to the action of the smasher, would the type indentations be removed and the

book be in condition for sewing?

(Objected to for the reason that the use of the smashing machine has already been set up in this case as an anticipation of the process of dry-pressing covered by the patent in suit, and has been substantially adjudicated by the court against the defendant; and the defendant is therefore not entitled to reopen that question in this

proceeding.)

(Defendant's counsel states that he has no desire to reopen any question as to infringement, but that the first witness called testified that the only process used by him prior to the alleged date of the infringement was the old smashing-machine process, which was free for any one to use, and that therefore the comparison should be made between that process and the process of the Jones patent, instead of the antiquated old fuller-board process.)

(Counsel for plaintiffs calls attention to the fact that the witness referred to was the defendant himself, and that whatever testimony he may have given on this subject was given under this same ob-

jection.)

A. No, sir; the type indentations would not be removed, but the book might be in condition for sewing.

X Q. 70. Why would not the type indentations be removed, if the sheets were flattened out smooth and ready for sewing?

A. For the reason that the power of the pressure would not be sufficient and of too short a duration.

X Q. 71. Does it require more pressure to remove type indenta-

tions than it does to flatten down the folded edges of the signatures?

A. Yes, sir.

X Q. 72. Is there any limit to the power that might be applied

to a smasher? If so, what limit?

A. There is a limit, but what limit I couldn't answer; but I know that I have seen the front frame of the smasher cracked and forced apart by not properly regulating the pressure in changing from one thickness of book to another.

X Q. 73. How much pressure does it require to remove type indentations in a pile of signatures, say, six inches thick?

A. A great deal more than is contained in a -masher—in the most powerful -masher that ever was built.

X Q. 74. Is there more or less power in a -masher than there would be in a Jones machine, if it were operated by hand like the

machine illustrated on page 116 of complainants' record?

A. There is less power in a -masher than there is in the machine shown here on page 116 when operated by hand, so far as the removal of indentations of type are concerned, from the fact that the power from this hand machine is retained by the cords placed around the bundle of sheets before the pressure is taken off, while in the smashing machine the power is retained but momentarily, and the smashing machine is only intended to expell the air that may be retained in the folding of the sheets.

X Q. 75. Do you think that you could apply power enough to that machine by hand to break its iron frame, as you say that the

smasher was broken?

A. I think not.

X Q. 76. Then why do you say the smasher has less power than

this machine?

A. From the fact that the power of the smasher is not retained, while in the other machine the power applied is held by the cords which hold the sheets. It is on the same principle that you fold a sheet of paper and strike it with a hammer to straighten out the fold, and take a similar piece of paper and fold it, open it out, and lay it under a paper-weight, leaving it lie under that weight for some time, and better results will be accomplished by the paper-weight.

XQ.77. It is your opinion, then, that after the indentations have been flattened out they will return again if not held out. Am I

right?

A. No, sir.

X Q. 78. Then why do you say that if they are subjected to a greater pressure in a smasher than in a hand press the ones subjected to the pressure of the smasher would not be removed, while the one subjected to the lighter pressure in the hand press would be if the pressure was partially held by strings?

A. I answered that just a few moments ago, and I repeated that if the power obtained by the smasher could be retained, as in the case of the hand press, by cords, then I believed the result would be

equally satisfactory.

X Q. 79. But the strings used for tying the Jones bundles do not retain the whole pressure put upon them while in the press, do they?

A. They retain the pressure sufficient in quantity to accomplish

the work that the machine was constructed for.

X Q. 80. Yes; but Mr. Busch says the smasher does the same thing, and that he has done it with a smasher. Now, I don't yet understand why, if it requires a certain pressure to take out the indentations, how that pressure, when relaxed, as it is in the Jones machine, would hold the indentations out, if they require holding out; that is what I would like you to explain.

247 (The introductory part of the question is objected to by counsel for plaintiffs as not correctly stating the substance or effect of Mr. Busch's testimony; and this and all the foregoing and any succeeding questions relating to the use of the smasher are objected to for the reasons stated in the objection to cross-question 69.)

(In reply to the first part of the objection counsel is referred to cross-question 23 and its answer of Mr. Busch's, which is as follows:

"X Q. 23. In your business from 1883 to 1893, what kind of machines did you employ to do the work which you did after September, 1893, on the Seybold machine?

A. A smashing machine.")

A. I want to say that when Mr. Busch makes that assertion, that he produces the effect of dry-pressing by the use of a smashing machine, he makes an assertion that will not bear the criticism of expert printers. Those familiar with the Jones machine know that when the pressure is run out there is an extra amount of pressure put on to allow for the stretching of the ropes or twine.

I ought to explain further that when this machine first came into use we experimented with the pressure power until we had obtained

the desired results, allowing for the stretching of the twine.

X Q. 81. If the Jones process, as you term it, is such a valuable improvement over the old cumbrous process, as you claim it to be, can you explain why the house you are with now, which is one of the largest in the United States, has not adopted it?

(Objected to as irrelevant, immaterial, and not proper cross-examination, ans as calling for the mere opinion of the witness with regard to matters which would not naturally be within his knowledge and concerning which he is not shown to have any means of information.)

A. I cannot, for the reason that I have never been asked nor been consulted with in regard to their methods of conducting their work outside of my own line of business.

Re-redirect by Mr. Jacobs (without waiving objections):

Q. 82. In all your experience, covering, as you have said, thirty-nine years, have you ever known or heard of a smasher or smashing

machine being used for the purpose of removing type indentations from printed sheets?

A. I never have.

Q.83. In your judgment, based upon your experience and your knowledge of the use of such machines and of what is necessary for the removal of type indentations, is a smasher a practically operative machine for such purpose?

A. No, sir; I think not; I am positive about it; I never heard of

it being intended for that purpose.

Q. 84. If a charge of printed sheets and fuller-boards were put into a hydraulic standing press of, say, a hundred-tons pressure and the pressure applied and immediately released, would or would not, in your judgment, the type indentations be removed from the sheets?

A. No. sir.

Q. 85. If signatures were placed in the ordinary way in a Jones press and the pressure applied and immediately released without any tying of the bundle, would or would not the type indentations be removed?

A. No, sir; the retention of the pressure is what accomplishes

the result.

CHARLES A. SUYDAM.

Sworn to and subscribed before me this 30th day of September, 1856.

FREDERICK M. OTT,

Notary Public.

(Adjourned to October 1, 1896, at half past nine a. m.)

Остовек 1, 1896—9.30 а. т.

Examination resumed pursuant to adjournment.

Present: Same counsel.

Joshua W. Jones, being produced, sworn, and examined, saith,:

Examined by Mr. Jacobs:

Q. 1. You are one of the plaintiffs in this case?

A. I am.

Q.2. And the same Joshua W. Jones who formerly testified therein?

A. I am.

- Q. 3. In your former deposition you stated your means of knowledge of the printing and bookbinding arts from the commencement of your apprenticeship, in 1844, until your resignation of the office of superintendent of public printing of the State of Pennsylvania in August, 1883. Please tell us whether or not you have since 1883 kept up your knowledge of the progress of those arts; and, if so, in what manner.
- A. I have kept up since then my knowledge of said arts by having visited some establishments and through the trade publications to

which I am a subscriber, and each one that I received I looked over carefully, — whether there was such a thing as a new process discovered for the operation of removing type indentations, technically known as dry-pressing. It was my interest to watch this feature particularly, and I did so. I found no process mentioned; neither did I see any other process in any establishment which I went through, excepting the process of pressing between fuller-boards or my own.

Q. 4. Have you or not since 1883 down to the present time been taking the principal journals of those trades published in this country?

A. I have, and part of the time those of England.

Q. 5. And have you carefully read them from time to time?

A. I carefully read anything contained in them that was of interest to me.

Q. 6. Has it or not been the custom of those journals to describe or otherwise call attention to any important inventions or discoveries

in the various branches of those arts?

A. It was the custom for those journals to speak of all new discoveries and inventions relating to the paper-printing and book-binding arts. To illustrate: At the time of my invention the subject was taken up by the trade journals, both in this country and in Europe, and was discussed. Almost all of them that fell into my hands doubted the process and that sheets could be pressed in that

manner without offsetting.

Q. 7. From the facilities which you have had for gaining information during the period named, as well as from your knowledge of the arts prior to your resignation as superintendent of public printing, are you in position to say whether or not you are acquainted with the practical processes of removing type indentations from printed sheets in use or open to the public during the period beginning with September 1, 1893, and ending February 10, 1895?

A. I am. There was but one modern process, and that was the

pressing of the sheets between fuller-boards.

Q. 8. Were there any older processes as cheap and practicable as that?

A. No, sir; not to my knowledge.

Q. 9. Had you or not taken occasion, either prior or subsequently to 1883, to study the older processes, and do you believe that you were familiar with them?

A. I can't say that I made a particular study of them, but I have read of them. I never practised the older processes; in that sense I was not familiar with them. I was familiar with the modern process of pressing them between fuller-boards, having practiced the same.

Q. 10. Did you or not know what those old processes were and how they compared with the fuller-board process, with respect to

economy and practicability?

A. I only know of one older process, and that was to press the sheets between heated iron plates. This process must have been very expensive, and it is said that it did not produce good work; that the heat would destroy the ink. I think it is also mentioned

that it discolored the ink.

Q. 11. Leaving out of view, now, your own process which was covered by your patent, what process or processes was or were open to the public during the period beginning September 1, 1893, and ending February 10, 1895?

A. The process of placing the sheets between fuller's-boards and pressing them. The old process of pressing them between heated

iron plates was an obsolete one.

Q. 12. It has been attempted, in this proceeding, to be shown on behalf of the defendant that the use of a smasher was, during the period named, a practicable method of removing type indentations from printed sheets. What do you have to say with regard to this?

A. That is an utter impossibility, to do the work contemplated and known as pressing the sheets smooth, removing the indentations, and said indentations to remain permanently smoothed out,

and it might be termed "a lick and a promise."

Q. 13. Are you familiar with the use of a smasher; if so, to what

extent?

A. I am familiar with the use and purpose of the smasher, having the same in the establishment which I was manager of: have seen it in almost daily use, and have myself done work on the same. The use it is for and the work it accomplishes is to smash the books when gathered and collated, to remove the air between the sheets, making the head, back, and front folds mashed even and solid with the body of the page, and to produce solidity to the entire book.

Q.14. Will you state now why, in your judgment, a smasher would not practically perform the work of removing type indenta-

tions from printed sheets?

A. First, it would be impracticable to smash freshly printed sheets without first having gone through the process of drying the ink, as a smasher operates very fast, and, as it were, gives a powerful blow. A blow of less power than that produced by the smasher will offset the ink from one page to the other. Second, the smashing machine gives a sudden and quick pressure. The dwell of the pressure is less than a quarter of a second, and it is only the longcontinued pressure on the sheet that will restore the disturbed fibres of the paper, produced in the process of printing. The elasticity of the indentations would, again, cause the indentations to reappear. Even if it were practicable it would be an expensive operation, as the capacity of a smasher for one operation is small. I do not believe that a book over three inches in thickness can be smashed at one time. It takes considerable time in the operation. First, the books have to be evened up carefully on the head and back, so that each signature is flush and even with each other. The book then has to be laid on a pasteboard or similar substance, another placed on the top. It is then placed between the bed and head of the smasher and smashed, removed; the boards also removed. These are the operations required in the process of smashing. I would also add that it is a very dangerous operation. In the putting the

books into the smasher by the least inattention the operator is liable to have his fingers or hand smashed. I know of a case where such an accident did occur, and the operator had to have his hand amputated.

Q. 15. Have you ever used or seen used a smasher upon books made up of undry-pressed sheets; and, if so, were the type indents-

tions, as a matter of fact, removed by the operation?

A. No.

Q. 16. Did you ever know of a smasher being used for the purpose of removing type indentations?

A. No.

Q. 17. Did you ever, before the taking of defendant's testimony in this case, hear or know that such a thing was con-

sidered by any one as possible?

A. No; and it would not comply with the law or the contract of the defendant, which fixes the price for press-work, including drypressing; nor with the provision that the work be done in a neat and workmanlike manner, nor with the provision "and the printing and binding and all other work to be first class and kept up to the standard of the times."

Q. 18. Will you state now the cost of dry-pressing printed sheets by the fuller-board process, stating in detail how you arrive at the

result, the amount of wages assumed, and so forth?

A. By the extremely low wages paid here and the cheap class of labor used in the process as it might be done here, the dry-pressing by the fuller's boards, including all the processes the sheet passes through, including that of smashing, which smashing is only done for the purpose of displacing the air, leveling the folds, and solidity of the book, taken on the basis of the amount of work done by the State printer from September, 1893, to the time of his fire in February, 1895, it would cost about twenty-seven cents per thousand sheets.

Assuming that the figures I obtained from the auditor general's office, copied from the bills of Mr. Busch, it appears that there were ten millions six hundred and seventy-one thousand five hundred sheets that were printed and dry-pressed from September 1, 1893, to February 10, 1895. There would be about four hundred and forty working days. There would have to be done on an average of twenty-four thousand two hundred and fifty-four sheets daily. drying of this number of sheets would require the labor of at least two girls at four dollars per week each, or one dollar thirty-four and a third cents per day, equal to five and a half cents per thousand sheets. It would require to press between boards five presses. each charged with about five thousand sheets. The labor to fill and unfill these presses would require at least six girls at four dollars per week, or sixteen and a half cents per thousand. Bundling by hand, twenty-four thousand five hundred and fifty-four sheets will require the labor of one boy at the rate of three dollars per week, about two and a half cents per thousand. Smashing this amount of sheets could not be done in less than one day. A boy at three dollars and a half per week would make it two and a half cents per thousand sheets; total, twenty-seven cents per thousand. I doubt whether the same could be done elsewhere for double that amount.

0. 19. How do you arrive at the number of sheets to each charge

of the press, to wit, five thousand?

A Taking as a basis that the open space of a press between platen and head is five feet. This would be a very high press; the top would be very high, and to fill in the sheets and boards in a press of this height would be a very difficult thing and hard work

for girls to do, as the labor of filling near the top would be such hard work that girls should not be expected to do it.

252 Two hundred and fifty sheets of sixty-pound paper, including the swell caused by the impression in printing, and sheets loosely laid one on top of another, measures one and a half inches. Sheets laid between fuller's boards on an average of three each would require eighty-four boards for two hundred and fifty sheets; twentyfour boards to one inch; eighty-four boards, three and a half inches; one wooden board, one inch; total, six inches for two hundred and fifty sheets; twenty-five hundred sheets, sixty inches, or five feet. Now, this is presuming that the sheets and boards would be put in. solid at the top. This would be almost an impossibility, as they could not readily fill the entire space of five feet without having a little room of a few inches between the top of the pile and the bottom Twenty-five hundred sheets—these are double sheets, and make five thousand copies when cut in two. Even by this process I can show that the ink will sometimes, when not thoroughly dried, offset and smear, and therefore the sheets have to be very carefully handled in laying them between the boards and removing them. I have a small sample of board which has been used for this purpose and shows the marks of the smear in drawing the sheets across the board in the act of laving them in or removing them, and also the offset of the ink from the sheets bearing the faint outlines

Q. 20. Assuming the distance between the platen and the head of the press to be five feet, what would be the height of the top of the

pile from the floor?

A. I should say it would be at least seven feet, if not more, from the floor to the under side of the head. First is the base, which is a very heavy casting; the ram, as I have known presses, were about from eighteen to twenty-four inches. The kettle in which this ram works is not less than about three inches of metal on the bottom. The platen, I should say, would not be less than four inches where it lies on the top of the ram.

Q. 21. Is the press which you have supposed about as large as

could be practically used with the labor of girls?

A. Yes.

Q. 22. If a smaller press were used, would the cost of the operation be greater or smaller?

A. I don't know as it would; it would require more presses, and

they are an expensive piece of machinery, and it would take up more floor space.

(Recess to 1.30 p. m.)

Q. 23. In the fuller-board process, can the drying of the printed sheets be dispensed with, assuming the paper not to have been "wet down" before printing?

A. No; not directly, or soon after the sheets leave the printing press. They might be if the sheets were allowed to stand for a long time, until the paper had naturally absorbed the wetness of the ink.

This, on sized and supercalendered paper, such as the State furnishes, would require a very long time; how long I cannot tell.

Q. 24. Would it be practicable in an office such as that of the State printer of Pennsylvania to allow sheets to remain long enough for such natural drying process before binding them up into books?

A. I can't say as to whether he could leave them in such a stage until the binding of the book, but I will say that it would not be practically economical to allow the work to stop at this stage. The overcrowding of the work to be done between the printing of the sheets and the binding of the book would require, in my opinion, alone, for the dry-pressing and folding and gathering, collating, and sewing, smashing, if they had to be smashed—would require, on a book of five hundred pages and an edition of twenty thousand copies or more, more room than this building of the court-house contains.

Q. 25. You were acquainted with the building in which Mr. Busch carried on the State printing and binding before his fire in

February, 1895, were you?

A. I knew the building. I have been in it twice; the first time was on the twenty-eighth of November, 1892; the second time was during the taking of the first testimony here, while Mr. Hill was here, in September, 1894. I am well satisfied that that building would not have been sufficiently large to have dried and dry-pressed, between boards, and stored the sheets, from the commencement of printing to the gathering of the sheets in the book, of the item of twenty-two thousand one hundred and fifty copies Annual Report of the Superintendent of Public Instruction, six hundred and eightysix thousand six hundred and fifty sheets, and left room sufficient to do the work required on the other stages up to the point I have mentioned without getting additional room outside of said building: whilst the Report of the Superintendent of Public Instruction was but one item out of sixteen, running from fifty copies to thirty-two thousand and fifty copies, the one containing fifty sheets, the other one million three hundred and fourteen thousand and fifty. items appear on the bill of Mr. Busch, December 31, 1893. This work must have evidently been done between that date and the first of July prior. I will state that the total number of sheets of these items in the bill of December 31, 1893, is two millions six hundred and seventeen thousand seven hundred and forty sheets. I do not say that I believe that all of these sheets were stored at one and the same time, but it is evident that the sheets for the Report of the Superintendent of Public Instruction were all printed and stored before they were bound into books, and also that the item of thirty-two thousand and fifty copies of Agriculture of Pennsylvania, one million three hundred and thirteen thousand and fifty sheets had to be stored before there were any of them bound into books. There are other large items, such as five hundred and forty-seven thousand three hundred and ninety sheets, and so, also, with the balance of

the items, together with the ones I have mentioned, would
have had to have been dried and pressed and folded before
the operation of gathering was commenced, and this requires
a large amount of floor space in the method of dry-pressing between

fuller-boards.

Q. 26. Are we to understand from your last answer that the building would not have been large enough to have carried on these operations by the old fuller-board process, assuming the sheets to have been dried by hanging on racks or assuming them to have been dried as suggested in your answer to question 23?

A. Both.

Q. 27. Why would it not have been large enough, assuming the

sheets to have been dried on racks?

A. The sheets were dried on poles fixed near the ceiling of the room. The floor space under the poles was substantially occupied by the tables on which the sheets were laid before hanging them up to dry and again putting them on after they were dry and trucking them from one part of the room to another or to the elevator, if there was one, to transport them to another room, and also for the operator to move underneath the poles. This drying them on poles would require a very large room to dry the number of sheets given in my answer to question 25.

Q. 28. Would the dry-pressing itself by the fuller-board process

have required more room than by your process?

A. It would. I estimate that the press itself that would take in a sheet twenty-six by forty, together with the pumps, the table to manipulate the sheets and boards, and the room required for the operators, would require about eighty-four square feet of floor space to one press. On this basis, it would require for five presses and the room to operate them about four hundred and twenty square feet.

As near as I remember now, my machine and room to operate

the same requires about thirty-two square feet floor space.

Q. 29. The defendant, Mr. Busch, has told us in his answer-to questions 13, 19, and 20 that he was allowed by the State twenty-eight extra sheets for each one thousand copies of any printed signature for waste, the saving out of which went to him under his contract. Is there any difference in waste under the two processes, to wit, the fuller-board process and yours? If there is, state what it is.

A. There is. The allowance of twenty-eight sheets to the thousand is certainly a liberal one. I have never known or heard of such liberality. It was the custom to allow ten sheets to the printer for waste, and this was the amount that was allowed by me when I

was superintendent of public printing. To make one thousand perfect copies it required, under the old process, practically the extra ten sheets, so that there was little, if any, paper saved to the printer. The sheets were wasted by the old process first in making ready a form for first impression and register. On an edition of, say, five thousand copies this waste was practically nominal. The great waste occurred after the sheets were printed in having to pass through so many handlings. They would get soiled, torn, and

marred in handling and hanging up to dry, taking them down again, and in handling them through the fuller's board, 255 and using them in tying up to protect the outsides of the By the Jones process fully nine-tenths of this waste is bundles. saved to the printer, as there is but one process between the printing press and the dry-pressing. The only waste would be that of first impression and register on the printing press. On an allowance of ten sheets to the printer for waste, in ten million six hundred and seventy-one thousand five hundred sheets it would be one hundred and six thousand seven hundred and fifteen sheets. Nine per cent. of this amount would be ninety-six thousand and thirty-nine sheets, or four hundred and one quires, equal to two hundred reams. sixty pounds to the ream, or twelve thousand pounds. This would be saved to the printer by the Jones process. I would also add that sheets done by the Jones process can be stored in at least one-half the floor space that they could be if bundled by hand in the old process.

(By consent of counsel, the examination of Joshua W. Jones is suspended at this point to allow the deposition of R. A. Johnston.)

R. A. Johnston, being produced, sworn, and examined, saith:

Examined by Mr. JACOBS:

Q. 1. State your age, occupation, and place of residence.

A. Age, fifty-one; occupation, paper dealer, and place of residence, Harrisburg.

Q. 2. You are a member of the firm of Johnston & Company?

A. Yes, sir.

Q. 3. Have you at present the contract for furnishing the State of Pennsylvania the supercalendered book paper used in its public printing?

A. Yes, sir.

- Q. 4. When did your contract begin?A. In July, 1895, and runs two years.
- Q. 5. Were you a bidder on the contract for furnishing the same paper two years before?

A. Yes, sir.

Q. 6. And are acquainted with the character of the paper which was required by that contract to be furnished to the State printer for the work of the State?

A. Yes sir.

Q. 7. What was the market price of that kind of paper during

the period beginning September 1, 1893, and ending February 10, 1895?

A. Six to seven cents per pound.

(The testimony is objected to as immaterial and no cross-examination.)

R. A. JOHNSTON.

Sworn to and subscribed before me this first day of October, 1896. FREDERICK M. OTT, Notary Public.

256 Deposition of Joshua W. Jones resumed:

Q. 30. Question 15, propounded to you this morning, was a double question, and as your answer was a general negative, without indicating to which of the members of the question it related, your testimony upon that subject of inquiry does not appear to be clear; I will therefore ask you again whether or not you have ever used or seen used a smasher upon books made up of sheets which had not been dry-pressed.

A. Yes: I have seen it and have done it myself.

Q. 31. Seldom or frequently?

A. Oh, quite frequently. It was done on all work that was not considered of the finest. It was done on all State documents prior to the act of 1876 requiring the sheets to be dry-pressed.

Q. 32. As a matter of fact, were the type indentations removed

by that operation?

A. No.

(The objection to the above testimony is the same as to that taken to the first witness.)

Cross-examination by Mr. MURRAY:

X Q. 33. Prior to the date of your patent, was there any process known of dry-pressing without first drying the sheets after they had left the printing press, and before they went into the press, for removing the indentations?

A. Not so far as book-work was concerned and sheets printed on

both sides.

X Q. 34. Then, the only dry-pressing known was the dry-pressing you have described in your previous answer, which involved the step, first, of drying the sheets on racks before they were subjected to pressure. Is that right?

A. Prior to the invention of my machine, it was.

X Q. 35. Then, that process was what was technically known in the art prior to that time as dry-pressing. Am I again right?

A. It was the term applied to that process in this city and the

western part of this State.

Dry-pressing, or by the word "dry-pressing," it was in contradistinction from all the other pressings that the sheets got, from the time they went through the printing press to the completion of the book when bound. In some places it was called "smooth-pressing," and sometimes, I think, simply "pressing of the sheets;" and these terms were local, to a certain extent, but they all meant one and the same thing. I will state further. The word is also given in the Standard Dictionary.

X Q. 36. And they all meant that the sheets must be dried on

racks before they went to any of the presses?

A. That was the custom.

X Q. 37. And the only custom you knew of prior to 1877?

A. Yes; and is the only custom that I know of to the present time, outside of my own process; and the greatest difficulty that I had to surmount was to convince printers that I could

do this work by my process without offset, both in this country and in England. In London, where I had a machine on exhibition, I applied to a party for the loan of some sheets that I might demonstrate that the work could be done by my process, and — no amount of persuasion would they consent, saying that they would not take the chances of having their sheets ruined. Further, I had virtually made a sale of a machine to a publisher, who countermanded the order when I was ready to ship the machine for fear that his work would be ruined by it; and that publisher is a large and prominent one, and I presume he still does his work by the process of drying and pressing them between boards. I have no knowledge of his having purchased any machine, either from the W. O. Hickok Manufacturing Company or the Seybold Company, since that time.

X Q. 38. What time was that?

A. This was in 1880, to the best of my recollection, that I was in

London; it may have been in 1881.

X Q. 39. I notice that the law of the State of Pennsylvania, which requires that the work done by the State printer should be dry-pressed, was approved the first day of May, 1876. That law must then have referred to the process of drying the sheets on racks, must it not?

A. I can't tell you to what the law referred or what was in the

minds of the members of the legislature.

X Q. 40. But, so far as you do know, there was no other process known at that date, was there?

A. May, 1876, there was not.

X Q. 41. Was the hydraulic machine which the witness Mr. Suydam says was put in the State printing office in the fall of 1877, and which he also says was the first machine manufactured by you except an experimental device, sold prior or subsequent to the date you filed your application on which patent No. 204,741 was granted, which application was filed, as appears from the patent, October 24, 1877? I refer to the machine which is now in the State printing office and used by Mr. Busch.

A. In the first place, I do not know, from my own knowledge, what machine Mr. Busch uses. I sold to Mr. L. S. Hart an iron machine which was operated by hydraulic pressure, the date of which sale I cannot now fix, but I think it was after the date when

this application was filed, on October 24, 1877. The patent attorney who made this application for me was very slow in his work, and I know that I had given it into his hands a considerable time before the date it was filed in the Patent Office, and I may have had the iron machine in contemplation and perhaps had it built on or about this date. I can't say positively.

X Q. 42. You have taken out other patents on this same class of machines, the drawings of which more nearly resemble the machine you sold to the State printer, Mr. Hart, than does the drawing of

the patent No. 204,741, have you not?

(Objected to as irrelevant and immaterial and not proper cross-examination.)

258 A. The drawing of patent No. 204,741 does not give a proper perspective of the first machine I sold to Mr. Hart. The first wooden machine I had with Mr. Hart did not have the bulk-compressor at the right-hand end, but it is more correctly illustrated on page 116 of plaintiffs' printed record. I have had manufactured and sold other machines, combining the same general features, with the exception of the modes by which the power was obtained. Yes; but they contain the same general features.

X Q. 43. How many patents of that kind have you taken out, being as I presume, all of them improvements upon the structure

claimed in the patent No. 204,741?

(Same objection.)

A. I can't say from memory just now how many patents I have taken out for improvements and for the bettering of the machine, but in all cases they contained the same process and were for the same purpose; some of them were simply with regard to the pumps of the hydraulic machines. The drawings may have shown the entire machine and pumps.

X Q. 44. But they were all included in the exclusive license which you granted to the Hickok Manufacturing Company, were

they not?

(Same objection.)

A. Yes; all my patents.

X Q. 45. Among these was the patent 452,898, of May 26, 1891, which has been withdrawn from this suit, and also the patent No. 212,947. You can't tell how many others, can you?

(Same objection.)

A. No; I can't tell how many others at this time. I could get the information.

X Q. 46. From your testimony I assume that you considered the important discovery you had made was in the fact that type indentations could be removed by your process without first subjecting the sheets, after being printed, to the drying process and with-

out offsetting the ink while removing such indentations. Am I right about that?

(Same objection.)

A. I can't answer for your assumption, nor can I see how you can

construe, from my testimony, such assumption.

X Q. 47. I assumed it from the fact that you have gone through a great many figures to show a saving effected in the use of your process in omitting the old process of drying the sheets on racks; but if I am wrong, will you please state what you consider the most important feature of your invention?

A. I have frequently gone through the estimate of saving of paper by my process over that of the process of pressing them prior to my process; also the other economical features by the use of my

process in the matter of room, labor, time, and the more perfect work produced by my process. The whole combination are the features in my process over that prior to my invention.

(Same objection.)

X Q. 48. Yes; but we are taking an accounting now, and you have enumerated the different steps by which you have effected the different savings, and have specifically enumerated the savings effected by each step; and one of these steps was in taking the paper directly from the printing press to your machine without subjecting it to the drying process. Now, do you consider that of any import-

ance; and, if so, how much?

A. It is of very much importance, and the cost for doing it is more than double the cost of doing the entire work on my machine—that is, the completed work that is required on my machine. Time, in my process, is a large factor. The sheets being tied up under pressure and the pressure retained, the sheets are stored until wanted for gathering. The only time required for the work on the machine to do five hundred sheets is but a few minutes. By the evidence that Mr. Busch gave, that the work that was done by him required only one-fifth of a boy's time, at the wages of three dollars and a half, this would be but one-half cent per five hundred. I think that Mr. Busch is mistaken in this, and I am free to say that he may double or treble that amount.

(The last part of the answer is objected to by counsel for defendant as not responsive to the question and as argumentative.)

X Q. 49. Did you think, when you made your application for a patent, that you were the first one to discover the fact that printed sheets, fresh from the printing press, could have their type indentations removed without offsetting the ink, without first subjecting the sheets to the old drying process?

A. I did think so, and I was so well convinced in my own mind that the very next day after I had first conceived the idea I ordered an experimental wooden machine to be made, which cost me either ninety-two or ninety-four dollars, and when it was completed and taken to Mr. Hart's establishment I myself took from the fly boards of the printing press some sheets and had them folded and put them through my machine. I did this to satisfy myself that I was right in my conception.

XQ. 50. Is that wooden machine fairly represented by the figure at the left-hand side of the drawing of the patent No. 204,741?

A. It is more fairly represented by the illustration on page 116 of plaintiffs' printed record, with the exception that the lower and upper heads in this are each cast in one piece. The drawing on patent No. 204,741, figure 3, more fairly represents those parts.

X Q. 51. Is there anything said in the specification of the patent No. 204,741 setting forth the advantage obtained by pressing the sheets of signatures without first subjecting them to the drying pro-

cess or any suggestion that the sheets should be so treated?

A. I don't know that it does. There is a copy of it here which is printed and can be ascertained by reading the specification.

If I had had an expert patent attorney, as either yourself or

Mr. Jacobs, if it is not inserted I presume it would have been, for I knew it to be a fact when I gave him the case. But unfortunately he was one of those gentlemen who worked very slow, supposed he knew all, and I having very little, if any, experience in the taking out of patents, he had his own way of making the specifications and claims.

X Q. 52. Did you not discover the omission when he read the

specification over before you signed and swore thereto?

(Objected to as irrelevant and immaterial.)

A. I can't say whether I did or not.

X Q. 53. When did you discover it, if not then?

(Same objection.)

A. I can't even fix that time; it may have been some time after

I obtained the official letters patent.

X Q. 54. The specification and claim five enumerate all the other advantages of which you have just testified, claim five having as one step the omission of fuller-boards, but it does not refer to the omission of the drying process. Why did you not reissue the patent when you made the discovery?

(Same objection.)

A. I can't even answer that, only I was always under the impression, and I am yet, that a reissued patent was a weaker instrument than the original patent. I can't say where I got that impression from, but I think it was from the attorney who obtained this patent for me.

X Q. 55. In the testimony taken and printed in the complainants' record the advantage of the omission of this drying-process step is not referred to by yourself or any of the expert witnesses on behalf of the complainants, except the witness Thomas B. Penicks, whose testimony was given after the expiration of your patent, and who

was recalled, as appears on page 90, for the express purpose of giving this testimony. How do you account for these omissions?

(Objected to as irrelevant and immaterial.)

A. I can't account for it in any other way than that it must have been overlooked or the question not asked; whilst I knew from the start that this was a fact, but as for myself my knowledge of taking and giving testimony is very limited in patent cases.

(Recess until 7.15 p. m.)

X Q. 56. Throughout the testimony a good deal has been said about the advantages derived from your supposed invention from the fact of the t-pe indentations being concaved or convexed, whatever that may mean. Is there anything said in the patent about that?

(Objected to as irrelevant and immaterial.)

261 A. No; neither do I claim that they are produced by my process.

X Q. 57. Is there anything said in the patent about removing type indentations by your press?

A. I don't think there is, in those words. That is covered by the process of dry-pressing in the fifth claim, if I remember rightly.

X Q. 58. I understand you to say that you succeeded in practising your process to your own satisfaction on the first wooden press which you had made, which you say was like a cut on page 116 of complainants' record, except the heads which were like figure 3 of patent No. 204,741. Was the work done perfectly on that machine—that is, were the typ-indentations perfectly removed when the bundles were untied after being left under pressure? What I want to know is, was this a mere experimental machine or did it do practical work?

(Objected to as irrelevant and immaterial.)

A. It was a practical machine, and was practically used until it was superseded by the iron machine, and it did satisfactory work.

X Q. 59. In stating your knowledge of the prior art, did you mention all the processes that you knew to be old prior to your invention, as set forth in your patent here in suit?

A. I did.

X Q. 60. Did you know of a patent granted to W. R. Dingman, October 20, 1863, for a paper press and tying engine for compressing sheets of paper in bundles and tying them while under pressure to hold the pressure until the cords were released, which was testified to by both complainants' expert, Robertson, and defendant's expert, Mr. Hood?

(Objected to for the reason that the patent named was set up in defendant's answer as an anticipation of the Jones invention, and has been passed upon by the court, and for the further reason that it does not cover any machine for or process of dry-pressing printed

sheets, and is therefore irrelevant to the inquiry in the present proceeding.)

A. I would ask to what time that question refers.

X Q. 61. To the time you mention in your answer, in which you say that you are familiar with all the processes in use prior to your invention.

(Objected to as assuming what the witness has not stated.)

A. Prior to my invention, I would answer no. I did not have knowledge of such a patent.

XQ. 62. You know of it now, do you not, and have examined it

and understand its mode of operation?

(Same objection as to question 60.)

A. I know of it now. I have looked over the same, but I can't now recall its particular operations or operation. If I had a copy it would recall, no doubt, the impressions I had in regard to it when

I did look over it. This patent of W. R. Dingman, the title is "Cotton press" (examining a copy of the patent which was handed to him). This press shows that it is for the purpose

handed to him). This press shows that it is for the purpose of tying paper in reams in a paper mill, and this is done prior to the printing. The paper is merely put in a commercial shape for handling or shipping outside of the mill. There are no boards used to protect the paper nor to distribute an even pressure over the entire surface of the bundle, and the bundle is tied only one way, and, to my mind, it could not be used in the shape of the drawing for the purpose of dry-pressing printed sheets, and the work could not be accomplished on this press. As I understand it, it is merely for holding the quires in place during the operation of tying the paper into reams. When the paper is removed from the press there is actually no retained pressure over the surface of the bundle.

X Q. 63. If a bundle of printed signatures were substituted for the ream of paper, and end boards used, would the pressure be

retained after the bundle was tied and removed?

(Same objections.)

262

A. I don't think I should be called upon to bring out or endeavor to do so new inventions on old patents such as this is. Neither am I am I here to testify to the inventions of others.

X Q. 64. And you decline to answer the question; is that what I

am to understand you to mean?

(Same objections.)

A. I don't believe that this machine could be made a practical machine for this purpose. It certainly is not in its present shape.

X Q. 65. It has a movable head, a stationary head, means for bringing the heads together, spaces in the head permitting the operator to pass his arm around the compressed bundle to tie the bundle while under pressure. Those are all the features of the Jones machine. Now, I simply ask you whether or not, if printed signatures were substituted in this machine for the plain, unprinted

sheets that are shown and described in the patent, and end boards placed above and below the printed signatures, the printed signatures compressed as this machine compresses the plain sheets, and tied while under pressure—whether or not the process would then be the same as the process practiced on your machine, and whether the type indentations would not be removed if the pressure was left on long enough.

(Same objections.)

A. I would say that this press is incapable of doing the work that is done by my machine and process. In the first place, I fail to see any guides for to even up against the head and back of the printed sheets; and as it is necessary to obtain proper results, the sheets have to be piled up evenly on the back and head folds all one way. The swell produced by the folds would cock the bundle, and, to my mind, utterly impossible to make a straight and even bundle, as when the pressure would be applied the sheets would fly out,

and the chances are they would fall on the floor. There is but one way of tying shown in this press, whilst in my press

the sheets are tied crossways over the end board—that is, two ways. X Q. 66. All you have said refers to your machine, about which I did not ask you. I was asking you simply about the process of your fifth claim, which says nothing about any machine or any parts of a machine. But suppose the signatures were smashed flat in a bulk-compressor, such as is shown in your patent, and described as a means for preparing your sheets for the press or for the process—in other words, "smashed," as your patent calls it—could they not be placed in the Dingman machine, between end boards, subjected to pressure, without the use of fuller-boards, and while under pressure tied in compact bundles, and then removed immediately from the press?

(Same objections.)

A. The smashing of the folds of the sheets by the bulk-compressor. This is merely done to reduce the swell of the folds in the head and back, particularly the head folds, as the heads of the sheets are very much more swelled than the back, excepting near the top, and in using the bulk-compressor it was only used to put the pressure on about one-half of the sheet as the foot of the sheets were held in the hand. This did not flatten out the sheets sufficiently to prevent them from cocking entirely. It was only to enable the more readily evening up of the sheets and handling them, and I don't believe that this process could be performed in this press. I presume, however, that the process might be practised in any press where you could get the front and back folds to keep in perfect alignment, if means were provided for retaining the pressure after the signatures had left the press, provided there was sufficient pressure, and that pressure distributed and held evenly over the entire surface of the sheets, and the strings were strong enough.

X Q. 67. Could the Jones process be practised on the John

Palmer press, a cut of which is shown at page 52 of defendant's record?

(Same objections.)

A. Not as this cut shows.

X Q. 68. Why?

(Same objections.)

A. Because the head and back folds of the sheets could not be placed and held in alignment; they would squash out when the

pressure is applied.

X Q. 69. You examined that machine; heard the testimony of the three witnesses Schrank, McKee, and Davis as to its use for twenty years at the shop of John Palmer and his successor at Philadelphia, which use was described particularly in answer 22, on page 13 of defendant's record, by the witness Schrank. Please read that answer and tell us what step in the Jones process is omitted in the use described in that answer so far as the fifth claim is concerned or the use of the Jones press is concerned.

264 (Same objection, and plaintiffs' counsel calls attention to the fact that the answer referred to does not contain the full description by the witness Schrank of the use of the press in question, but that the manner of using it is to be gathered also from his other answers.)

A. As I said before, that any press which was so constructed that the sheets could be placed all one way, the process could be accomplished if there were means for the retaining of the pressure, for tying up the bundles, and thereby retaining the pressure by means of the tie, provided rigid end boards were used to distribute the pressure over the entire surface of the bundle. The operation. according to this answer to question 22, varies considerably from that in my process. He says first in using it the strings were laid in the bottom block or platen. In my process the first thing that is done is putting in a rigid end board. Schrank says, "A piece of paper liad on top of the string, a piece of pasteboard laid on top of the paper." In my machine the sheets are filled in the trough, above the end board. Schrank says the gathered books or signatures piled up in bundles of ten and a piece of pasteboard on top and a heavy paper on top again. The string was then brought over the top of the pile, the top block was then screwed down and the pressure applied. The slack of the string was then taken up and the bundle tied and removed. In the Jones process, after the sheets are filled into the trough and end board is then placed at the top of the sheets, pressure applied, and the cords passed around the sheets and tied, then removed from the press. The operations dispensed with in the Jones process is the laying of the strings in the bottom block, the placing of a piece of paper, the placing of pasteboard on top, and a heavy piece of paper. These are not done in the Jones.

I can't say that, as far as the operation is concerned, I can see any

sheets that are shown and described in the patent, and end boards placed above and below the printed signatures, the printed signatures compressed as this machine compresses the plain sheets, and tied while under pressure—whether or not the process would then be the same as the process practiced on your machine, and whether the type indentations would not be removed if the pressure was left on long enough.

(Same objections.)

A. I would say that this press is incapable of doing the work that is done by my machine and process. In the first place, I fail to see any guides for to even up against the head and back of the printed sheets; and as it is necessary to obtain proper results, the sheets have to be piled up evenly on the back and head folds all one way. The swell produced by the folds would cock the bundle, and, to my mind, utterly impossible to make a straight and even bundle, as when the pressure would be applied the sheets would fly out.

263 and the chances are they would fall on the floor. There is but one way of tying shown in this press, whilst in my press the sheets are tied crossways over the end board—that is, two ways.

X Q. 66. All you have said refers to your machine, about which I did not ask you. I was asking you simply about the process of your fifth claim, which says nothing about any machine or any parts of a machine. But suppose the signatures were smashed flat in a bulk-compressor, such as is shown in your patent, and described as a means for preparing your sheets for the press or for the process—in other words, "smashed," as your patent calls it—could they not be placed in the Dingman machine, between end boards, subjected to pressure, without the use of fuller-boards, and while under pressure tied in compact bundles, and then removed immediately from the press?

(Same objections.)

A. The smashing of the folds of the sheets by the bulk-compressor. This is merely done to reduce the swell of the folds in the head and back, particularly the head folds, as the heads of the sheets are very much more swelled than the back, excepting near the top, and in using the bulk-compressor it was only used to put the pressure on about one-half of the sheet as the foot of the sheets were held in the hand. This did not flatten out the sheets sufficiently to prevent them from cocking entirely. It was only to enable the more readily evening up of the sheets and handling them, and I don't believe that this process could be performed in this press. I presume, however, that the process might be practised in any press where you could get the front and back folds to keep in perfect alignment, if means were provided for retaining the pressure after the signatures had left the press, provided there was sufficient pressure, and that pressure distributed and held evenly over the entire surface of the sheets, and the strings were strong enough. X Q. 67. Could the Jones process be practised on the John Palmer press, a cut of which is shown at page 52 of defendant's record?

(Same objections.)

A. Not as this cut shows.

X Q. 68. Why?

(Same objections.)

A. Because the head and back folds of the sheets could not be placed and held in alignment; they would squash out when the

pressure is applied.

X Q. 69. You examined that machine; heard the testimony of the three witnesses Schrank, McKee, and Davis as to its use for twenty years at the shop of John Palmer and his successor at Philadelphia, which use was described particularly in answer 22, on page 13 of defendant's record, by the witness Schrank. Please read that answer and tell us what step in the Jones process is omitted in the use described in that answer so far as the fifth claim is concerned or the use of the Jones press is concerned.

264 (Same objection, and plaintiffs' counsel calls attention to the fact that the answer referred to does not contain the full description by the witness Schrank of the use of the press in question, but that the manner of using it is to be gathered also from his other answers.)

A. As I said before, that any press which was so constructed that the sheets could be placed all one way, the process could be accomplished if there were means for the retaining of the pressure, for tying up the bundles, and thereby retaining the pressure by means of the tie, provided rigid end boards were used to distribute the pressure over the entire surface of the bundle. The operation, according to this answer to question 22, varies considerably from that in my process. He says first in using it the strings were laid in the bottom block or platen. In my process the first thing that is done is putting in a rigid end board. Schrank says, "A piece of paper lind on top of the string, a piece of pasteboard laid on top of the paper." In my machine the sheets are filled in the trough. above the end board. Schrank says the gathered books or signatures piled up in bundles of ten and a piece of pasteboard on top and a heavy paper on top again. The string was then brought over the top of the pile, the top block was then screwed down and the pressure applied. The slack of the string was then taken up and the bundle tied and removed. In the Jones process, after the sheets are filled into the trough and end board is then placed at the top of the sheets, pressure applied, and the cords passed around the sheets and tied, then removed from the press. The operations dispensed with in the Jones process is the laying of the strings in the bottom block, the placing of a piece of paper, the placing of pasteboard on top, and a heavy piece of paper. These are not done in the

I can't say that, as far as the operation is concerned, I can see any

steps that are omitted as he describes it. There are other parts of his testimony, if I remember correctly, he says the sheets or books were reversed head and tail. If I am correct, it would not accomplish the process.

X Q. 70. Your patent does not say whether the sheets should be laid all one way or head and tail, as I remember. Examine it and point out where there is any statement in it as to how the sheets

must be laid in order to carry out your process.

(Objected to as irrelevant and immaterial, and for the further reason that the Palmer press and process were set up in defendants answer and passed upon by the court, and the question thus decided cannot be reopened in this proceeding.)

A. No; the patent does not say so, but the drawings show this. In figure 2 you will find at the lower right-hand corner a jagged line; also the upper line is quite irregular, whilst the lower line of the bundle is comparatively straight. Such a bundle cannot be made by reversing the sheets head and tail alternately in bunches.

X Q. 71. A bundle of printed signatures subjected to pressure and tied up between end boards in the Palmer press would be protected from the twine cutting into the bundles

and there would be no waste after they were tied up, and they could be as conveniently stored as could the bundles tied up in the Jones

press; is that correct?

A. If it were capable of doing the work in the manner that the Jones press does or the Seybold, to my mind—that is, the ends of the bundles were protected with rigid end boards—there would be no further waste of sheets till they reached the completion of the book.

X Q. 72. And there would be as much saving of the paper in practising the process described by Schrank, McKee, and Davis with the Palmer press as there would be by the Jones process on the Jones press, would there not?

A. To my mind, as the process is described by Schrank, McKee,

and Davis, I should think not.

X Q. 73. In the answer before referred to Schrank describes the process briefly as subjecting gathered books or signatures to pressure between pasteboard on top and bottom, and, while under pressure, tying them into compact bundles and then removing the bundles from the press. Now, what difference is there between such a bundle and the bundle of the fifth claim of your patent? And, if there is more waste in the one than the other, give your reasons why.

(Objected to for the reason that the question assumes what the witness Schrank did not say, to wit, that the sheets were gathered into "compact bundles.")

A. As testified by Mr. Schrank, to my mind, they were not in compact bundles, as at one place he says, in his answer to question 28, "The bundle was removed. We would straighten it up by knocking it down on the floor." This cannot be done, the straight-

ening up of a bundle that is compact. If a bundle is tied up under pressure sufficient to make it solid and protected by end boards, there can be no waste whilst remaining in a compact bundle.

X Q. 74. Does your patent say how compact your bundle must

be or what amount of pressure must be applied to it?

X Q. 75. Well, try to remember that I am speaking about your patent and not about the way your process has been practised by persons who have been taught by you outside of your patent. Your patent simply says that the bundles shall be subjected to pressure between end boards, and that while under pressure tied and immediately removed. Schrank says that the Palmer bundles are subjected to pressure, and, while under pressure, tied and removed from the press. Now, why is the one a compact bundle and the other not a compact bundle, especially when your patent drawing shows a wooden frame with a screw to drive the movable platen, just as the Palmer press does, and your specification does not specify whether your end boards shall be wooden end boards, metal end boards, or

any particular kind of end boards?

Λ. In the first place, on the Palmer press there could be but very little pressure exerted, and a bundle which would 266 have to be piled up in bunches alternately reversed, with the heads and back folds one bunch one way, then another bunch laid opposite, with the head and back folds opposite to the first, and so on until the pile was complete, could not be put in a compact bundle on the Palmer press nor upon any other press, and this is the manner in which the bundles were made in the Palmer press. bundles of sheets were so made and subjected to great pressure, such as is required by my process, the sheets would be more or less injured by reason of the folds pressing irregularly over the front and foot edges, thereby not removing the swell of the folds, but would virtually make the sheet at the back folds bend, which would form a curve that would be almost impossible to straighten out, and it would therefore also not make a compact bundle. As to end boards my patent says, "Said end boards are made of any suitable material affording strength and rigidity.

X Q. 76. The question was why a collection of printed sheets subjected to pressure in the Palmer press and while under such pressure tied into bundles with end boards and then removing them from the press would not make a compact bundle, while subjecting printed sheets of paper to precisely the same operation in a Jones press

would make a compact bundle?

(Objected to because assuming that the sheets are subjected to precisely the same operation in a Jones press as in the Palmer press.)

A. The Palmer press is incapable of making a compact bundle, by reason that you cannot place the sheets in that press in such a way as to make a compact bundle. The only way you could make a bundle of folded sheets in that press was by reversing the sheets in bunches alternately, and the edges would project. Bundles with projecting edges would not, in the sense that I use the term in my

process, be compact bundles.

X Q. 77. You assume that the Palmer sheets or signatures were placed in the press as they came from the folder. Suppose they were subjected to the action of a smasher before they were placed in the press, would the Palmer press then make a compact bundle out

of such smashed sheets?

A. Under those conditions, the sheets being smashed perfectly flat and solid and the air displaced between the sheets, I think it would be capable to place such sheets in the Palmer press and tie them into bundles; but the pressure would not have been sufficient to keep the sheets so retained for any length of time, especially in large editions, where they have to be stored until the completion of the work. The bundles would become loose by reason of the light pressure which could be exerted by the Palmer press on them before tying. The bundles would fall apart and sheets become scattered over the floor, and many wasted in this way by dust, soiling, and crumpling.

(Adjourned to October 2, 1896, at 9.30 a. m.)

267

Остовек 3, 1896-9.30 а. т.

Examination resumed pursuant to adjournment. Present: Same counsel.

Cross-examination of Joshua W. Jones by Mr. Murray continued:

(Witness adds to his answer to cross-question 77:)

I wish to add that a bundle tied up after the sheets were smashed, that this would be after the sheets had gone through the process of smashing, and would have to be done after all the intermediate steps between the printing and smashing had been gone through with and in which all the waste occurs. After the sheets are gathered into books there is no waste, nor can there be any. The steps described by Schrank were taken after the sheets were dried, pressed, and gathered into books and smashed. The Palmer press is incapable of performing the work of making a compact bundle prior to the smashing; even then it would not be practicable, as it has no guides to even the sheets up against and hold them in alignment, in consequence of which the sheets would slip and -quash out, and it would smear and blur the printing. The guides in my press prevent this, and there are none in the Palmer press.

X Q. 78. Mr. Francis E. Davis, who testified to the use of the Palmer press and who had seen it daily, says, in answer to question

36, on page 24 of defendant's printed record:

"Q. 36. But you know that bundles were tied in the Palmer press before the pressure was taken off, do you not?

"A. They certainly were; that is the object of the press-to make

the bundle as compact as possible."

Now, are you willing to say that the bundle of signatures put in the Palmer press, as Mr. Schrank and Mr. Davis describe, could not be tied in compact bundles between end boards while the pressure was on and then removed from the press?

(Counsel for plaintiffs objects to this method of singling out special passages from the testimony of the witnesses Schrank, Davis, and McKee, and insists that if the opinion of the present witness is desired with regard to the mode of operation and efficacy of the Palmer press the whole of the testimony of those witnesses should

be placed before him and not merely isolated passages.

Counsel for the defendant replies that the witness' counsel is able to take care of him; that he has a right to re-examine after the cross-examination is closed, and that he can then put in the whole or a part of these witnesses' testimony; and defendant's counsel insists that this line of cross-examination of an adverse and interested witness is entirely proper.)

A. Not as Mr. Schrank describes it on defendant's record in his answer to question 25:

"Q. 25. How were the books arranged in the bundle, with refer-

ence to each other?

"A. They were piled up back and front or head and tail."

1 say that such a bundle could not, in the sense of my claim 5 of my patent, and would not be a compact bundle.

X Q. 79. As I understand your testimony, on page 22, you never charged any royalty for the use of the fifth claim of your patent from the parties who had purchased machines from your licensee, the Hickok Manufacturing Company; that is right, is it?

A. That is so.

X Q. 80. And that license also included your patent No. 212,947, as shown by the form of license on page 9 of the record, did it not?

(Objected to as irrelevant and immaterial.)

A. That is so.

X Q. 81. Then when you received a stipulated royalty agreed upon between yourself and the Hickok Manufacturing Company for each machine it sold you had no further claim for royalty from the Hickok Manufacturing Company, the purchaser of the machine, nor from any subsequent purchaser who might buy the machine from the party to whom the Hickok Manufacturing Company had sold it; that is correct, is it not?

(Same objection.)

A. Not exactly, as I understand it. I had no further claim upon the Hickok Manufacturing Company or the party who purchased the same. The purchaser was licensed to use the machine in a certain place, and if he removed from that place to another I agreed to transfer the right to use said process to the new shop or bargaince. Under this license I did not give the right to sell the machine or transfer the license to any other party. Whether I could have collected a license fee from another party than the one to whom the machine was sold I do not know. I never did it. This applies to the process.

X Q. 82. Had the Hickok Manufacturing Company sold the machine to Mr. Busch instead of the Seybold Machine Company, you would have had no claim against him for damages or profits, would you?

(Same objection.)

A. No.

Redirect examination by Mr. Jacobs, without waiving objections:

Q. 83. You have been asked on cross-examination with respect to the Palmer press as a means for bundling printed sheets and saving waste. Assuming, now, that it could do all that is claimed for it, is there, under the old fuller-board process of dry-pressing, any waste of sheets prior to the tying of them up in bundles?

(Objected to as immaterial.)

A. There is. The sheets become torn and soiled in bandling them, through the drying process and the placing them between the boards and up to the stage of folding is where the great 269 waste occurs. If the sheets are dry-pressed before folding, and then tied up with protecting boards to protect the sheets on the ends of the bundles, providing this protection is sufficient to

prevent the cutting of the edges of the sheets by the twine, the item of waste of the sheets used is the only saving not accomplished by the tying of the bundles by hand. Of course, I refer now to that if the sheets were tied in a press under pressure.

Q. 84. What proportion, under the old process, of the waste of sheets occurs prior to the bundling?

(Same objection.)

A. Say a sheet twenty-six by forty, sixty pounds to the ream, about eight such sheets would be eight out of the ten which are allowed to the printer, are wasted.

Q. 85. You mean, by your last answer, wasted prior to the bun-

dling, do you?

A. I do.

Q. 86. The defendant, Mr. Busch, in his answer to question 27 says: "Mr. Bigelow said he would have sold me one to do the work for five hundred dollars and saved me all this trouble."

Do you know what Jones machine the Hickok Manufacturing Company was selling for five hundred dollars at that time?

A. The steam screw-power signature press shown in cut on page

115 of plaintiffs' record.

Q. 87. I infer from Mr. Busch's answer, taken in connection with the question to which it was given, that the machine referred to was one of the same size and to do the same work that was done by the Seybold press which he had. As you were at Mr. Busch's establishment several times and saw the work carried on there with the Seybold machine, please state whether or not the Jones steam screw-power signature press referred to in your answer to question

86 is a machine upon which about the same amount and kind of work can be done as upon the Seybold machine which Mr. Busch had.

(Objected to for the reason that it does not appear that that was the machine referred to by Mr. Bigelow, and therefore irrelevant and incompetent, as calling for secondary evidence.)

A. As to the same size, the machine will take in as many sheets as the Seybold. The Seybold is capable of taking in a larger sheet, but by reason of this it would not be so convenient for handling the sheets through it, as the space around the rod-trough in the Seybold machine is much larger, and therefore makes it more unhandy to fill and tie. It will do the work of Mr. Busch, and about the same amount as can be done on his machine. This steam screw-power press is especially adapted for the size of work that is done for the State by him. The number of sheets pressed, either in the Jones press or the Seybold, in a given time, depends entirely upon the skill and capacity of the operator; as the time for apply-

ing the pressure, in either case, is a very small and infinitesimal factor, in proportion to the time required for getting the sheets ready, filling them in the press, tying them

into compact bundles, removing them, and marking the signature on the end. I refer, when I say "around the rod-trough," to that part across the machine, not in the length.

Q. 88. Was there any cheaper Jones machine, then, manufactured

which would do the work of Mr. Busch?

A. I think not. It might possibly have been done on the hand screw-power machine. This, however, would not be an economical machine where so large a quantity of work is done as by Mr. Busch, and the wages, distributed over a period of from one to two years for the labor required to do Mr. Busch's work on this machine, would make it a very much more expensive machine. I question whether his work could be done on two such hand machines.

Q. 89. Do you remember the price at which the hand machines

sold at that time?

A. No, sir; I do not.

Recross-examination by Mr. Murray:

X Q. 90. The hand machine referred to is the one illustrated on page 116 of the complainants' printed record, is it not?

A. Yes.

X Q. 91. Throughout your testimony, in comparing the processes of preparing printed sheets ready to be bound, you have always referred to the wet process as practised by Mr. Thomas B. Penicks, who, at the time he gave his testimony, was operating fourteen of your hydraulic machines instead of the dry process referred to in your patent, have you not? I will read from Mr. Penicks' answer to question 1, when he was recalled, on page 90 of complainants' printed record:

"In the Jones process the sheets do not have to go through the

process of drying, but are folded wet as taken from the press and

pressed wet."

A. This refers to sheets that were dampened; the paper was dampened before printing. There is some of the work in the Government Printing Office that I think is still printed on wet paper, but there is much that is printed on dry paper. Mr. Penicks referred to that which was printed on damp paper. My interpretation of "wet" covers both paper printed wet or dry. On the wet paper the paper and the ink are both wet. Dry-paper printed sheets the printing is wet, in the same sense as a painter will designate wet paint and dry. Freshly painted and before dry painters call "wet."

X Q. 92. Where, from Mr. Penicks' testimony, do you find that part upon which you base your assumption that he was referring

to paper dampened or wet before printing?

A. In his answer to question 1, page 90, of the plaintiffs' record,

in these words: " * * * the paper being wet.

X Q. 93. Does that refer, in your opinion, to the wet ink upon the paper after it leaves the printing press, as he states, or to the paper being wetted before it was printed?

A. To both, as the drying of the wet paper would naturally also

dry the iak.

X Q. 94. In Mr. Penicks' answer to question 3, page 69, he describes the ponderous old process of dry-pressing in substantially the same manner as you and all the witnesses called here have described it, and states that all the work was printed in the press-room and then forwarded to the drying-room for dry-pressing, and at no place do I find, either in his testimony or that of any of the other witnesses, any statement that paper required to be wet or dampened before printing on any of the modern printing machines. I will ask you, now, if you know of any modern printing machine used in book-work that does not print on dry sheets; and, if you do,

state where it is located.

A. I would state that any printing press, whether it be old or modern, will print on dry paper—even old Ben. Franklin's press was capable of printing on dry paper. The question of printing on either wet or dry paper I consider is the fad of the printer. I know that the wetting of sized and supercalendered paper, such as is furnished by the State to Mr. Busch, would injure the surface of the paper and destroy the gloss of the calendering. The printing of paper dry is not a discovery of recent years; therefore I cannot say where there is a press or any party who do their printing on wet sheets, unless it is that the Government may do it on their large editions, such as the Agricultural Report, which is printed on what is known as machine-finished paper of the cheapest quality and grade of book paper.

JOSHUA W. JONES.

Sworn to and subscribed before me this second day of October, 1896.

FREDERICK M. OTT,

Notary Public.

RICHARD MILES, being produced, sworn, and examined, saith:

Examined by Mr. Jacobs:

Q. 1. State your age, occupation, and place of residence.

A. Fifty-four years of age; I am chief clerk of the W.O. Hickok Manufacturing Company; residence, Harrisburg, Penna.

Q. 2. How long have you occupied that position?

A. I couldn't state exactly that. I have been there since 1879, and have gradually gone up. I couldn't tell you when I became chief clerk. I think it has been about ten years.

Q.3. Whose duty is it in that establishment to keep track of the cost of articles manufactured and furnish the data for estimates

thereof when required?

A. It is my duty.

Q. 4. Are you familiar with the "Jones steam screw-power signature press," a cut of which, printed on page 115 of complainants' printed record, I now hand you?

A. Lam.

- Q. 5. Please state the cost of manufacturing that machine, including the materials, labor, and so forth, at the Hickok establishment in 1893.
- A. I have no accurate data of any machines built in 1893. I have accurate data of machines built within four or five months, the cost of which was one hundred and thirty-eight dollars and sixty-eight cents each. We now have some improved appliances which we did not have in 1893, and the cost of materials at the present time is slightly less, and from comparisons that I have been able to make, to the best of my judgment and belief, the cost of manufacture in 1893 was about fifty dollars greater on each press than in 1896.
- Q. 6. Does the estimate for 1893 include material as well as labor?

A. Yes, sir.

Q.7. What Jones signature press cheaper than the steam screwpower signature press was the Hickok Company manufacturing in 1893?

A. We manufactured a hand-power machine.

Q. S. Was it the one shown on page 116 of complainants' printed record?

A. Yes, sir.

Q. 9. What was the price of the hand-power machine in 1893?

A. Three hundred and fifty dollars.

Q. 10. Were these two, to wit, the steam screw-power and the hand-power presses, the cheapest Jones signature presses manufactured by the company at that time?

A. Yes, sir.

Q.11. Can you tell us, approximately, the price in 1893 of hydraulic standing presses, taking in a sheet of twenty-six by forty inches and having an opening between the head and platen of, say, four or five feet?

(Objected to as immaterial and irrelevant.)

A. At that time we were selling a press taking a sheet twenty-six by forty; the distance between the top of the platen when down and under side of cap forty-eight inches, for four hundred and eighty dollars without the pump, and nine hundred and sixty dollars including the pump. This price did not include any connections between the press and the pump, which were extra, and always made to suit special requirements.

(Cross-examination waived by counsel for defendant.)

RICHARD MILES.

Sworn to and subscribed before me this second day of October, 1896.

> FREDERICK M. OTT, Notary Public.

273 In the Supreme Court of the District of Columbia. In Equity.

No. 15391, Docket No. 36.

HARRISBURG, PA., Oct. 2, 1896.

I hereby certify that the witnesses whose depositions are hereto attached, namely, C. M. Busch, Charles A. Suydam, Joshua W. Jones, R. A. Johnston, and Richard Miles, were severally duly qualified by me and examined at the time and place set forth in the deposition of each, and that they subscribed their several depositions in my presence.

Witness my hand and notarial seal the day and year above

mentioned.

SEAL.

FREDERICK M. OTT, Notary Public.

Endorsed on cover: District of Columbia supreme court. No. 903. Clarence M. Busch, appellant, vs. Joshua W. Jones et al. Second addition to record per stipulation of counsel. Court of Appeals, District of Columbia. Filed Oct. 2, 1899. Robert Willett, clerk.

274 Thursday, November 9th, A. D. 1900.

CLARENCE M. Busch, Appellant,
vs.

Joshua W. Jones and The W. O. Hickok Manufacturing Company.

No. 903.

The above-entitled cause was argued by Mr. George J. Murray, attorney for the appellant, and was submitted to the consideration of the court on the record and briefs by Mr. M. W. Jacobs, attorney for the appellees.

275 CLARENCE M. Busch, Appellant,

Joshua W. Jones and The W. O. Hickok Manufacturing Company.

(Mr. Chief Justice ALVEY delivered the opinion of the court:)

This appeal is brought here from a final decree of the court below, passed in a cause instituted by the appellees, Joshua W. Jones and The W. O. Hickok Manufacturing Company, against Clarence M. Busch, the appellant, to have the latter restrained from further infringement of certain patents issued to the said Joshua W. Jones, and for an accounting as well for the damages suffered by the appellees as for the gains and profits derived to the appellant from the infringements of the patents. The patents were for improvements in press and process by which was effected the pressing of folded sheets or signatures of printed matter by first subjecting them to pressure, then tying them between boards in a compact bundle and removing them from the press and allowing them to remain tied a sufficient length of time to efface the impressions produced by printing—a process known to printers and bookbinders as dry-pressing.

The bill was filed on the 10th of March, 1894, alleging the infringements of two patents issued to appellee Jones, numbered respectively 204,741 and 452,898, the former dated the 11th day of June, 1878, and the latter dated May 26th, 1891, both having relation to and intended to secure the exclusive right to the said Jones, as the first, original, and true inventor and discoverer of certain new and useful improvements in bookbinders' dry-press and sheetie, and of a certain new and useful process for treating folded sheets in dry-pressing, &c., described in said letters patent, to make, use, and dispose of the appliances and process of said invention and discovery. The patent No. 452,898, dated May 26, 1891, embraced smashing and tableting machines, but that patent is out of the case,

there being no attempt by the complainants to show by proof that that patent had been infringed as distinguished from patent No. 204,741. The whole controversy in this case therefore is based upon the alleged infringement of patent No. 204,741.

The defendant Busch by his answer denied that the complainant Jones was the first and original inventor or discoverer of the device or process described in patent No. 204,741. He also denied that he had in any manner infringed any patent right owned by the plaintiffs or either of them, or that he had derived profit or gains from any such alleged infringement. He denied on information and belief that said Jones was the first, original, and true inventor of the improvements or process set forth in the patent and claimed therein, and he also denied that the alleged improvements and process were new or useful, or that the same had not been known and used by others prior to the alleged invention thereof by said Jones, or that the same had not been patented or described in any printed publication prior to his alleged invention thereof, and he further denied that the alleged improvements or process had not

been in public use or on sale for more than two years prior to his application for letters patent therefor. The defendant alleges that patent No. 204,741 is void because it required no invention to produce the alleged improvements therein claimed, and that the alleged improvements described in said patent are not patentable inventions within the meaning of the patent laws, but if such alleged improvements were patentable under the law, still the defendant insists that the patent is void for that the alleged inventions and the same principles and combinations and every substantial and material part thereof shown, described, and claimed therein as new were. prior to the date of the application for said patent and the date of said alleged inventions by said Jones, shown, described, and set forth in certain publications and patents specifically mentioned and referred to in the answer. The defendant says that the press he is using is a patented one, but differs radically in construction and mode of operation from the alleged invention shown, described

and claimed by the plaintiff Jones. The defendant denies the right of the complainants to any injunction on the allega-

tions of the bill.

Replication was entered, and the parties proceeded to take evidence, and a considerable volume of evidence was produced, consisting largely of expert testimony—that is to say, the testimony of witnesses skilled in and familiar with the art to which the subjectmatter of the patent relates. The cause came on to hearing, and the court below, by an interlocutory decree of the 11th of February. 1896, declared and decreed that the patent No. 204.741, granted to Jones, for bookbinders' dry press and sheet-tie, was good and valid in law; that Jones was the original and first inventor of the improvement and process described and claimed in the patent; that the W. O. Hickok Manufacturing Company was the sole and exclusive licensee under the patent, and that the defendant had infringed said letters patent and the exclusive rights of the complainants thereunder, and particularly the patent right embraced in and covered by the 1st, 2nd, and 4th claims of said patent, and also by practicing the process embodying the improvement specified and particularly claimed in the 5th claim of said letters patent.

It was also adjudged and decreed that the plaintiffs should recover from the defendant the profits, gains, and advantages which said defendant had received or made or which had arisen and accrued to him by reason of any infringement of said patent rights since the date of said patent, and also the damages which the plaintiffs had sustained by reason of such infringement, to be assessed according to law; and for the purpose of taking such account of the gains, profits, and advantages and of ascertaining the damages proper to be assessed, the case was referred to the auditor of the court, with directions to state the account and report the same to the court, and it was also ordered and decreed that a perpetual injunction be issued,

as prayed in the bill.

The claims in the patent that were by the preceding decree adjudged and determined to have been infringed by the defendant

were the following:

278 "1. In a printer's and bookbinder's dry press and sheettic, the compressing heads C D D' and B² F' F, constructed with cross-ways L² L², centrally arranged through them, substan-

tially as and for the purpose herein set forth.

"2 The inclined press bed, H H², provided with longitudinal slots, H¹ H¹, in its sides, in combination with the press heads, B² F′ F and C D D′, having through them the cross-ways, L² L², correspondingly arranged with said slots, substantially as and for the purpose set forth."

"4. In combination with the dry-press bed, H H², the device of a set of removable ledges, f, or a set of adjustable guide-rods, m,

arranged as and for the purpose set forth."

These three claims have reference to the structure and arrangement of the press machine. The following claim is descriptive of the process by which the dry-pressing is effected without the use of

fuller-boards:

"5. The process herein described for treating folded printed sheets of paper in dry-pressing, the same consisting of subjecting a collection of such sheets to pressure without the use of fuller-boards, and while under such pressure tying them into compact bundles with end boards, then removing them immediately from the press, and allowing them to remain tied sufficiently long to fix and complete

dry-pressing."

Under the reference made by the decree, the auditor examined all the facts of the case and made a full and clear report of his findings from the facts and stated an account accordingly. He ascertained the amount due the plaintiffs from the defendant to be \$3,491.70, with interest from the 26th day of March, 1897, the date of filing the report and account in court. To this account thus stated the defendant excepted upon various grounds, but the exceptions were all overruled by the court, and the report and account were ratified and confirmed; and afterwards—that is to say, on the

4th day of April, 1899—the court passed a final decree, whereby it was adjudged and decreed that the previous interlocutory decree of Feb. 11, 1896, under which the account was stated, should be confirmed and made final, and that the defendant should

should be confirmed and made final, and that the defendant should pay to the plaintiffs the amount ascertained by the auditor, with costs. It is from this latter decree that the appellant has appealed.

In support of his appeal he has assigned eight errors. These alleged errors are the following, stating them in the order in which

they have been assigned:

Ist. That the court below as a court of equity had no jurisdiction to take cognizance of the case, because there was complete remedy at law, and even if the bill of complaint did show ground for the exercise of jurisdiction, because an injunction was prayed, yet, as no steps were taken to procure an injunction during the life of the patent, the remedy at law was adequate, and the court, as a court of equity, should not have proceeded with the cause.

2nd. That the patent in suit, so far as the 5th claim is concerned, is void, because even if the alleged process was new, it is apparent that it was the mere function of the machine that was claimed.

3rd. That the patent is void for want of novelty by reason of anticipation by the patents set up in evidence and by reason of public and common use, not only of the combinations covered by claims 1, 2, and 4, but also by reason of the process practiced on the Palmer press years before the application for the patent by Jones.

4th. That the patent is void for want of invention, so far as the 5th claim is concerned, because the process had been used prior to the application by Jones for patent, without the use of any machine

to assist in carrying out the process.

5th. That the claim 4 of the patent is void for ambiguity.

6th. That the single machine used by the defendant, in view of the state of the art preceding the Jones invention, did not infringe

either of the claims 1, 2, and 4.

280 7th. That the court should, on the motion of the defendant, have vacated the interlocutory decree after the auditor had made his report showing that there were no damages to be assessed.

8th. And finally that the court erred in overruling the exceptions to the auditor's report and account and in adopting the principles

upon which the account was stated.

It is quite apparent that several of these assignments of error are but different modes of stating substantially the same proposition and will not therefore require separate and distinct consideration.

1. The question of jurisdiction raised by the appellant we can hardly regard, in view of the repeated decisions of the Supreme Court of the United States upon the subject, as being open for discussion upon the facts alleged and shown in proof in this case. If it were true that the suit had been begun so recently before the expiration of the patent that under the rules and practice of the court no injunction could have been obtained before such expiration, the bill should have been dismissed for want of equity jurisdiction; but the bill in this case was filed on the 10th of March, 1894, and the patent did not expire until the 11th of June, 1895, about fifteen months after suit brought. The pleading had been made up and the plaintiff's prima facie proof taken by Sept. 24, 1894, and the further delay in the taking of the proof seems to have been at the instance of the defendant. Under such circumstances the jurisdiction of the court had attached, with ample time for its exercise; and at most it was a discretionary matter with the court below whether the bill should be retained and the cause be proceeded with, notwithstanding the expiration of the patent on the 11th of June, 1895, or to dismiss the bill and turn the parties over to their action at The court exercised its discretion in favor of retaining the law. bill and proceeding to take the account; and this court, being in the exercise of appellate jurisdiction, will not review the mere dis-

cretionary determination of the court below of such question unless it were shown that the exercise of the discretion was in a manner clearly illegal. That has not been shown in

this case. Clark vs. Wooster, 119 U.S., 322, 325.

In the case just referred to, of Clerk vs. Wooster, it was said by the court, speaking by Mr. Justice Bradley: "The jurisdiction had

attached, and although, after it attached, the principal ground for issuing an injunction may have ceased to exist by the expiration of the patent, yet there might be other grounds for the writ arising from the possession by the defendants of folding guides illegally made or procured whilst the patent was in force. The general allegations of the bill were sufficiently comprehensive to meet such a case. But even without that, if the case was one for equitable relief when the suit was instituted, the mere fact that the ground for such relief expired by the expiration of the patent would not take away the jurisdiction, and preclude the court from proceeding to grant the incidental relief which belongs to cases of that sort. This has often been done in patent causes, and a large number of cases may be cited to that effect, and there is nothing in the decision of Root Railway Co., 105 U. S., 189, to the contrary." Other cases are cited to the same effect. "It is true that where a party alleges equitable ground for relief, and the allegations are not sustained, as where a bill is founded on an allegation of fraud, which is not maintained by proofs, the bill will be dismissed in toto, both as to the relief sought against the alleged fraud, and that which is sought as incident thereto."

In that case it was held that, although there were only three days for the patent to run, it was within the discretion of the court to take jurisdiction, and having done so, without enjoining the defendant, it was competent for it to proceed to grant the other incidental

relief sought by the bill.

And so in the case of Beedle vs. Bennett, 122 U. S., 71, it was held that if a bill be filed in equity to restrain an infringement, and be filed before the expiration of the patent, the jurisdiction

of the court is not defeated by the expiration of the patent by 383 lapse of time before the final decree. In that case the court said that, "as the patent was in force at the time the bill was filed and the complainants were entitled to prelimit ary injunction at that time, the jurisdiction of the court is not defeated by the expiration of the patent by lapse of time before final decree." But it is clear that if the bill upon its face or the evidence produced gives rise to the fair presumption that the suit was instituted in equity merely to evade an action at law, the bill will not be entertained. Root rs. Railroad Co., 105 U. S., 189, 211. For it is now a well-settled principle that a bill in equity for a naked account of profits and damages against an infringer of a patent cannot be maintained; that such relief ordinarily is incidental to some other equity, the right to enforce which secures to the patentee his standing in court, and that the most general ground for equitable interposition is that which tends to insure to the patentee the enjoyment of his specific right by injunction against a continuance of the infringement. 105 U.S., 215, 216,

It is contended, however, that the court below was without equity jurisdiction to take cognizance of the case, because it is shown that the defendant was not a manufacturer of the invented article, but a mere user of a single machine, and that damages could be easily measured by the difference between the cost and the selling price of

that machine without reference to a master to take an account, and therefore the remedy at law was adequate and complete; but this contention cannot be supported. It was not the press only, but the process also, covered by claim 5, used, it is true, in connection with the machine, that were being used by the defendant in alleged violation of the rights of the plaintiffs under the patent, and it was the right of the plaintiffs to have such user restrained, down to the time when the patent expired.

In the case of Mills Manf. Co. vs. Whitehurst, 56 Fed. Rep., 589, 594, where a similar defense was set up and relied on by an

infringer, the court, in disposing of the defendant's contention, said: "The second defense, that the complainant has an adequate remedy at law, and therefore is not entitled to sue in equity, must be overruled. * * * The defendants are users, not manufacturers, but if infringers they may be enjoined, and that disposes of the objection to the jurisdiction." And the same principle is laid down as clear law by the Supreme Court of the United States in the case of Birdsell vs. Shaliol, 112 U. S., 485, 487.

We discover no want of jurisdiction in a court of equity to entertain the bill in this case, and to administer the relief therein prayed.

2. The next contention is that the patent, as to claim 5 therein. such claim being for process only, is simply void, because it is for the mere function of the machine, and therefore not patentable This contention presents an important question, and the defendant relies in support of his contention upon certain decisions of the Supreme Court of the United States, and especially the decisions made in the recent cases of Risdon vs. Locomotive Works vs. Medart, 158 U. S., 68, and Westinghouse vs. Boyden Power Brake Co., 170 U. S., In these cases there is some general phraseology used in the opinions of the court which, if considered in a general broad sense. might be taken to give some color to the contention of the defendant: but we do not think that upon consideration of the entire opinions in those cases, that any such proposition was intended to be decided by the court as that contended for in this case. This is manifest, we think, from what was said by the court in the case of Westinghouse vs. Boyden Co. After referring to the previous cases in which the subject had been considered, the court said: "These cases assume, although they do not expressly decide, that a process to be patentable must involve a chemical or other similar elemental action, and it may be still regarded as an open question whether the patentability of processes extends beyond this class of in-Where the process is simply the function or

operative effect of a machine, the above cases are conclusive against its patentability; but where it is one which, though ordinarily and most successfully performed by machinery, may also be performed by simple manipulation, such, for instance, as the folding of paper in a peculiar way for the manufacture of paper bags, or a new method of weaving a hammock, there are cases to the effect that such a process is patentable, though none of the powers of nature be invoked to aid in producing the result: "and the court, after citing several cases in support of the proposition stated, pro-

ceeds to say: "This case, however, does not call for an expression of an opinion upon this point, nor even upon the question whether the function of admitting air directly from the train pipe to the brake cylinder be patentable or not, since there is no claim made for an independent process in this patent, and the whole theory of the specification and claim is based upon the novelty of the mechan-

ism."

Now, it is quite clear, we think, that the operation described in claim 5 of the patent under consideration requires the effective force of a mechanical structure, and though the result produced be the effect of a process used in connection with the machine, yet that result can only be produced by the combination of machine force and a skilful manipulation of the material to be operated upon according to the process, aided by the co-operation of the principles of natural law. There is no chemical action involved, it is true, but there is an elemental action, that of tight cohesion under a high degree of pressure effected by a special mechanical contrivance, and to produce new and beneficial results by such means or process would seem to be clearly within the reason and contemplation of the patent laws.

This question would seem to be settled by express decision. In the case of Cochrane vs. Deener, 94 U. S., 780, a case of infringement and where the question of the patentability of a mechanical process was presented, Mr. Justice Bradley, delivering the opinion of the court, said: "That a process may be patentable, irrespective

of the particular form of the instrumentalities used, cannot 285 be disputed. If one of the steps of a process be that a certain substance is to be reduced to a powder, it may not be at all material what instrument or machinery is used to effect that object, whether a hammer, a postle and mortar, or a mill. Either may be pointed out, but if the patent is not confined to that particular tool or machine the use of the others would be an infringement, the general process being the same. A process is a mode of treatment of certain materials to produce a given result. It is an act or a series of acts performed upon the subject-matter to be transformed and reduced to a different state or thing. If new and useful, it is just as patentable as is a piece of machinery. In the language of the patent law, The machinery pointed out as suitable to perform the process may or may not be new or patentable, whilst the process itself may be altogether new and produce an entirely new result. The process requires that certain things should be done with certain substances and in a certain order, but the tools to be used in doing this may be of secondary consequence."

In the case of Tilghman vs. Proctor, 102 U.S., 707, it was held that a valid patent may be granted for applying and carrying a well-known principle into practical, useful effect by means of a mechanical contrivance and apparatus, and in the celebrated and much-considered Telephone cases, 126 U.S., 1, 532, the question of the patentability of process was discussed and the principle stated with great fulness and clearness by the late Chief Justice Waite. In the

course of his elaborate opinion he said:

"In this art, or, what is the same thing under the patent law, this process, this way of transmitting speech, electricity, one of the forces of nature, is employed; but electricity left to itself will not do what is wanted. The art consists in so controlling the force as to make it accomplish the purpose. It had long been believed that if the vibrations of air caused by the voice in speaking could be re-

produced at a distance by means of electricity the speech itself would be reproduced and understood. How to do it was the question." And after stating that Bell had devised a way in which the necessary changes of intensity could be made and speech actually transmitted, the chief justice proceeded to say: "In doing this, both discovery and invention, in the popular sense of those terms, were involved; discovery in finding the art and invention in devising the means of making it useful. For such discoveries and such inventions the law has given the discoverer and inventor the right to a patent—as discoverer, for the useful art, process, method of doing a thing he has found; and, as inventor, for the means he has devised to make his discovery one of actual value." And he then proceeds to declare that an art—a process—which is useful, is as much the subject of a patent as a machine, manufacture. or composition of matter, and that of this there can be no doubt. and he refers to the previous cases upon the subject.

Without referring to other authority, it is clear, we think, upon the authorities to which we have referred, that the claim 5 in the patent under consideration is not merely, as contended by the defendant, a claim for the function of a machine, but is for a process in the operation of which a machine is used as one of the essential means to produce the desired result. That result being new and

useful, it was the proper subject for a patent.

3 and 4. The third and fourth errors assigned relate to the question of the want of novelty by reason of the alleged auticipation by prior patents and of public and common use of the combination covered by claims 1, 2, and 4, and also by reason of the practice of the process covered by claim 5, with the knowledge of Jones, the patentee, years before the application by Jones for his patent on the Palmer press.

Before referring to the evidence in the case it may be proper to state the general principles or presumptions that arise upon the grant of the patent alleged to have been infringed, and upon whom,

in such case as this, the burden of proof rests.

It is a general principle that a patent is prima facie evidence of its own validity, and that it was regularly issued, and the burden of proving the want of novelty in the invention covered by it is on the party seeking to establish that fact. Singer Manf. Co. es. Brill, 7 U.S. App., 601. Consequently the want of novelty in the invention is matter of defense, unless it appears on the face of the patent that a device is without novelty or invention. Fruit Packing Co. vs. Cassidy, 7 U.S. App., 424. Therefore, when the Patent Office grants a patent for a device which accomplishes the same result as a prior patent, though according to a different method or process, the latter patent is to be taken as evidence of a determination by the

office that the latter invention is of value and does not conflict with or infringe the prior patent; and this presumption will be indulged until overcome by satisfactory evidence to the contrary. Packard 18, Lacing Stud Co., 33 U. S. App., 306; Boyden Power Brake Co.,

25 U.S. App., 475.

The witnesses examined in the case have very fully and clearly explained the operation of the press, embodying claims 1, 2, and 4, and the manner of manipulating, arranging, and compacting the printed sheets of paper, preparatory for the binder, described in claim 5, and have shown wherein these several claims were for valuable and substantial improvements upon all former devices known and used in the art of bookbinding, especially intended for dry-pressing the printed sheets, and effacing therefrom the impressions produced by printing. The state of the art prior to and at the date of the patent in question is stated by Mr. Jones himself, the patentee, who was examined as a witness. He is a skilled bookbinder and printer, of large and varied experience in the art, and he describes the former process of preparing the printed sheets for the binder thus:

"The sheets were taken, after being printed, and dried. The drying was done by laying them over a peel and hung up on poles near the ceiling of the room. They were then taken to a table and laid out flat, averaging from one to six sheets, and were laid be-

tween fuller or glazed boards alternately. They were then laid into a large screw-press in bunches about an inch and a half or two inches in thickness, and then a cherry board was placed on them, and so on alternately until the press was filled, when a force of hands, consisting of eight or ten persons, would apply the pressure by means of a long iron lever. The sheets were then allowed to remain in the press over night, and the press was emptied the next morning in the same manner that it had been filled—that is the sheets and fuller or glazed boards were piled up on a table and the operators proceeded to take out the flat pressed sheets, laving them to one side the pile and laying the boards off on another pile. This was all done before the folding of the sheets." In answer to another interrogatory he says: "The fuller boards, probably more commonly known in the trade as glazed boards, they being a board about the thickness of a heavy card-board and made of some very hard fibre, and being a hard board with a finished surface they act as a hard substance placed between two rough, soft, yielding substances, and the sheets being placed from one to six between said boards it gives a comparatively solid surface interposed between the vielding surface of the sheets, whereby by using pressure and allowing that pressure to remain continuously on the sheets and boards while in press from twelve to twenty-four hours it smooths out the indentations or impressions made by the printing on the sheets." The pressure referred to could be produced either by screw power worked by hand or by a hydraulic press.

A full statement of the operation of dry-pressing under the Jones patent is given by Mr. Robertson, examined as an expert witness on the part of the complainants. He is a patent solicitor and mechanical expert, with practical knowledge of printing and bookbinding.

In describing and explaining the invention of Jones covered by the patent in question this witness says: "The invention described in said patent and illustrated in the drawings and covered by the claims referred to in the question is a process for

treating folded printed sheets, whereby the impressions made 989 in the letter-press printing process are flattened out, so that the paper will resume its original smoothness or substantially so, which process is carried out in such a manner that the operator can be continually putting in the signatures or printed matter and removing them in tied-up bundles, whereby with one press a much larger number of signatures can be pressed and at a very much reduced cost for labor over that of the process previously employed. The improvement also consists in a means for carrying out this process. which means is shown in the drawings, and more particularly in that part which is shown to the left hand of Fig. 1 and details in Previous to the invention of Mr. Jones, as described Fig. 3 and 4. in said patent, it was the custom to press printed sheets by inserting them between heavy paper boards, sometimes called 'fuller-boards' but generally now called 'glazed boards,' and putting said boards, with the printed papers between them, into a powerful press, by which pressure was produced on said boards by various means sometimes by means of screw pressure, sometimes by hydraulic pressure. After the pressure was produced on the paper it was continued by allowing the press to remain with its pressure on to its fullest extent for ten or twelve hours or more, say from one night to the next morning, when the pressure was removed, the papers and boards taken from the press and separated by removing the boards from the pile of combined boards and paper, and putting the boards on one side on one pile and making another pile of the printed papers. This was necessarily comparatively a slow process, inasmuch as with one press only as much printed paper as the press would hold when put between the boards could be pressed in about ten or twelve hours. so that where much work had to be done a number of such presses were necessary. It was also costly as to labor, because the sheets had to be placed between the boards and removed therefrom afterwards, which took much time, especially where, as in the case of fine work, only one sheet was placed between two boards, and

290 when this was done comparatively few sheets could be pressed at once, because the boards took up much more room than

the paper did, they being quite thick.

"By the process set forth in this patent the printed sheets are not allowed to remain in the press for any considerable length of time, but only long enough for the operator to tie up the bundle, when they are immediately removed, the entire process of putting the paper into the press, tying it up in the bundle, and removing it therefrom taking but a few minutes. * * * A large number of bundles may be pressed and tied up in the course of a day and left tied up betwe-n the boards with the pressure upon them as long as is thought necessary to smooth out the impressions produced by the printing press or until the signatures may be wanted by the binder to complete the operation of making the book for which the signatures are printed. The printed paper or signatures are thus allowed to remain for a considerable time tied up in bundles, which time may be from twenty-four hours to three or four days and may extend to a year or more, the longer the better, as it is upon the time in which the bundles remain tied up subject to pressure between the boards that the smoothness of the printed paper depends, the mere pressure produced by the press in the short time the paper remains in it having comparatively little effect upon the impression produced by the printing press. The pressure of the press and the mere tying up would produce but little effect if the signatures were immediately untied as soon as they were removed from the press, and the long-continued pressure after the bundle has left the press is therefore an essential part of the process and without which it would not be much of a success."

The witness proceeds at great length and with fulness and particularity to show the operation and the value of the Jones patent over and as compared with the pre-existing methods of accomplishing the objects of the patent, and he shows that the process and method of operation under the Jones patent is not only better than

the prior method of dry-pressing, but is a novel and valuable improvement in the art. The testimony of this witness is amply supported by the testimony of the expert witnesses Grier, De Vinne, Nicholson, Penicks, and Suydam, all witnesses of high and unquestioned qualification, well acquainted with the former state of the art of bookbinding and the appliances used, and quite familiar with the value and decided improvement in the art effected by the patent issued to Jones.

The defendant not only sought to throw doubt upon the question of the novelty of the invention of Jones, and thus to defeat the claims of his patent, but attempted to show, even conceding his invention, that neither of the claims in the patent was patentable, and that there was a want of substantial improvement upon the old or former methods or process of dry-pressing in the art of bookbinding; but the testimony to which we have already referred would seem to be ample to refute this contention on the part of the defendant.

The witness who testified in support of this contention of the defendant is Mr. Hood. He is a patent solicitor, but neither a bookbinder nor a printer, and only has such knowledge of those arts as he has gathered in a general way by observation and reading. He, however, expresses a very decided opinion against the novelty, usefulness, and patentability of Jones's inventions covered by the patent No. 204,741; but no other of the expert witnesses examined in the cause expresses any such opinion. Indeed, Mr. Hood himself, in attempting to analyze the several claims of the patent and to describe the scope and operation of them, does not very materially differ from them as to the conclusion at which he arrives.

There is nothing in the evidence that is sufficient to support the

third and fourth assignment of error by the defendant.

5 and 6. Under the fifth assignment of error it is urged that claim 4 of the patent is void because of ambiguity, and under the

30 - 96

sixth assignment of error it is contended that the single machine used by the defendant, in view of the preceding state 292 of the art, did not infringe either of the claims 1, 2, and 4.

We percieve no such ambiguity in claim 4 as to require it to be declared void for that cause. The purpose of that claim, as stated by Mr. Hood, is to provide for the combination with the press bed of two alternative forms of guides for centering the sheets in the press, or, as stated by expert Robertson, the two parts designated in the claim are substantially equivalent to each other, and either can be used for the purpose of supporting the signatures with equal

facility.

As to the question of infringement, the testimony in the case leaves no doubt on that subject. The infringement was of the construction of the press under claims 1, 2, and 4 and in the use of the process described in claim 5. The testimony of Jones, the patentee, and of several other witnesses clearly establish the fact of infringement, and though the press operated by the defendant was manufactured by and purchased from the Seybold company of manufacturers and he purchased and operated only a single press, still, if that press or machine was so constructed as to embrace and to be operated upon the essential principles of the press or machine covered by the patent issued to Jones, notwithstanding some change in the location, arrangement, and management of parts, there was an infringement, for which the party operating the machine would be responsible. Mere superficial dissimilarity in construction, which is most that is shown or that can be contended for in this case, will not protect against infringement; but the difference must be substantial rather than formal. Sessions vs. Romadka, 145 U. S., 29: National Cash Register Co. vs. Boston Cash Indicator & Record Co., 156 U. S., 502; Western Elec. Co. vs. Sperry Elec. Co., 18 U. S. App., In this case the proof is clear that the machine or press used by the defendant, obtained from the Seybold Manufacturing Co., was substantially the same as that secured by the patent to Jones,

and therefore such use was an infringement of that patent, and the defendant is responsible for that use as an infringer from the time that the press was commenced to be used or

operated by him to the time it was destroyed by fire.

7. In the view we have of this case, the seventh error assigned becomes immaterial, and we make no further reference thereto.

8. The only other question remaining for consideration is that relating to the measure of damages, gains, and profits and the principle upon which damages, gains, and profits in such case as the

present should be ascertained and assessed.

The auditor in his report states that he did not find in the cause evidence sufficient to enable him to assess damages to the complainants by reason of the infringement; but he has stated an account of gains, profits, and advantages derived by the defendant from the use of the machine and process' from September, 1893, to the 10th of February, 1895, when the press or machine was destroyed by fire. During all the time of the use of the machine and process the defendant was the public printer for the State of Pennsylvania, and

it was in the performance of the work of such public printer that the machine and process were used. The auditor ascertained and reported that the defendant had realized advantages in the use of the machine and process as savings in the cost of labor the sum of \$2,782.50, and as savings in waste of paper the sum of \$709.20, making a total saving of \$3,491.70, which he reported as the gains

and profits that accrued to the defendant.

The method of ascertainment adopted by the auditor to reach the result reported by him is supposed to be in accordance with settled authority, and especially the decision of the Supreme Court in Tilghman vs. Proctor, 125 U.S., 136. In that case it was held that upon a bill in equity for infringing a patent, if the defendant has gained an advantage by using the plaintiff's invention, that advantage, whether by way of gains or savings, is the measure of the profits to be accounted for, even if from other causes the business in which the invention was employed by the defendant did not result

in profits, and if the use of a patented process produced a definite saving in the cost of manufacture he must account to the patentee for the amount so saved; and in the case of McCreary rs. Penn. Canal Co., 141 U. S., 459, it was held that in a suit in equity for an infringement, in estimating the profits the defendant had made by the use of the plaintiff's invention, where the device was a mere improvement upon what was known before and was open to the defendant to use, the plaintiff was limited to such profits as had arisen from the use of the improvement over what the defendant might have made by the use of that or any other device without the use of the plaintiff's invention. These two cases, it would seem, furnished the auditor with the principles upon which he proceeded

in stating the account in this case.

It is certainly true that there is great difficulty in arriving at precise accuracy in stating an account of the savings, gains, and profits in such case as the present; but where the master or auditor has fully examined and collated the facts of the case and made careful deductions therefrom, as would seem to have been done in this case, and the court below, upon hearing, has ratified and confirmed the finding and account of the auditor, the reasonable presumption is that the conclusion reached is just and proper, and an appellate court will not be disposed to disturb that conclusion unless the evidence clearly requires it to be done. In this case we do not perceive wherein any injustice has been done the defendant by the findings and conclusion of the auditor. The allowance of interest on the amount of the assessment from the time of bringing in the report and account was manifestly right, and upon a full review of the whole case our opinion is that the decree appealed from must be affirmed, and it is so ordered. Decree affirmed.

295

Tuesday, February 6th, A. D. 1900.

CLARENCE M. Busch, Appellant,
vs.

Joshua W. Jones and The W. O.
Hickok Manufacturing Company.

No. 903. January Term, 1906

Appeal from the supreme court of the District of Columbia.

This cause came on to be heard on the transcript of record from the supreme court of the District of Columbia, and was argued by counsel. On consideration whereof it is now here ordered, adjudged, and decreed by this court that the decree of the said supreme court in this cause be, and the same is hereby, affirmed with costs.

Per Mr. CHIEF JUSTICE ALVEY.

February 6, 1900.

Tuesday, May 1st, A. D. 1900.

On motion of Mr. Charles E. Riordon, of counsel for the appellant in the above-entitled cause, it is ordered by the court that said appellant be allowed an appeal to the Supreme Court of the United States on giving bond in the sum of five hundred dollars.

296 In the Court of Appeals of the District of Columbia.

CLARENCE M. Busch, Appellant,
vs.

Joshua W. Jones and The W. O. Hickok
Manufacturing Company, Appellees.

No. 903. October Term,
1899.

Bond.

Know all men by these presents that we, Clarence M. Busch, the appellant above named, and the American Surety Company of New York, N. Y., and branch office at Washington, D. C., are held and firmly bound unto the above-named J. W. Jones and the W. O. Hickok Manufacturing Company in the sum of five hundred (\$500) dollars, to be paid to the said J. W. Jones and the W. O. Hickok Manufacturing Company; for the payment of which, well and truly to be made, we bind ourselves and each of us and our legal representatives, jointly and severally, by these presents.

Sealed with our seals and dated the eight day of June, 1900.
Whereas the above-named Clarence M. Busch has prosecuted an appeal to the Supreme Court of the United States of America to reverse the decree rendered in the above-entitled suit by the Court of

Appeals of the District of Columbia: Now, therefore, the condition of thi

Now, therefore, the condition of this obligation is such that if the above-named Clarence M. Busch shall pay all costs of

said appellees if he fail to make said appeal good, then this obligation shall be void; otherwise the same shall be and remain in full force and virtue.

CLARENCE M. BUSCH, By GEORGE J. MURRAY,

His Attorney.

Sealed and delivered in presence of— M. K. GUILFORD.

> AMERICAN SURETY COMPANY OF NEW YORK, By JNO. S. LOUD,

Resident Vice-President.

[Seal American Surety Co., N. Y.]

Attest: ADOLPH DAMMANN, Resident Ass't Secretary.

5 cents U.S. internal-revenue stamps.

Bond approved. R. H. ALVEY, Ch. Justice.

(Endorsed:) Court of Appeals, District of Columbia. Clarence M. Busch, appellant, vs. Joshua W. Jones and The W. O. Hickok Manufacturing Co., appellees. Bond on appeal to Sup. Court U. S. Court of Appeals, District of Columbia. Filed Jun- 13, 1900. Robert Willett, clerk.

298 United States of America, 88:

To Joshua W. Jones and the W. O. Hickok Manufacturing Company, Greeting:

You are hereby cited and admonished to be and appear at a Supreme Court of the United States, at Washington, within 30 days from the date hereof, pursuant to an order allowing an appeal, filed in the clerk's office of the Court of Appeals of the District of Columbia, wherein Clarence M. Busch is appellant and you are appelles, to show cause, if any there be, why the decree rendered against the appellant should not be corrected and why speedy justice should not be done to the parties in that behalf.

Witness the Honorable Richard H. Alvey, Chief Justice of the Court of Appeals of the District of Columbia, this thirteenth day of June,

in the year of our Lord one thousand nine hundred.

R. H. ALVEY, Chief Justice of the Court of Appeals of the District of Columbia.

Without waiving objections, service accepted this 15th day of June, 1900.

M. W. JACOBS, Attorney for Joshua W. Jones and the W. O. Hickok Mfg. Co. [Endorsed:] Court of Appeals, District of Columbia. Filed Jun-18, 1900. Robert Willett, clerk.

299 Court of Appeals of the District of Columbia.

I, Robert Willett, clerk of the Court of Appeals of the District of Columbia, do hereby certify that the foregoing printed and type-written pages, numbered from 1 to 298, inclusive, contain a true copy of the transcript of record and proceedings of said Court of Appeals in the case of Clarence M. Busch, appellant, vs. Joshua W. Jones and The W. O. Hickok Manufacturing Company, No. 903, January term, 1900, as the same remains upon the files and records of said Court of Appeals.

Seal Court of Appeals,
District of Columbia.

In testimony whereof I hereunto subscribe my name and affix the seal of said Court of Appeals, at the city of Washington, this 18 day of June, A. D. 1900.

ROBERT WILLETT, Clerk of the Court of Appeals of the District of Columbia.

Endorsed on cover: File No. 17,816. District of Columbia Court of Appeals. Term No., 96. Clarence M. Busch, appellant, es. Joshua W. Jones and The W. O. Hickok Manufacturing Company. Filed June 27, 1900.



Office Supreme Court U.S. FILED

By of cheerray for confident Market Medical.

James H. Market M

Supreme Court of the United States

OCTOBER TERM, 1901.

No. 96.


CLARENCE M. BUSCH, APPELLANT.

25.

JOSHUA W. JONES, ET AL., APPELLERS.

Brief for Appellant.

GEO. J. MURRAY, Counsel for Appellant



SUPREME COURT OF THE UNITED STATES.

OCTOBER TERM, 1901.

CLARENCE M. Busch, Appellant,

VS.

No. 96.

Joshua W. Jones and The W. O. Hickok Manufacturing Company, Appellees.

This appeal is brought here from a decision of the Court of Appeals for the District of Columbia affirming the decree of the Supreme Court of the District of Columbia in a suit brought by Joshua W. Jones and The W. O. Hickok Manufacturing Company against Clarence M. Busch, the appellant in this case.

The case was originally brought in the Supreme Court of the District of Columbia March, 1894, against Clarence M. Busch, a resident of the District of Columbia, for the use of a machine purchased from the manufacturer, The Seybold Machine Company, of Dayton, Ohio, which machine was used by the esaid Busch at Harrisburg, Pa., the said Busch being at the time the suit was brought the State Printer for the State of Pennsylvania.

The suit was brought by Jones, the patentee, and his exclusive licensee, The W. O. Hickok Manufacturing Company, upon two letters patent of the United States, the one dated June 11, 1878, which expired June 11, 1895, one year and three months after the suit was filed, and no motion for preliminary injunction had been made prior to the interlocutory decree, which was January 30, 1896 (R. pages 145, 146), more than eight months after the patent of June 11, 1878, had expired; and also upon letters patent dated the 26th day of May, 1891, granted to Jones and assigned to The W. O. Hickok Manufacturing Company, as alleged in the bill of complaint, prior to the time said patent was granted, but while the application for said patent was pending in the United States Patent Office, the application for said letters patent of May, 1891, having been filed July 26, 1889, and

the contract between Jones and The W. O. Hickok Manufacturing Company having been executed the 27th day of December.

1889 (R. p. 96).

Profert of this agreement, which was recorded in the United States Patent Office, was made in the bill of complaint, and by reference to this agreement, it appears that it gave an exclusive license to The Hickok Manufacturing Company under both of the patents in suit, six other patents and other applications then pending for improvements upon the inventions described in the first patent of June 11, 1878. By the terms of this agreement all the patents and processes of Jones, of whatever character. whether in patents already granted, in applications pending or in other improvements relating to the same subject matter, were assigned absolutely to The W. O. Hickok Manufacturing Company by Jones as the patentee, reserving only to Jones a royalty of 25 per cent. on the machines manufactured by The W. O. Hickok Manufacturing Company. There was no reservation whatever to Jones for any other royalty for his machines or for his process, excepting the 25 per cent. of the selling price of the machine at the time the contract was made.

Complainants closed their testimony July 27, 1895 (R. page 89), after the patent of June 11, 1878, had expired, and no motion was made for a preliminary injunction. The patent of May 26, 1891, not having been referred to or introduced in evidence, all claims under it were abandoned, and the case of complainants rested solely on patent No. 204,741, of June 11, 1878, which contained the process claim carried out, as claimed by the complainants, by the machine illustrated in said patent and covered

by claims 1, 2 and 4 thereof.

The interlocutory decree in the Supreme Court of the District of Columbia was entered February 11, 1896 (R. p. 146), eight months after the patent of June 11, 1878, had expired, and one year after the machine complained of as an infringement had been destroyed by fire (R. p. 179), the machine having actually been used but fifteen weeks. (Auditor's report, p. 154—Schedule A, R, p. 156).

The auditor's report was filed March 26, 1897 (R. p. 147), awarding \$3,491.70 as profits for the use of the machine and process during the period of fifteen weeks. (Schedule A, R.

p. 156.)

Exceptions to the auditor's report were filed April 8, 1897 (R. p. 157), and on December, 1898, motion was filed to vacate

the interlocutory decree so far as the fifth claim of the patent in suit was concerned, as the auditor had returned no profits or damages due to The Hickok Manufacturing Company by reason

of the purchase of the alleged infringing machine.

These exceptions and the motion to vacate were overruled on January 19, 1899, and the auditor's report ratified and confirmed, and amended final decree entered April 4, 1899. (R. pp. 158, 159.) From this final decree appeal was taken to the Court of Appeals for the District of Columbia, allowed, and exceptions filed April 19, 1899. (R. p. 160.)

The Court of Appeals of the District of Columbia, in an opinion by His Honor Judge Alvey (R. p. 223), affirmed the decision of the Supreme Court of the District of Columbia, Feb-

bruary 6, 1900. (R. p. 236.)

From this decision appeal was taken to this court, allowed May 1 and perfected June 13, 1900. (R. pp. 236-237.)

SPECIFICATION OF ERRORS RELIED UPON.

The decree of the lower court is alleged to be erroneous for substantially the same reasons given in the case appealed to the Court of Appeals of the District of Columbia, printed at page 160 of the record, and recited in the opinion of His Honor Judge Alvey (pp. 225 and 226 of the printed record), which are more briefly stated as follows:

1. The trial court, sitting as a court of equity, had no juris-

diction of the case.

(a) Because the bill of complaint, taken in connection with the contract or agreement published at page 96 of the record, of which profert was made, and with the answer of defendant, showed that complainant had a complete and adequate remedy at law.

(b) Because at the time of the hearing it appeared from the record that the only patent before the court had expired before the hearing, no motion for preliminary injunction having been made prior to the expiration of the patent, and defendant being a mere user of one machine, which machine was destroyed by fire before the case was brought to hearing.

That the patent in suit, so far as the fifth or process claim is concerned, is void, not only on its face, but in view of the evidence, because it is, as the evidence shows, but a mere

function of the machine.

3. That the patent is void for want of novelty by reason of anticipation by public and common use prior to any alleged invention of Jones, and also by reason of anticipation by the prior state of the art, as shown by the evidences of the witnesses and the patents and publications in evidence, and particularly by the process practiced on the Palmer press years before the application for the patent in suit was filed.

4. That the patent is void for want of invention, so far as the fifth claim is concerned, because the process had been in use and practiced without the use of any machine to assist in carrving out the alleged process long prior to any invention of

Jones.

5. That claim 4 of the patent is void for ambiguity.

6. That the patented machine used by defendant, in view of the state of the art preceding Jones' invention, did not infringe any claims of the patent in suit.

7. That the trial court erred in not granting the motion of defendant to vacate the interlocutory decree after the auditor had made his report, and in view of the evidence disclosed in the record and the evidence brought out before the auditor on

accounting.

8. That the trial court erred in overruling the exceptions to the auditor's report and account, and adopting the principles upon which the account was stated, and particularly because the account was based wholly and entirely upon supposed profits or savings which occurred in the printing office, and before the printed sheets were folded into signatures, whereas the patent only relates, so far as the fifth claim is concerned, to signatures after they have been printed, dried, folded and smashed.

9. Because the report of the auditor, the decree of the Supreme Court of the District of Columbia, and its affirmance by the Court of Appeals of the District of Columbia, are all based upon incompetent evidence and expert testimony relating to a supposed process not disclosed, referred to or even sug-

gested in the patent in suit.

10. Because the court erred in approving the report of the auditor and his method of comparison in ascertaining the profits returned, the comparison being between the improved hydraulic press of Jones, which was the subject of numerous patents to Jones subsequent to the patent in suit, and a process of removing type indentations from flat printed sheets, before folding, by what is known as the old ponderous process, not in use in any establishment for many years prior to the Jones invention, and not for a half century prior to the time of infringement, instead of between the structure shown in the Jones patent, the modern smasher and the process practiced on the Palmer press, set forth and fully described in prior publications, and particularly in the Dingman patent of October 20, 1863.

JURISDICTION.

The court, sitting as a court of equity, had no jurisdiction to order an injunction at the time the bill of complaint was filed, because the bill showed on its face that the complainants, Jones and The W. O. Hickok Manufacturing Company, had entered into an agreement, profert of which was made, whereby Jones gave the exclusive right under the patent in suit, and under all of his patents allowed and applications pending for improvements upon the same invention, to The W. O. Hickok Manufacturing Company, for a specified royalty upon each machine manufactured and sold by Jones' exclusive licensee, reserving no rights to Jones, the patentee, for either machine or process outside of the specified royalty, based upon the selling price of the machine, which included the alleged process covered by the fifth claim of the patent in suit. The grant (for it was a grant) in the agreement, profert of which was made, and which is printed at page 96 of the record, included not only the patent in suit, but numerous other patents specified in the agreement, which, being subsequent, could not, of course, include the process claim. There was, therefore, a complete and adequate remedy at law, whether the alleged infringing machine, or any number of them. contained any of the inventions in any of the patents granted subsequent to the patent in suit.

Jones was a mere nominal party to this suit, and entitled to simply 25 per cent at the time the contract was executed, or less if modified according to the terms of the contract. The Hickok Manufacturing Company were entitled simply to the profits it would have made had the defendant purchased the machine from it, instead of from a third party. This is the real conclusion drawn from the bill of complaint as filed, raised by the answer of the defendant, and confirmed by the testimony of Jones in his answer on page 218 of the record.

"XQ. 2. Had The Hickok Manufacturing Company sold the machine to Mr. Busch, instead of The Seybold

Machine Company, you would have had no claim against him for damages or profits, would you? "A. No."

The question, then, was simply a question of accounting at the time the bill of complaint was filed, so far as the patent of June 11, 1878, was concerned; and it is believed, also, so far as the later patent of May 26, 1891, was concerned, because that and others were included in the exclusive license or grant. But the later patent, having been dismissed from the suit by implication, the complainant not having introduced it in evidence. or taken any testimony in relation to it at the close of their testimony, the bill was evidently framed to avoid the question of jurisdiction. This is confirmed by the facts, inferred from the bill of complaint, and by the further fact that the patent had never been sustained by any court and no motion for preliminary injunction ever made. The patent had but a short time to run, and had actually expired before the testimony was closed. long before the case could be reached for hearing, and after the single machine which was sued for infringement had been destroyed by fire.

The question of jurisdiction, if not settled by the pleadings and the proofs taken thereunder, therefore, becomes a question of fact to be determined on the hearing. At the first hearing, upon which the interlocutory decree was entered, it clearly appeared that the court had no jurisdiction, for the reasons above stated; first, the only patent before the court had expired, no motion for preliminary injunction had been made before its expiration, and the single machine used by defendant had been destroyed by fire, and at the time the decree was entered the defendant had purchased and was using at the state bindery in Harrisburg, Pa., one of the complainant's improved signature presses. It was clearly the duty of the court to dismiss the bill before the interlocutory decree was entered.

Way vs. Way, 64 Ill., 406.

"Although the question is not raised by the pleadings or suggested by counsel, and where not apparent upon the face of the bill, or the bill is framed to avoid the point, if, looking at the proofs, it appears that the case is one for which there is a plain and adequate remedy at law, it is the duty of the Court to decline jurisdiction and dismiss the bill."

Dumont et al. vs. Fry et al., 12 Fed. Rep., 21, and cases cited, especially Lewis vs. Cook, 23 Wall., 466. Campbell vs. Ward, 12 Fed. Rep., 150.

McConnell vs. Prov. S. L. A. Soc., 69 Fed. Rep., 113.

Root vs. L. S. & M. S. Ry. Co., 105 U. S., 189.

Burdell vs. Comstock, 15 Fed. Rep., 395.

Davis vs. Smith, 19 Fed. Rep., 823.

Mershom vs. J. F. Pease Furnace Co., 24 Fed. Rep., 741.

Racine Cedar Co. vs. Joliet Wire Check Blower Co.,

27 Fed. Rep., 368.

The only question, therefore, to be determined is how much profit would the complainant have made had the defendant purchased from The Hickok Manufacturing Company the steam power press manufactured by it, or the Jones hand-power press from The Hickok Manufacturing Company, instead of purchasing the alleged infringing machine from The Sevbold Machine Company. The hand-power machine, which is printed in front of page of of the record, The Hickok Manufacturing Company sold for \$350.00, which machine, it is apparent, is a great improvement over the wooden machine represented in the patent sued on, and the Jones steam-power press printed on the preceding page, which The Hickok Manufacturing Company sold for \$500.00, was a great improvement over the Jones handpower press, which hand-power press, although a great improvement over the wooden press shown in the patent in suit, would not do the work defendant was required to do by his contract.

Jones' testimony, questions and answers 86, 87 and

88, R. pp. 218 and 219.

Miles' testimony, questions and answers 7 to 10, R.

p. 221.

Busch, cross-question and answer 27, page 181; re-direct questions and answers 44 and 45, page 184.

This is a much simpler case than that before His Honor Judge Blodgett in Campbell vs. Plano Mig. Co. et al., 24 Fed. Rep., 738.

In that case His Honor said the only question to be established was the number of machines to be accounted for, "and this can be established as readily and completely in a suit at law

as in a suit in equity."

Section 724, Revised Statutes, quotes the code of law with full power to compel the production of books and papers as evidence under all circumstances where they might be compelled to produce the same in chancery cases, and this power, the unquestioned right of plaintiff to examine all the agents and employees as witnesses, seems to give all the facilities required for a complete remedy at law.

Judge Blodgett gives the same interpretation to the decision of the Supreme Court in Roots vs. Railway Co., 105 U. S., 189, as has been given to it by nearly every court since the rendition of that decision, and states that the decision proceeds upon the ground that all patentees have an adequate remedy at law in suits against infringers, except in cases where there is a right to injunction as part of the relief sought, but in all cases where the only question is as to the amount of profits and damages, and if the complainant is not entitled to an injunction, the remedy is at law.

Whatever facts may have existed prior to that decision as to the right of the parties to sue in equity, they are fully discussed in the opinion and finally settled, and nearly all decisions (at least in patent cases) since that decision have followed it, and notably the decision above referred to in the 12 Fed. Rep.

An instructive case on this point is Spring vs. Domestic

Sewing Machine Company, 13 Fed. Rep., 446.

In that case an interlocutory decree had been entered and an order of reference to a master made for accounting, no objection having been taken to the bill or to the jurisdiction of the court. In view of the decision in Roots vs. Ry. Co., then just published, defendant's counsel moved for a rehearing on the ground of want of jurisdiction, just as defendant's counsel did in this case. The decree theretofore entered was opened and the bill dismissed.

To the same effect is Curry vs. McCauley et al., 11 Fed. Rep., 365. In that case the court dismissed the bill suc sponte. Complainant had a legal remedy when the suit was filed.

Cecil Nat'l Bank vs. Thurber et al., 59 Fed. Rep., 913.

In Whitehead, Trustee, vs. Entwhistle, 27 Fed. Rep., 778, a demurrer was sustained because complainant had an adequate remedy at law. Defendant was, therefore, under Section 723 R. S., and Article 7 of the Amendment to the Constitution of the United States, entitled to right of trial by jury.

Consolidated Middlings Purifier Co. vs. Wolf et al., 28 Fed. Rep., 814.

The question in the present case upon the bill of complaint, and the facts shown in the record, is: Can the complainants maintain their bill on the equity side of the court after the patent had expired, after the machine complained of as an infringement had been destroyed by fire, and no proof whatever that there was any continuing infringement intended or possible. It is elementary that a party who has a plain, adequate and complete remedy at law can not successfully invoke the jurisdiction of a court of equity.

Ross vs. City of Ft. Wayne, 58 Fed. Rep., 404.

It is plain from the record that the suit was not brought for injunction, but to evade the question for the purpose of bringing a suit in equity instead of at law.

In the opinion of the Court of Appeals affirming the decision of the Supreme Court of the District of Columbia, on pages 226, 227 and 228, several decisions are cited in support of the decision arrived at by the Court of Appeals of the District of Columbia. It is believed that not one of these decisions has any bearing upon this case.

The first decision relied upon is Clark vs. Wooster, 119 U. S., 322-325. The quotation from the opinion by His Honor Mr. Justice Bradley shows clearly that the facts in that case are wholly different from the facts in this case, and, while the case of Roots vs. Railway Co., 105 U. S., 189, is cited with approval, His Honor also recites the facts of that case which take it out of the ruling of Roots vs. The Railway Co., which facts are entirely different from the facts in this case. In that case the folding guides which were illegally procured while the patent was in force were still being used, and the prayer for injunction against the continuing infringement, still existing at the time the case was tried, was proper. These were the only facts that

took that case out of the ruling in Roots vs. Railway Co. In this case the facts were entirely different. Before the expiration of the patent, and before the hearing of the case, the single machine charged as an infringement was destroyed by fire. The right to an injunction ended before the patent expired, before the case came into the Supreme Court of the District of Columbia, and there was no right to an injunction, as none had been applied for during the life of the patent.

The next case cited is Beedle vs. Bennett, 122 U. S., 71. The quotation from the opinion in that case ought to be sufficient to defeat complainant's right, for the facts in this case are precisely what the court in that case states gives the party the right to a trial by jury in a case at law, as well settled by the decision of the Supreme Court in Roots vs. Railway Co., as the

following quotation will show:

"But it is clear that if the bill upon its face, or the evidence produced, gives rise to a fair presumption that the suit was instituted in equity merely to evade an action at law, the bill will not be entertained (Roots vs. Railway Co., 105 U. S., 189-211), for it is now a wellsettled principle that a bill in equity for a naked account of profits and damages against an infringer of a patent can not be maintained; that such relief ordinarily is incidental to some other equity; the right to enforce which gives to the patentee his standing in court, and that the most general ground for equity interposition is that which tends to insure to the patentee the enjoyment of his specific right by injunction against a continuance of the infringement. 105 U.S., 215, 216."

The next case cited by His Honor Judge Alvey (page 228) is the case of Mills Mfg. Co. vs. Whitehurst, 56 Fed. Rep., 589-That was not a well-considered case, but the facts in the case were that the patent was still in existence at the time the opinion was rendered, and the alleged infringer was continuing to use machines which the court found to be an infringement upon the patent, and there was no proof in the case that there was any established license fee granted by the patentee, either exclusively or otherwise, to the complainant. It is hardly necessary, however, to give much consideration to this case, because a petition for rehearing was granted, on application of

defendant, by the same judge who tried the case, which is reported in 60 Fed. Rep., 81. Upon proofs furnished on rehearing before the same judge, the petition for rehearing was sustained and the bill of complaint dismissed. (65 Fed. Rep., 996.) An appeal from this decision was taken by the complainant to the Circuit Court of Appeals for the Sixth Circuit, and was tried before Judges Taft, Lurton and Hammond, and in an opinion rendered by His Honor Judge Taft, the decree of the Circuit Court dismissing the bill of complaint was affirmed with costs. 72 Fed. Rep., 496.

The Court of Appeals also stated (page 228 of the record) that the principle upon which the decision of the Supreme Court of the District of Columbia was affirmed is laid down as clear law by the Supreme Court of the United States in the case of Birdsell vs. Shaliol, 112 U. S., 485-487. That case lays down no such law, although there are some facts in it which place the parties complainant in nearly the same position that the complainants are in this case.

In that case the patentee, like Jones in this case, had given an exclusive license for a specified territory to manufacture, use and sell machines covered by the patent. An infringer began to manufacture machines containing the patented inventions. The patentee sued the infringer without joining his exclusive On accounting he was adjudged to be entitled to recover the amount of his license fees (so much per machine), but without costs and without any right to injunction against He subsequently, as trustee for his licensee, brought a suit, practically for the benefit of his licensee, to enjoin the sale of the machines made in infringement of his licensee's right. As the court had in the prior suit determined that the patentee himself had no right in equity, the claim was made that the patentee had no right to bring a suit for the benefit of his licensee for an injunction and accounting for the profits the licensee would have made had the infringer purchased the machines from the licensee, instead of having manufactured The Supreme Court held in that case that the suit brought by the patentee for the benefit of his licensee to enjoin a continuing infringement during the life of the patent, and for profits made by the infringer by the manufacture and sale of the machines, less the royalty that had been recovered by the patentee, gave the licensee a standing in a court of equity.

But in that case, as in all other cases in which the decision

in Roots vs. The Railway Co. has been followed, it has been made to appear that the infringement was a continuing one, and the proper remedy against the continuance of the wrong was an

injunction. No such facts appear in this case.

In McDonald et al. vs. Miller, 84 Fed. Rep., 344, the same interpretation is given to Roots vs. Railway Co., Clark vs. Wooster, and Beedle vs. Bennett, as above contended for by appellant, His Honor Judge Seaman stating, in that case, that the formal right to an injunction, without the actual need or intention to exercise it, is not sufficient to give a court of equity jurisdiction.

In referring to Clark vs. Wooster, 119 U. S., 322, His

Honor says:

"The trial court having proceeded to a decree without objection by the defendant, it was held that jurisdiction appearing 'at the inception of the suit, even though upon a narrow ground'—namely, the present right to an injunction—retention of the bill, under the circumstances, was so far discretionary that the decree will not be reversed; but the opinion clearly recognizes the general doctrine as above indicated."

This case also cites Hayward vs. Andrews, 106 U. S., 672, which also gives the proper interpretation to Roots vs. Railway, and His Honor Justice Matthews, in rendering the opinion of the court, cites

Thompson vs. Railroad Co., 6 Wall., 134; Walker vs. Dreville, 12 Wall., 442; Morton vs. Morton, 99 U. S., 330; Hunt vs. Hollingsworth, 100 U. S., 103,

quoting from the opinion of Mr. Justice Davis in the case in 6 Wall.:

"The absence of a plain and adequate remedy at law is the only test of equity jurisdiction, and it is manifest that a resort to a Court of Chancery was not necessary to enable the railroad company to collect their debts."

In this case, like that, the complainants had a plain and adequate remedy at law, and the Supreme Court of the District of Columbia should have dismissed the bill.

PATENT IN SUIT.

The only patent that we need to consider is the patent of June 11, 1878, No. 204,741, and this will be considered regardless of the state of the art preceding the alleged invention of Jones, excepting only such public and common use as the court may take judicial notice of, and which was known to all persons skilled in the art prior to any alleged invention of Jones.

The title of the patent is "Bookbinders' Dry Press and Sheet Tie." In the specification the invention is stated to be an improvement in bookbinders' dry press and sheet tie, and it is stated that the invention is fully disclosed in the specification and accompanying drawings. The standard dictionaries describe a dry press as a press used in printing, in which sheets are pressed smooth. This is the definition given in the Standard Dictionary of the English Language, in Knight's Mechanical Dictionary and other well-known publications.

A smashing machine is defined in the dictionaries as "a heavy and quick press used by bookbinders to flatten and smooth and make solid the springy folds of books before they are sewed," which is practically the same definition given for a

dry press in the Standard Dictionary, to wit:

"Dry Press - In printing, a press for smoothing printed sheets."

The same dictionaries give:

"Press Boards — In printing, smooth and neatly jointed boards of wood, between which printed sheets are pressed in a standing press."

"Pressing Boards (2) — One of the smooth, jointed boards, of pine or cherry, used in standing presses."

The definition of signature in the dictionary is:

"Signature -- especially in bookbinding - a sheet after it has been folded and is ready to be gathered."

These are the technical terms used in the patent, and were well known many years before any alleged invention of the patentee Jones.

It was equally well known prior to the Jones invention that sheets of printed matter, after leaving the printing press, were dried and folded before they went to the bindery, where they were gathered into signatures, smashed and tied up in bundles, ready to be used when they were to be sewed and bound into books. There is no dispute, and can be none, so far as the above facts are concerned.

Looking now at the patent: What did Jones invent, as shown by the drawings, described in the specification and particularly referred to in the claims? Looking at the drawing, Fig. 1, it discloses a smashing machine on the right hand side. Connected to it on the left hand side is a press with a bundle of folded signatures in it ready for removal from the press. Fig. 2, as shown and described, is a perspective view of a bundle of sheets tied and ready for setting aside, and Figs. 3 and 4 are detail views of divided presser heads for the press, to permit the operator to pass his hand between the divided heads and tie the bundle before the pressure is removed.

The third paragraph states the object of the invention, which is, first, to furnish a bulk compressor device, to be used to prepare the matter properly before it is inserted in the dry press proper, thus saving time and repeated travel from the smasher to the dry press before the operation of tying. (Presumably as was done prior to the Jones improvement.) The second object of his invention is stated to be to furnish a dry press proper, in which the pressing parts or heads are divided or have ways through them to readily manipulate the twine to tie the bundles while they are still under pressure, in order to retain the force of the press after the bundles are removed.

The third object of his invention is to provide slots in the sides of the press, which correspond with the press heads, to pass the twine through and around the sides of the bundle while the pressure is on.

The fourth object is to provide an alternate arrangement to adjust the press trough to different sized bundles, and the fifth object of his invention is a new process for treating printed and folded sheets of paper in dry pressing, consisting of subjecting a collection of such sheets to pressure without the use of fuller boards, and, while under such pressure, tying them into compact bundles, with end boards thereon; then removing them immediately from the press and allowing them to remain tied sufficiently long to fix and complete the dry pressing. This is practically the language of the nith or process claim.

The fifth or process claim of the Jones patent, No. 204,741, in view of the specification and drawings, is misleading, and must be spelled out in order to determine exactly what it is,

but climinating the senseless statements and surplusage, it will read as follows:

The process herein described for treating folded printed sheets of paper, the same consisting of subjecting a collection of such folded and printed sheets to pressure and, while under pressure, tying them into compact bundles between end boards, in order that the said tied bundles may be removed immediately from the press and the pressure retained until the pressed signatures are desired for use.

It is believed the above is a fair reading of the claim.

In view of this statement, and public and common knowledge, regardless of what the anticipatory matter may disclose, or the testimony of experts, what is this patent?

In every baling press it is well known that the material, whatever it is, must be subjected to pressure. It is well known that bands, strings or ties are put around the bales to retain the pressure. It is well known that these bands can not be put around the bales while under pressure, unless there is some provision, in the pressure head and in the sides of the trough, box or other receptacle, to allow the bands to be passed around and tightened while the pressure is on, secured while the pressure is on, and removed from the press to retain the pressure.

The above facts were matters of common knowledge. It was also a matter of common knowledge that merchants or manufacture, in whatever branch of business engaged, folded packages or bundles, whether sheets of paper, dry goods, groceries, pictures or any other line of goods they dealt in, in compact bundles, putting such pressure on as could be done by hand, tying them in two or four ways, if desired, and allowing them to remain tied, to hold whatever pressure is put upon them, until the merchandise, goods or whatever it was, was desired to be used.

What did Jones invent, as disclosed by his patent? He did not invent a bulk compressor, dry press, standing press, or smasher. Whatever it may be called, it is the same machine. Although it is shown in his drawings and in his specification, he makes no claim for it, nor does he make claim for it as an element in any combination, excepting the process of the fifth claim. He did not invent that.

From his specification, he did not invent any new process for removing type indentations; none of his claims is to that, or refers to it, and it was well known long prior to the Jones invention, and it is obvious that if any type indentations are to be removed, they must be removed after the printed sheets have been dried, before the printed sheets are folded, especially under the modern practice, in use at the date of the infringement, by machine folding, which subjected the sheets to the action of rollers into which the sheets were driven and passed, and especially before they went to the smasher, which smoothed the sheets, drove the air out from between them, and the old smashers, used more than a half century ago, as shown in well-known publications, exerted a pressure of from fifty to eighty tons. All of this work was done long prior to the Jones invention, as disclosed in his patent, to wit: they were printed, dried, folded and smashed.

From the patent it would appear that the smasher was not connected with the bundling press, and the first object of the Jones invention was to connect the smasher with the bundling press, standing press, dry press, or whatever it may be called, that was used in book bindery work, so as to avoid the trouble and loss of time in traveling from the smasher to the bundling or tie press.

It then appears, upon the face of the patent, and in view of what was old and well known, that there was no novelty whatever disclosed in the Jones patent, excepting only the attachment of the dry press to the smasher, so far as the fifth claim is concerned, and nothing in the dry press or bundling press or sheet tie, whatever it may be called, shown at the left hand of Fig. 1, that had not been used in every old bundling or baling press ever used, to wit: compressing the material to be acted upon, tying the material in bundles while under pressure, removing the material from the press, allowing the ties to hold the pressure until it was desired to use the material, whether hay, cotton, wool, manure, tobacco or any other material that required baling to put it upon the market.

The structure disclosed in this patent involves no invention, in view of the well-known facts above stated. The case in favor of the patent is not so strong as that decided by the Supreme Court in King vs. Gallun, 109 U. S., 99, affirming the decision of His Honor Judge Drummond in King vs. Trostel et al., 16 O. G., 956 There was but one claim of the patent relied on in that case, and that was for the bale as a new article of manufacture. That the bale was new, so far as baling plastering hair was concerned, was not disputed, but the Supreme Court, speak-

ing by Mr. Justice Woods, held that it involved no invention, in view of the fact that it was well known that the packing of articles of commerce into small parcels for convenience in handling and retail sale, and tying them together into bundles for convenience in storage and transportation, is as common as any fact connected with the trade. The opinion cites, as matters of common knowledge, packages of wool, feathers and plug tobacco as having been treated in the same manner.

That the described process is merely a function of the machine, and therefore not a proper process claim under the ruling of this court in Risdon Locomotive Works vs. Medart. 158 U. S., 68; Westinghouse vs. Boyden Power Brake Company, 170 U. S., 537; the universal decisions of the Supreme Court, the United States Circuit Courts and the United States Circuit Courts of Appeals, since the rendition of that decision, seems almost too clear to require discussion, and is practically admitted in the decision of His Honor Judge Alvey, on page 228 of the record, unless there is some elemental action involved, and he finds that elemental action to be "tight cohesion under a high degree of pressure, effected by a special mechanical contrivance, and to produce new and beneficial results by such means or process."

Whatever the elemental means may be, or the chemical action (which, it is admitted, is not involved in the fifth claim), it must be a new discovery. Jones discovered nothing. It was well known that "tight cohesion under a high degree of pressure effected by a mechanical contrivance" would flatten out and smooth anything subjected to it. The patent admits that prior to the Jones invention this was done by what was termed the old ponderous process, and the pressure was retained ad libitum by allowing the article under pressure to remain in the press for the desired length of time. It was well known long prior to Jones' invention that this "tight cohesion" was produced in all baling processes, the tight cohesion of the press held by bands or ties while the material was under pressure, and the bale or bundle immediately removed from the press.

This case can not be brought within the decision of the United States Court in Cochrane vs. Deener, 94 U. S., 780; Tilghman vs. Proctor, 102 U. S., 707, or the telephone cases, 126 U. S., I.

The elemental action in Cochrane vs. Deener was utilizing the force of gravity to carry heavy substances down from an elevation, while passing a current of air through the whole mass to drive the lighter substances upwardly and separate the two,

and it was new with the patentee.

In Tilghman vs. Proctor, the new discovery was that, in subjecting fat mixed with water in a closed vessel to a temperature of four hundred to six hundred degrees, the chemical combination would be broken up and the glycerine, fatty acids and the water, when the temperature was reduced, would be held in mechanical combination and easily separated. The material underwent a change by both of these processes, and it mattered not by what mechanism the separation was effected.

In the telephone cases, the inventor employed a vibratory or undulatory current of electricity, which had never been applied before, in contradistinction to the merely intermittent or pulsatory current, and the apparatus for producing electrical undulations upon the wire, which apparatus had never been

employed before.

Under these decisions, any old machines might be employed to carry out the process, and still be an infringement upon the patents, because the result had never been produced. For instance, the machine or apparatus shown in the Cochrane patent was never used, but the old separating machines were employed, with improvements that accomplished a result that never was accomplished before. In Tilghman vs. Proctor, no infringer ever dreamed of using the machine or clumsy apparatus described in the Tilghman patent, but used a common kettle, with sufficient strength to resist the pressure put upon These old kettles and the reels, middlings purifiers and separators, when changed to produce the separation described in the patents in suit, were not infringements, because no old machine had ever produced the result. Jones' alleged process, if tight cohesion was the element he employs, was used in every baling press ever invented or used. It was used in the press involved in the suit above referred to - King vs. Gallun, 100 U. S., 99. It was also used in the Dedrick press of October 29, 1872, and June 2, 1874, both of which patents were long prior to the Jones invention, and the reissues of which were involved in Dedrick vs. Cassell et al., 9 Fed. Rep., 306.

This court can certainly take notice of its own decisions and the published opinions of the United States Circuit Court of Appeals, when the court's attention is directed to them, as matters of public and common knowledge. The court, refer-

ring to the Dedrick patents, on page 313, in describing the patent in that case, states:

"The language of the specification is 'the follower O, with tying grooves, is inserted in the press box in rear of the finished bale and forced along with it,' thus constituting a partition between the bales and facilitating the passage of the bands. In the original patent a single claim was founded on this, in the following words: '(10) The follower O, constructed with grooves on both sides, in combination with the bale-chamber,' etc."

We there have the press, the follower, or press heads, with tying grooves in them, and the press box, which is, of course, grooved to allow the bales to be tied while under pressure. In the reissue two claims were founded upon this single claim:

> "(6) The follower O, constructed with grooves on both sides for the ties, in combination with the balechamber," etc.

On page 315, in speaking of the claim of the reissue 8,296, the court say:

"On the reissue 8,296, the only claim involved is the following: 'the press or case provided with one or more apertures (0) for the purpose set forth.'"

No objection was found to this claim, because it was a useful improvement or addition, and with Dedrick it was new. As the court say in the next paragraph:

"It was very plainly described in the specification, and, although an occasional use of it only was then contemplated, the propriety of inserting it in the reissue can not be now questioned."

We have, therefore, in this press the follower, or head, provided with tying slots, and the case provided with one or more apertures to permit the tying bands to be passed around and hold the pressure of the press when the bale is removed. The

court in that case held the claim valid, because it was new with Dedrick. If it was new with Dedrick in 1872 or 1874, it can not be new with Jones in 1877, nor could he be entitled to a patent upon a process claim which was refused to Dedrick on a patent issued long before Jones' invention. The baling press was also described in Fox vs. Camp. 10 Fed. Rep., 675. The patent in that case was granted August 27, 1867, to Charles Brown, and was first before the Circuit Court for the Southern District of New York before His Honor Judge Wheeler, reported in 3 Fed. Rep., 898. In that case the validity of the patent was denied because the defendant, the licensee, had acquired a prior patent for the same process, in which the well-known process of baling hay was applied to other kinds of hay than short-cut hay. His Honor Judge Wheeler, on page 899, says:

"There is considerable doubt whether the patent, as between the owners and the public generally, is of any validity. Hay has long been baled, to the common knowledge of all. The whole invention in controversy consists in baling hay, cut short, in the same manner, etc."

It is evident that the appeal in this case would have been dismissed had defendants not been estopped from alleging the invalidity of the patent. But the case was sent to a master to take account of damages and profits, and the master in that case adopted the same rule as the auditor did in this case. It came before His Honor Judge Blatchford on exceptions to the master's report in the case above cited (10 Fed. Rep., 675), and the report was set aside.

The specification of errors herein assigned is believed to be in compliance with the rules of this court, but in referring to the evidence the same testimony may apply to several assignments. If the separate assignments were taken up in numerical order, it would cause unnecessary repetition. The testimony referred to next will necessarily apply generally to assignments 2, 3, 4 and 9, as that appears from the printed record, pages 222 to 235, to be the order in which the evidence was considered by the Circuit Court of Appeals for the District of Columbia.

REFERENCE TO EVIDENCE.

It is clear, from the opinion of the Court of Appeals of the District of Columbia, paragraph beginning near top of page 231, that said court erred in basing its decision upon incompetent testimony, particularly as specified in assignment No. 9.

The state of the art, as set out by Mr. Jones himself, the patentee, is quoted by the court from Jones' answer to XQ. 38, page 31. The concluding statement of this answer clearly shows that the old process referred to by Jones was, as he states, "This was all done before the folding of the sheets." And it was done upon flat sheets in the printing room and before the sheets reached the binder, while the Jones process, as described in his patent, has nothing to do with the sheets until after they are folded into signatures after they have been printed, dried, folded and smashed, and the press was not intended to be used on the flat sheets — cross-question and answer 56, page 34:

"XQ. 56. Is the press shown in your letters patent No. 204,741 capable of bundling and tying papers other than folded, printed signatures?

"A. It was not so intended. The limits of its capa-

bilities I am not prepared to say."

In Jones' answer to XQ. 40, page 32, he gives the same definition of dry press and dry pressing as is given by Nicholson in his work published in 1856, an abstract of which is given in the testimony of the witness Hood, record pages 102 and 103.

Jones admits in his testimony (page 200) that there is nothing in the patent referring to any advantages by omitting the drying process prior to the time the sheets were folded, although he admits that he discovered that the old, ponderous process, as it is termed, was not necessary in a modern printing press.

"XQ. 51. Is there anything said in the specification of the patent No. 204741, setting forth the advantage obtained by pressing the sheets of signatures without first subjecting them to the drying process, or any suggestion that the sheets could be so treated?

"A. I do not know that it does. There is a copy of it here, which is printed, and can be ascerained by reading the specification. If I had an expert patent attorney, as either yourself or Mr. Jacobs, if it is not

inserted, I presume it would have been, for I knew it to be a fact when I gave him the case, but, unfortunately, he was one of those gentlemen who work very slow — supposed he knew it all — and I, having very little, if any, experience in the taking out of patents, he had his own way of making the specification and claims."

"XQ. 52. Did you not discover the omission when he read the specification over before you signed and swore thereto?

"A. I can't say whether I did or not."

"XQ. 53. When did you discover it, if not then?

"A. I can't even fix that time; it may have been some time after I obtained the official letters patent."

See also XQ. 57.

This expert witness' attention is also called to the Dingman patent of October 20, 1863, printed at page 123 of the record, and also to the Palmer press, printed after the deposition of Harrison P. Hood, record page 118.

He practically declines to answer a plain question in relation to this Dingman patent; terms it a cotton press, and does not think it could be used in the shape of the drawing for the purpose of dry pressing printed sheets, or that the work could be accomplished on it; but he gives no reason, and in the next question (XQ. 63. page 211) he is asked:

"XQ.63. If a bundle of printed signatures were substituted for the ream of paper, and end boards were used, would the pressure be retained after the bundle was tied and removed?

"A. I do not think I should be called upon to bring out, or endeavor to do so, the new inventions on old patents such as these, neither am I here to testify to the inventions of others."

He is also asked if the Jones process could be practiced on the John Palmer press. His answer is, "Not as this cut shows."

[&]quot;XQ. 68. Why?

[&]quot;A. Because the head and back folds of the sheet

could not be placed and held in alignment. They would mash out when the pressure is applied."

In short, the difference he finds between the Palmer press and the process practiced on it, as testified to by the witnesses Schrank, McKee and Davis, printed at pages 164 to 173 of the record, and the Jones press or process, is that it is intended in the Palmer press to turn the signatures head and tail, as he terms it, that sufficient pressure could not be exerted upon it, and that two strings are used in the Palmer press, while only one was necessary in the Jones press and process; but the patent, as he admits (XQ. 74, page 215), says nothing about the amount of pressure to be applied, nor about which way the sheets should be turned before being put into the press, excepting that he claims the drawing might show that they were all placed one way; nor is there anything said in the patent about one, two or any number of strings being used, nor about the bundle being tied in one direction, as shown in the Dingman patent, or in two directions, as practiced on the Palmer press.

Jones is asked (XQ. 77, page 216) if the sheets were subjected to the action of a smasher before they were placed in the press, if the Palmer press would then make a compact bundle out of such smashed sheets, and he answers in the affirmative.

"Under those conditions, the sheets being smashed perfectly flat and soild, and the air displaced between the sheets, I think it would be capable to place such sheets in the Falmer press and tie them into bundles."

Before this answer was closed adjournment was had, and after adjournment witness desired to add to his answer. In this he describes practically the process that was gone through with in his patent.

> "The Palmer press is incapable of performing the work of making a compact bundle prior to the smashing."

The Jones patent shows that his bundle is smashed before being subjected to the press and sheet-tie proper. He says, further, "even then it would not be capable, because it has no side guides to even up the sheets. They would slip and quash out, smear and blur the printing. The guides in my press prevent this, and there are no guides in the Palmer press."

It is submitted that it would not be invention to add side guides to the Palmer press. It is also evident that, if it were material to consider the drawing, description and size of the parts as given by the witness, the Palmer press would be equally as powerful, if not more so, than the wooden hand press shown in the drawings of the Jones patent, but the process would be the same, and the machine would be the same, regardless of its size, as it is a problem for a mechanic and requires no invention to construct a machine adapted to the character of work it is intended to perform.

It will be noticed that the testimony of Jones quoted in the opinion, page 231, was given on the prima facie case, and the state of the art was not before him at the time he gave such testimony. He did not at that time know of the Dingman press and the other presses referred to by him in his subsequent testimony, nor did he know of the Palmer press or the work that had been done on it, and when he gave that testimony he was totally ignorant of what had been done in the art prior to his alleged invention, outside of the city of Harrisburg, where he resided.

The opinion (beginning last paragraph, page 231) quotes from the testimony of the expert Robertson. The testimony quoted from Robertson was also given before he had any knowledge of the state of the art as disclosed by the patents, and the subsequent evidence taken in relation to them before he knew anything of the Palmer press, and, indeed, before he knew anything that had taken place in the art of printing subsequent to the year 1862 — more than fifteen years prior to any alleged invention of Jones. See Robertson's testimony, conclusion of his answer to cross-question 16, page 43:

"About this time I became interested in sewing machines, and dropped the printing business for a time, but occasionally did a little work. The last time I worked as a journeyman printer was in 1862.

"XQ. 17. It was during the period, then, from 1850 to 1862 that you had occasion to observe the processes carried on in the art of bookbinding, was it?

[&]quot;A. It was."

(25)

"XQ. 26 (page 44). Did you ever have occasion to observe any such bundles of folded printed matter from 1862 to 1874?

"A. No, sir."

"XQ. 73 (page 51). In your consideration of claims 1, 2, 4 and 5 of the Jones patent, you have considered said claims in the light of Mr. Jones being a pioneer, have you not, both in the construction of the press and the process therein set forth?

"A. I have."

This witness Robertson is called in rebuttal, and the state of the art as disclosed by the patents (particularly the Dingman patent), and public use of the Palmer press, was placed before him, and he is candid enough to state that Jones is not a pioneer, and the Jones process and press were not broadly new, and, fairly considered, was anticipated or limited by the prior state of the art. In fact, that, in view of the state of the art, what Jones did did not amount to invention, unless other things not mentioned in the patent might be interpolated as part of the Jones invention.

Before referring to this expert's testimony, a brief description of the Dingman patent of October, 1863; the Palmer press, as described by the witnesses Schrank, McKee and Davis; the Cooley patent of October 16, 1806, and the Craig patent of July

4, 1865, will tend to clearness.

First, as to the Dingman patent (page 123 of the record): The inventor, in his preamble, states that he has

"invented a new and useful machine for combining and facilitating the operation of pressing and tying paper into reams or bundles, which I call the combination paper press and tie engine."

Then follows a description of the mechanism, giving the size and dimensions of the machine, and referring to the specification by the parts. Briefly, it is a machine composed of a frame having a platen to receive the paper, divided presser heads to compress the paper upon the platen, means for bringing the divided heads down on the bundle of paper by means of a hand or pilot wheel; and it is suggested at the top of page 124 that this pilot wheel may be substituted by a pulley, to be operated by the motive power of the mill through suitable gearing. It is also provided with a ratchet and pawl to hold the divided presser head and keep the paper under pressure while the operator passes the string around through the divided heads and ties the bundle to retain the pressure as long as desired, after which, "by a reverse movement of the hand wheel, the pawl being raised, the pressure is relieved and the paper removed."

The inventor Dingman, in describing the preceding state of the art upon which his invention was an improvement, in the first paragraph on page 125, describes what the witnesses Jones and Robertson, as quoted in the opinion of the Court, describe in more concise but substantially the same language.

It is to be noted from this that both in the old process and in the Dingman process the material to be operated upon was folded sheets. But the description goes further, and at the end of the specification describes the usual mode of tying paper in bundles at and prior to the date of Dingman's invention.

"The usual mode of tying paper is by passing a string, cord or twine around the ream, with a noose or loop, at the end through which the other end is passed, and then drawn upon with the hand until the loose ream or bundle is sufficiently compressed. This operation is laborious and tedious, requiring much time, requiring strong twine, and unavoidably draws the ream awry or the paper out of place."

Is there anything in the process of the fifth claim, aside from the mechanism described in the Jones patent, that is not fully described in the Dingman patent as having been practiced by hand prior to Dingman's invention in October, 1863?

> "The following, on the other hand, are some of the advantages I claim for my press and my mode of tying."

The inventor stated that at that time he had not only invented the press, but a method or process of tying, and, continuing, states that his invention consists:

"First. It combines in one machine both the press

and the tie table, and occupies much less space than the old press alone, and can be easily moved from place

to place to suit convenience.

"Second. It effects a great saving of time and labor, requiring no longer to take the paper from the finishing table, press, and tie it in this machine than it does to remove it from the ordinary press to the tie table alone. The tying process, with my press, instead of being laborious, is simple and easy, requiring comparatively light cord or twine, and leaves the ream perfectly square.

Third. The paper is pressed uniform in thickness, and no part of the ream can be moved out of place by the process of tying, since it is held firmly while this is

being done.

"Fourth. Ordinarily, now a full press of paper is made before any of it is pressed. With my machine it can be pressed about as fast as it is made, so that it need not lie loose about the mill and be wasted, as is often the case in the ordinary process.

"Fifth. Instead of requiring a man, as it does for the old process, effecting comparatively little work, a boy or even a girl is sufficient to press and tie with my machine, and does more work, and does it better."

What advantages are set forth in the testimony of Jones and Robertson, taken on the prima facie case, and quoted in the opinion of the court, or set forth in the Jones patent, that is not as fully and as clearly described in this Dingman patent, issued fourteen years before Jones made his application? It has the same divided head as the Jones patent for passing the arm through to tie the folded sheets while under pressure. It is contended, however, by the witnesses, that it only ties the bundles in one way, while by Jones' process they are tied in two That is not important, but if it were, we find in the Cooley patent the bundling press, having grooved platens for tying the bundle, while under pressure, in both ways. We do not find in this Cooley patent the divided heads or platens, as shown in the Jones patent, but we do find identically the same head as shown in the Seybold machine, in the Jones steam-power press, in the Jones hand press introduced by the complainants below, and in the Jones hydraulic press printed in the record between pages 30 and 91. But the string passed in one or two or a dozen ways makes no difference, because the clamp shown in complainant's exhibit, "Jones' Form of License," printed in front of page 89 of the record, is a plain mechanical equivalent for the strings or twine, and this is shown in the Craig patent of July 4, 1865. (R., page 131.)

Robertson's testimony (R., page 87), referring to the Craig

and Cooley patents:

"XQ. 49. Do you consider that the presser heads shown in the cut on the last page or back of complainants' exhibit, 'Cut of Jones' bundle or printed signatures,' to be a patentable improvement over the presser heads shown in the Jones patent in suit?

"A. I should hardly say so. It seems to me they are only mechanical equivalents of the device shown in

the Jones patent in suit for the same purpose.

"XQ. 50. Do you consider the adjustable clamp shown in Figs. 3, 6 and 7, on the first page of the exhibit above referred to, to be a patentable improvement over the string or chain ties shown in the other figures on the same sheet, and also in the Jones patent?

"A. So far as I can see, it is only an ordinary clamp, but it may contain some features in the detail of construction, not now apparent to me, which would render the same patentable. I do not consider that, considered simply as a substitute for the tie, would be an improvement over the cross-tie shown in Fig. 5, because, as all the pressure on the parts comes in the center of each one, there would be a tendency for the pressure of the paper to bend the parts outward at their ends, and therefore, for the purpose of removing indentations. I should consider it an inferior device to the cross-ties shown in Fig. 5, as the pressure on the parts is equal in all directions when the cross-tie is used.

"XQ. 51. Would your opinion be the same if two clamps were used, one near each end of the bundle?
"A. I think the pressure would be more equable under the circumstances, as there would not be the

same tendency to bend the board at the end.

"XO. 52. Would the employment of either one or

two of these clamps, instead of the cross-tie, be an evasion of the fifth claim of the Jones patent?

"A. I think not.

"XQ. 53. In the employment of either one or two of these clamps, it would not be necessary to have cross-grooves in the presser heads, would it?

"A. It would not.

"XQ. 55. The grooves in the patent (Cooley) and in the illustration referred to are the same shape in crosssection and at right angles to each other, are they not?

"A. They are, to both parts of the question.

"XQ. 56. And the slots in the sides and ends of the press box are arranged in line with the groove in the Cooley patent, are they not?

"A. They are.

"XQ. 57. In the Craig patent No. 48,523, there is shown in Fig. 3 a bale held compressed by two clamp ties, passing over boards at each end of the bale to hold the pressure of the press. Is there any substantial difference between the method of holding the pressure illustrated in the Craig patent and in Figs. 6 and 7 of complainants' exhibit 'Cut of Jones' bundle of printed signatures'?

"A. No, sir.

"XQ. 63 (page 88). Would it require any invention to change the ways in the Palmer press to the shape of the ways shown in the Cooley patent?

"A. It would not. But even then such ways would not be equivalent to the cross-ways of the Jones patent.

"XQ. 64. Not even if the circular openings were made large to pass the hand and arm of the operator through them?

"A. If they were made large enough to pass the hand and arm of the operator through them, they would then be practically the same as the cross-ways shown in the Jones patent."

In Robertson's testimony (pages 84 and 85), he states, in answer to XQ. 40, that it would not require invention to provide the Palmer press with back and side guides like the Kellogg patent; but, in answer to cross-questions 43 and 44, he considers the inclined position of the trough or bed and the cross-ways as

another advantage over what is shown in the Dingman patent. So far as the Dingman patent is concerned, the witness Robertson agrees with the witness Hood in his (Hood's) answer to XQ. 56, page 117 of the record.

Robertson considers the Dingman patent a pioneer.

"XQ. 45 (page 85). Do you consider claim 1 of the Dingman patent to refer to a process or specific mechanism?

"A. It seems to be a combination of the two; both process and mechanism. And somewhat similar claims to that in the Dingman patent, the courts have construed them to be for mechanism employed, if I recollect the decisions right.

"XQ. 40. The claim is informal, but considering it as a claim for the mechanism, as follows:

"'In a paper press and tying engine, the combination of a series of jaws, or corresponding upper and nether metallic plates, all disconnected, so that while the paper is being subjected to the required pressure it may be easily tied into reams or bundles,' would you consider the Jones press to contain such invention?

"A. If the broad construction usually given to pioneers in the art were given to this claim, I believe that the Jones press would come under that description; but it may be that, in view of the broad specific description of the parts contained in the claim, the courts would limit it to the construction shown in the drawings, which the Jones patent does not show.

"XQ. 47. Suppose it be limited to the specific elements of a claim like the following:

"'In a press and tying engine, the combination of the frame, the stationary bed plate consisting of a series of metallic plates disconnected from each other, the movable platen consisting of a series of metallic plates arranged opposite the metallic plates in the stationary bed, and means substantially such as shown to move the upper platen to or from the stationary bed for the purpose of compressing a bundle of sheets and holding the pressure while the bundle is tied,' would the Jones press contain such invention?

"A. I believe such a claim would cover the Jones machine as shown in his patent.

"XQ. 48. Assuming the first claim of the Dingman patent to be for the process, and removing the informalities, to read as follows:

"The process herein described for treating sheets of paper, the same consisting of subjecting a collection of such sheets to pressure and, while under such pressure, tving them into compact bundles, and then removing them immediately from the press,' would the practice of the Jones process, as it is described in the patent in suit, be within the terms of that claim?

"A. It would."

It is evident from this witness' testimony that, so far as the state of the art shows, Dingman was a pioneer, and the substituted claims which the witness was asked about are substantially the claims of the Dingman patent, only put in better shape; and if there was nothing prior, Dingman's broad generic claims would have been allowed if made.

Referring now to the Palmer press. The cut of the Palmer press is found after the testimony of the witness Hood, between pages 118 and 119 of the record, and the testimony of the practical bookbinders, Schrank, McKee and Davis, who knew of this public use of the press prior to 1874 - not only this press, but others of the same kind-begins at page 164 of the record. There is no dispute about this press having been in use prior to 1874, and it was still in the bindery and in use at the time the testimony of these witnesses was given.

Schrank, page 165:

"O. 5. Please state what means was employed by Mr. Palmer, or in his establishment, for pressing bundles or tving up signatures while you were in his employ.

"A. They had a press there with a screw in it of about an inch and a quarter, with blocks with slots in for the purpose of taking up the slack of strings after the pressure was applied.

"O. 6. State when that press, such as you have described, was first put in use by Mr. Palmer, if

you know.

"A. He had a press made when I was out of his employ, in the year 1873, but I had used the process on another press — that is, blocks — previous to that which I had seen in use at the place of Mr. George W. Storey, who carried on the process of folding books at the northwest corner of Third and Walnut streets, when I was about fifteen years of age. I was errand boy for John Palmer. I introduced it into Mr. Palmer's shop in 1863."

(The witness was sixty-three years of age when he gave

his deposition.)

"Q. 7. State how you came to introduce that press into the establishment of Mr. Palmer in 1863.

"A. I used it in tying up those signatures and bundles of books. I found I could not tie them tight with the process he had, and I proposed to him to have these blocks made that I had seen in use in Storey's place. I had them made about six by ten inches and one inch and a half thick, with a grooved slot in them, so that the slack of the twine could be taken up after the pressure had been applied, and the cause of it was that the bundles would be tight.

"Q. 8. Were those blocks used on the press the same or different from the one that was employed in 1873?

"A. They were used on a press called the Single-Screw Stewart Press, a press similar, only with heavier screws.

"Q. 9. How recently have you seen the press which you say was used by Mr. Palmer in 1873 or 1874?

"A. I think it was last Thursday, April 18, 1895, in Russell & Bates' bindery, 509 Locust street, Philadelphia.

"Q. 10. State whether it was in the same condition when you saw it last as in the year 1873 or 1874, and if

there were any changes, describe them.

"A. I think the cast-iron block was broken, and they are now and have been using one of the original blocks of wood.

"Q. 11. Please examine this sketch I hand you, and state what it represents.

"A. It represents the press that was used for that purpose.

"Q. 12, Do you notice any differences between the sketch and the press now at Russell & Bates' place, 509 Locust street?

"A. It is the same press which I have removed twice. I removed it first from the Wiler building into the Tatham building in 1874, and in 1880 we removed it into the annex of the Tatham building.

"Q. 13. What time was this press that was used at the Palmer bindery, and represented by this sketch as the Palmer press, fitted with iron blocks, as spoken about?

"A. About the year 1873, when he had it built.

"Q. 14. How are you enabled to state positively that this press was made in 1873, and moved into the Tat-

ham building in May, 1874?

- "A. I went back to Mr. Palmer's employ in February, 1874, and on the 19th of May he started to move the bindery to the Tatham building out of the Wiler building. On the afternoon of the 20th of May, in moving one of the presses, I slipped on the floor and fell, and cut my cheek, which gave me a black eye. On that night my mother died 20th of May, 1874. I had to go to the funeral with a black eye, which I did not like to do, but I had to do it.
- "Q. 15. How long after 1874 did you continue to work for Palmer?
- "A. I think in 1882 or 1883 he died, and then I worked for his widow up to 1888.
- "Q. 16. How extensively was this press used in the bindery while you were employed there?
- "A. It was employed for two or three days in the week, and then would stand idle for a day or so.
- "Q. 32. For what purpose were the books put into bundles in the Palmer establishment, as you have described?
- "A. For their preservation and to save space in storage until they went to be bound and delivered to the publishers, and they stored them in their storerooms. Among whom were the firms of T. & J. W. Johnson, law publishers, 535 Chestnut street; Messrs. Kay & Bros., on Sansom street, between Seventh and Eighth streets, on the south side; and then we stored

some for W. & O. H. Morrison, on the sixth floor of the Tatham building."

McKee's testimony (pages 170 to 172) is practically the same as Schrank's. He describes the press and process in his answer to Q. 4, as follows:

"It consists of a screw, and the platen is attached to the screw, and after the books are got between, papers are first laid on the bottom, and then a piece of pasteboard, and then the books are laid on top of this, and another piece of paper on the top; and then, if they could find old sides enough of old books that were torn from books - for instance, books that were sent just for being rebound - they were saved for this purpose and put on top of the paper. After placing these on the top, this block was placed on the top of that, and. the cords put through, and then they turned what I call the lever, but you call it the bar. As it neared the bundle it had to be guided by the hand, so as to bring it down - in bringing it down so they could bring it down square on the tops of the bundles. Then the pressure was put on - whatever pressure was deemed necessary - cords run through them tight, and then were tied at the ends. Whatever little slack there might be there as the pressure was taken - the pressure being taken off, the books would rise, leaving the bundle tightened."

The witness Davis (on page 173), who was a foreman for John F. Busch, bookbinder, and was working in the Tatham building, which was also occupied by John Palmer from 1872 to 1878, says:

"Q. 4. What, if any, means did Mr. Palmer have in his place for pressing and tying up signatures at the time he moved into the Tatham building, and during the time he was occupying rooms in that building?

"A. He had a standing press that worked with an iron bar with two arms on it. They would fill that press with a certain number of sheets, a board on top

and bottom, and tie the ropes around them two ways, and let up the press and take the sheets out.

"Q. 5. Describe the lower platen, upon which the pile of signatures rested, and the upper platen, which was brought down to compress the pile in that press?

"A. I could not do that; I never knew it.

"Q. 6. How did they get the strings around the pile to tie up the bundles?

"A. I never examined the machine at all.

"Q. 7. But you do know that the signatures were put in the press and the platen brought down to compress the pile of signatures, and then strings tied around the pile to hold it compressed when the upper platen was withdrawn, do you not?

"A. I do.

"Q. 8. How recently have you seen that machine? "A. I have not seen it since they moved out of the

building. It was there all the time Mr. Palmer and Mr. Busch occupied the building.

"Q. 9. Do you think you would recognize the machine, or a drawing of it, if you were to see it now?

"A. Well, I think I would.

"Q. 10. I now hand you a sketch, marked 'Exhibit of Palmer Press.' Will you please examine that and state whether it is similar to or differs from the press used by Mr. Palmer at the time when he was in the Tatham building?

"A. Well, the standing of the press, it seems to me, is about as his was, and the mode of screwing down is exactly the same, but the blocks, top and bottom, I

could not say anything about.

"Q. 11. Do you know what the purpose of the slots of the top and bottom blocks in a press of this kind were used for?"

"A. To put a rope through for tying the bundle. It could not be tied any other way unless the slot was there.

"Q. 12. You saw the press of Mr. Palmer used while he was in the Tatham building, did you not?

"A. I did. We had to pass through his room to go to the elevator; he had a sawing-out machine between our door and this press; nearly every day I had to pass

through there to go to the elevator, and saw a man tying up sheets there, and I would see the boy take the sheets from the press and take them to the sixth floor,

"Q. 13. These were tied up while the bundles were in the press, were they not?

"A. They were.

"Q. 14. And you say that they could not be tied up unless the cross-slots were in the upper and lower blocks. Did you notice, when the bundles were to be removed to be carried to the sixth story, whether these blocks had cross-slots in them or not?

"A. That was my opinion; I did not notice it.

"Q. 15. Have you seen a press for tying up signatures, since the time you moved out of the Tatham building, which had blocks between which the bundles were compressed, which blocks are provided with cross-slots like these in the sketch shown you?

"A. I have not.

"Q. 16. Have you not one in your own establishment, with the same kind of blocks for tying up signatures, which was made under your order?

"A. I have a wooden one, made under my order, which has but one slot - that is crosswise of the sheet

- and ties but one way with one rope.

"Q. 17. What suggested the idea to you of making that press with the slotted blocks and single cords for tving up bundles?

"A. I had the idea that we could not tie the rope sufficiently tight unless there was a slot in the block

to let it slide through.

"Q. 18. Did you get that idea from the press you saw at the Palmer place, which you say strings were drawn through and tied tightly after the bundles had been compressed?

"A. Never did; never thought anything about his

press.

"XQ. 22. For what purpose was the press concerning which you have testified used in the Palmer bindery?

"A. Used for tying up folded sheets."

"XQ. 30. The press in the Palmer bindery was used

merely for bundling gathered books for the purpose of

storage, was it not?

"A. I could not say they could bundle gathered sheets as well as books, whether they were all one signature or gathered books, it is all the one thing; I never examined the work that was doing in the press, whether they were bundles of signatures only, or whether they were gathered books."

"RDQ. 33. Can you give a brief description of the manner employed by the workmen who worked on this press in Mr. Palmer's place, to place the sheets in position in the press, tie the bundles and remove the tied

bundles from the press?

"A. Well, I can give you a description of the way in which we do it. We take the sheets from the folding machine, count them off in twenty-five, and put six twenty-fives in the press, and then put the pressure on, tie the rope, take the pressure off, and take the bundle out. It is the same way he did them at that time, only they had hand folding; but that was the same principle exactly.

"Q. 34. Were the strings that tied the bundles placed in position for tying before the pressure was put on in

both cases?

"A. They are in our case.

"Q. 35. How was it in the Palmer case?

"A. I could not say; I never noticed; I could guess at it; there is one thing certain, they could not put the string on after the pressure is on.

"Q. 36. But you know the bundles were tied in the Palmer press before the pressure was taken off, do you not?

"A. They certainly were, as that is the object of the press — to make a bundle as compact as possible.

"Q. 37. Then, as I understand you, it would be impossible to place the string and tie the bundles unless the top and bottom blocks were grooved, as shown in this sketch? (Palmer press.)

"A I think it would be.

The testimony of Jones and Robertson, after they knew of the Palmer press, clearly shows that even these experts recognized that the Jones patent was not by any means a pioneer invention, and that the Palmer press and process, as practiced on it, differed in no essential features, involving invention, from the device shown, described and claimed in the Jones patent.

Jones' testimony (page 212):

"XQ. 67. Could the Jones process be practiced on the John Palmer press, a cut of which is shown at page 52 of defendant's record?

"A. Not as this cut shows.

"XQ. 68. Why?

"A. Because the head and back folds of the sheets could not be placed and held in alignment; they would

squash out when the pressure is applied.

"XQ. 69. You examined that machine; heard the testimony of the three witnesses, Schrank, McKee and Davis, as to its use for twenty years at the shop of John Palmer and his successor at Philadelphia, which use was described particularly in answer 22, on page 13 of defendant's record, by the witness Schrank. Please read that answer and tell us what step in the Jones process is omitted in the use described in that answer, so far as the fifth claim is concerned, or the use of the Jones press is concerned.

"A. As I said before, that any press which was so constructed that the sheets could be placed all one way. the process could be accomplished, if there were means for the retaining of the pressure, for tying up the bundles, and thereby retaining the pressure by means of the tie, provided rigid end boards were used to distribute the pressure over the entire surface of the bundle. The operation, according to this answer to question 22, varies considerably from that in my He says, first, in using it, the strings were laid in the bottom block or platen. In my process the first thing that is done is putting in a rigid end board. Schrank says, 'A piece of paper laid on top of the string, a piece of pasteboard laid on top of the paper.' In my machine the sheets are filled in the trough above the end board. Schrank says the gathered books or signatures piled up in bundles of ten, and a piece of pasteboard on top, and a heavy paper on top again.

The string was then brought over the top of the pile, the top block was then screwed down and the pressure The slack of the string was then taken up, and the bundle tied and removed. In the Jones process, after the sheets are filled into the trough an end board is then placed at the top of the sheets, pressure applied, and the cords passed around the sheets and tied, then removed from the press. tions dispensed with in the Jones process are the laving of the strings in the bottom block, the placing of a piece of paper, the placing of pasteboard on top, and a heavy piece of paper. These are not done in the Jones. I can't say that, as far as the operation is concerned. I can see any steps that are omitted, as he describes it. There are other parts of his testimony; if I remember correctly, he says the sheets or books were reversed. head and tail. If I am correct, it would not accomplish the process."

The witness evidently dodges a square answer to the questions put to him, pointing out, through his deposition, utterly immaterial differences between his process and the process described by the witnesses who testified as to the Palmer press, which differences are not set out in his patent. The following is an example:

"XQ. 76. The question was why a collection of printed sheets, subjected to pressure in the Palmer press, and while under such pressure tied into bundles with end boards, and then removing them from the press, would not make a compact bundle, while subjecting printed sheets of paper to precisely the same operation in a Jones press would make a compact bundle?

"A. The Palmer press is incapable of making a compact bundle, by reason that you can not place the sheets in that press in such a way as to make a compact bundle. The only way you could make a bundle of folded sheets in that press was by reversing the sheets in bunches alternately, and the edges would project. Bundles with projecting edges would not, in the sense that I use the term in my process, be compact bundles. "XO. 77. You assume that the Palmer sheets or sig-

natures were placed in the press as they came from the folder. Suppose they were subjected to the action of a smasher before they were placed in the press, would the Palmer press then make a compact bundle out of

such smashed sheets?

"A. Under those conditions, the sheets being smashed perfectly flat and solid, and the air displaced between the sheets, I think it would be capable to place such sheets in the Palmer press and tie them into bundles; but the pressure would not have been sufficient to keep the pressure so retained for any length of time, especially in large editions, where they have to be stored until the completion of the work. The bundles would become loose by reason of the light pressure which could be exerted by the Palmer press on them before tying. The bundles would fall apart and sheets become scattered over the floor, and many wasted in this way by dust, soiling and crumpling."

It will be seen from this witness' testimony that the only difference he claims between his process, as he understand it (but not set out in his patent), and the Palmer press, is that it would be difficult to get pressure enough on the Palmer press to make bundles as compact as they could be made on the Jones steam-power or hydraulic press. It his assumption be right, it would not aid his patent, either for the process or for the machine, as covered by his claims.

The witness Robertson refers to the Palmer press (page 83)

as follows:

"XQ. 38. If the bulk of signatures, after being compressed in the smasher or bulk compressor shown in the Jones patent, were placed between the platens of a vertical press, and the platens brought together, do you think the type indentations would be removed from the signatures if the pressure was left on long enough?

"A. If the platens were brought together with sufficient force, and the pressure retained long enough, I see no reason why the type indentations would not be

removed.

"XQ. 39. Well, if the same bundle were put in the Palmer press, and pressure applied and the bundle tied to retain the pressure, why wouldn't the type indentations be removed if the bundles remained tied long

enough?

"A. If sufficient pressure could be produced on the Palmer press, the bundle inclosed in proper end boards, and the bundles tied and kept tied long enough, I believe the type indentations would be removed; but, at the same time, there would most probably be imperfections in the bundle of signatures so pressed, inasmuch as it would be very difficult to keep all the folded edges of the sheets in line, and the result would be that some of the folded edges would overlap the folded edges of the others, and thus the sheets would be imperfectly pressed, although the indentations might possibly be removed if great care were exercised in setting the bundle of signatures in the press."

In answer to XQ. 40, the witness admits the process might be practiced on the Palmer press, but not commercially practical.

"XQ. 41. By 'commercially practical' I suppose you mean that the process carried out on the Palmer press, or on the other presses you have referred to, could not be economically carried out. Am I right?

"A. Generally speaking, that is the way I wish to be

understood.

"XQ. 59 (page 87). The Palmer device, as represented by respondent's exhibit 'Sketch of Palmer Press,' is a bookbinder's press and sheet-tie, having compressing heads constructed with cross-ways centrally arranged through them, for the purpose of tying bundles of folded signatures while under pressure, is it not?

"A. Broadly speaking, that is correct, but not in the sense of the first claim of the Jones patent in suit. The claim is to the special 'cross-ways L2 L2,' constructed to — as stated in about the middle of the first column of page 1 of the specification, 'afforded access through them to readily insert and manipulate the twine, and to tie the bundles of paper while held compressed, thus

securing the bundle together by a powerful tie.' Such cross-ways are not shown in the Palmer press.

"XQ. 63. Would it require any invention to change the ways in the Palmer press to the shape of the ways shown in the Cooley patent?

"A. It would not; but even then such ways would not be the equivalents of the cross-ways of the Jones patent.

"XQ. 64. Not even if the circular openings were made large enough to pass the hand and arm of the operator through them?

"A. If they were made large enough to pass the hand and arm of the operator through them, they would then be the same, practically, as the cross-ways in the Jones patent."

It appears from the above that, if Jones made any invention, it is not disclosed in his specification in the patent in suit, in such clear and exact terms as to enable a mechanic skilled in the art to make and use the same.

It is unintelligible to even the skilled experts called on behalf of complainants. A patent is a contract between the inventor and the public by which the inventor, in consideration of the exclusive use of the invention, secured to him for a limited time, confers upon the public a knowledge of the invention during that period, and an unrestricted right to use it after that period has expired.

The specification is the instrument in which the terms of these mutual considerations and terms are declared, and on its completeness and accuracy depend the validity and the value of the contract itself. Its object is two-fold: First, to place the invention fully within the knowledge of the public; second, to find the exact limits of that exclusive use which the public is advised the patent has undertaken to protect. That is the object and purpose of the specification.

Robinson on Patents, Sec. 481, and cases there cited.

This proposition has been so well settled that it is hardly necessary to cite a great number of authorities in support of it.

The Supreme Court, in Merrill vs. Yeomans, 94 U. S., 568,

should be sufficient. The Supreme Court in that case, speaking by Mr. Justice Miller, says:

"A developed and improved condition of the patent law and of the principles which govern the exclusive right conferred by it, leaves no excuse for ambiguous language or vague descriptions. The public should not be deprived of rights supposed to belong to it without being told what it is that limits these rights. The genius of the inventor constantly making improvements in existing patents, the process which gives to the patent system its greatest value, should not be restrained by vague and indefinite descriptions of claims in existing patents, from the salutary and necessary right of improving on that which has already been invented. It seems to us that nothing can be more just and fair, both to the patentee and to the public, than that the former should understand and correctly describe just what he has invented, and for what he claims a patent."

In the case at bar the complainants' experts even, and the inventor Jones himself, do not concur as to what Jones invented

and disclosed in his patent 204,741.

The inventor Jones, in his testimony already quoted, admits that his actual invention is not disclosed in his specification; that he discovered the omission afterwards: did not reissue his patent when he discovered it, because he was informed that a reissue patent was weaker than the original patent. Acting on this advice he constructed new machines, which embodied his actual invention, to-wit: the steam power press and the hydraulic press, for which he obtained letters patent subsequent to the date of the patent in suit, and among those patents was the one granted for the hydraulic press about which the witnesses. Jones. Suvdam, Penicks and others, testified, and which was dated March 4, 1870, No. 212,977; No. 219,734, dated September 16, 1879; No. 223,355, January 6, 1880; No. 224,696, February 17. 1880; No. 227,197, September 27, 1881, and reissue 9598, March, 1881 (see contract, page 96 of the record), and also patent No. 452,898, which was sued upon, which is dated May 26, 1891, the application for which was pending on the 27th day of December, 1889, when the contract between Jones and The W. O. Hickok Manufacturing Company was executed. Paragraph 5,

bill of complaint, page 3 of the record.

The suit, so far as the latter patent is concerned, having been abandoned when complainants' testimony was closed, it can not be considered, but the testimony of all the witnesses on behalf of complainants, in considering the Jones invention, have in mind the later improvements, and the effort of appellees' counsel has been to direct their attention to the Jones invention as disclosed in his later patents, instead of confining their testimony to the patent No. 204,741.

The expert Robertson, in his testimony on prima facie case, gives what he understands to be the invention of Jones at the time he made his application for the patent in suit. On page 37 he considers one improved feature of the Jones invention arranging the sheets in relation to each other, so that the Jones sheets when folded have the convex impressions of one-half of the sheet brought in contact with the convex side of the other half of the sheet by the act of folding the sheet in two. He apologizes in the second paragraph of his answer on page 37 for the preceding portion of his answer by stating:

"I have given at some length what I consider the main features of difference between the old and new processes, because in my opinion the process is one that is not easily understood at first, and very few would be likely to understand it unless the essential differences between it and the old processes were pointed out."

Now, it is submitted that, under this statement alone, the specification is vague and uncertain, because there is nothing said in the specification about how the sheets should be folded; in fact, the specification, as the ordinary skilled mechanic would understand it, has nothing to do with the folding, or any step, prior to the printing, drying, folding and smashing. The experts Penicks and Suydam seem to have read the specification and understood it as the expert Robertson understood it, but the inventor Jones does not agree with them.

"XQ. 56 (page 210). Throughout the testimony a good deal has been said about the advantages derived from your supposed invention, from the fact of the type indentations being concaved or convexed, whatever that may mean. Is there anything said in the patent about that?

"A. No; neither do I claim that they are produced by my process."

They all rely upon the Jones process, as disclosed in his patent in suit, for removing type indentations. There is nothing in the patent about this, nothing in the claims, and Jones himself, in answer to XQ. 57 (page 210), does not claim there is, unless it may be imported into it by the term "dry pressing."

The evidence just quoted bears also on the specification of

errors 8 and 10.

It could hardly be expected that even a skilled mechanic would know how to produce a practical operative device from the specification, drawings and claims of the Jones patent which would include the Seybold patented press and sheet-tie, or to construct a machine or device that would accomplish any beneficial result.

Attention has been called before to the fact that there never was a machine, excepting perhaps an experimental wooden machine, made like the drawings of the Jones patent in suit. This was found impracticable and thrown aside, and the Jones hydraulic press, about which all the witnesses have testified, put up in the state bindery at Harrisburg, Pa., before the date of the Jones patent in suit. And, as before stated, this hydraulic machine, and all the improvements put upon it, were covered by subsequent patents not involved in this suit. The auditor, the Supreme Court of the District of Columbia and the Court of Appeals of the District of Columbia all seem to have considered that the Jones invention was the hydraulic press about which Jones and all his witnesses testified throughout the whole of the suit. The testimony of the expert witnesses referred to in the opinion (R., pages 223-231) is as follows:

The witness Suydam, in his direct testimony (Q. 6, page 188), in correcting his answer after adjournment, makes his

answer 6 read:

"It was in the fall of 1877 the first machine made and used was at the state bindery, of which I then was foreman."

In his answer to XQ. 49 (page 191), he describes that

machine, and that answer describes the Jones hydraulic press which was in use at the state bindery in the fall of 1877, and was used by Busch after the Seybold machine had been destroyed by fire and Busch had leased or purchased the state bindery.

"XQ. 51. Did you ever see any other kind of machine than the one described in the preceding answer that was said to be made under the Jones patent?

"A. I saw several that were made under the J. W.

Jones patent

"XQ. 52. Were they the same or different from the one you have just described?

"A. Practically the same, except an experimental machine made of wood, which, I believe, led to the invention of the present hydraulic machine."

The expert Robertson, in the concluding part of his answer to direct question 8, on page 40, states:

> "I should imagine that the model or press from which the drawing of the Jones press was made had a wooden bed, and was, therefore, more convenient to make it with a slot instead of open spaces shown in the model," etc.

That is exactly what the drawing does show.

The testimony of the expert witness Thomas B. Penicks is much relied upon by the complainants (appellees here), and it appears that he never heard of or knew any other Jones press than the hydraulic press introduced by the witness De Vinne, illustrated between pages 90 and 91 of the record. There are three letters of Mr. Penicks introduced in evidence. The first one, dated February 25, 1879, printed at page 90, commences:

"Your note of the 23d inst., asking my opinion of the advantages and value of J. W. Jones' patent hydraulic printers' and binders' pressing machine is at hand.

"I am pleased to have the opportunity of bearing testimony to the worth of these valuable machines. The three octavo and one quarto machines have been in operation several months." * * *

This brings the sale by Jones to the government printing office back to the fall of 1878.

There is another letter, dated February 5, 1880, printed on the same page of the record, referring again to the hydraulic press, and to nothing else. A third letter of Penicks is printed on page 91, dated August 3, 1886. It states:

"Dear Sir:—The hydraulic pressing machines of J. W. Jones, of Harrisburg, Pa., were introduced in this office in the year 1878."

The testimony of the witness De Vinne is also to the advantages of the use of the Jones hydraulic press.

The absurdity of comparing the savings made by this press and the numerous other presses of Jones, for which he had obtained subsequent patents, is clearly apparent, and particularly in comparing the advantages of the Jones hydraulic press and the Seybold patented press (which were clearly improvements over the Jones hydraulic press, or Seybold could not have obtained his patents) with an old method or process, used fifteen or twenty years before lones or even Dingman, whose patent was granted October 20, 1863, had improved upon the old processes, instead of comparing the advantages that might be obtained by the use of the Jones invention as disclosed in his patent, by any means which was free to the defendant to use; as, for instance, the Palmer press, the other presses testified to by the witnesses Schrank and Davis prior to the date of the Palmer press, the Dingman patent and the old processes of tying by hand without the use of any press, as testified to by all of complainants' witnesses.

It appears from the record and from the testimony of complainants' witness Miles, chief clerk of The W. O. Hickok Manufacturing Company, that the hand-power press manufactured by The W. O. Hickok Manufacturing Company, printed in front of page 91 of the record, sold for \$350.00. This is an iron machine, iron frame, solid heads like the ones shown in the hydraulic machine and in the Jones steam-power press, and also in patents prior to any invention by Jones, and it is evidently a much stronger and more substantial machine, with these additional improvements upon it, than the duplex machine illustrated

in the Jones patent here in suit; and yet the complainant Jones, in his answer to Q. 88 (page 219), says:

"I question whether his (Busch's) work could be done on two such hand machines."

It appears from the testimony before the auditor and the auditor's report (Schedule A, page 156), that with the Seybold press sued as an infringement Busch did his work with one machine and with the labor of one boy one-fifth of the time,

When it is taken into consideration again that there was no testimony before the auditor that any profit would have been made had The Hickok Manufacturing Company sold one of their steam-power presses to Busch, instead of his having bought his press from The Seybold Machine Company, there is certainly no basis for even nominal damages.

Jones could be entitled to no damages or profits. He had never received a dollar of royalty for the use of his process, never asked a dollar of royalty, nor is it proven what royalty he received, if any, for the sale of his machines by The W. O. Hickok Manufacturing Company under all his patents at the date of the use of the Seybold machine by Busch.

Jones' testimony (page 218):

"XQ. 82. Had The Hickok Manufacturing Company sold the machine to Mr. Busch instead of The Seybold Machine Company, you would have had no claim against him for damages or profits, would you? "A. No."

Assuming that all the witnesses produced by complainants were honest, that the Supreme Court of the District of Columbia and the Court of Appeals for the District of Columbia believed they were, and acted upon the assumption that they were, it is perfectly clear that complainants below (appellees here) so shaped the case and the Jones patent 204,741 that all of these parties believed (and it is fair to assume that they had examined the said patent) that the actual invention of Jones involved in this suit was the Jones hydraulic press and the other features shown in the cuts of the Jones hydraulic press, the Jones steampower press and the Jones hand press, illustrated in the exhibits introduced in evidence, which were subjects of subsequent appli-

IUI

cations and subsequent patents, instead of the Jones patent 204,741 here in suit.

Is there any better evidence that the drawings and specification of the patent here in suit are vague and indefinite, and do not comply with the statute which requires that the invention must be so fully and accurately described that the public and those skilled in the art to which the invention relates may know exactly the limits of patentee's claims?

As before pointed out, it is clear that the Dingman patent discloses everything shown, described and claimed in the Jones patent in suit; and, although the claims may be considered informal, they would be fairly construed, if Dingman was a pioneer (and he certainly was so far as the Jones patent is concerned), to cover the machine and the process disclosed in the Jones patent in suit. The expert Robertson, as before quoted, clearly admits this fact.

Again, looking at the Palmer press and the testimony of the witnesses in relation to it, there is no doubt that if John Palmer had made an application for letters patent for the invention disclosed in the Palmer press and described by the witnesses Schrank, Davis and McKee, that he would have been entitled to cover everything that is shown in the Jones patent here in suit, and not only that, but to include the structure shown in the Jones hand-power press (R., front of page 91), and also the Jones hydraulic and steam-power press introduced between pages 90 and 91 of the record. The expert witnesses Robertson and Hood, and even Jones, do not contradict this proposition.

Looking at the whole case: There is not a new function or result suggested in the Jones patent in suit. There is not a new element in the claims or either of them. There is nothing in this whole case that would not infringe upon the Dingman patent—a patent, if taken out by John Palmer commensurate with the invention disclosed in the Palmer sketch and in the testimony of the witnesses Schrank, McKee and Davis; a machine constructed in accordance with the improved hydraulic press, the hand-power press and the steam-power press of Jones shown in the subsequent patents, the Cooley patent and the Stibbs patent, if these patents were entitled to be construed or reissued to cover what is shown and fairly described in them, regardless of what the state of the art was preceding the date of these very early patents. It is, therefore, clear that Jones could

not be a pioneer, and it is equally clear that he would be an infringer if he used even the hand-power press illustrated in front of page 91, upon each and every one of these patents. Being later than these, the courts can not, by any construction. so broaden the claims of his patent as to include what had preceded the date of his alleged invention.

The Supreme Court has passed upon this question many times, notably in the case of Ide vs. Ball Engine Co., 149 U.S., His Honor Justice Brown correctly states the law in the

following language:

"There can be no doubt that if the attachment of the dash pot to the shaft governor had been a novelty at the fime his patent was taken out, the Buckeye governor would have been an infringement. This being so, it is equally clear that, existing as it did before his patent, they are an anticipation."

Paraphrasing this language, it is fair to say that there can be no doubt that if the claims of the Jones patent had been a novelty at the time his patent was taken out, the Dingman press, the Palmer press, the Cooley press and the Stibbs press would have been infringements upon his claims. This being so, it is equally clear that, existing as they did before his patent, they are anticipations.

It seems almost needless to cite a great number of authorities in support of appellant's position that, in view of the prior state of the art as disclosed in the record and testified to by complainants' own witnesses, there is no patentable invention

disclosed in the Iones patent No. 204,741.

It should be remembered that the invention disclosed in this patent is not an integral machine like the machine of the Dingman patent, like the Palmer press or like the presses testified to as being in public and common use by the witnesses Schrank and Davis even prior to the date that the last Palmer press, from which the sketch was made, was put into use. it discloses a machine having a smasher or bulk compressor combined with a bundling press, or sheet-tying engine, as Dingman calls it.

A case in point, however, is Appleton Mfg. Co. vs. Star Mfg. Co., 60 Fed. Rep., 411, affirming a decision rendered by His Honor Judge Gresham in 51 Fed. Rep., 285. The patent

in suit in that case was for a corn-husker, and the claims were process claims. It appeared from the testimony that machines had been used for accomplishing practically the same result in analogous branches of the art before they were in use. To adapt these machines to accomplish the result or object attained by the patent in suit in that case, certain mechanical changes were necessary. The court held that these changes, in view of what had been done in analogous branches of the same art, did not require invention. The claim of the complainant below in that case, like here, was that in one organized machine he carried out the processes which had been theretofore carried out by separate machines.

That is what Jones claims here, and what would possibly be true if the suit had been brought upon some of his subsequent patents — even the old hand-power press shown in front of page 91 — but it is not true of the structure shown in the patent. His Honor Judge Gresham in the court below, in commenting upon

this case, said:

"The difference between the mechanism described for carrying out the process and defendant's mechanism is merely structural. It is not true that the patent shows an integral machine. It describes three old and well-known devices - a cutter, a thresher and a separator — mounted on a platform in juxtaposition. and so geared as to operate by a single band wheel, each device operating, however, just as before. are not combined or incorporated into a single machine, with all its parts co-acting upon a common principle or in obedience to a common law. The steps in the alleged process are the same, whether performed by a cutter, a thresher and a separator mechanically connected, as shown in the patent, or by the same old devices, or their equivalents, having no connection whatever and widely separated."

In this case, like that, it is not true that the smasher, dry press and sheet-tie are all one integral machine, but are, like the machine in suit in the case cited, at least two old and well-known devices: First, the smasher or bulk compressor to smash and smooth the sheets after they have been printed, dried and folded; and, second, a bundling press to compress the folded

and smashed sheets and tie them while under pressure, precisely as they have been tied in the Dingman press, in the Palmer press; tied by hand as testified to by all the witnesses, and tied

as they were in every baling press time out of mind.

The bill was dismissed for want of invention. That decision was affirmed by the Circuit Court of Appeals. The court, in 60 Fed. Rep., 411, in an opinion by His Honor Judge Woods, affirms the decision of the Circuit Court, and the cases referred to by His Honor clearly support the decision and are equally

applicable to this case.

A late decision of the Supreme Court of the United States is Mast, Foos & Co. vs. Stover Mfg. Co., 177 U. S., 485–20 Supreme Court Reporter, 708. In that case the patent in suit had been sustained by the Circuit Court and by the Circuit Court of Appeals for the Eighth Circuit, and also by His Honor Judge Grosscup by granting a preliminary injunction in view of these decisions. The case was appealed to the Circuit Court of Appeals for the Seventh Circuit, the preliminary injunction theretofore granted dissolved and the bill dismissed because the device as covered by the claims did not disclose patentable invention, although it was admitted by the court that the same device had never been used in ordinary mills prior to the patentee's adoption of older devices, His Honor Judge Woods stating:

"The first to make such an improvement is not in fact an inventor, and to infer invention merely because it had not been produced sooner, would be to reach a false conclusion by an argument neither presuasive nor plausible."

See Parlin & Olendorff vs. Moline Plow Co., 89 Fed. Rep., 329.

The case was taken to the Supreme Court on writ of certiorari, and the remarks by His Honor Mr. Justice Brown are

equally applicable to the case at bar.

An instructive case on this point is Fuller-Warren Company vs. Michigan Stove Company, 86 Fed. Rep., 463. This was an appeal from the Circuit Court for the Eastern District of Wisconsin — Michigan Stove Company vs. Fuller-Warren Company, 81 Fed. Rep., 376.

In the lower court His Honor Judge Seaman held the pat-

ent infringed, so far as the second and fifth claims were concerned, because the testimony showed that the result attained by the combination was beneficial and had become popular with the trade. The Circuit Court of Appeals, in a decision by His Honor Judge Woods, 86 Fed. Rep., 463, reversed the decree of the Circuit Court for the reasons stated in the last paragraph of the opinion, on page 466. From this ruling a writ of certiorari was taken to the Supreme Court of the United States, and in a brief opinion (172 U. S., 19 Sup. Ct. Rep., 866) the writ of certiorari was denied.

Another instructive case is Plumb vs. N. Y., N. H. & H. R. Co., 97 Fed. Rep., 645. His Honor Judge Townsend, in deciding the case, states the law fully and fairly, and this decision and

the cases cited in it seem clearly in point in this case.

Craig et al. vs. Michigan Lubricating Co., 72 Fed. Rep., 173. His Honor Judge Swan dismissed the bill of complaint for substantially the same reasons which defendant here relies upon. This case was appealed to the Circuit Court of Appeals for the Sixth Circuit (81 Fed. Rep., 870), and tried before Judges Taft and Lurton, Circuit Judges, and Judge Sage, District Judge, and in an able opinion by His Honor Judge Sage the decree of the Circuit Court was affirmed.

In Blakesley Novelty Company vs. Connecticut Webb Company et al. (78 Fed. Rep., 480), decided by His Honor Judge Townsend, since the decision in Locomotive Works vs. Medart, is clearly in favor of appellant's contention in this case, and the decisions cited by His Honor in support of this ruling (on page 481), like all others since the decision in Risdon vs. The Iron Works, clearly state the law as contended for by appellant, and

are respectfully referred to.

At the hearing of this case before the Supreme Court of the District of Columbia, upon exceptions to the master's report, the auditor supported his findings by reference to Fenton Metallic Mfg. Co. vs. Office Specialty Co. The Supreme Court of the District of Columbia affirmed the decision in that case and also the finding of the auditor. Appeal was taken by the defendant—the Office Specialty Mfg. Co. vs. Fenton Metallic Mfg. Co.—to this court. The case was heard and reported in 174 U. S., 492, 19 Sup. Ct. Rep., 641. In an able opinion rendered by His Honor Mr. Justice Brown, the case was reversed and a mandate sent down with instructions to order the bill to be dismissed.

King vs. Gallum, 100 U. S., 99. This case seems to be on all fours with the case at bar. The patent is on a baling press, which was for baling plastering hair. The case was brought into the Supreme Court from the decision of the Circuit Court of Appeals for the Seventh Circuit, rendered by His Honor Judge Drummond. The patent upon which the suit was brought was dated June 30, 1874 - more than two years before the application for the patent here in suit was filed. His Honor Judge Drummond dismissed the bill of complaint, holding the patent void for want of patentable invention. The Supreme Court of the United States, in a decision rendered by His Honor Justice Woods, affirmed this decision. The reasoning by His Honor Judge Drummond and the Supreme Court in that case is clearly applicable here.

The auditor, in making his report, was clearly wrong in his comparison of defendant's machine, with all its patented improvements upon it, with the old, ponderous process used many years before the alleged invention of Jones, instead of the profits defendant might have made had he used the old process shown in the Dingman patent, the old Palmer press, the ordinary smasher or bulk compressor and hand-tie, all of which defendant was free to use, and the thing shown in the Jones patent in suit, or had he used in his printing establishment any of the old printing resses he was free to use - the Gordon press, for instance, testified to by the witness Grier, which made no type indentations and obviated the necessity for using fuller boards or the old "ponderous process" so much relied upon by the witnesses on behalf of Jones.

The rule of the Supreme Court is laid down in Mowry vs. Whitney, 14 Wall., 651, and Black vs. Thorn, 111 U. S., 122, referred to with approval in nearly all the recent cases, notably Keystone Mfg. Co. vs. Adams, 151 U. S., 139, and the cases

therein cited.

The bill of complaint alleges infringement of two patents; alleges that the two patents, one twelve years later than the one now in suit, were infringed by the single Seybold machine used by Busch, which was the subject of still later patents, and that the inventions described in both of said patents were used conointly in the same Seybold press.

One of these patents has been dismissed from the suit.

The "agreement" was an exclusive sale of all of the Jones patents to The W. O. Hickok Manufacturing Company, not only

of those mentioned in the agreement, but of all others pending or which Jones might invent relating to the same subject matter, only reserving a specified royalty, which was subject to change at any time on agreement of the parties. There was no proof in the record as to what that royalty was at the time of the complained of infringement. There was no attempt to separate the invention covered by all the claims of the Jones patent now in suit, with all the advantages that were added to it by the subsequent patents, nor any attempt to prove what, if any, profits were due to the complainant Jones for the use of the four claims of the patent in suit.

There is positive proof that the improved form of the Jones patent shown in the hand press would not do the work that Busch was doing—that two of those machines would not do the work. There is proof that if the defendant had bought one of the steam-power presses covered by some of the Jones subsequent patents from The Hickok Manufacturing Company, instead of the one he did purchase in the open market from The Seybold Machine Company, he could have procured it for \$50.00 more than he paid for the Seybold machine, and in that

event would not be liable for any damages.

The burden of proof was on the complainants to show the actual profits made by defendant from the use of the invention covered by the patent in suit. As was well said by this court in Garretson vs. Clark, 111 U. S., 120, quoting with approval the statement of the rule made in the court below by Judge Blatchford:

"The patentee must in every case give evidence tending to separate or apportion defendant's profits and the patentee's damages between the patentee feature and the unpatented features, and such evidence must be reliable, tangible, and not conjectural or speculative."

Until that is done the complainant has not made out a *prima* javie case, and defendant is not called upon to put in any testimony in rebuttal.

Following the rule stated in all the prior cases, and particularly in the cases referred to in 111 U. S., 120, and 151 U. S., 139, only nominal damages should have been awarded, even assuming that defendant had used a combined bulk compressor

and sheet tie like the Jones patent in suit, or the Dingman patent, fifteen years earlier than the Jones alleged invention, to remove type indentations which, in the opinion of all the witnesses called on behalf of complainants, was the invention of Jones, instead of, as the fact is, that his invention had nothing to do with printed folded sheets until they had been printed, dried (if drying was necessary), folded and smashed.

The decree of the lower court, it is submitted, should be

reversed at appellee's costs.

GEORGE J. MURRAY,

Counsel for Appellant.

Office Subjects Course to S

ORFORDY TERM 1960:

No. 96

GLARENCE HE BUSCLE AgreENE

JOSHUA W. JONES, RT. AL., Applica

make for Arguithms.

Court A

SUPREME COURT OF THE UNITED STATES.

OCTOBER TERM, 1901.

No. 96.

CLARENCE W. BUSCH, Appellant,

US.

JOSHUA W. JONES AND THE W. O. HICKOK MANUFACTURING COMPANY, Appellees.

BRIEF FOR APPELLEES.

The appellant in his "Specifications of Errors relied upon" has alleged ten errors, which fall into five general classes, the 1st specification relating to the jurisdiction of the Trial Court to entertain the suit; the 2nd, 3rd, 4th and 5th to the validity of the patent sued on and its several claims; the 6th to its infringement by the Appellant; the 7th to the action of the Trial Court in refusing, on motion of the Defendant, to vacate its interlocutory decree declaring the validity of the patent and its infringement and sending the cause to the Auditor of the Court for an accounting of damages and profits, and the 8th, 9th and 10th to the assessment of savings and profits by the Auditor. These several groups of alleged errors will be considered in their order.

IST ASSIGNMENT OF ERROR.

Jurisdiction of the Trial Court.

The first assignment of error attacks the jurisdiction of the Trial Court. Several grounds appear to be urged

and these will be briefly considered.

(a) It is urged that the Court below had not jurisdiction because the patent in suit had but a short time to run and expired before the taking of testimony in the case was completed, without any application for a preliminary injunction having been in the meantime made. It seems difficult to believe, in the light of the authorities and the facts of this case, that this objection can be seriously urged. The bill, which prayed not only for an accounting, but also for an injunction, both preliminary and final, was filed March 10, 1894, and the patent expired June 11, 1805, one day more than fifteen months afterwards. The pleadings were all in about June 1, 1894. Immediately after the summer vacation following plaintiffs' prima facie proofs were put in and were completed September 24. 1894, nearly nine months before the expiration of the patent. Mr. O. M. Hill, of Cincinnati, originally appeared for the defendant, attended at the taking of plaintiffs' proofs and cross-examined their witnesses. But shortly afterwards he fell sick and, after a lingering illness of some months, he died in January or February, 1895. Mr. Murray, appellant's present counsel, was employed to succeed Mr. Hill about March, 1895, and properly requested and was cheerfully given time to familiarize himself with the case, with the result that he took the testimony of four witnesses at Philadelphia on April 26 and 27, 1895, seven months after the completion of plaintiffs' proofs. Further time was requested by Mr. Murray to arrange for the examination of his expert witness, and on June 13 to 17 he took the testimony of his expert, Mr. Hood, concluding defendant's answering proofs nearly nine months after the completion of plaintiffs' prima facie case and six days after the expiration of the patent. Moving as promptly as possible the plaintiffs took their rebutting proofs in New York, Philadelphia and Washington on July 22-27, and the case was promptly put upon the Equity List for hearing in October.

These facts are recited for the purpose of showing that, although the bill was filed in ample time to obtain an injunction on final hearing, according to the usual course of Equity practice, yet that this purpose was defeated by the accident of the sickness and death of Mr. Hill and the

introduction into the case of his successor.

The law upon this subject is well settled. If between the date of filing the bill and the expiration of the patent there is not sufficient time for the plaintiff to obtain equitable relief, the Court has no jurisdiction, e. g.; where the bill is filed one day before the expiration of the patent, Davis v. Smith, 19 Fed. Rep., 823; Am. Cable Co. v. Citizen's Ry. Co., 44 id., 484; or four days, Mershon v. Furnace Co., 24 id., 741; Bragg Mfg. Co. v. Hartford, 56 Fed. Rep., 292; or five days, Burdell v. Comstock, 15 id., 395. In all these cases it was held that, because of the clear insufficiency of time for obtaining equitable relief by injunction, the prayer for an injunction was a mere pretext for transferring a mere claim for damages from a Court of law to a Court of equity. But where, according to the usual course of equity practice in the particular Court, there is sufficient time to obtain equitable relief by injunction, either preliminary or final, the Court is justified in entertaining jurisdiction of the bill, and, having once properly acquired jurisdiction, will retain it for the purpose of granting complete relief by an accounting or otherwise, even after the expiration of the patent; and this is so, even though no motion for an injunction is actually made during the life of the patent; Clark v. Wooster, 110 U. S., 322, and cases cited (Patent expired 15 days after filing of bill, and it did not appear that an injunction was applied for; that it might have been applied for being considered by the Court to be sufficient); Beedle v. Bennett, 122 U. S., 71, 75; Adams v. Howard, 19 Fed. Rep., 317; N. Y. Grape Sugar Co. v. Peoria Sugar Co., 21 id., 878, (three months-no injunction asked); Toledo Mower & Reaper Co. v. Johnston Harvester Co., 24 id., 739 (26 days); Adams v. Bridgewater Iron Co., 26 id., 324 (23

days—no injunction asked); Brooks v. Miller, 28 id., 615; Kittle v. Graaf, 30 id., 689 (21 days—no injunction asked; Kittle v. Rogers and others, 33 id., 49 (several cases, 30-50 days—no injunction asked); Singer Mfg. Co. v. Wilson Sewing Machine Co., 38 id., 586 (4½ months); Ross v. Ft. Wayne, 63 id., 466 (2½ months); and other cases might be cited.

In Clark v. Wooster, supra, Mr. Justice Bradley, delivering the opinion of the Court, said:

"The bill does not show any special ground for equitable relief, except the prayer for an injunction. To this the complainant was entitled, even for the short time the patent had to run, unless the Court had deemed it improper to grant it. If, by the course of the Court, no injunction could have been obtained in that time, the bill could very properly have been dismissed, and ought to have been. But by the rules of the Court in which the suit was brought only four days' notice of application for an injunction was required. Whether one was applied for does not appear. But the Court had jurisdiction of the case, and could retain the bill, if, in its discretion, it saw fit to do so, which it did. It might have dismissed the bill, if it had deemed it inexpedient to grant an injunction; but that was a matter in its own sound discretion, and with that discretion, it is not our province to interfere, unless it was exercised in a manner clearly illegal. We see no illegality in the manner of its exercise in this case. The jurisdiction had attached, and although, after it attached, the principal ground for issuing an injunction may have ceased to exist by the expiration of the patent, yet there might be other grounds for the writ arising from the possession by the defendants of folding guides illegally made or procured whilst the patent was in force. The general allegations of the bill were sufficiently comprehensive to meet such a case. But even without that, if the case was one for equitable relief when the suit was instituted, the mere fact that the ground for such relief expired by the expiration of the patent, would not take away the jurisdiction, and preclude the court from proceeding to grant the incidental relief which belongs to cases of that sort. This has often been done in patent causes, and a large

number of cases may be cited to that effect; and there is nothing in the decision in Root v. Railway Co., 105 U. S. 189, to the contrary. Cotton Tie Co. v. Simmons, 106 U. S., 89; Lake Shore, &c., Railway v. Car-Brake Co., 110 U. S., 229; Consolidated Valve Co. v. Crosby Valve Co., 113 U. S., 157; Thompson v. Wooster, 114 U. S., 104."

In Adams v. Bridgewater Iron Co., supra, in which the life of the patent was but twenty-three days, the bill prayed for a perpetual, but not for a provisional injunction, and Judge Colt held that the Court had jurisdiction, remarking:

"The fact that no preliminary injunction was asked for we do not deem material. The bill prays for a perpetual injunction, and the plaintiffs had a right, at any moment, to amend their bill and ask for a provisional one. The case was cognizable in equity at the time the bill was filed, and it was not impossible to have obtained equitable relief during the life of the patent. It was not a mere device to transfer a plain jurisdiction at law to a court of equity, as courts have held where the patent has only several days to run."

In the face of doctrine so well settled and so abundantly administered in the courts, it is surprising that the jurisdiction of the Court below should be here attacked upon the ground that the patent had but fifteen months to run at the filing of the bill and expired before the final decree was entered, and it is still more surprising to find it charged in Appellant's brief that "the bill was evidently framed to avoid the question of jurisdiction." The bill was framed for no such purpose, but for the bona fide purpose of obtaining an injunction, and the Court below did grant an injunction restraining the defendant from using or selling any machine made or used by him prior to the expiration of the patent, as was suggested by Mr. Justice Bradley, in Clark v. Wooster, might be done, and as was done by Judges Wheeler, Blatchford and Nixon in the following cases, in which the power of the Court to grant injunction after the expiration of the patent, is discussed and upheld: Am. Diamond Rock Boring Co. v. Sheldon, 1 Fed. Rep., 870; same v. Rutland Marble Co., 2 id., 357; Reay ex'x v. Raynor, 19 id., 308; Reay v. Envelope Co., id., 311; Toledo Mower & Reaper Co. v. Johnston Harvester Co., 24 id., 739, and N. Y. Belting and Packing Co. v. Magowan, 27 id., 111.

Something further is predicated upon the destruction of the infringing machine during the pendency of the suit. It is not the fact, as is alleged in Appellant's brief (p. 6) that "at the first hearing, upon which the interlocutory decree was entered it clearly appeared that * * * the single machine used by Defendant had been destroyed by fire," etc. This did not appear until long afterwards. to wit: in the taking of the testimony in the accounting before the auditor (Record, p. 179). The hearing was had in October 1805, the interlocutory decree was entered February 11, 1896, and the testimony referred to was taken September 29, 1896. The fact of the distruction of the machine was not at the time of the hearing known to the Court or counsel for Plaintiffs. But even if it had so appeared at that time, the jurisdiction of the Court, which had properly attached upon the filing of the bill, could not have been ousted by the destruction of the machine and the cessation of the infringement.

(c) As a further objection to the jurisdiction of the Court below it is urged that the defendant was not a manufacturer, but "a mere user of one machine" and the damages could be easily measured by the difference between the cost and selling price of that machine, without reference to a Master, and therefore the plaintiffs had a plain and adequate remedy at law. Under similar circumstances precisely the same point was made, by counsel for appellant here, in Mills Mfg. Co. v. Whitehurst, 56 Fed. Rep., 589, 594, and some of the same authorities were cited in support of it. The Court disposed of the contention as follows:

"The second defense, that the complainant has an adequate remedy at law, and therefore is not entitled to sue in equity, must be overruled. Crandall v. Manufactur-

ing Co., 24 Fed. Rep., 738, which is especially relied upon, was a suit against a licensee for royalties, and has no application here. Nor has Root v. Railway Co., 105 U. S., 189, where the patent had expired. The defendants are users, not manufacturers, but, if infringers, they may be enjoined; and that disposes of the objection to the jurisdiction."

Of the other authorities cited by appellant on the question of jurisdiction, Ross v. City of Ft. Wayne, 58 Fed. Rep., 404, was reversed by the Court of Appeals in Ross v. Ft. Wayne, 63 id., 466; in Campbell v. Ward, 12 Fed. Rep., 150, as in Root v. Ry. Co., the patent had expired at the time the suit was brought, and in Burdell v. Comstock, 15 Fed. Rep., 395, Davis v. Smith, 19 id., 823, and Mershon v. Furnace Co., 24 id., 741, the bill was filed within from one to five days of the expiration of the patent.

In Hayward v. Andrews, 106 U. S. 672, and in Spring v. Sewing Mch. Co., 13 Fed., 446, the patent had not expired, but it was held in the former case that the assignee of the patent, to whom were also assigned all claims for damages for past infringement, could not maintain a bill in equity for the enforcement of such claims, upon the mere ground that he could not sue at law in his own name; while in the latter it was held that the assignor could not, after his assignment maintain a bill for the recovery of damages accruing during his ownership. In Consolidated Middlings Purifier Co. v. Wolf, 28 Fed., 814, and Crandall v. Piano Mfg. Co., 24 Fed., 738, it was held that a bill in equity cannot be maintained by a licensor against his licensee, his remedy being by an action at law upon his In McDonald v. Miller, 84 Fed., 344, where the patent had but 22 days to run and the subpoena was returnable after its expiration, Judge Seaman exercised the discretion, which it was held in Clark v. Wooster belonged to him, by dismissing the bill; as did Judge Blodgett in Racine Seeder Co. v. Joilet Co., &c., Co., 27 Fed., 368 (decided before Clark v. Wooster), where the patent had two months to run. The remaining cases cited are cases of ejectment bills, bills for the delivery of

chattels, for the mere recovery of money, a bill discovery where it did not appear that the complainant was otherwise without sufficient evidence to establish his claim at They establish merely that, where there is a plain, adequate and complete remedy at law, equity has no jurisdiction,-which is not disputed,-and beyond this they have no possible application to the case at bar. the time of the filing of the bill in the present case there was a continuing infringement by the defendant of the patent in suit, which had still fifteen months to run, and it requires no citation from the abundant authorities construing R. S., section 4921, to show that, under such circumstances, a suit at law to recover damages for past infringement would be neither an adequate nor a complete remedy, and that nothing short of an injunction and an accounting of profits as well as damages would be. It is sufficient to refer to Birdsell v. Shaliol, 112 U. S., 485. 487, and Tilghman v. Proctor, 125 id., 136. In the former case, where, as in the case at bar, a bill in equity was filed by the patentee and his exclusive licensee against the user of a single machine, it was held that the court had jurisdiction, even after the recovery by the patentee of a judgment at law for damages against the manufacturer and satisfaction thereof. Mr. Justice Gray, after pointing out that a sale by the patentee or his licensee carries with it an implied license to use and sell throughout the entire term of the patent, says (p. 487):

"But an infringer does not, by paying damages for making and using a machine in infringement of a patent, acquire any right himself to the further use of the machine. On the contrary, he may, in addition to the payment of damages for past infringements, be restrained by injunction from further use, and, when the whole machine is an infringement on the patent, be ordered to deliver it up to be destroyed. Suffolk Co. v. Hayden, 3 Wall., 315, 320; Root v. Railway Co., 105 U. S., 189, 198; Needham v. Oxley, 8 Law Times (N. S.), 604; S. C. 2 New Rep. Eq. & Com. Law, 388; Frearson v. Loe, 9 Ch. D., 48, 67. No more does one, who pays damages for selling a machine in infringe-

ment of a patent, acquire for himself or his vendee any right to use that machine. In the case of a license or a sale by the patentee, the rights of the licensee or the vendee arise out of contract with him. In the case of infringement, the liability of infringers arises out of their own wrongful invasion of his rights. The recovery and satisfaction of a judgment for damages against one wrong-doer do not ordinarily confer, upon him or upon others, the right to continue or repeat the wrong."

(c) But it appears to be suggested that the patentee was entitled to recover only the royalty or license fee, which it is assumed he established, and that an action at law would be a sufficient remedy for that purpose. no such royalty or license fee was established. clusive license to make and vend, the Hickok Mfg. Co., agreed to pay to the patentee for that privilege 25 per cent. of the selling price of each machine sold; but this was not in the usual sense an established royalty, and certainly could not avail the infringer as against the rights of the exclusive licensee, which is a party to this suit. Beyond this the patentee was accustomed, upon the sale of a machine by the Hickok Co., to issue to the purchaser thereof a license to use upon that machine the process of "Dry-Pressing" covered by the 5th claim of the patent in suit. But this was not in any sense establishing a license fee, and the license issued was by its terms expressly limited to the particular machine, designated by style and number, and always a machine made under the patentee's own patents.

But even if such royalty or license fee had been established, it is definitely settled by Tilgham v. Proctor, 125 U. S., 136, that in such case a patentee has, as against an infringer, the election either to sue at law for the royalty or to proceed in equity for an injunction and an accounting, not only of damages, but also of profits. See also Bragg v. City of Stockton, 27 Fed. Rep., 509; Brooks v. Miller, 28 id., 615, and Birdsell v. Shaliol, supra., where is quoted with approval the following language of Lord

Hatherley, in Penn v. Bibby, L. R. 3 Eq., 308:

"'With regard to the damages, it has never, I think, been held in this court that an account, directed against a manufacturer of a patented article, licenses the use of that article in the hands of all the purchasers. The patent is a continuing patent, and I do not see why the article should not be followed in every man's hand, until the infringement is got rid of. So long as the article is used, there is continuing damage.' 'As to the royalties, I cannot compel the plaintiff to accept the same royalty from these defendants as he receives from others. I cannot in the decree do less than give the plaintiff his full right, and I cannot bargain for him what he may choose, or may not choose to do.'"

THE PATENT AND THE PARTIES.

The parent in suit, No. 204,741, granted June 11, 1878. to Joshua W. Jones, one of the plaintiffs in the Court below and one of the appellees in this Court, covers,-not. as is ingeniously suggested by counsel for appellant, a press and its mere function or mode of operation,-but. 1st. A process of "dry pressing," or removing type indentions from printed sheets, set forth in claim 5 of the patent. and, 2d. A press of peculiar construction and adapted to the convenient carrying of this process in the effect, the novel features of which press are covered by claims I to 4 inclusive; and this is substantially what is stated by appellant's own expert witness, Mr. Hood. His language so completely answers much that is assumed and argued in appellant's brief, that we quote it at length, in order that the Court may have, at the outset and before any discussion is entered upon, the deliberate view taken by appellant's expert of the general scope of the patent and the purpose of the invention. He says (Printed Record, pp. 100-1):

"A. The invention shown and described in the Jones patent, No. 204,741, relates to a means for removing from printed sheets the type indentations and elevations made during the process of printing, whereby a smooth surface is given to the back side of the printed sheet. One of the methods in common use for accomplishing this result, at the time of the filing of the ap-

plication of the Jones patent was as follows: A pile was formed of printed sheets and hard glazed boards, called fuller boards, arranged alternately, one on the The pile thus formed was placed between the platen and the follower of a suitable press and a powerful pressure applied. The pile being allowed to remain under pressure for several hours. The purpose of the Jones invention appears to be to save this great expenditure of time and to dispense with the use of the fuller boards. To this end Jones contrived the idea of retaining the pressure communicated by the press to the pile after the pile had been removed from the press. For this purpose he contrived a press in which the pile of printed sheets, made up without fuller boards, might be placed, a stiff board of substantially the same size as the printed sheets being placed at each end of the pile, and the platen and follower of the press being so constructed that cords might be conveniently passed around the package formed of the printed sheets and end boards. and securely tied while the pile was still in the press. A package was thus formed which, when removed from the press, would retain the printed sheets under pressure any length of time desired and leave the press free for use in forming other packages."

And the same view is somewhat more clearly set forth by appellees' expert witness, Mr. Robertson (Record, p. 35, Ans. 4), to which the Court is respectfully referred.

Counsel for appellant has, in his brief (p. 45), fallen into error in saying that there is nothing about "removing type indentations" in the patent or in the claims. In the 2d paragraph of the specification (Record, p. 93) it is said: "Fig 2 is a perspective view of a bundle of sheets tied and ready for setting aside as by my process of treating printed papers or sheets to remove therefrom the indentations of type." And, having thus, at the very beginning of his specification, once stated in these explicit terms the object of his process, he thereafter calls it by the name by which is was, as we shall hereafter see, technically known in the trade, viz: "dry- pressing."

Counsel for appellant appears to have been, in his understanding of the scope of the patent, somewhat confused by the fact that, as an adjunct to the press, is shown and described a "Bulk Compressor," by means of which the large or swollen heads of folded sheets may be compressed preliminarily to their insertion in the press. But this "Compressor" is not covered by any of the claims, is not in controversy here and has in practice been found unnecessary. It was not claimed by defendant's expert witness to be essential either to the carrying out of the process or the operation of the press. It has really nothing to do with the case, and its introduction in appellant's argument tends only to confuse and in no respect to en-

lighten the discussion.

The patentee, Mr. Jones, on December 27, 1889, entered into a contract in writing with the W. O. Hickok Mfg. Co., of Harrisburg, Pa., by which he made said company his exclusive licensee to manufacture and sell machines made in accordance with the Letters Patent in suit. Said company was therefore joined as co-plaintiff in this suit, and the agreement is in evidence (Record, p. o6, et. seg.). The defendant, Mr. Busch, was at the time the bill was filed, and both before and afterwards, State Printer, or contractor for the public printing of the State of Pennsylvania, his contract requiring, among other things, that the sheets of all the work done by him for the State should be "dry pressed." His printing establishment was at Harrisburg, Pa., but he was at the time the bill was filed an inhabitant of the District of Columbia, residing at Washington.

THE 5TH, OR PROCESS CLAIM, AND THE 2ND, 3RD AND 4TH ASSIGNMENTS OF ERROR.

The 4th assignment of error charges "that the patent is void for want of invention, so far the fifth claim is concerned, because the process had been in use and practised without the use of any machine to assist in carrying out the alleged process long prior to any invention of Jones." Precisely what is meant by this language is not clear. It is nowhere distinctly referred to in the argument, nor is any evidence, upon which it could be based, pointed out. If by the language above quoted, it is meant to say that,

prior to the Jones' invention, printed sheets were tied up in loose bundles by hand, we do not dispute the statement. But, as will hereafter appear, the process claimed is not the mere tying up of printed sheets in bundles, either by hand or by machine, but involves other matters which were entirely new with Mr. Jones.

The third assignment of error charges want of novelty because of prior patents and public use, and because the process was practiced on the so-called Palmer Press. The second assignment charges that the process, even if new, covers a mere function of the machine. These two points

we will consider in their inverse order.

THE PROCESS.

The process referred to is clearly and for most purposes sufficiently described in claim 5 of the patent, as follows:

"The process herein described for treating folded printed sheets of paper in dry-pressing, the same consisting of subjecting a collection of such sheets to pressure without the use of fuller boards, and while under such pressure tying them into compact bundles with end boards, then removing them immediately from the press, and allowing them to remain tied sufficienty long to fix and complete dry-pressing."

THE STATE OF THE ART PRIOR TO THE INVENTION.

But in order to understand the full scope and value of the process it is necessary to refer briefly to the state of the art. As is well known, when a sheet of paper is passed through a printing press the fibre of the paper is to some extent displaced by the pressure of the type and impressions or indentations in the paper are thus produced, the displacement appearing on the side next the type as sunken, hollow or concave, and on the opposite side as raised or convex. When the sheet is reversed and the opposite side is printed upon,—care being always taken in good printing offices that the corresponding lines on the opposite sides of the paper shall accurately "register,"—the raised or convex surfaces are forced back and gener-

ally speaking the impressions now appear on the side last printed as concave and on the side first printed as convex, the general result being that, except from broken lines, spacing, &c., substantially all the impressions appear on one side of the sheet as convex and on the other as concave; and it is hence apparent that, when a number of unfolded sheets of the same signature are piled one upon another, the concave indentations of each sheet will substantially form a matrix for the convex indentations of the sheet next above or below it, depending upon whether the sheets are laid with their first or their last printed sides uppermost. To remove these type indentations and thus present a page of smooth and even surface, particularly in fine books, is a matter of great importance to book printers, and hence great labor and expense, when necessary to the attainment of this object, have not been considered wasted. The removal of these type indentations is technically known in the art as "dry pressing." ("Dry Press. A press in which the sheets are pressed smooth." Standard Dictionary, verb. "Dry;" "Dry Press (printing), one in which sheets are pressed smooth," Knight's Mech. Dict.: "Dry Press, in printing, a press for smoothing printed sheets;" Cent. Dict. verb. Press; "Removing the heavy impressions made by the printing press. the paper with a smooth surface," Grier, Record, p. 14, Ans. 10-20. That this is the sense in which the term is used in the patent is shown by the use of the phrase "remove therefrom the indentations of type" in lines 13-15 as synonomous with "dry-pressing" in the other parts of the patent.)

Prior to the Jones invention, "dry pressing" was a part of the work of the printer who delivered the sheets to the binder flat or unfolded (DeVinne, Record, p. 56, ans. 14; Nicholson, p. 62, ans. 15-16) and dry-pressed (DeVinne, p. 55, ans. 13; Nicholson, p. 60, ans. 7-8; Schrank, p. 168, ans. 33-35, and Davis, p. 175, ans. 25); and the process of dry-pressing as very slow and cumbersome (see DeVinne, pp. 55-6, ans. 1 et seq. and 23; Penicks, pp. 64, et seq., ans. 4 et seq.) and expensive (Penicks, p. 68, ans. 22, Robertson, p. 36, ans. 4. See also description of

the old process by Suydam, pp. 185-6, ans. 10-11, p. 188,

ans. 28).

The sheets having been printed wet, or at least the ink being wet, the first step was to thoroughly dry them, which was done by hanging them on poles near the ceiling or on racks in a steam-drying room and allowing them to remain there some hours. (Penicks re-called p. 79, ans. 1; Jones, p. 31, ans. 38; DeVinne, p. 55, ans. 7.) Having been thus thoroughly dried-hence "dry-pressing"the sheets were laid out flat and inserted between "glazed boards," sometimes called "press boards," and sometimes "fuller boards," from their use by fullers in their preparation of cloth-"a thin, very hard, highly calendered and very compact mixture of textile rubbish, of which oakum is a very large constitutent"—(DeVinne, p. 55, ans. 5), closely resembling the "press board" used in the ordinary office "letter copying-press." The number of sheets thus laid between each couple of "fuller boards" varied according to the character and quality of the work. the work was very fine and exact, one printed sheet was laid between these press boards. When it was not so exact, two or three sheets were put between the boards after being thoroughly dried" (DeVinne, Record, p. 55, ans. 6; see also Grier, p. 16, ans. 48; Robertson, pp. 43-4, ans. 19-20), or in the printing of public documents in the Government Printing Office, four sheets (Penicks, p. 68, ans. 22). The sheets with the fuller boards between which they were inserted were then piled in an Hydraulic Press and subjected to enormous pressure, which was retained upon them until the process of dry-pressing or removing the type indentations was completed, usually over night (Grier, p. 17, ans. 54; Jones, p. 31, ans. 38; Robertson, p. 36, ans. 4; re-called, p. 77, ans. 7; DeVinne, p. 55, ans. 8; Hood, p. 116, ans. 40), although in the Government Printing Office, where, perhaps, speed was of more consequence than completeness of finish, four hours appear to have been enough (Penicks, p. 68, ans. 22). But at all events they were allowed to remain in press a considerable time (Hood, p. 116, ans. 40).

One further step remained to complete the process,

namely: The pressure having been removed, to remove the mixed pile of sheets and fuller boards from the press, carefully separate them and distribute them to their respective piles. (Robertson, p. 36, ans. 4; Suydam, p. 188, ans. 28). It is apparent that the process of dry-pressing thus carried on involved great labor and therefore great expense, Theodore L. DeVinne testifying that "to fill and unfill a press" containing about 1,750 sheets, "would always take a man and a boy, sometimes a man and two boys, a day" (p. 55, ans. 9-12), and Mr. Penicks testifying that in the speedier and perhaps less exact work of the Government Printing Office, where presses of great capacity were used, it required the services of six men to dry

press 24,000 sheets in a day.

It is also apparent that the use of "fuller boards" was essential to the sucess of this process. From what has already been said with respect to the indentations of each sheet forming a matrix for the corresponding elevations of the sheet next to it, it is evident that, in a pile from three to six feet high-according to the height of the press used-the indentations of the sheets removed a few inches from the head or foot of the machine, the points at which the pressure is applied to and distributed over the pile, would be rather protected from the pressure than otherwise affected by it, and that their effacement would be at least very irregular and uncertain. It was therefore necessary to interpose between the sheets at very short intervals hard substances-"fuller" or "press boards"which should directly communicate the pressure to the raised surfaces of the paper and accomplish their effacement with certainty and regularity. It was indeed not contended by the defendant that in this process fuller boards could be dispensed with and Theodore L. De-Vinne, than whom no one in this country is more competent to testify with regard to the art of printing, declared that he "never knew it to be done with success" (p. 57, ans. 26).

It was, however, contended on behalf of defendant that "fuller boards" were dispensed with in certain other pro-

cesses of removing indentations in use prior to the patent in suit, to wit: Treating folded sheets (a) by beating with a hammer, (b) by rolling and (c) by smashing and pressing in a hydraulic press and, misled by the terms "smoothness" and "solidity," the defendant's expert, Mr. Hood, cited upon this point passages from "The English Cyclopedia, Arts and Sciences" and "A Manual of the Art of Bookbinding," by James B. Nicholson. It is to be observed, however, that Mr. Hood had no practical acquaintance with either of the arts of printing or bookbinding (p. 111-2, ans. 8-13), and had never seen the operation of dry-pressing carried on (ans. 12). He thought that this operation was the work of the bookbinder (p. 112, ans. 14-18), although DeVinne, the printer, (p. 55, ans. 13), and Nicholson, the bookbinder and the author of the book referred to (p. 60, ans. 7-8), as well as defendant's witnesses, Schrank (p. 168, ans. 35), and Davis (ans. 26-8), all testify that it was the work of the printer. He considered the "gathering" and "collating" of sheets in the bindery as "the same process" (ans. 15-16), although his author, Nicholson, testifies that they are distinct operations (p. 61, ans. 14), (see also defendant's witness, Mc-Kee, p. 170, ans. 3), and generally he admitted that his testimony was based wholly upon the papers submitted to him in this case and some other publications which he does not name, and not upon any practical knowledge of either of the arts of printing or bookbinding (pp. 111-2, ans. 13). It is therefore not surprising to find him misled by the terms "smoothness" and "solidity" into the belief that the operations of "beating," "rolling" and "smashing," described in the works on bookbinding, had for their object, among others, the removal of the type indentations (ans. 21-35), but he admits that in the use of the hydraulic press iron plates are introduced "at intervals along the pile to evenly distribute the pressure" (ans. 22), a clear equivalent for the fuller boards, if the process had for its object the effacement of the type indentations.

In rebuttal the plaintiffs called Mr. Nicholson, who testified that the beating, rolling, *smashing*, &c., described in his book had nothing whatever to do with the removal

of type indentations, which had already been "done-or attempted to be done-by the printer," but that "they were designed to make the book solid by driving out all the air that was in or between the sheets." If it were necessary to add anything to the testimony of Mr. Nicholson, it might be said that the beating of printed sheets with a hammer would not produce the result sought to be attained by dry-pressing, (a) because of the irregularity of the surface of the page necessarily resulting from such treatment; (b) because it would tend to blur the typography and smear the paper, and thus mar, instead of make, the beauty of the page, and (c) because a sudden blow of the hammer would not restore the displaced and elastic fibre to its original place, such result requiring continued pressure. (See Penicks, p. 67, ans. 17; Robertson, pp. 36-7, ans. 4; pp. 89, ans. 66.) And finally Mr. Hood himself admits (p. 115, ans. 34):

"The passages to which I have referred are undoubtedly for the instruction of the bookbinder, and if it is a fact that the printed sheets came to him with the type indentations removed, then the processes described do not necessarily include the removal of type indentations."

In other words his whole theory is built upon the assumption that dry-pressing was done by the bookbinder and not by the printer, an assumption which, as we have seen, is thoroughly disproved by the witnesses on both sides.

In the accounting before the Auditor the defendant again brought forward the smasher, this time as a means open to the defendant at the time of his infringement for accomplishing the same result as that accomplished by the use of the Jones process. The defendant did not directly testify that he had used a smasher for removing type indentations or "dry pressing," but that he had prior to his contract with the State of Pennsylvania done upon it the work he had subsequently done upon the infringing machine (Busch, p. 181, ans. 23). His statement, which was drawn out by a leading question of counsel, was very guarded and its explanation is that, prior to said contract,

Mr. Busch was a bookbinder and, the work of "dry-pressing" being that of the printer before delivering the sheets to the binder (see supra, p.), his experience in pressing printed sheets related only to the solidification of the gathered book for sewing or the other operations of binding. Such solidification is accomplished by the smashing machine (Record, Nicholson, pp. 60-1, ans. 9-10; Robertson, p. 73, ans. 3; Suydam, p. 186, ans. 14, p. 195, ans. 74; Jones, p. 199 ans. 13), and, as it is also accomplished by the Jones Press, the use of the smasher being dispensed with, (Busch, p. 183, ans. 40), he apparently fell into the mistake of considering their principal functions identical; and in his answer to question 30 (p. 182), in giving his reason for purchasing the infringing machine, he practically admitted that the smasher would not "dry-press."

But over against the unsupported and vague testimony of the defendant himself there is the direct and positive testimony of Mr. Suydam, a disinterested witness, and Mr. Jones, both men of very long and extensive experience, that type indentations will not be removed by a smashing machine (Suydam, pp. 194-7, ans. 69-80, 82-85; Jones, pp. 199-200, ans. 12-17; p. 205, ans. 30-32), and the reasons given by these witnesses must commend themselves to the Court, as they did to the Auditor, as conclusive. It is manifest without testimony that long continued and retained pressure is necessary to restore the disturbed and elastic fibres of the paper to their original seats, and such is the testimony of the witnesses on this point (Penicks, p. 67, ans. 17; Robertson, pp. 36-7, ans. p. 89, ans. 66; Suydam, ut supra, Jones, p. 169, ans. 14); while the dwell of pressure in the smashing machine is less than a quarter of a second (Jones, Rec., p. 199, ans. 14), and hence is relatively small, (Suydam, p. 191, ans. 47), and is manifestly insufficient to permanently efface the indentations. If the smashing machine could accomplish such purpose, it is astonishing that so distinguished a printer as DeVinne should have found that the Jones process enabled him "to dry press work which before was never dry pressed at all," e. g.; the "Century Magazine" (Record, p. 56, ans. 23).

We must here call attention to what is, no doubt, an unintentional misquotation in Appellant's brief (p. 13), of a definition of "smashing machine" said to be contained "in the dictionaries," viz: "A heavy and quick press used by bookbinders to flatten and smooth and make solid the springy folds of books before they are sewed." The particular dictionary is not named, but, inasmuch as in his brief in the court below the Appellant referred to a somewhat similar definition in the Century Dictionary, we may infer that the latter is the definition the quotation of which is attempted. The "Century" definition is: "A heavy and quick press used by bookbinders to flatten and make solid the springy folds of books before they are sewed." mention is made of "smoothing," nor have we discovered any definition which does make such mention. But placing side by side the Century Dictionary's real definition of "smashing machine" and its definition of "dry-press," erroneously attributed by Appellant to the Standard Dictionary, viz: "Dry-Press-In printing, a press for smoothing printed sheets," the difference between the functions of the two machines clearly appears. The one is "in printing" "for smoothing printed sheets," i. e., for removing type indentations, &c. The other is "used by book binders to flatten and make solid the springy folds of books before they are sewed.

It thus appears that the only process of "dry-pressing" printed sheets in use prior to the date of the application by Jones for the patent in suit was the "ponderous oldstyle of pressing sheets between fuller boards," above briefly outlined and more fully described by plaintiff's witnesses, Robertson (1st deposition, pp. 35-7, ans. 4; 2nd deposition, p. 77, ans. 7) and Jones, (p 31, ans. 38), and to some extent by Grier (pp. 15-16, ans. 37 and 46-8), and DeVinne (pp. 54-6, ans. 4-14), and by defendant's witnesses Schrank (p. 168, ans. 33-35), Davis (p. 175, ans. 26-9), and Hood (p. 100, ans. 4). (See also Suydam, pp. 185-6, ans. 10-11, p. 188, ans. 28.)

THE JONES INVENTION.

Such being the state of the art Mr. Jones, who was at that time Superintendent of Public Printing of the State

of Pennsylvania, startled printers by the announcement of the process covered by the fifth claim of his letters patent here in suit. As we have seen, in the process used prior to the invention of Mr. Jones, sheets were drypressed only (1) after being thoroughly dried, (2) unfolded and laid flat in the press, (3) between fuller boards and (4) by retaining them under pressure in the press until the operation of dry-pressing was completed. The Jones process was an innovation in all four of these particulars. (1) The sheets are pressed wet or dry just as they come from the printing press without the preliminary drving required by the old process, (Penicks, p. 106). (2) They are pressed folded instead of being laid in the press flat. (3) Fuller boards are dispensed with and (4) the bundles, after being tied, are immediately removed from the press, the sheets being retained under pressure between rigid end boards by means of the tie until the process of dry-pressing is completed. All of these matters are important to the trade, involving great saving of space, labor, and expense, and in each of them the new process was a distinct advance in the art, with the general result that the removal of type indentations was performed not only much more expeditiously and cheaply but also much more effectually, and further that work could now be dry-pressed which, by reason of the cumbersomeness of the old process, was formerly not submitted to dry-pressing at all.

The rationale of the Jones process as distinguished from that which preceded it is well stated by Mr. Robertson, and as the matter is one of some little difficulty we take the liberty of quoting at some length from his depo-

sition (Record, pp. 35-7, ans. 4):

"Previous to the invention of Mr. Jones as described in said patent it was the custom to press printed sheets by inserting them between heavy paper boards, sometimes called 'fuller boards,' but geenrally now called 'glazed boards,' and putting said boards with the printed papers between them into a powerful press, by which pressure was produced on said boards by various means, sometimes by means of screw pressure, some-

times by hydraulic pressure. After the pressure was produced on the paper it was continued by allowing the press to remain with its pressure on to its fullest extent for ten to twelve hours or more, say from one night to the next morning, when the pressure was removed, the papers and boards taken from the press and separated by removing the boards from the pile of combined boards and paper, and putting the boards on one side on one pile and making another pile of printed papers. was necessarily comparatively a slow process, inasmuch as with one press only as much printed paper as the press would hold when put between the boards could be pressed in about ten to twelve hours, so that where much work had to be done a number of such presses were necessary. It was also costly as to labor, because the sheets had to be placed between the boards and removed therefrom afterwards, which took much time, especially where, as in the case of fine work, only one sheet was placed between two boards; and when this was done comparatively few sheets could be pressed at once because the boards took up much more room than the paper did, they being quite thick.

By the process set forth in the patent the printed sheets are not allowed to remain in the press for any considerable length of time, but only long enough for the operator to tie up the bundle, when they are immediately removed, the entire process of putting the paper into the press, tying it up in the bundle and removing

it therefrom taking but a few minutes.

As the entire operation, so far as the use of the press is concerned, only takes but a few minutes, which may be from two to five for each bundle, a large number of bundles may be pressed and tied up in the course of a day, and left tied up between the boards with the pressure upon them as long as is thought necessary to smooth out the impression produced by the printing press, or until the signatures may be wanted by the binder to complete the operation of making the book for which the signatures are printed. The printed paper or signatures are thus allowed to remain for a considerable time tied up in bundles, which time may be from twenty-four hours to three or four days, but may be extended to a year or more, the longer the

better, as it is upon the time in which the bundles remain tied up subject to pressure between the boards that the smoothness of the printed paper depends, the mere pressure produced by the press in the short time the paper remains in it having comparativaly little effect upon the impression produced by the printing press. The pressure of the press and the mere tying up would produce but little effect if the signatures were immediately untied as soon as they were removed from the press and the long-continued pressure after the bundle has left the press is therefore an essential part of the process, and without which it would not be much of a success. There is one important difference between the old process and the new that I think has much to do with the success of the process set forth in the Jones patent, No. 204,741. the old plan where two or more sheets were set between boards the convex side of the impression on one sheet came in contact with the concave side of the sheet above it, so that these sheets would have little or no effect upon each other in smoothing out the impression produced by the printing press, and especially would this be the case where half a dozen or more sheets were placed between two boards. In the new process described in the Jones' patent under consideration, the sheets when folded have the convex impression of one-half of a sheet brought in contact with the convex side of the other half of the sheet by the act of folding the sheet in two, provided the sheet when being folded had its convex side of the impression uppermost. If, on the contrary, the concave side of the impression were uppermost, the concave part of the sheet would be folded together, but on the second fold the cenvex sides would come together in the center of the fold, so that under any circumstances the convex part of the impression on one sheet would be pressed by or come in contact with the convex impression on the same sheet, or with the convex impression of another sheet coming next to it, and thus the convex impressions coming in contact with each other tend, when under pressure, to efface each other, and, as I believe I said before, the longer the pressure is continued by keeping the bundles tied up, the more the impression is effaced and the smoother the paper becomes, so that I regard it as important that, if the process is to be carried out successfully, the paper should be folded so that the convex impressions should come in contact with other convex impressions, and that the bundles of signatures when tied up should remain for a considerable period of time in the tied up condition under the pressure imparted to them by the press.

I have given at some length what I consider the main features of difference between the old and new processes, because in my opinion the process is one that is not easily understood at first, and very few would be likely to understand it unless the essential differences between it and the old process were pointed out."

Again in his second deposition (Record, p. 77, ans. 7), he says:

"In the old fuller board process the printed sheets were laid in an open state unfolded between fuller boards, which are comparatively thick sheets of paper or pasteboard, and the pile of printed sheets and fuller boards was set in the press, generally either a screw press or hydraulic press, and thus great pressure produced upon them. This was generally done over night so that the sheets could be under pressure all night long, and were removed from the press next morning, so as to allow of the press being used for another lot of sheets to be pressed the next night. I should have stated that besides the fuller boards there were a number of wooden boards set at intervals in the pile, and as there were frequently nearly as many fuller boards as sheets of printed paper, comparatively few sheets could be pressed at a time in a large press. As a consequence many presses were required in a large establishment, and many employes required to fill and empty the press.

In the Jones process the sheets are folded ready for the binder, and are then inserted in the bed of the press with the folded edges all in line, and with end boards at top and bottom of the bundle, after which the press is set in motion until the requisite pressure has been produced, when the operator passes the tie string around the bundle in one direction and then in the opposite direction and secures the end of the tie. The pressure is removed by running the head of the press away from the bundle and the latter removed for storage or carried to the binder, as desired, after which another lot of signatures is set in the press and pressed and tied as before, so that with one press a very large number of sheets could be dry-pressed and tied in bundles in a very short time, and with even better results as to removing indentations than when the sheets are pressed between fuller boards in a hydraulic press. These better results are due mainly to the fact that in the old-fashioned process, when two or more sheets are set between each two fuller boards, the concave part of one impressed sheet would rest upon the convex part of another; whereas in the Jones process one-half of the impressed convex indentations came into contact with corresponding convex indentations on the adjacent pages, whereby each convex indentation acted upon the convex indentation on the other page, and thus tended to flatten each other out."

The difference between the two processes, so far as concerns the relation to each other of the concave and convex sides of the type indentations, may be thus graphically shown:



Fig. 1, representing the old process with the unfolded sheets, flat as they come from the printing press, laid between fuller boards and the consequent meeting of convex and concave sides of the impressions, and Fig. 2, representing the Jones process, in which no fuller boards are interposed and the folded sheets present convex side to convex and concave to concave. The bundle resulting from the Jones process is shown in "Complainant's Exhibit, Cut of Jones Bundle of Printed Signatures," and is as follows:

Fig. 3.



That the process invented by Mr. Jones was a surprise to those specially skilled in the art is shown by the testimony of the witnesses Penicks and DeVinne. The former, who was superintendent of the folding room of the Government Printing Office, at Washington for 25 years, thus narrates his doubts as to the feasibility of the Jones process and his astonishment at its results (pp. 64-5, ans. 5):

"In the year 1878 the Hon, John Defrees was Public Printer. He sent for me and Mr. Oliver Reed, who was then foreman of the press room, and said to us: 'There is a man by the name of J. W. Jones, who has invented a machine for removing indentations of type from sheets after they are folded. He has this machine running at the State Printing Office, at Harrisburg, Pennsylvania. I want you to act as a committee and go to Harrisburg, see this machine in operation and investigate the work.' We felt very skeptical about the claims of Mr. Jones for removing the indentations of type in signatures after they were folded, so we thought we would take some of the work that was printed in the Government Printing Office. We were not willing to go there and see the work that was printed by them and pressed. We took five hundred octavo sheets and five hundred quarto sheets. These signatures were given a heavy dose of ink for this especial purpose, and at the time I thought we were putting up a job on the Jones press, and that it would be impossible for them to remove the indentations of type from these thousand signatures, and there would be no set So we went to Harrisburg, carried the thousand sheets to the State Printing Office, examined the workings of the Jones signature press, saw our thousand sheets pressed. We then sealed the bundles for fear that some one might tamper with them in our These sheets were pressed at noon. next morning we went to the State Printing Office and found the seals of the bundles unbroken. We opened the bundles, examined the sheets carefully, and to our astonishment the indentations of type were removed, and there was no set off of color, and the sheets were perfectly smooth. We then returned to Washington with the thousand sheets, showed them to the Public Printer, and made a favorable report upon the work done by the Jones signature press. We recommended to him that he purchase one machine on trial."

And Theodore L. DeVinne, one of the most distinguished printers in America, formerly a junior partner and subsequently the head of a famous printing house, as an official of the well known society of Typothetae, taking "much interest in everything that related to the development of the printing art," acquainted with the literature of the subject and informed by personal observation of the processes used in the great printing houses of New York City, himself an author of books and contributions to trade and other journals in this country and England on the subject of printing, the printer of such publications as the "Century Dictionary," and the "Century Magazine," testifying specifically that at the date of the Iones application for the letters patent here in suit he was acquainted with the processes then in use, and that "it was part of" his "business to know all useful processes for dry-pressing"—this witness, thus pre-eminently qualified to testify as a practical expert with regard to the art in the successful prosecution of which he spent over a half century, testifies (p. 57):

"Q: 24. In what, as you understand it, do the chief

features of the Jones process consist?

A. First—the novelty of pressing sheets in bulk after folding, without any press board between to protect against set-off. I disbelieved in the possibility of the process until I was convinced by its practical working."

The idea of dry-pressing folded sheets was not new to this witness, and some process by which it could be done was apparently greatly desired by him.

"Q. 25. Was it possible by the methods in use prior to October 24th, 1877, to dry-press sheets in bulk after folding?

A. It was not possible. I had tried it many times to

my sorrow and spoiled the work."

But it was Mr. Jones who taught those skilled in the general art of the process by which folded sheets might be dry-pressed, and that without the use of "fuller" or "press boards."

The same witness continuing his answer to question 24, states a second chief feature of the Jones process:

"Second. In the novel methods used for retaining pressure on these printed signatures after they left the press."

"Q. 30. What are the novel methods of retaining pressure upon the printed sheets after they have left the press in the Jones process as referred to in your answer to question 24?

A. To me the novelty consists in tying up the pressed signatures between hard wood boards in such a manner that the pressure is not relaxed."

Both DeVinne and Penicks considered the Jones process a distinct advance upon the process preceding it. The former testifies:

"Q. 18. Have the Jones press and process been in continuous use in your establishment since 1879?

A. They have.

Q. 19. Please state the results of the use of the Jones press and process as compared with the old method of dry-pressing described in your preceding answers?

A. It does better work and at less cost. It saves waste of paper, and allows pressed signatures to be stored and handled with greater facility.

Q. 20. In what respect does it do better work?

A. The pressing is more uniform. In the old process of pressing by a screw or hydraulic press it often happened that indentations in some corner were not thoroughly removed.

Q. 21. Are they thoroughly removed by the Jones

press and process?

A. They are. The pressure is uniform throughout.

Q. 22. Do you or not consider the Jones process an advance upon the processes in use prior to October 24, 1877?

A. I do so consider it.

Q. 23. In what respect and to what extent; please

state as fully as you think proper?

A. It enables me to dry-press work which before was never dry-pressed at all. When the "Century Magazine" had the comparatively small circulation of 60,000 copies a month, we wanted to dry-press it by hydraulic presses, at that time the best machines in use. We made calculation as to the number of presses that would be required and the amount of space that the presses would occupy, and the cost of doing the work, and we gave up the project as being entirely impracticable. We got the Jones dry-presser at a later date because it seemed to us the only machine that could do the work quickly and with reasonable economy. We have also applied Jones dry-presser to many other books. The workmanship done by it has always been satisfactory to binder and publisher. This machine has enabled us to do a great deal of work, and do it well, within little time."

Mr. Penicks testifies on the same general subject as follows (p. 65 ans. 7-9):

"A. There was a great improvement in the appearance of the work, the indentations were removed uniformly, and there was a glossy surface produced by the signature press that was not obtainable from the old style of hydraulic pressing. The work pressed by these machines was advantageous, there being no waste of signatures that necessarily came from handling by the old process, and the large saving by the process made the saving to the Government, the cost of the work, comparatively nothing.

Q. 8. Did you or not consider the Jones press and

process an advance in the art?

A. Most undoubtedly. It is one of the best pieces of machinery that was ever introduced into the printing and book-binding trades.

Q. 9. In what, as you understand it, did the novelty

of the Jones process consist?

A. The novel part of it to me was the fact that you could remove the indentations of type after the signatures had been folded, something that was never heard of before in my experience in the trade; also the uniform manner in which the signatures were pressed, removing all the swell in the head, back, and front of the sheets which necessarily occurs in folding; and the solidity of the bundles for books, making the signatures and bundles after being pressed as hard almost as a rock."

He then proceeds to state (ans. 11) the number of sheets which can be dry-pressed by the Jones process, ranging from 50,000 to 75,000, in a day of eight hours. and says that no man should be allowed to operate a machine "who does less than 50,000 in eight hours," and (ans. 22) states that in the Government Printing Office. by the old process about 24,000 sheets were dry-pressed per day in a single press at a cost in wages of \$12, while by the Jones process 50,000 sheets were dry-pressed in the same time in a single Iones machine at a cost in wages of \$2.40, a saving in wages per machine of \$0.60 per day, with more than double the output. The same witness, in his report to the Public Printer under date of August 3. 1886, (Complainant's Exhibit Thomas B. Penicks' letter of August 3, 1886, printed record, p. 91), states more fully the saying by the Jones process, and particularly that after the introduction of the first four Jones machines the pay rolls were reduced about \$68 per day.

Mr. Penicks in his deposition and in his several letters to the Public Printer, which are in evidence (printed record, pp. 90-91), states other items of great economy besides the mere saving in wages and great advantages resulting from the use of the Jones process other than that

of economy.

Use of the Palmer Press No Anticipation of Claim 5.

In the face of all this, however, we are told by defendant's expert, Mr. Hood, that there is no invention in the process covered by the 5th claim of the Jones patent. We have seen that in his want of familiarity with the arts of printing and book binding he was misled by certain passages cited by him from printed publications, into the belief that the processes therein described were processes of dry-pressing, whereas in fact they related to entirely

different matters, and were applied to sheets gathered into books after being dry-pressed. Still more remarkable perhaps is his assertion with regard to the Palmer press—a crude bundling machine, concerning the proof of which more will be said hereafter—to wit (ans. 5):

"The process used in connection with the press shown in the Palmer sketch and described by the witness Schrank in his answer to question 22, is the same process as that described in claim 5 in the Jones patent in suit."

This assertion is made in the face of the testimony of defendant's witness Schrank and others that, (1) the Palmer press was not used for the purpose of removing type indentations, but merely for the purpose of tying up sheets in bundles for storage, "just for making a neat bundle out of it for storage" (Schrank, pp. 167-8, ans. 36, 20-21, 32; Davis, p. 175, ans. 22-3; McKee, ans. 12); (2) the sheets were already dry-pressed by the printer by the old fuller board process before being delivered at the Palmer bindery (Schrank, p. 168, ans. 33-35; Davis, p. 176, ans. 26-29); (3) instead of the rigid end boards used in the Jones process for the purpose of distributing and retaining distributed the pressure upon the sheets, old pieces of paste-board were placed on the ends of the bundles to prevent the sheets from being cut by the cords (Schrank, p. 168, ans. 37-8)-"pasteboard or binder's board," "to protect the sheets from being soiled. Paper would answer just as well" (Davis, p. 176, ans. 31-2); (4) the bundles were so loosely tied and apparently so crooked that when removed from the press it was the practice of the workmen to straighten them by knocking them upon the floor (Schrank, pp. 167-9, ans. 28-30), and (5) the press was incapable of being used for dry-pressing (Davis, p. 175, ans. 25).

It is apparent from the absence of the rigid end boards and the substitution therefor of flexible pasteboard, as well as the loose and crooked character of the bundles, that dry-pressing could have been neither aimed at nor attained in the use of the Palmer press as described by defendant's witnesses, and that Mr. Hood's opinion on

this point is as unwarranted as his opinion with regard to the "beating," "rolling" and "smashing" processes. And it is evident that the straightening of the bundles by knocking them upon the floor would cause the rubbing of the raised surfaces produced by the type indentations and thus smear and blur the sheet and wholly defeat the result so neatly attained by the Jones process, to wit: the removal of the type indentations without set-off; while the use of flexible pasteboard in place of rigid end boards would permit bulging in the middle of the bundle and thus, while perhaps to some extent effacing the indentations at the edges, would fail to efface them in the center of the page and thus produce work which would not be accepted by the publisher.

That the bundles of the Palmer press were loose and crooked is not surprising as it contained no guides to keep the gathered books pressed in it straight in piling. "We only used our eye in piling" (Schrank, p. 167, ans. 28), the pile as it rose apparently being steadied by the hand of the operator. Moreover it appears to have been impossible to pile sheets in with their backs all one way, and hence the gathered books "were piled up" back and front or "head and tail," an arrangement not conducive to good work in dry-pressing. On this point Mr. Penicks says, speaking of the trough of the Jones machine (pp. 66-7, ans. 15-16):

"Q. 15, In the Jones machine did the inclined trough perform any special function? If so, please state what it was.

A. Yes; the incline of the trough allowed the trough to be filled with signatures with the backs all one way, and the heads all one way, which otherwise could not be done by one person in an upright machine, as it would be almost impossible to pile up sheets a foot high with backs and heads all one way.

Q. 16. Was there any advantage in having the sheets with the heads all one way?

A. Yes; if the heads and backs were not laid all one way in pressing, the sheets would undoubtedly slip and the heads or backs of the sheets would be twisted and

kinked, and by the sheets all lying one way it brings all the printed matter exactly over printed matter and thereby the indentations of type are more easily removed."

And he might have added that in the operation of drypressing the slipping of the sheets under pressure would undoubtedly break the protecting film of the ink and cause the sheets to be smeared and blurred.

Of Mr. Hood's conclusions with reference to the use of Palmer press Mr. Robertson speaks as follows (p. 76, ans.

3):

"In looking over my testimony, I find I omitted any reference to Mr. Hood's conclusions in reference to the Palmer press. As I understand such press, it is simply used for making bundles of signatures after they have been folded, so that they could be conveniently stored, and was not designed or used for the purpose of taking out indentations, nor were the bundles capable of being tied up in the same manner as they could be in the Jones press. As stated by the witnesses who gave evidence as to the construction of said press, it was necessary to lay two strings across each other in the bottom of the press, which strings were tied separately after the pressing was completed, thus entailing two operations where one only is necessary in the Jones press. I do not believe that the process carried out by the Palmer press is the same process as that described in claim 5 of the Jones patent, for the process of dry-pressing had already been carried out on the sheets before they were folded, as testified to by the witness Schrank in his answer to question 33; but independent of this, as there were no rigid end boards used it is impossible that the process referred to in claim 5 could have been carried out, even if the press had been powerful enough to produce the necessary pressure, which I doubt, especially in view of the fact, as stated by one of the witnesses who testified about the press, that when the bundles were crooked they could be straightened by striking them on the floor."

The difference between the bundles of the Palmer press and those of a signature press like the Jones press or the press used by the defendant is apparent. The former were loose and crooked while those of the Jones press were "hard as a rock" (Penicks, p. 65, ans. 9), and those of the defendant's press were so compact that the point of a blade of a pocket knife could only with difficulty be forced between the sheets (Jones, p. 26, ans. 8.)

The Patents Cited as Anticipations of Claim 5.

Not less unwarranted is Mr. Hood's assumption that the Jones process is anticipated by the processes of baling hay and stable manure, described in letters patent Nos. 125,786 (baling short cut straw or hay), 169,518 (baling hay) and 181,389 (baling manure and other substances). One of the necessary elements of the Jones process is the use of the "rigid" "end boards," "of suitable size to nearly match the size of the folded work" for the purpose of distributing "the pressure over the whole area of the ends of the bundle." Mr. Robertson describes these functions on page 42 (ans. 11-13) printed record, to which the Court is respectfully referred.

Mr. Hood himself says (Record, p. 117):

"Q. 54. What, as you understand it, is the function

of that rigid end board in the Jones patent?

A. It is to distribute the pressure over the whole area of the ends of the package, and also to prevent cutting or marring the pages with the twine used in binding or tying the package."

Turning now to the patents cited by Mr. Hood, we find that the invention in No. 125,786 "consists in a hollow cylindrical bale, braced at the ends by segmental wooden strips and hoops, cords or wires, arranged to extend across the strips and down the sides of the bale on planes parallel to the axis of the latter, whereby said hollow bale is very effectually bound without impairing its ventilation," the purpose of the use of the segmental wooden strips being not "to distribute the pressure over the whole area of the ends of the bundle," but to expose as much of the ends as possible and thus secure ventilation. In No. 169, 518, "four sticks," which may be "sticks previously employed for baling long hay or other rough sticks," are arranged on the four edges of the ends of the top and bot-

fom of the bundle, "the cross edge sticks BB," overlapping "the longitudinal edge sticks AA," and being held in place "by two or more thin wood slats CC," "arranged at a distance of two or three inches apart," one of the objects of the invention apparently being to avoid "a close covering on the same side of the bale" and thus to afford an opportunity for "evaporation." The invention alleged in No. 181,389, is substantially the same as that in No. 169,518, omitting the cross-slats CC of the latter, the only pressure on the bale being left as open as possible to "provide desirable ventilation." It is, therefore, perfectly manifest that the "segmental wooden strips," "sticks," "slats" and "frames" shown and described in these patents are not in any sense the equivalents of the end boards described in the Jones patent and clearly shown in his drawing, Fig. 2, and that they do not perform the same function. Upon this subject Mr. Robertson testifies as follows (p. 74, ans. 3):

"Referring to the patents in the order in which Mr. Hood has mentioned them, I find that No. 181,389, issued to J. B. Archer, was for a patent for 'Baling Manure and other Substances.' In said patent there is shown a bale held under compression by means of cross-ties, and an open frame at top and bottom, and which open frames are incapable of producing the result aimed at in the Jones patent, for instead of removing indentations from sheets of paper, it would produce much worse indentations or impressions than those produced by the act of printing. The same remarks apply to the patents Nos. 169,518 and 125,786. The inventors, if they can be called such, of the bales shown in these three last mentioned patents never had the least idea of tying up the material they used under pressure for the purpose of removing indentations, nor would these patents, in my opinion, suggest to any one such an idea. As a matter of fact, the matter put up in such bales, instead of being smoothed or the indentations removed from it, had a much greater number of indentations put into it by the pressure than it had before it went through the openration of pressing and tving. There is nothing in the patents just referred to, even

when taken in connection with the extracts from the Nicholson work and Cyclopaedia, that would in anywise suggest the discovery made by Mr. Jones, that indentations could be removed from printed matter by the process described in his patent." (See also Penicks, p. 66, ans. 14.)

It is contended at considerable length in appellants' brief that the Jones process might have been practiced on the press of the Dingman patent. The complete answer is that it was not. Moreover it is evident it could not be without such changes in the construction of the press as would involve invention, and, even if the press were suitable to carry it out, it would not follow that the process was not new with Jones.

If it is true that these processes were identical with that of the Jones patent, which as we have seen is considered as of great value by printers, it seems astonishing that they were not earlier applied by such printers as DeVinne, for instance, to the treatment of printed sheets, and that it was left for Mr. Jones to introduce it into the art, after

the grant of his patent in 1878.

But without prolonging the discussion it is confidently submitted that Mr. Hood's theory that the Jones process was anticipated, either by the loose bundling in the Palmer press of sheets already dry-pressed and gathered into books or by the baling of straw, hay and stable manure according to the patents cited, is wholly unwarranted and that upon all the evidence Mr. Jones stands as the inventor of a process of dry-pressing wholly new, clearly useful and involving invention of a very high order and in every respect a great advance in the art.

DOES THE FIFTH CLAIM SET FORTH A PATENTABLE PROCESS?

At the final hearing of this case the only defenses set up to the 5th or process claim of the patent were those suggested by defendant's expert witness, Mr. Hood, and above discussed, viz: anticipation and want of invention. The motion to vacate the interlocutory decree was, however, mainly based upon a new defense, viz: that the 5th

claim was not a valid process claim within the intimations of the Supreme Court in Risdon Locomotive Works v. Medart, 158 U. S., 68. This defense was thus brought forward for the first time, nearly three years after the entry of the interlocutory decree, although the final hearing was had six months after the decision of the case referred to, and, as no intimation of this defense was given during the taking of the testimony, of course no expert evidence addressed to it was given on either side.

The Medart case did not announce, and was not intended to announce any new doctrine and all that it actually decides is that "a valid patent cannot be obtained for a process which involves nothing more than the operation of a piece of mechanism, or, in other words, for the mere function of a machine," (p. 77); and such is stated to be its effect in Westinghouse v. Boyden Power Brake Co., 170 U. S., 537, 556. But in the Medart case Mr. Justice Brown, in delivering the opinion of the Court, after remarking: "that certain processes of manufacture are patentable is as clear as that certain others are not, but nowhere is the distinction between them accurately defined." said:

"It may be said in general that processes of manufacture which involve chemical or other similar elemental action are patentable, though mechanism may be necessary in the application or carrying out of such process, while those which consist solely in the operation of a machine are not. Most processes which have been held to be patentable require the aid of mechanism in their practicable application, but where such mechanism is subsidiary to the chemical action, the fact that the patentee may be entitled to a patent upon his mechanism does not impair his right to a patent for the process; since he would lose the benefit of his real discovery, which might be applied in a dozen different ways, if he were not entitled to such a patent. But, if the operation of his device be purely mechanical, no such considerations apply, since the function of the machine is entirely independent of any chemical or other similar action."

This language has been much misinterpreted and has created the impression among some that no process is patentable which is in its nature mechanical and does not involve "chemical or other similar elemental action." But it is not so held, and the same learned Justice in the more recent case of Westinghouse v. Power Brake Co., declares the question to be an open one. He there says (p. 556-7):

"Most of the prior authorities upon this subject are reviewed in the recent case of Ridson Locomotive Works v. Medart, 158 U. S., 68, in which it was also held that a valid patent could not be obtained for a process which involved nothing more than the operation of a piece of mechanism, or the function of a machine. See also the same effect Wicke v. Ostrum, 103 U. S., 461, 469. These cases assume, although they do not expressly decide, that a process to be patentable must involve a chemical or other similar elemental action, and it may be still regarded as an open question whether the patentability of processes extends beyond this class of inventions."

And a little further on in the same opinion he shows that processes involving neither "chemical or other similar elemental action," such as manufacturing paper bags and weaving hammocks, have been held patentable by respectable authorities, and he cites Eastern Paper Bag Co. v. Standard Paper Bag Co., 30 Fed. Rep., 63; Union Paper Bag Manufacturing Co. v. Waterbury, 39 Fed. Rep., 389; Travers v. Am. Cordage Co., 64 Fed. Rep., 771, to which other cases might be added.

Two things, which are important in our discussion, are clear from the language of Mr. Justice Brown in the Medart case; 1st, That a process may be patentable which involves the use of mechanism, and 2nd, That in such cases, the inventor may be entitled to patents upon both his mechanism and his process. And these propositions are fully supported by all the cases in which process patents are considered.

The Cases Involving Process Claims.

It may be well to briefly review the more important cases upon the subject of process claims.

In O'Reilly v. Morse, 15 How., 62, Chief Justice Tawney, in the opinion of the Court, said (p. 119):

"Whoever discovers that a certain useful result will be produced, in any art, machine, manufacture, or composition of matter, by the use of certain means, is entitled to a patent for it; provided he specifies the means he uses in a manner so full and exact, that any one skilled in the science to which it appertains, can, by using the means he specifies, without any addition to, or subtraction from them, produce precisely the result he describes. And if this cannot be done, by the means he describes, the patent is void. And if it can be done, then the patent confers on him the exclusive right to use the means he specifies to produce the result or effect he describes, and nothing more. And it makes no difference, in this respect, whether the effect is produced by chemical agency or combination; or by the application of discoveries or principles in natural philosophy known or unknown before his invention; or by machinery acting altogether upon mechanical principles."

In Tilgham v. Proctor, 102 U. S., 707, 728, Mr. Justice Bradley, after quoting the above language of the Chief Justice in O'Reilly v. Morse, said:

"It seems to us that this clear and exact summary of the law affords the key to almost every case that can arise. 'Whoever discovers that a certain useful result will be produced in any art by the use of certain means is entitled to a patent for it, provided he specifies the means.' But everything turns on the force and meaning of the word 'means.' It is very certain that the means need not be a machine, or an apparatus; it may as the court says, be a process. A machine is a thing. A process is an act, or a mode of acting. The one is visible to the eye,—an object of perpetual observation. The other is a conception of the mind, seen only by its effects when being executed or performed. Either may be the means of producing a useful result."

It is true that Mr. Justice Bradley, immediately following the above passage, instances as process "the heating of a substance to a certain temperature," which would

probably involve "elemental action. But this was merely an illustration and there was no evident thought of restricting the notion of "patentable process" to cases of that kind. On the contrary, he said broadly: "A process is an act or a mode of acting." It is also true that in Corning v. Burden, 15 How., 252, 257-8, Mr. Justice Grier, in delivering the opinion of the Court, speaks of processes "by chemical action" and "by the operation or application of some element or power of nature," and instances the arts of tanning, dveing, making water-proof cloth and vulcanizing India-rubber, and, further on, says that "the term process * * * * will include all methods or means which are not effected by mechanism or mechanical combinations." But he also expressly refers to the "application * * of one substance to another" as a process. He is here distinguishing between a process and the mere function of a machine, and his language should be read in connection with what he said. at the same term, in his dissenting opinion in O'Reilly v. Morse, supra., with respect to the patentability of the art of printing, which is purely mechanical and does not "involve chemical or other similar elemental action." He said (pp. 131-2):

"The great art of printing, which has changed the face of human society and civilization, consisted in nothing but, a new application of principles known to the world for thousands of years. No one could say it consisted in the type or the press, or in any other machine or device used in performing some particular function, more than in the hands which picked the types or worked the press. Yet if the inventor of printing had, under this narrow construction of our patent law, claimed his art as something distinct from his machinery, the doctrine now advanced, would have declared it unpatentable to its full extent as an art, and that the inventor could be protected in nothing, but his first rough types and ill contrived press."

This illustration doubtless did not support the contention of the learned Justice in favor of Morse's 8th claim, but, we submit, it does conclusively demonstrate the pat-

entability of an art or process which is wholly mechanical and involves neither "chemical" nor "other similar elemental action."

In Cochrane v. Deener, 94 U. S., 780, Cochrane had at the same time taken out five patents relating to the bolting of flour, one of which was for the process and the remaining four were for apparatus for carrying out the pro-The process consisted of passing the ground meal through a series of bolting-reels clothed with cloth of progressively finer meshes, which passed the superfine flour and retarded the escape of the finer and lighter impurities; and, at the same time, subjecting the meal to blasts or currents of air introduced by pipes so disposed that the force of the blast might act close to the surface of the bolting cloth; by which means the superfine flour was separated and the impurities got rid of. It was held that the patent was valid and that the patentee was not limited to any special arrangement of the machinery. delivering the opinion of the Court, Mr. Justice Bradley used this oft-quoted language:

"A process is a mode of treatment of certain materials to produce a given result. It is an act, or a series of acts, performed upon the subject-matter to be transformed and reduced to a different state or thing. If new and useful, it is just as patentable as is a piece of machinery. In the language of the patent law, it is an art. The machinery pointed out as suitable to perform the process may or may not be new or patentable; whilst the process itself may be altogether new, and produce an entirely new result. The process requires that certain things should be done with certain substances, and in a certain order; but the tools to be used in doing this may be of secondary consequence."

In commenting upon Cochrane v. Deener in the Medart case, Mr. Justice Brown said (p. 76): "It will be observed in this case that the process for which the patent was sustained was not chemical in its nature, but, as stated in the opinion of the Court, was a series of acts performed upon the subject-matter to be transformed and reduced to a different state or thing." And it is to be further

observed that the blast of air which rendered effective the purifying operation was produced by the purifying apparatus. Perhaps the distinguishing feature of the case is the fact that the inventor, after having, by means of his apparatus, set in motion the currents of air, availed himself of the elemental quality of the air, viz: its fluid action, for floating the lighter impurities and depositing the heavier flour, but the case appears to be a complete answer to the view that mechanical processes, even when carried on by the use of machinery, are necessarily unpatentable, and overwhelmingly refutes the suggestion made by some that no process is patentable which does not involve chemical action.

In New Process Fermentation Co. v. Maus, 122 U. S., 413, where the process was one of clarifying beer, and hence was, at least to some extent, chemical, Mr. Justice Blatchford, in delivering the opinion of the Court, said (pp. 427-8):

"Within the rules laid down by this court in Corning v. Burden, 15 How., 252, 267, in Cochrane v. Deener, 94 U. S., 780, 787, 788, and in Tilghman v. Proctor, 102 U. S., 707 722, 724, 725, we think that the method or art covered by the third claim of the patent is patentable as a process, irrespective of the apparatus or instrumentality for carrying it out. It is the performing of a series of acts upon the beer in the kraeusen stage, producing new and useful results in the art of making marketable beer."

and, after briefly describing the process, he continued:

"This is, as was said in Cochrane v. Deener, 'a mode of treatment of certain materials to produce a given result,' and 'an act, or a series of acts, performed upon the subject matter to be transformed and reduced to a different state or thing,' and 'requires that certain things could be done with certain substances, and in a certain order.' It is, therefore, a process or art. The apparatus for carrying out the process is of secondary consequence, and may itself be old, separately considered, without invalidating the patent, if the process be new and produces a new result."

It is to be observed that although "chemical or other similar elemental action" was here involved, there is no mention of that fact and no attempt is made to limit the definition of art or process by it. On the contrary, the definition is stated broadly and the decision of the case is put upon the same broad ground as that in Cochrane 7. Deener.

In Eames v. Andrews, 122 U. S., 40, the Driven Well Patent was broadly sustained, after much, very protracted and hotly contested litigation. The claim in that patent was as follows: "The process of constructing wells by driving or forcing an instrument into the ground until it is projected into the water without removing the earth upward, as in boring, substantially as herein described." Here again every step and every instrumentality employed in the process was mechanical, but here again it may be said that the inventor availed himself of the tight packing of the earth around the driven tube to form an air-tight connection with the surrounding earth and thus relieve the water in the well from atmospheric pressure; and to that extent the process involved "elemental action."

In Lawther v. Hamilton, 124 U. S., I, the patent was for a process of extracting oil from seeds. Prior to the invention of Lawther the method used was: (1) Crushing the seed between revolving rollers; (2) passing the crushed seed through muller-stones, by which it was pulverized; (3) treating with heat and moisture, by steam or otherwise, and (4) finally subjecting to hydraulic pressure, by means of which the oil was extracted. The inventor ascertained, "by practice, that in crushing the seed the tearing, pulverizing action of the muller-stones was injurious, and so he dispensed with that mechanical operation in the crushing step of the process, and employed the rollers alone. He thereby simply omitted one of the instrumentalities previously used in the first stage of treatment of the seed." The Court below held the patent to be invalid upon the ground that, although the omission of the muller-stones was a useful improvement yet, as each step in the process was old, to wit: the crushing of the seed, heating and moistening it and finally the application of hydraulic pressure, "the discovery or invention was not of a new series of acts or steps constituting the process, but only of certain mechanical changes in carrying into effect the well-known old steps of the process;" and while he might be entitled to a mechanical patent, he was not entitled to a process patent. The Supreme Court in reversing this decision, Mr. Justice Bradley delivering the opinion, said:

"The view thus taken by the Court below seems to us open to some criticism. If, as that Court says, and we think rightly says, the omission of the mullerstones is a real improvement in the process of obtaining the oil from the flaxseed; if it produces more oil and better oil cakes, and it is new, and was not used before; why is it not a patentable discovery, and why is not such new method of obtaining the oil and making the oil cakes a process! There is no new machinery. The rollers are an old instrument, the mixing machine is old, the hydraulic press is old; the only thing that is now is the mode of using and applying these old instrumentalities. And what is that but a new process? This process consists of a series of acts done to the flaxseed. It is a mode of treatment. first part of the process is to crush the seed between rollers. Perhaps, as this is the only breaking and erushing of the seed which is done, the rollers are required to be stronger than before. But if so, it is no less a process."

It is to be observed that in this case the process was clearly mechanical—unless it should perhaps be thought that the heating and moistening of the seed involved "elemental action"—and the Court limited the invention to the use of the kind of instrumentality described for crushing the seed, to wit: "powerful revolving rollers." See also remarks of Mr. Justice Blatchford upon this case in Crescent Brewing Co. v. Gottfried, 128 U. S., 158, 168.

We have already cited several cases decided by Circuit Courts and referred to by Mr. Justice Brown in Westinghouse v. Power Brake Co., in which process patents for making paper bags and weaving hammocks were sus-

tained by such experienced and eminent patent lawyers as Judges Colt, Wallace and Coxe. To these may be added several cases decided since the Medart case and in which that case was considered.

In Am. Fibre-Chamois Co. v. Buckskin-Fibre Co., 72 Fed. Rep., 508, the Circuit Court of Appeals in the Sixth circuit held patentable "a process of rendering wood-fibre paper soft and pliable by moistening it with a thin water solution of gelatin, then crumpling and pounding it and finally drying and smoothing it." It is true that Judge Taft, in delivering the opinion of the Court, in reply to the contention that the process must be held invalid under the authority of the Locomotive Works v. Medart, thought he saw in the moistening of the paper and the treatment of it in a moistened condition something resembling chemical action, but the decision is put upon the authority of Cochrane v. Deener, and Mr. Justice Bradley's definition of a process there.

In Chicago Sugar Refining Co. v. Glucose Co., 84 Fed. Rep., 977, the Court of Appeals for the Seventh Circuit sustained the validity of a claim for: "The process of treating corn in the manufacture of starch, glucose, and

other products, etc."

The apparatus for carrying out the process was pointed out in the specification and was covered by another patent to the same inventor. In delivering the opinion of the Court, Judge Showalter, after considering Corning v. Burden, Locomotive Works v. Medart, Eames v. Andrews and Cochrane v. Deener, puts the decision upon the ground that the apparatus pointed out was merely "subsidiary to the process," supplying "the conditions under which the process, the operation of natural forces, goes on towards the ultimate result of obtaining from the corn the starch, the oil germs, and the hulls." And elsewhere in the opinion (p. 980) he says: "The apparatus is functional, towards the result intended, only as supplying conditions under which movements and changes of structure due to the natural qualities of the substance treated take place,"-language which is peculiarly applicable to the present case.

In Melvin v. Thomas Potter, Sons & Co., 91 Fed. Rep., 151, Judge Dallas sustained a patent for

"the process of manufacturing linoleum floor cloth, consisting in forming sheets of spongy texture from linoleum composition, cutting these sheets into shapes, arranging the shapes on a block or form, placing the shapes against a canvas, pressing the block until the shapes adhere to the canvas, removing the blocks and finally heating and again pressing the materials, substantially as set forth."

In the course of the opinion he said:

"Notwithstanding the decision of the Supreme Court in the leading case of Corning v. Burden, 15 How., 252, some processes of manufacture are certainly patentable, although no test by which they may be distinguished from those which are not, and which can be definitely applied to all cases, has been authoritatively established, Locomotive Works v. Medart, 158 U. S., 71, 15 Supt. Ct., 745. But no universal test need now be suggested, and I will not venture to propose one. It is sufficient for the present purpose to say that the criterion set up by the respondent can not, in this instance, be adopted. The question is not whether the mode of operation described and claimed by Melvin is chemical or is mechanical, but whether it is in fact a process, or is merely an aggregation of mechanical functions. I find no warrant in the authorities for the assumption that, unless a chemical change be effected by a process, no patentable invention or discovery can be involved in it. It is true that in both Corning v. Burden and Locomotive Works v. Medart processes involving chemical reaction were contrasted with methods which comprise nothing but sucessive mechanical steps to produce a merely mechanical change in the substances operated upon. In doing this, however, the Courts were illustrating, not defining, the difference between a patentable and an unpatentable process."

And after quoting the well-known language of Mr. Justice Bradley in Cochrane v. Deener, he continued, referring to that case:

"This, as was observed in Locomotive Works v. Medart, supra, was said in a case in which a patent was sustained for a process which 'was not chemical in its nature, but, as stated in the opinion of the Court, was a series of acts performed upon the subject-matter to be transformed and reduced to a different state or thing.' This terse description of the process which was held to be patentable in Cochrane v. Deener may, with perfect aptitude, I think, be applied to the process now under consideration."

In Simonds Rolling Mach. Co. v. Hathorn Mfg. Co., 93 Fed. Rep., 958, the Court of Appeals for the First Cirsuit, affirming the Circuit Court (90 Fed. Rep., 201), sustained a patent for

"the method herein described of making rolled-metal forgings by acting upon all parts of a metal bar in spiral lines, so as at each part in succession and upon such lines to cause the bar to rotate, and to strain and spread the metal axially, and compress it to the required shape and size."

In the Circuit Court Judge Putnam had before him the cases discussing the patentability of processes, including Westinghouse v. Power-Brake Co., and he held the invention of the patent to come "within the statutory term 'Art,' in that it involved the application of knowledge or science to effect the desired result and did it;" and with respect to this patent his decision was confirmed by the Court of Appeals. It is to be observed that the method or process of this patent was exclusively mechanical, the mechanism by which it was carried out being pointed out in the patent and in part, at least, covered by a prior patent to the same inventor.

The latest case is Chisholm v. Johnson, 106 Fed., 191, in which Judge Bradford held valid a patent for a process of hulling peas by impact, produced by the operation of a machine, holding, however, that the process involved a new application of the forces of nature.

To these we may add several additional cases decided before the Medart case. In Hake v. Brown, 37 Fed., 783,

Judge Wheeler held valid a claim for "a method of making bevel-edged cards, and ornamenting the edges by piling them obliquely so that the slope of the pack corresponds to the desired bevel, compressing them to hold them in position, beveling, ornamenting and finishing the whole pack on the sloping edge and successively treating the other sides and ends in the same manner." But, as bevel-edged cards were old, and as those made by the process differed from others in no way unless in design, claim two of the same patent, which was for card treated in the manner described, was held invalid.

In Clement Mfg. Co. v. Upson & Hart Co., 50 Fed., 538, Judge Shipman held patentable a claim "for an improvement in the manufacture of cutlery and tools, consisting in simultaneously welding a tubular handle to a blade and closing up the opposite end of the handle by

forging between dies."

It Watson v. Stevens, 51 Fed. Rep., 757, decided by the Circuit Court of Appeals for the First Circuit, the patent in controversy was for the method of and apparatus for compressing shank stiffeners. Two claims were in issue, the first being for the machine and the second for the method in which the machine was used. Both claims were sustained, although the latter covered a method or process which was purely mechanical, no elemental actiom being involved, and was carried out by the use of the machine covered by the first claim.

It may be well to look at the cases which are cited on the other side of the question. In Risdon v. Medart Mr. Justice Brown cites the following cases in which processes have been held not to be patentable, viz: McKay v. Jackman, 12 Fed. Rep., 615; Brainard v. Cramme, 12 Fed. Rep., 621; Gage v. Kellogg, 23 Fed. Rep., 891; Hatch v. Moffit, 15 Fed. Rep., 252; Sickels v. Falls Co., 4 Blatchf., 508; Excelsior Needle Co. v. Union Needle Co., 32 Fed. Rep., 221. But an examination of these cases shows that in every one of them the alleged process was merely the function or operation of a patented machine without any co-operation of forces or instrumentalities outside of the machine. And in most of them the alleged process claim

was an afterthought and was sought to be covered by a reissued patent. The process claim was therefore held void as merely functional and in most of the cases upon the additional ground that it was improperly included in

the reissued patent.

The appellant has cited several cases which may also be examined. In Wells Glass Co. v. Henderson, 67 Fed. Rep., 930, there was a mere aggregation of mechanical functions and in that sense there was no patentable process. In Blakesly Novelty Co. v. Connecticut Web Co., 78 id., 480, a claim for an alleged process was adjudged invalid upon the ground that it involved "merely the use of well-known instrumentalities upon old objects to accomplish the better result, without any change or adaptation except by means of skilful manipulations." In this case Locomotive Works v. Medart was referred to, but considered inapplicable. In Appleton Mfg. Co. v. Star Mfg. Co., 60 id., 411, the Court, after remarking that "the utterances of the Supreme Court upon the question whether or not a mechanical process is patentable are not in clear harmony," and pointing out that in Cochrane v. Deener the process was "entirely mechanical in character and operation," held the patent sued on to be void upon the ground that it covered merely "a discovery of a new use for old devices, which does not involve patentability:" and this was the ground upon which the case had been decided in the Court below (51 Fed. Rep., 284).

The Result of the Authorities Relating to Process Claims.

Whatever suggestion may have been made or doubts raised as to the true nature of a patentable process, the result of the decisions and the reasoning of the Supreme Court and of the best considered cases in the lower courts is, at least, that, while the mere function or mode of operation of a machine is not patentable, yet the fact that a machine or other mechanical appliances are used in carrying it out does not derogate from the patentability of a process, provided something outside of the machine and its mere operation co-operate with it to produce the desired result, and provided, also, the alleged process is not

a mere aggregation of functions, but is a true process, or in other words, "a mode of treatment of certain materials to produce a given result, * * * an act or series of acts performed upon the subject matter to be transformed and reduced to a different state or thing."

The Fifth Claim of Plaintiff's Patent Under the Authorities.

The process consists of seven distinct steps, unless perhaps, the 3rd and 5th should be considered as substantially one: 1st. The folding of the sheets, because by the terms of the claim the process is "for treating folded printed sheets of paper in Dry-Pressing;" and, as they must be first folded before they can be "treated," the claim is to be construed as though it read: "The process herein described for treating printed sheets of paper in dry-pressing, the same consisting of first folding said sheets, and then subjecting a collection of such sheets to pressure without the use of fuller boards, &c." 2d. The insertion of the rigid end-boards. 3rd. The application of the pressure of the press. 4th. The tying of the bundle while under said pressure. 5th. The removing of the pressure. 6th. The immediate removal of the bundle from the press. And 7th. Allowing the bundle to remain tied sufficiently long to fix and complete the dry-pressing.

The fifth claim therefore does not cover the mere operation or function of the patented press. The operation of the press is but one step in the process. Its function is to compress whatever is put into it and this function is exhausted as soon as the power has been fully applied. But the dry-pressing has not yet been done. It is shown by several witnesses that, if the bundle were not tied or after tying were immediately opened, the desired result would not be produced (Robertson, Record, pp. 36-7; p. 89, ans. 66; Suydam, p. 197, ans. 84-5). In order to effect the result of dry-pressing, it is necessary to allow the bundle, not to remain in the press under pressure, but to remain under the pressure outside of the press "sufficiently long to fix and complete dry-pressing;" and it is so expressly stated in the claim. The process was entirely new and, as shown by the witnesses, a very valuable one

in the art. Outside of the mere operation of the machine are the folding of the sheets, which is done before they are put into the press; the tying of the bundle, which is done not by the machine, but by hand, and the subsequent retaining of the sheets under the continued pressure of the tie, which is also outside of the press. Moreover the rigid end-boards are not necessary to the operation of the machine nor even to its practical use for some purposes, but are additional to it, because, for the mere bundling of printed sheets or gathered books, the press could be used without such end-boards, as, e. g., the Palmer Press is said to have been used.

Nor is the process claimed in any sense a mere aggregation of mechanical functions, but each step is necessary to the carrying out of the process and co-operates with every other to produce the unitary desired result. first step, folding, is necessary, not merely because the press used is adapted to receive folded sheets, but because the process can be carried out only by presenting face to face the raised surfaces caused by the printing and, by their action upon each other under continued pressure. causing their effacement. The folding also appears to be necessary because in the operation of folding a film is created upon the ink and smearing and set-off in the pressing are thereby prevented (Suydam, p. 194, ans. 68). The rigid end-boards are necessary, because only by their use is it possible "to distribute the pressure over the whole area of the ends of the bundle," and thereby obtain uniform smoothness over the entire surface of the page. The pressure of the press is necessary to produce the conditions under which the effacement of the type indentations is ultimately effected. The tying of the bundle is necessary, as it is to be removed from the press. removal of the bundle from the press is necessary in order that the press may be utilized for succeeding bundles, otherwise but two press-fulls a day could be dry-pressed. And, finally, the allowing of the bundle to remain tied for a sufficient length of time is necessary, because, as we have seen, the dry-pressing would not otherwise be effective. Each of these steps therefore is essential to the process and co-operates with every other step to produce the result of effacing the type indentations.

If then the process claimed is not the mere function of the machine or a mere aggregation of mechanical functions, why is it not patentable? Certainly it can not be said that it does not clearly fall within Mr. Justice Bradley's definition of a process in Cochrane v. Deener.

The omission of the fuller-boards is also to be noted, for in this respect the case resembles Lawther v. Hamilton; and as in that case the whole improvement resided in the omission of the muller-stones and the providing of crushing rollers more powerful and suitable than theretofore used, so here the improvement in part resides in the omission of fuller-boards, which had always been used in dry-pressing, and at the same time providing instrumentalities suitable for supplying the place of these omitted instrumentalities. It is submitted on the authority of Lawther v. Hamilton that, if there were nothing else in the process but the omission of the fuller-boards, it would be patentable.

The Process Involves "Elemental Action."

But even if the language used in Locomotive Works v. Medart is to be given its broadest possible scope, the claim in question would not be obnoxious to any doctrine either laid down or suggested there, and we submit that it covers a patentable process, because it involves "elemental action," or the operation of natural forces.

As this defense was not raised until very recently, we have not in the record any expert testimony on either side expressly directed to the question. But such testimony is unnecessary, as the validity of our present proposition must be apparent with but slight examination. We have seen that, when the pressure of the press is relieved the indentations caused by the printing are not effaced, and that they are effaced after the bundle has remained under the pressure of the tie for a sufficient length of time and, as Mr. Robertson points out (Record, pp. 36-7), the longer it so remains the better. The effacement of the type indentations is therefore going on in the bundle

after it has been removed from the press and is manifestly due to something which is outside of the mere operation of the press. It is apparent that the fibres of the paper are resilient and spring back upon any relaxation of the pressure, and that the cord with which the bundle is tied is also elastic. The immediate result of relaxing the pressure of the press therefore is that the bundle is to some extent opened or spread and the cord is to the same extent stretched (Suydam, p. 196, ans. 80). The opposing forces, the resiliency of the fibres and the elasticity of the tie, are thus brought into competition, with the result that the latter, being the stronger—for "a powerful tie" is expressly demanded by the terms of the specification (p. 1. line 33, Record, p. 93)—prevails, and the displaced fibres are gradually and surely forced back into their original seats. Moreover, as the raised surfaces of the paper are opposed to each other, the resiliency of the fibres which thus act upon each other, is itself an efficient agency in gradually working back the fibres into the seats from which they have been displaced by the type. Can there be any doubt, then, that this is "elemental action." within the meaning of the language used in the Medart and Westinghouse cases, and is it not as clearly such action as was the action of the current of air in Cochrane v. Deener, the absence of atmospheric pressure in Eames v. Andrews, or the action of heat and moisture in the other cases above referred to?

In the language of the Court of Appeals in Chicago Refining Co. v. Glucose Co., supra, the apparatus pointed out in the patent is merely "subsidiary to the process," "is functional, towards the result intended only as supplying conditions under which movements and changes of structure due to the natural qualities of the substance treated, take place."

We submit, therefore, that the 5th claim of the patent in suit is not anticipated or limited by any of the matters brought forward in this case, and is, even upon the strictest construction of the language used in the Medart case, a valid process claim.

THE MACHINE AND THE 3RD ASSIGNMENT OF ERROR.

But to accomplish this process of dry-pressing Mr. Jones invented also a press, the chief features of which are (a) the inclined press-bed, having longitudinally slotted sides, (b) the compressing heads having open crossways with which the longitudinal slots in the sides correspond, "to afford access to the work while in the press to tie it into bundles," and (c) the adjustable guide rods for centering bundles of signatures of different sizes; all of which perform important functions in the conduct of the operation of dry-pressing according to his process. The most striking of these features and possibly the most important for the pressing of folded signatures is the inclined press-bed or trough. It is thus described in the specifications:

"It consists of a bed, H H2, mounted upon uprights, E and K, in such manner that it has a downward inclination from the former to the latter upright, as shown in Fig. 1, and the sides of said bed H H2 are set latterly inclined, trough form, so that the folded paper may securely lodge and carry therein while being operated on. The sides H and H2 of said bed are longitudinally slotted at H1, to correspond with the open ways L2 L2 of the press-heads, as shown in Fig. 4, to afford access to the work while in the press to tie into bundles, as shown in Figs 1 and 2."

And one of the objects of the invention is stated to be:

"To furnish a press-frame, having sides peculiarly set and arranged and provided with longitudinal slots therein corresponding with the ways in the press-heads, above referred to, and for the same purpose as well as to rightly lodge and center the paper with relation to the middle of the press-heads."

The hydraulic press used in the old process was a standing press in which the sheets were spread out flat between fuller-boards, and the pile was built up with wooden boards inserted at intervals (Jones, p. 31, ans. 38; Robertson, p. 27, ans. 7), to steady it and keep it reasonably true. But it is evident such a press would not answer for dry-

pressing folded sheets, one and perhaps the principal reason being that folded sheets by reason of their folds are much thicker at their backs and heads than at their outer and lower edges, and hence it would be practically impossible to pile up any considerable number of them; and even if such pile could be made the inevitable result would he that, as soon as pressure was applied, the sheets would slip and the "set-off" which is to be so carefully guarded against in dry-pressing would take place. The difficulty of erecting such a pile even of gathered books was experienced in the use of the so-called Palmer press to such an extent that the operators were compelled to pile books "back and front or 'head and tail,' " and even then the result was loose and crooked bundles which had to be straightened by knocking them on the floor-an operation wholly inadmissible in dry-pressing. But in the inclined trough of the Iones press the sheets, laid with their backs and head folds down (Penicks, p. 68, ans. 24), are securely lodged and carried, and when the pressure is applied only gentle pressure by the workman is necessary to keep them straight and in the line of resistance.

Several of the plaintiffs' witnesses testify with regard to the importance of the inclined trough. Mr. Penicks' statement (p. 67, ans. 15-16), has already been quoted, supra, p. (see also, p. 77, ans. 44-7). Mr. DeVinne, speaking of the most striking features of the Jones process, says (p. 57, ans. 24):

"I may add one, and that is his aparatus for keeping folded signatures in a gutter or channel, and directly in the line of resistance so that they will not spring or wobble under pressure."

And (ans. 31):

"In that position it keeps the signatures straight and up to the guides and side before pressure is applied, when pressure is applied a gentle pressure on the part of the workman can keep the signatures to be pressed in line. If the sheets or signatures were upright without any defense or protection on either side, they would spring and wobble, and I do not see how it would

be possible to keep them straight or in the line of resistance."

These witnesses compare the inclined trough with the press admitting only a vertical pile. Mr. Robertson compares it with the horizontal trough and also states another advantage. He says (p. 76);

"Q. 5. In the Jones machine does the incline press-

bed perform any special function?

A. It does; it has two purposes, one of which is to keep sheets from falling down when piled in the press without the assistance of any device for keeping them in place, such as is necessary when the trough is laid horizontal. The other purpose is to keep one of the heads in such a position that the operator can readily manipulate the tie in the crossways."

The second striking feature of the Jones press is the compressing heads provided with open crossways. The specification states that one of the objects of the invention is "to furnish a dry-press proper in which the compressing parts or heads—that is, the base and plunger—are constructed dividedly or with ways through them to afford access through them to readily insert and manipulate the twine, and to tie the bundles of paper while held compressed, thus securing the bundle together by a powerful tie, which, when they are removed from the press, retains its force ad libitum."

And also:

"The sides H and H2 of said bed are longitudinally slotted at H1 to correspond with the open ways L2 L2 of the press-heads, as shown in Fig 4, to afford access to the work while in the press to tie into bundles as shown in Figs. 1 and 2."

The object of the open crossways therefore is to afford access to the work in order to readily insert and manipulate the twine and to secure the bundle by a powerful tie, an object which apparently could be accomplished only by free access of the hand and forearm. The function and great advantages of these open crossways as illustrated by

practical use are thus stated by Mr. Penicks (pp. 68-9, ans. 24-5):

"Q. 24. How were the signatures tied in the Jones

machine or process?

A. In this inclined rectangular trough you placed a pressing board in the lower end of the trough against the lower platen connected to the piston. The signatures were then placed against the block,-heads against the outer side of the trough, and the backs against the lower side of the trough,-until the trough contained five hundred signatures; then another end presing block was placed at the upper end of the bundle of signatures near the upper stationary platen in the trough; then the pressure was applied and the work in the trough was gradually pressed up to the upper platen of the trough until the amount of pressure required was obtained, these platens, top and bottom, being split crosswise, and the large opening admitting of the arm. The rope was then passed through these openings around the bundle of the work with the pressure on, and securely After the bundles are securely tied, the pressure is removed from the signatures in the trough. work can then be removed from the pressing machine for storage purposes with the pressure still retained.

Q. 25. Did the open crossways admitting the hand and forearm perform any function in this operation?

A. Yes, necessarily. It would be almost impossible to tie the rope around the bundles all the way unless these openings were in these cross-heads, as they admit, especially the large opening in the platen, of passing the arm through the large opening in the platen, then through the opening in the head crosswise section to the opening in the lower bed of the press, then around the large opening in the lower crosswise section, to the opening in the back, then around again to where it is tied."

And Mr. Robertson states (p. 76-7, ans. 6):

"Q. 6. Do the open crossways of the Jones machine

perform any special function?

A. They allow the insertion of the hand and part of the arm of the operator, whereby he can readily pass the cord around the bundle of signatures in both directions and manipulate the loop so as to bring it in the center of the end board when the tie is being fastened." The third striking feature of the Jones press is the use of the adjustable rods, the function of which is apparent without extended explanation, namely: to form in a large sized press a receptacle for small sized sheets and to vary the size of the receptacle according to the size of the sheets so that the tie will come directly over the center of the bundle, without which the pressure would not be evenly retained upon the sheets and the bundle would be liable to become crooked and hence the process of drypressing would become inefficient.

These three features of the Jones press are covered singly or in combination by claims 1, 2 and 4 of the let-

ters patent in suit, which are as follows:

"I. In a printer's and bookbinder's dry-press and sheet-tie, the compressing heads C D D' and B2 F' F, constructed with crossways L2 L2 centrally arranged through them, substantially as an for the purpose herein set forth.

2. The inclined press-bed H H2, provided with longitudinal slots H1 H1 in its sides, in combination with the press-heads B2 F' F and C D D', having through them, the cross-ways L2 L2, correspondingly arranged with said slots, substantially as and for the pur-

pose set forth.

4. In combination with the dry-press bed H H2, the device of a set of removable ledges, f, or a set of adjustable guide-rods, m, arranged as and for the purpose

set forth.'

A vigorous attack was made upon the 1st and 2nd claims, and, besides the so-called Palmer press, numerous patents for hay, cotton, wool, yarn, tobacco, and manure presses, antedating the Jones application for the patent in suit, were cited for the purpose of showing that the matters covered by said claims were either anticipated or involved no invention.

The Proof of the Alleged Palmer Press.

Before referring to the patents cited by defendant, it may be well to consider briefly the proof of the so-called Palmer press, which is set up in the answer as an anticipa-

tion of the Jones press, and is alleged to have been used in the bookbindery of John Palmer, in Philadelphia, as early as 1873 or 1874. Four witnesses were called for the purpose of describing this press and its operation and fixing the date of its introduction into the Palmer bindery. One of the witnesses, McKee, by some marvelous process is enabled to guess as the date of its introduction the precise time fixed by the principal witness, Schrank, to wit: 1873 or 1874, but says he is not positive, and on cross-examination he declines to fix even approximately the date of any of the important events which he narrates, admitting his utter inability to do so for the reason that his memory, at 74 years of age, "is not so bright as it was." He was, with several brief intermissions, in the employ of Palmer and his successors from 1849 or 50 to the time of giving his deposition, and states no circumstance in support of his guess at the date given by him. The only important matter contained in his deposition bearing upon this question is that, to the best of his knowledge and belief, Palmer introduced this press into his bindery while he was in the Tatham building (ans. 7).

Another witness, Davis, was employed in the bookbindery of John F. Busch in the Tatham building from 1872 to 1878, during which time he saw a press for bundling gathered books in the bindery of Palmer in the same building, but he gave it very little attention, is unable to describe the important parts of the press and makes no attempt to fix the time when he first saw it, except within the limits of the years above stated.

The bookkeeper of Tatham & Bros. was called to prove the date when Palmer moved into the Tatham building, to wit: on or about May 15, 1874, but there is nothing in the case to show how long he remained there, and it appears by the testimony of several witnesses that he moved twice into the Tatham building and once into the Tatham annex.

The principal witness is Mr. Schrank, who alone attempts to fix the date of the Palmer press with definiteness or positiveness. His story is that in 1863 he introduced into Palmer's establishment a somewhat similar

impression that the inventor may be treated as the lawful prey of the infringer. The doctrine was laid down by this court in Coffin vs. Ogden, 18 Wall., 120, 124, that 'the burden of proof rests upon him,' the defendant, 'and every reasonable doubt should be resolved against him."

To same effect, see Deering v. Winona Harvester Works, 155 U. S., 286, 300-301.

The Patents Cited.

The principal point of the attack made by Mr. Hood with the patents which he cites is the first claim covering the compressing heads constructed with open crossways. Mr. Robertson, in his answer to question 3 (Record, pp. 73-6), to which the Court is respectfully referred, furnished a complete answer to this attack and leaves little to be added. It is admitted that many of the patents cited show grooves or slots and even cross grooves in which strings may be laid and even, by the aid of a needle or rod, inserted when the pressure is on and drawn taut, but they show no such open crossways—peculiarly adapted to a "dry-press"—as those shown and described in the Jones patent, by means of which, by the insertion of his hand and forearm, the operator is enabled to have "free access to the work," "to manipulate the twine" and "secure a powerful tie," such as is necessary for the purpose for which the press was especially designed. The Dingham press, upon which great stress is laid by the Appellant, and the only paper press cited by him, is merely a machine for bundling wrapping paper and incapable of producing much pressure (Robertson, pp. 88-9, ans. 65), in which the paper is held in position by a series of clamps while the string is passed around between them one way and tied; and it is confidently submitted that there is nothing in its construction as shown by the drawing or described in the specification which would naturally suggest to one skilled in the art the compressing heads, constructed with open crossways, of the Jones patent.

As to the second claim, Mr. Hood is very unfortunate. The only trough-like press-bed which he could find is in the tobacco press of Hardesty. This is a horizontal and not an inclined trough, and the slots in its sides have no function except to save material. It is a mere receptacle for the hogshead and false hogsheads while the tobacco contained in the latter is forced into the former, and the hogshead is not tied but headed up. But here again Mr. Hood's usual fatality attends him, when he boldly declares (ans. 4, p. 100): "I do not think it involved invention to incline the press-bed, especially in view of the fact that inclined trough-shaped beds or receptacles, arranged to receive and hold in regular order a series of folded sheets, was a common construction in folding machines for folding printed sheets."

Pressed on cross-examination to say what machines he had in mind when testifying as above, he cites U. S. Patent No. 186,309. But an inspection of that patent reveals that he is again mistaken, as it shows and describes merely two boxes for the alternate reception of sheets from the folding machine and not inclined to the horizon, but horizontal and inclined toward each other. This structure is fully explained by Mr. Robertson (ans. 3, pp. 75-6).

Mr. Hood cites several other trough-like structures shown in several U. S. patents, but he admits that in these he "believes" "the trough is not inclined but lies horiontal," and an inspection of the patents fully corroborates his "belief."

In view, therefore, of the complete failure of the attack upon the second claim and of the great utility of the inclined press bed as shown by the testimony of the witnesses Penicks and DeVinne, it is confidently submitted that the claim must be sustained.

CLAIM 4 AND THE 5TH ASSIGNMENT OF ERROR.

As to the 4th claim no anticipation has been set up and defendant's expert, Mr. Hood (Record, p. 119, ans. 58), distinctly admits that, among various patents cited by him, he did "not find any reference for the 4th claim," and, as the so-called Palmer press contained no guiderods of any kind, of course it cannot be relied upon as an anticipation, either in whole or in part, of said claim.

But it is contended that this claim is void for ambiguity, and Carr v. Rice, I Fish., 325, is cited in support of the contention. In that case the claim was for "the upright stationary bolt, or bolt and scourer combined with its top and cover, or in combination with claims 1, 2 and 4, or either of them, or their equivalents, to produce like results in the flouring process," and the claim was very properly rejected as "good for nothing, on account of its uncertainty." But very different from this claim is claim 4 of the patent in suit, which is clear and certain, and the only criticism to which it is open is that it is in the alternative. But all alternative claims are not void, for such claim will be sustained when it is the equivalent of two claims, one for each alternative; Tuck v. Bramhill, 6 Blatch., 95; S. C., Fish., 400, where Judge Blatchford held valid a claim for the forming of a roll of packing for pistons "either in connection with the India rubber core, or other elastic material, or without the core," remarking:

"This is equivalent to two separate claims,—one for the forming of the roll with the core and one for the forming of it without the core. The patentee might have made two such claims, separately numbered, and both would have been good claims, if the inventions were new with him. He did that in effect in the claim he made."

A claim similar to that in Tuck v. Bramhill was sustained by the Supreme Court in Rubber Co. v. Goodyear,

9 Wall., 788, 795.

In Brown v. Whittemore, 5 Fish., 524, the fourth claim of the patent sued upon was "The arrangement of the rake-head E and foot-treadles H J and G K, or either, in relation to each other and the axle B substantially as and for the purposes set forth." In disposng of this branch of the case Lowell, J., said (p. 527):

"We agree with the defendant's argument that the patentee might not be able to claim an alternate combination as he does in his fourth claim, if the separate combinations would not make an operative machine; but it seems that the combination of either of the foottreadles with the rake-head and the axle does make such a machine."

And it was held that the claim was valid and infringed, the defendant using but one set of treadles.

In Union paper Bag Co. v. Nixon, 6 Fish., 402, 412, the claim covered *inter alia* "pulleys d d or their equivalents." In holding this claim valid Emmons, J., said:

"An alternative claim is void only in those instances when it claims positively neither of several subjects, but is good if all, of many which are mentioned, are claimed, as one of the other are employed by an infringer. If it is said A or B is claimed, this asserts a right to neither; but to claim the one or the other, as either are used, with the assertion that it has been discovered both are interchangeably available for specified purposes, is not an alternative claim, within the cases cited by defendants. Such is the third claim in this case."

It thus appears that an alternative claim is valid either (a) when it is the equivalent of two claims, each of which standing by itself would be a valid claim, or (b) when the alternative elements are equivalents.

In the present case claim 4 of the Jones patent may be sustained upon either ground-upon the latter ground because, as Mr. Robertson points out (record, p. 38), the removable ledges and adjustable guide-rods are substantially equivalent to each other and an inspection of the patent, and particularly figures 3 and 4 of the drawing, shows that the ledges are guide-rods and differ from the socalled rods only in location and in being rectangular instead of round. The specification shows that both kinds of rods perform precisely the same function, viz: centering intermediate and small sized sheets, in precisely the same manner, to wit: by decreasing the size of the trough. Both are removable and "are allowed to pass freely through" one of the compressing heads by means of openings therein made for their accommodation. clearly equivalent do they appear to be that it is difficult to see how the defendant, using only the adjustable guiderods, could escape the charge of infringement if the claim included merely the ledges and were silent with respect to the rods.

But assuming that the claim cannot be sustained upon the ground of the equivalency of the alternative elements, it is submitted that it must be sustained upon the other ground, to wit: that the claim is substantially equivalent to two separate claims, each covering one of the two alternative elements "in combination with the dry-press bed." It is not left "uncertain which of the several things the inventor intends to claim," but it is made abundantly clear that he intended to cover each of them and this is sufficient to support the claim, Robinson on Patents, vol. 2, sec. 520.

In the Telephone Cases, 126 U. S., 1, 537-8, a claim for "the method of, and apparatus for, transmitting vocal and other sounds telegraphically," &c., was held to be substantially two claims, (1) for "the method" or process and (2) for "the apparatus;" and there seems to be no good reason why a claim in the disjunctive should not be given similar effect.

6TH ASSIGNMENT OF ERROR—INFRINGEMENT.

As to the infringement of the process claim there is no controversy. By his contract with the State of Pennsylvania the appellant was bound to "dry press" his work (Grier, Record, pp. 13-14, ans. 9, 21; Busch, p. 182, 5, ans. 30), and the superintendent of Public Printing testifies that the work was "dry pressed" by the appellant in a manner identical with the process described in the patent in suit and covered by the 5th claim (Record, Grier, pp. 13-15, ans. 10-33; see also Miller, pp. 19-20, ans. 22-31; Jones, pp. 24-6, ans. 6-12; Robertson, pp. 41, ans. 10), and no denial of this fact is made or attempted, and it is moreover expressly admitted by Busch himself (p. 180, ans. 8).

It is clear also that the 1st and 2nd claims were infringed. The machine used by the appellant, as described by the witnesses, Miller (Record, p. 18, et seq.) and Jones (p. 24, et seq.), and as shown in "complainants' exhibit

model No. 1" and "complainants' exhibit wood-cut of Seybold Signature Press," (see Record, between pp. 88 and 89), contains, 1st, compressing heads constructed with open cross-ways arranged centrally through them: and, 2nd, an inclined press-bed provided with longitudinal slots in its side, in combination with the press-heads having through them the cross-ways arranged correspondingly with said slots. Mr. Robertson makes the usual comparison between claims 1 and 2 and the press used by the defendant (Record, pp. 39-40), finding all the elements of these claims embodied in the press, and his conclusions are not controverted by Mr. Hood.

As the infringing machine contains the adjustable guide rods in the combination covered by claim 4, it is clear that that claim was also infringed; and this does not appear

to be denied.

7TH ASSIGNMENT OF ERROR.

In this assignment the appellant complains that the Court below erred in over-ruling the motion to vacate the Interlocutory Decree. But this we submit is not assignable as error. The granting or refusal of relief by rehearing or reconsideration and vacation of a decree is purely discretionary and is therefore not reviewable: Brockett v. Brockett, 2 How., 238; Steines v. Franklin County, 14 Wall., 15, 22; Buffington v. Harvey, 95 U. S., 00: Lewisburg Bank v. Sheffey, 140 id., 445, 452. reviewable error of the Court, if any there was, consisted in entering the Interlocutory Decree and in subsequently confirming it by the final decree, and not in over-ruling defendant's motion. Moreover the motion, which is not printed with the record, was very irregular, and set forth no specific grounds upon which a reconsideration of the decree was asked. Furthermore the motion asked for such reconsideration of the Interlocutory Decree only in so far as it sustained plaintiff's fifth claim and was not based on the grounds now set forth in this assignment of error.

8th, 9th and 10th assignments of error—exceptions to the auditor's report.

These assignments attack the action of the Court below in over-ruling the exceptions to the Auditor's report. The Court is respectfully referred to the very clear and able report of the Auditor (Record, pp. 147, et seq.), which is itself a complete vindication of the conclusions reached by him and, in all matters which it touches, a refutation of the argument contained in the appellant's brief. We are therefore relieved from the necessity of considering, except very briefly, this branch of the case.

The appellant, as we have seen, was the contractor to do the public printing of the State of Pennsylvania, and, by his contract, was required to "dry press" all his printed sheets, and for that reason, as he himself testified, he purchased the infringing machine (Busch, p. 182, ans. 30), and that he did "dry press" his work by the Jones process he also admits (Busch, p. 180, ans. 8, referring to Grier,

Record, pp. 13-14, ans. 11-17).

The rule for the ascertainment of the gains, savings and profits for which an infringer is bound to account in equity as laid down in Tilgham v. Proctor, 125 U.S., 136. is, that he is liable for "the profits," or "the fruits of the advantage which he derived from the use of (the) invention, over what he would have had in using other means then open to the public and adequate to enable him to obtain an equally beneficial result." And this is the rule which was followed by the Auditor. It was contended, however, at great length by the appellant in the Court below that, as the patent in Tilgham v. Proctor was for a chemical process, the rule there laid down is inapplicable But the elaborate discussion of the rule by the Court clearly shows that it was intended to be laid down as a rule of universal application in equity, irrespective of the special character of the invention, and so do the cases cited by the Court in support of it, which involved mechanical processes and machines.

As means adequate to enable the appellant "to obtain an equally beneficial result," the Smasher, the Palmer Press and the Gordon Press were set up by his counsel and were properly rejected by the Auditor. As we have seen/supra, pp. 17-19), the Smasher did not and could not "dry press" or remove type indentations, and the Palmer Press was never used for such purpose and could not be (supra, pp. 30-3.). The Gordon Press was introduced into the case in the cross-examination of Mr. Grier, who stated, that, having for some time used the fuller-board process of removing type-indentations in letter heads and similar commercial work, he procured a Gordon press, "that did the work without any necessity of removing the impressions;" and upon this flimsy ground the use of the Gordon press is now put forward as a basis of comparison with the Iones process. There are two answers to this contention: 1st, the Gordon press is suitable only for small job work such as bill heads, circulars, letter heads and cards, which are small in size and do not require any special smoothness of finish, the press making a very light impression, which in work of this character does not need to be removed. But it is incapable of printing such work as the defendant did for the State of Pennsylvania (see Grier, supra, and Suydam, Record, 192, ans. 56-58). And, 2nd, it does not "dry press" at all, and by his contract and the statute under which it was made, the defendant was bound to "dry press" all his work. Hence the Gordon press was not a means "adequate to enable him to obtain an equally beneficial result."

The Auditor adopted as the basis for comparison the old fuller-board process, and in this we submit he was clearly right for the reasons stated in his Report (Record, p. 149 et seq.). Appellant's allegation, in his 10th specification of error, that this process had not been "in use in any establishment for many years prior to the Jones invention, and not for a half century prior to the time of infringement," is wholly incorrect and has not a spark of evidence to support it. On the contrary, it is abundantly shown that this was the process in use immediately prior to the Jones invention (Robertson, Record, pp. 35 et seq.; DeVinne, pp. 54-5; Penicks, pp. 64-5; Suydam, pp. 185-6 et seq.; Jones, pp. 198-9); was still in use in at least one

establishment in Philadelphia as late as September, 1896 (Suydam, p. 192, ans. 53-4), and at the time of the infringement was the only process, other than that of Jones, capable of producing equally beneficial results (Jones, pp. 198-9, and see the testimony of the other witnesses cited). There was but one other process of "dry-pressing," viz: pressing the sheets between heated plates, and that was

obsolete (Jones, p. 199, ans. 11).

The appellant, however, complains of the comparison of the process of the patent with the old fuller-board process, upon the ground that in the latter the sheets are pressed flat and between fuller-boards, while in the former the sheets are pressed folded and fuller boards are dispensed with. But the elimination of the fuller-boards is one of the advantages of the new process, and of that advantage the appellant availed himself. As to the other point-it must not be overlooked that, under both processes the real starting point is the sheet, flat as it comes from the printing press. Under the old process the sheet, after being dried, is first dry-pressed and afterwards folded, while under the Jones process the sheet is first folded and then dry-pressed. But in both cases the same result is reached, to wit: dry-pressing and folding; and where, as in the case of the appellant, the same person is both printer and bookbinder, the same result is reached in the same establishment and by the same person. Why then, for the purpose of ascertaining profits, should the two processes not be compared?

Moreover the claim by its terms demands that the sheets be folded and it is abundantly shown that the folding of the sheets is a necessary condition of the successful carrying out of the process. And, as the sheets come from the press flat, is this not equivalent to saying that the first step in the process is the folding of the sheets? One of the great difficulties under which counsel for the appellant appears to have labored throughout this case is that the process claim speaks of dry-pressing only "folded sheets." But, as the preliminary folding is a necessary condition, and that condition is expressed in the claim, we submit that the claim must be construed as though it

started with the flat sheets and read: "The process herein described for treating printed sheets of paper in dry-pressing, the same consisting of first folding said sheets, and then subjecting a collection of such sheets to pressure without the use of fuller-boards, &c." If the claim had been put in these terms and had stated explicitly, as it does impliedly, the first step of the process to be the folding of flat sheets, the mind of counsel for appellant would doubtlessly have been relieved of much unnecessary worry and the case of much unnecessary discussion.

But after all the point to be reached is the saving to the appellant. By his contract with the State of Pennsylvania he was bound to dry-press his work, and he did it by the process of the patent in suit. And if, by the use of that process, the cost to him of first folding and then dry-pressing was less than that of first dry-pressing and then folding, why should he not account to the appellees

for the saving?

The Auditor, therefore, was clearly right in making his comparison with the fuller-board process as the only process of dry pressing them open to the public and adequate to enable the appellant "to obtain an equally beneficial result." And comparing the infringing process with the fuller-board process the Auditor found that gains and savings accrued to the appellant under two heads, viz:

saving of wages and saving of paper.

Saving of Wages.—The actual number of sheets dry pressed by the appellant and the actual cost thereof in wages was shown by the testimony of appellant himself (Busch, p. 180, ans. 5, 9-10). Over against this it was shown by competent evidence what it would have cost, at the wages paid in appellant's own establishment, to dry press the same number of sheets by the fuller-board process (Jones, p. 200 et seq., ans. 18 et seq.; Suydam, p. 186-7, ans. 15 et seq.

Saving in Paper.—It was shown that by the old fuller-board process there was a waste of about ten sheets of paper per thousand sheets (Suydam, p. 188, ans. 25; Jones, pp. 203-4, ans. 29), while by the Jones process this waste did not exceed one sheet per thousand (Jones, su-

pra), and according to appellant's own statement there was practically no waste (Busch, pp. 181-2, ans. 28), a saving by the infringement of at least nine sheets per thousand. It was also shown that at the time of the infringement this paper was worth in the market from six to seven cents per pound (Johnston, pp. 294-5); and this

saving the Auditor very properly allowed.

There was therefore a clear cut mathematical basis for the calculation of the savings of the appellant, and this case does not at all resemble any of the cases cited in the appellant's brief. Nor is it a case like the cases in which the saving by a machine is due in part to the patented features of the machine and in part to its other features. Here the entire saving was due to the infringement of appellees' process of "dry pressing" and that entire saving belonged to them, Crosby Valve Co. v. Safety Valve Co., 141 U. S., 441, 454, and cases cited.

One other matter may be noticed which, although perhaps not very important, may be misleading. The appellant is wrong in asserting, throughout his brief, that under the Jones process the sheets were smashed before being dry-pressed. There is no warrant at all for this assertion. He has evidently been misled by the fact that the patent shows a "Bulk Compressor" (see supra, p. 12), which, it was at first supposed by the inventor, would be a useful adjunct to enable him to compress the bulk of loosely folded sheets and thus enable him to get more sheets into his press. But, in the technical sense, it is not a "smasher" and its use is not "smashing" (see supra, p. 19). The 5th claim does not demand preliminary smashing, and as a matter of fact it was never done, nor has, in practice, the use of the Bulk Compressor been found necessary.

It is respectfully submitted that there was no error in any of the proceedings in either of the Courts below and that the decree of the Court of Appeals of the District of Columbia should be affirmed, at the costs of the appellant.

Respectfully submitted,

M. W. JACOBS, Counsel for Appellees.

Supreme Court of the United States.

October Term, 1901.

No. 96.

CLARENCE M. BUSCH, Appellant

2.2

JOSHUA W. JONES and THE W. O. HICKOK MANU-FACTURING COMPANY, APPELLEES.

Petition for a Re-Hearing.

To the Honorable Justices of said Court:

The Appellees in the above entitled Cause respectfully pray that the Court will rehear and reconsider the matters decided March 17, 1902, so far as they relate to the question of the validity of the fifth claim of the Patent No. 204,741, here in suit; and that an Order be entered affirming the judgment of the Court of Appeals of the District of Columbia.

The grounds upon which this application is made are:

(a) That the learned Court, in their said decision, as evidenced by the written Opinion filed March 17, 1902, giving the reasons for the said decision, in holding that the fifth claim of the Patent in suit, which is as follows:

"The process herein described for treating folded printed sheets of paper in dry-pressing, the same consisting of subjecting a collection of such sheets to pressure without the use of fuller-boards, and while under such pressure tying them into compact bundles with end boards, then removing them immediately from the press, and allowing them to remain tied sufficiently long to fix and complete dry-pressing."

describes the "mere operation and effect of the press" and is therefore invalid, inadvertently overlooked the fact that said claim demands, as the conditions of the carrying out of the process, certain things which are not essential to the mere operation and effect of the press, but are in addition thereto, and which were, before the invention set forth in said claim, wholly unknown in the art of dry-pressing, as follows:

1. Dispensing with the use of fuller-boards.-It is shown by the testimony that, in the only process of dry-pressing in use prior to the invention by the patentee Jones, "fuller" or "press" "boards," interspersed at very short intervals between the sheets-a single sheet in fine work, or, in work less fine, at most three to six sheets, being placed between a couple of "fuller-boards"-were necessary to produce the effacement of the type indentations. It is evident that the mere effective operation of the press demands neither the use nor the omission of fuller boards, which, so far as concerns such operation, may be omitted, as demanded by the claim in question, or, conforming to the only practice known prior to the invention in controversy, may be interposed between the sheets in the press and subsequently in the bundle. But one of the discoveries of the inventor, embodied in the claim, is that fuller boards, which had always before his invention been used in dry-pressing, may be dispensed with, thereby accomplishing a great saving in time and labor and in cost of materials; and-by so omitting one of the steps theretofore always practiced in the operation of dry-pressing, viz: inserting, by hand, the printed sheets between the fuller boardsrendering the process a new one, and patentable within the rule laid down by this Court in the case of Lawther v. Hamilton, 124 U. S., I.

2. Use of end-boards.—The claim in controversy demands the tying of sheets "into compact bundles with end boards." These end boards are in practice "hard wood boards," and are thus described in the Specification (Record, p. 95):

"They are used on the ends of the bundle of the paper under treatment to distribute the pressure over the whole area of the ends of the bundle, and also to prevent cutting or marring of the paper by the twine or other tying material. Said end boards are made of any suitable material affording strength and rigidity at little cost and of suitable size to nearly match the size of the folded work."

The use of strong and rigid end boards, "of suitable size to nearly match the size of the folded work," and suitable "to distribute the pressure," is not necessary for the practical and effective operation of the press, it being proved by Appellant's witnesses that, in the operation of tying up bundles of already dry-pressed sheets in the Palmer Press, "pieces of pasteboard or binder's board"-"paper would answer just as well"-were sufficient "to protect the sheets from being soiled" and cut by the cords with which they were tied. But for the operation of dry-pressing or removing the type-indentations, it is necessary that pressure shall, for a considerable time, be kept uniformly distributed over the whole face of the printed sheet, and it was one of the Patentee's discoveries, embodied in his fifth claim, that by the use of end-boards such as are described in his Patent, pressure applied in the press could, in the bundle, be kept thus distributed, and that thereby the operation of dry-pressing begun in the press could be completed in the bundle. The use of "end boards" is thus a necessary condition of the carrying out of the process, but is not necessary to the mere operation of the press.

3. Folding the Sheets.—In the old process of dry-pressing the sheets were laid out flat between fuller-boards, while in the present process the sheets are folded and fuller-boards are dispensed with. It is pointed out in the testimony that folding is an essential condition of the carrying-out of the

process. As a condition of dry-pressing, it was new with the inventor Jones and may be considered as embodied in his claim. And, as the sheets are folded by a separate machine prior to their insertion in the press, this necessary condition of the carrying-out of the process is wholly apart from the

mere operation of the press.

(b) In holding that "the process is the whole value, the sole purpose of the press," the learned Court inadvertently overlooked the fact that the press is applicable to another purpose than dry-pressing, as it appears by the following statement The patent is for a "Dry-Press and Sheet-Tie," and the evidence shows that, while prior to the invention in suit drypressing was always done by the printer before the folding of the sheets and the delivery of them to the binder, it was the practice, in the bindery, to tie up the dry-pressed and folded sheets in bundles for storage; this operation being usually done by hand, but, in the Palmer Bindery, having to some extent been aided by the use of an upright press. The patented press may thus be used in the bindery as a mere sheet-tying machine, for the bundling of sheets already dry-pressed, or it may be used for the operation of dry-pressing, in which case further bundling is unnecessary; but with the difference that, in the former use, the ends of the bundles required only protection from dirt and the cutting of the sheets by the tying cord-which protection was customarily afforded by the use of additional paper or pieces of pasteboard-while in the latter, the rigid end boards are required for the purpose of distributing and keeping distributed the pressure over the whole area of the printed pages.

On account of the errors above referred to, and to the end that equity may be done and that this Court may, upon fuller consideration and with the advantage of oral argument, revise its said judgment (if revision be right and proper), your petitioners pray that the Court may be pleased to take their Petition into consideration, and to grant a rehearing upon the question of the validity of the fifth claim of the said Let-

ters Patent, and to grant such other relief and order as in equity and good conscience may be proper.

M. W. JACOBS, Counsel for Appellees.

I certify that, in my opinion, the foregoing Petition for a rehearing is well-founded and that the same is not made for the purpose of delay.

M. W. JACOBS, Counsel for Appellees.

Supreme Court of the Anited States.

No. 96.—OCTOBER TERM. 1901.

Clarence M. Busch, Appellant,
vs.
Joshua W. Jones and The W. O. Hickok
Manufacturing Company.

Appeal from the Court of Appeals of the District of Columbia.

[March 17, 1902.]

This suit was brought by appellees against appellant for the infringement of letters patent No. 204,741, and letters patent No. 452,898, issued to Joshua W. Jones, one of the appellees. An accounting was prayed, and also an injunction, pending the suit. The bill contained the usual allegations of invention and utility, and of infringement by the defendant (appellant). The answer traversed those allegations, and alleged prior use, disclosure of the invention in prior publications, and also anticipation by prior devices and processes. The answer contained a list of the devices. No evidence was given as to, and no judgment passed on, patent No. 452.898. This appeal therefore is only concerned with patent No. 204,741. The patent was issued to Joshua W. Jones, one of the appellees, for a press and process (the relation of the two is disputed) for "dry pressing" and removing type indentations from printed sheets. The validity of the patent was sustained, and its infringement by the defendant (appellant) was found by the Supreme Court of the District of Columbia, and decree passed adjudging appellees the sum of \$3,491.70 with interest and costs. The decree was affirmed by the Court of Appeals, (16 D. C. App. 23.) The case was then brought here. The facts are stated in the opinion.

Mr. Justice McKenna delivered the opinion of the Court.

1. A question of jurisdiction is raised. It is contended by appellant that the case was not one of equitable cognizance, the appellees' remedy being, it is claimed, at law. The specification of error upon which the contention is based is expressed as follows:

"Because at the time of the hearing it appeared from the record that the only patent before the court had expired before the hearing, no motion for preliminary injunction having been made prior to the expiration of the patent, and defendant being a mere user of one machine, which machine was destroyed by fire before the case was brought to hearing."

This seeks to determine the jurisdiction of the court by conditions which came into existence after the commencement of the suit, not upon those

which existed at the time the bill was filed. It is, however, urged in argument that the contract between Jones and the W. O. Hickok Manufacturing Company conveyed the patent rights to the press only, and not the process described in the fifth claim of the patent, and that "the court, sitting as a court of equity, had no jurisdiction to order an injunction at the time the bill of complaint was filed." But what the contract provided was an issue to be made in the case, and pending its decision the preliminary relief by injunction could have been granted. Appellees' contention as to the jurisdiction is, therefore, not justified, and a discussion of the reasons for this conclusion is not necessary. They are expressed in Clark v. Wooster, (119 U. S. 322,) and Beedle v. Bennett, (122 U. S. 71.)

2. The patent is designated an "Improvement in Bookbinder's Dry-press and Sheet-tie." That is, a new press and process for removing type indentations from printed papers or sheets, the latter when folded being designated technically as "signatures."

The type indentations are made in printing, the type displacing somewhat the fiber of the paper, and the removal of the indentations is technically known in the art as "dry pressing," and the device by which it is done is called a "dry press." Such a press the patent is intended to cover, and also a particular process for dry pressing. As a process the validity of the patent is questioned, as a new machine its invention is controverted. An inquiry into the prior art becomes therefore important, and a witness, describing it and its imperfections, testified as follows:

"Previous to the invention of Mr. Jones as described in said patent, it was the custom to press printed sheets by inserting them between heavy paper boards, sometimes called 'fuller boards,' but generally now called glazed boards,' and putting said boards with the printed papers between them into a powerful press, by which pressure was produced on said boards by various means, sometimes by means of screw pressure, sometimes by hydraulic pressure. After the pressure was produced on the paper it was continued by allowing the press to remain with its pressure on to its fullest extent for ten or twelve hours or more, say from one night to the next morning, when the pressure was removed, the papers and boards taken from the press and separated by removing the boards from the pile of combined boards and paper, and putting the boards on one side on one pile and making another pile of the printed papers. This was necessarily comparatively a slow process, inasmuch as with one press only as much printed paper as the press would hold when put between the hoards could be pressed in about ten or twelve hours, so that where much work had to be done a number of such presses were necessary. It was also costly as to labor, because the sheets had to be placed between the boards and removed therefrom afterwards, which took much time, especially where, as in the case of fine work, only one sheet was placed between two boards; and when this was done comparatively few sheets could be pressed at once because the boards took up much more room than the paper did, they being quite thick."

It was to meet this condition that the Jones patent was conceived, and its object is stated to be first to "furnish a bulk-compressor device, to be used to prepare the matter properly before it is inserted in the dry-press proper, thus saving time or repeated travel by the latter, before the operation of tying; second, to furnish a dry-press proper in which the compressing parts or heads-that is, the base and plunger-are constructed dividedly, or with ways through them, to afford access through them, to readily insert and manipulate the twine, and to tie the bundles of paper while held compressed, thus securing the bundle together by a powerful tie, which, when they are removed from the press, retains its force ad libitum; third, a press-frame, having sides peculiarly set and arranged, and provided with longitudinal slots therein corresponding with the ways in the press-heads, above referred to, and for the same purpose, as well as to rightly lodge and center the paper with relation to the middle of the pressheads; fourth, certain ledges in the said press-frame and guides on the plunger thereof, to properly center different-sized sheets in press to secure the tie at the middle of the bundles both ways; fifth, a new process for treating printed and folded sheets of paper in dry-pressing, consisting of subjecting a collection of such sheets to pressure without the use of fullerboards, and while under such pressure tying them into compact bundles, with end boards thereon; then removing them immediately from the press, and allowing them to remain tied sufficiently long to fix and complete the dry-pressing."

The press is described in the patent with particularity, and illustrated by drawings. It may be said, generally, that it is a press in which bundles of signatures (sheets) are placed, at the end of which bundles rigid boards are attached to distribute the pressure which is exerted by the press. press moves in a "trough formed" bed so mounted as to incline laterally "so that the folded paper may securely lodge and carry therein while being operated on." Rectangular blocks are rigidly secured at both ends of the bed. The lower block is the base of what is called in the specifications "a divided head," constructed with "openings or ways." Opposing this there is a "plunger or follower," to which there is also attached a "divided head" having "openings and ways" between the parts of the head. "openings and ways" are to enable the operator to pass his hand between the parts of the press and tie the bundles. The operation of the press is as follows: A bundle of signatures (sheets) with rigid boards at its ends are placed in the press, pressure is exerted by means of a screw (other means may be used) which passes through the upper block and operates on the plunger or follower and the "divided head" attached to it, and as the bundle rests on the lower block and its "divided head," it is evident that the pressure on the sheets will be in proportion to the power applied. While under pressure in the press the bundles are tied, access to them being had through the openings in the "divided head." The bundle is then removed from the press and allowed "to remain tied sufficiently long

to fix and complete the dry pressing."

The advantage of the new method is that it is not so dilatory as the old and is more economical. In the old method the sheets, coming damp from the printing press, had to be dried before dry-pressing, and had also to be subjected to pressure in the press a number of hours to effect the smoothing (dry pressing) of the sheets. The quantity of the work, therefore, was limited by the number of presses. In other words, as expressed by one of the witnesses, "where much work had to be done a number of such presses were necessary." And it was further testified that "it (the old method) was also costly as to labor, because the sheets had to be placed between the boards (fuller boards) and removed therefrom afterwards, which took much time, especially where, as in the case of fine work, only one sheet was placed between two boards, and when this was done comparatively few sheets could be pressed at once, because the boards took up much more room than the paper did, they being quite thick." In the new method there is no such limitations as to time, nor does it require the same expenditure of money. In the new method the initial pressure is applied in the pressthe subsequent pressure necessary to remove the type indentations is continued in the tied up bundle. The operation, therefore, is comparatively rapid. "Putting the paper in the bundle," a witness testified, "tieing it up in a bundle and removing it therefrom," takes a few minutes. And the longer the sheets remain in the bundles the better the effect. Some time is necessary. Another advantage is claimed. It was testified that in the Jones method that the sheets when folded have the convex impression of one-half of the sheet brought in contact with the convex side of the other half of the sheet or of the sheet next to it, "and these convex impressions coming in contact with each other tend, when under pressure, to efface each other."

There is, however, no revelation in the specifications of the patent of the operation of opposing "convex impressions," nor a word to indicate that Jones was conscious of the advantage of that assistance to the pressure upon the sheets. The discovery seems to have been made by one of the witnesses, and also seems to have been disclaimed by Jones in the following question and answer:

"X-Q. 56. Throughout the testimony a good deal has been said about the advantages derived from your supposed invention from the fact of the type indentations being concaved or convexed, whatever that may mean. Is there anything said in the patent about that?

"A. No; neither do I claim that they are produced by my process."

There is a dispute as to the character of the patent. Appellees contend that it is "a process of 'dry pressing' or removing type indentations from printed sheets" (claim 5 of the patent.) Second. "A press of peculiar con-

struction and adapted to the convenient carrying of this process into effect. The novel features of which press are covered by claims one to four inclusive." The appellees contend that the patent is for a machine (claims 1 to 4) and also for a process (claim 5). And it is asserted the latter claim is but an operation or function of the machine. It is further contended that the machine and process were anticipated.

In discussing these contentions, it is not necessary to minutely observe the distinctions made and disputed by counsel. Even if the patent is primarily for a novel process, there is a claim for a novel press, and, by the consideration of the latter, we think, the validity of the former will be determined.

Was, then, the press anticipated, including broadly in the term the inquiry whether the press exhibited invention, in view of the prior state of the art? Anticipation is a question of fact, and the burden of establishing it is on the appellant. The patent bears a presumption of novelty and invention, and the lower courts, passing on the evidence, found against appellant's contention. Such united judgment this court accepts unless there is a clear showing to the contrary. (Brainard et al. v. Buck et al., and even urges that presses of various kinds had become so familiar. before the Jones patent, that judicial knowledge can be invoked for them. Hay presses, cotton presses, tobacco, wool and other presses are instanced, all of which, it is said, were used for applying pressure to masses of matter to compact them into bundles, and in all of which the pressure was retained by strings, ropes or bands of some kind. But wherein those presses differed one from the other and received special characterization and utility would be a matter of proof, not of assumption, and wherein the Jones patent differs from either of them and has derived its special applicability is certainly not so clear that it is demonstrated against the judgment of the Supreme Court and the Court of Appeals of the District. Nor are we nearer that demonstration by the specific patents, put in evidence by appellant. There is generic sameness we concede, but there are differences, and the Patent Office and both lower courts found novelty and invention in those differences.

The appellant introduced in evidence a patent issued to D. Kellogg, October 12, 1852, for a wool press; one to W. R. Dingham, October 20, 1863, for improvement in paper presses; one to S. Cooley, October 16, 1866, for a wool press; to Thomas Stibbs, September 19, 1871, for pressing yarn; to W. P. Craig, for a baling press; to Thomas G. Hardesty, for tobacco press; to G. B. Archer, for baling manure and other substances; to C. Brown, for baling short cut hay, and another for baling short cut straw; and a patent for a signature press to R. A. Hart. There was also

testimony of the existence of a press used in the bookbindery of one John Palmer, in Philadelphia. The press was used in a later stage of bookbinding than "dry pressing," for the purpose of tying printed sheets into bundles for storing. It was an upright press with opposing platens or heads in which there were grooves to receive the cords by which the bundle was tied while under pressure.

There is a certain resemblance between all of the devices. They are all instruments for exerting pressure upon substances placed between compressing heads or followers to compact such substances into bundles and afford facilities for tying the bundles while they are under pressure. The Dingham patent, the one most relied on by appellant, may be selected for illustration.

The Dingham device is an "Improvement in Paper Presses," and the inventor claimed to have "invented a new and useful machine for combining and facilitating the operation of pressing and tying paper into reams or bundles," which he called "the combination paper press and tie engine."

There were defects in the art of pressing and tying paper very similar to the defects in the art of dry pressing "signatures," and Dingham described the former as follows:

"The process of pressing and tying paper now generally employed requires a large and somewhat expensive press, which is located in some corner of the finishing room, and as the paper comes from the machine it is carried to the finishing table, there counted and folded, and when sufficient is obtained to fill the press (usually about one hundred reams) it is conveyed to the press and placed therein, and, by means of a large screw and follower, pressed for about twelve hours, or during the night. It is then removed and conveyed to the tie-table and there tied into reams. After this (it being, when it comes from the machine, usually double-crown, or double the length of the ordinary ream of wrapping paper) it is cut into two reams or single crown. The usual mode of tying paper is by passing a strong cord or twine around the ream, with a noose or loop at the end, through which the other end is passed, and then drawn upon with the hand until the loose ream or bundle is sufficiently compressed. This operation is laborious and tedious, occupying much time, requires strong twine, and unavoidably draws the ream away or the paper out of place."

This language is quite similar to that used by Jones and his witnesses to describe the defects which existed in the bookbinder's art, and the presses of the inventors also have similarity. In both sheets of paper are pressed by being placed between "compressing heads," which "are constructed dividedly," to use the words of the Jones patent, "separate and sufficiently disconnected (to use the language of the Dingham patent) to allow the string or cord for tying the paper to pass between." Each machine, therefore, comprises a compress and tie-table. In each there is the same rapidity of operation, the same economy of time and means, and in each the

pressure first applied by the machine is retained by cords and continued in the bundle. And it is manifest that this retained and continued pressure, which has for its purpose in the Jones patent to remove type indentations from the sheets, and in the Dingham patent to retain the sheets in the bundle, adds nothing to the operation of the press of the former and detracts nothing from the operation of the press of the latter. But notwithstanding these resemblances we may ascribe invention to the Jones patent if it be confined to the press proper. In other words, the press may be regarded as a form, adapted to the bookbinder's art, and although preceded by the Dingham patent in a general way, may be considered as an invention of that form.

The fifth claim of the Jones patent—the claim for the process—must be viewed from a different standpoint. The first four claims of the patent, as we have said, describe the elements, "In a printer's and bookbinder's dry press and sheet tie." The fifth claim is as follows:

"5. The process herein described for treating folded printed sheets of paper in dry-pressing, the same consisting of subjecting a collection of such sheets to pressure without the use of fuller-boards, and while under such pressure tying them into a compact bundles with end boards, then removing them immediately from the press, and allowing them to remain tied sufficiently long to fix and complete dry pressing."

The dependence, therefore, is not, as counsel for appellee contends, the press upon the process. It is the other way, the process upon the press; for it is impossible to consider the fifth claim as describing anything but the operation and effect of the press. Indeed, the process is the whole value, the sole purpose of the press. What, indeed, is the processwhat is the force at work? And the inquiry is entirely independent of questions as to what constitutes a patentable process discussed by this court in Risdon Locomotive Works v. Medart, (158 U. S. 68,) and in Westinghouse v. Baden Power Brake Co., (170 U. S. 537.) What, then, is the force at work and how is it applied? It is force (pressure) applied to sheets of paper placed between "compressing heads." In other words, a special application of pressure began in the press and continued in the bundle by means of strings and cords. This, however, is the operation and effect of the machine, and it is none the less so because the pressure is held indefinitely. Its existence in the bundle is not independent of the press. The pressure is as much an effect in the bundle as when first applied. The pressure is applied by the press and so, substantially, are the bands or cords which continue the pressure, and we cannot assent to the view that the continuation of the pressure in the bundles with the consequence of removing type indentations in the printed sheets is anything but the natural and direct effect of the machine.

Infringement was put in issue by the pleadings and passed on by the ower courts. They found as a fact that all the claims of the patent had

been infringed by appellant. The finding is not absolutely disputed. The assignment of error is "that the patented machine used by defendant, in view of the state of the art preceding Jones' invention, did not infringe any claims of the patent in suit." That is, appellant contends that the evidence exhibits a complete anticipation, or so limits and narrows the Jones' invention as to make the differences between the Jones press and that which was used by appellant more than formal. We have decided that the Jones press had not been anticipated, and both of the lower courts have found that the differences between it and appellant's press were not substantial. The evidence sustains the finding. The witnesses on behalf of appellees testified to the differences between the presses. They pointed out the essential resemblances of the presses and the merely formal character of the differences. There was no opposing testimony.

The accounting in the lower court, however, was had upon the basis of the validity of the process, (claim 5), and therefore the judgment of the Court of Appeals must be reversed and the cause remanded, with directions to that court to reverse the judgment and decree of the Supreme Court and remand the cause to the latter court for further proceedings.

in accordance with this opinion.

So ordered.

True copy.

Test:

Clerk Supreme Court, U. S.